

'AIN-I-ĀKBARI

OF

ABUL FAZL-I-'ALLAMI

Vol. II

11998

A Gazetteer and administrative Manual of Akbar's Empire and
past History of India.

Translated into English

By COLONEL H. S. JARRETT

Secretary and Member, Board of Examiners, Calcutta.

SECOND EDITION

Corrected and further annotated by

SIR JADU-NATH SARKAR, C.I.E., Hony. D.Litt.

*Honorary Member, Royal Asiatic Society of Great Britain and Ireland;
Corresponding Member, Royal Historical Society, Honorary Fellow,
Royal Asiatic Society of Bengal, and of Bombay Branch,
Royal Asiatic Society of G. Britain.*



CALCUTTA :

ROYAL ASIATIC SOCIETY OF BENGAL, 1 PARK STREET.

Work No. 271
Issue No. 1558

Rs. 25/-; £2/-; \$6.50

Printed by P. C. Ray, at Sri Gouranga Press, 5 Chintamani Das Lane, Calcutta.

EDITOR'S INTRODUCTION

After the lamented death of H. Blochmann on 13th July, 1878, at the early age of 40 years only, a search among his papers showed that he had not translated any portion of the *Ain-i-Akbari* beyond the first volume which the Asiatic Society of Bengal was then publishing. In fact, his careful editing of the vast text of the *Ain* had been such a laborious task, and his English version of the first volume of it was such a monument of scholarship and tireless research in annotation, that he could not have had the time to begin the translation of the second volume. The Society entrusted his unfinished work to Lt.-Col. H. S. Jarrett, who finished printing the translation of the second volume in 1891. Thus, Jarrett had at his disposal only such works of reference and learned treatises on India as were in print in 1884-1889. The authorities cited by him in his notes, as I have pointed out in the Introduction to my revised edition of the 3rd volume of his translation, have proved to be obsolete and often useless in the light of our knowledge today.

Since 1890, a complete revolution in these branches of orientology and the history of Hindu and Muslim India has been effected by the publication of Hastings's *Encyclopædia of Religion and Ethics*, the *Encyclopædia of Islam*, the *Grundriss* of Buhler, Elliot and Dowson's *History of India as told by its own Historians*, the *Cambridge History of India*, and many learned monographs on particular sovereigns and dynasties by Indian writers which touch the high-water mark of modern critical scholarship and exhaustive research.

All these authorities were unknown to Jarrett. His sole resource for the Hindu dynastic lists was Prinsep's *Useful Tables* (published in 1832) which is often based on this very *Ain-i-Akbari* and improved by reference to the mythical *Purānas* (as summarised in Wilson's translation of the *Vishnu Purāna*.) As for the Muslim rulers, he had to depend on the primitive *History of India* by Elphinstone (1841) or its source Firishta. Our reconstruction of Indo-Muslim history from inscriptions, coins and original Persian manuscripts was naturally missed by a writer of the years 1885-1889.

Therefore a mere reprint of Jarrett's translation and notes today would not do justice to the present state of Oriental scholarship and would naturally disappoint the modern reader. Thus the first task of an editor of Jarrett's translation is to correct and modernise his notes and elucidations by sweeping away his heaps of dead leaves, and giving more accurate information from the latest authorities. My second aim has been to lighten the burden of his notes, many of which are not only obsolete in information, but prolix to the point of superfluity. It is, I think, a mistake of the translator's duty to try to make a modern reader get all his ideas of Hindu philosophy, science, mythology, hagiography, and the topography and history of Muslim and Hindu India from the notes to an English translation of the *Ain-i-Akbari*. The modern reader will find very much fuller and far more accurate information on these subjects in the voluminous

encyclopædias, gazetteers and standard monographs published in the present century, which are available in the libraries of learned societies.

I have also economised space and saved the reader from frequent unnecessary interruptions, by the omission of Jarrett's notes on the emendations of the printed Persian text made by him (except in a few cases of vital importance.) The numberless variant readings which encumbered the pages of his second volume have been mostly cleared away by the acceptance of the true forms in the body of the book and rejecting all those that are palpably wrong or unhelpful in solving our doubt. It is well-known to the learned world that the editing of many of the volumes in the Persian and Arabic section of the *Bibliotheca Indica* series, was not done with the care and accuracy which characterise the oriental texts published in London or Paris, Leyden or Beyrut. Therefore all obvious misprints and wrong-readings in the text of the *Ain* have been silently corrected in this revised edition of the translation, and many hundreds of notes of the first edition deleted.

The third volume of the *Ain-i-Akbari* is an encyclopædia of the religion, philosophy and sciences of the Hindus, preceded by the chronology and cosmography of the Muslims, as required by literary convention, for comparison with the Hindu ideas on the same subjects. The second volume was designed to serve as a Gazetteer of the Mughal Empire under Akbar. Its value lies in its minute topographical descriptions and statistics about numberless small places and its survey of the Empire's finances, trade and industry, castes and tribes.

— Jarrett's translation of Volume II is weakest in this essential respect. For the more than six thousand place-names in this volume he could consult only Hunter's *Imperial Gazetteer of India* (in the rather crude early edition of 1887) ; but that work is quite unhelpful for the purpose of identifying the minute places mentioned in the *Ain*, and its volume of maps is on too small a scale to give the information we need. The highly useful and detailed provincial Gazetteers—such as Atkinson's *N. W. P. Gazetteer* and Campbell's *Bombay Gazetteer*, were completed after the Eighteen-eighties, too late for Jarrett's use. Nor did he consult the quarter-inch-to-the-mile maps of India published by the Surveyor-General and entitled the *Indian Atlas*. These two authorities,—the provincial Gazetteers and the Survey maps—are indispensably necessary for correctly tracing the place-names in the *Ain-i-Akbari*.

I have consulted these two primary works of reference and corrected Jarrett's (or Abul Fazl's) names and notes, with infinite labour, the nature of which can be understood only by comparing the list of *mahals* in a district (*sarkār*) in Jarrett's edition with the corresponding page in mine. Nine-tenths of the place-names in this book have been identified and entered in the corrected spelling in the course of my revision. This improvement of Abul Fazl's work will be completed and the nature of the gain to our knowledge of Mughal Indian topography will become evident to the modern reader, after the publication of a supplementary volume, on which Prof. Nirod Bhusan Roy is now working and which will contain a very much enlarged geographical index giving the location and exact references to mapsheets and Gazetteer-pages for each place mentioned here

and discussing the probable location or necessary emendation of the small proportion of places not satisfactorily traced by me. Very many of the mistakes in Jarrett (or rather in the printed Persian text followed by him) were due to the wrong placing or omission of dots (*nuqta*) and the well-known confusion of certain letters of the Arabic alphabet by our copyists. These I have silently corrected.

The chapter on the subah of Kashmir, which was the most confused and wrongly spelt in this volume,—has been revised throughout by Professor Nirod Bhushan Roy, on the basis of Stein's *Memoir* and *Chronicle of the Kings* and the official *Gazetteer* (by Bates). But the necessary changes are so many that the new information has been lumped together at the end, instead of being distributed in countless footnotes on the respective pages, and the useless notes and extracts of the first edition have been omitted.

I am deeply obliged to Prof. N. B. Roy for the care and persistence with which he has assisted me in this work of revision and performed the exacting task of reading the proofs (up to p. 192) of such a difficult book. A special word of thanks is due to the Sri Gouranga Press, which has patiently and efficiently done the rather exasperating work of printing this volume from a copy of the first edition, whose rotten paper crumbled at the touch, and on which my ink corrections had made the text even less readable than before. The sight of this press copy had scared away two first-rate printing establishments in Calcutta to whom it was previously offered, and the acceptance of the work of printing it was really a favour shown to the Society and to learning, by the Sri Gouranga Press. For my appreciation of the manner in which, on the whole, Jarrett completed a stupendous task, I refer the reader to my Introduction to the Translation of the Third Volume of the *Ain*, 2nd edition.

The absence of uniformity in the transliteration of oriental words in the Roman alphabet, is explained by the facts, (1) that Jarrett himself did not follow one uniform system throughout the first edition printed by him, (2) that the rotten paper of the single copy of this first edition which was given to me for preparing my press-copy, made it impossible for me to erase wrong marks and insert the latest-current signs in most places, and (3) that the typing of the entire book and the insertion of diacritical marks uniformly according to the system at present followed by the Society, could not be carried out for financial reasons. In short, this edition had to be printed in the rough practical form that I have given to it, or not at all. But two little hints may be given here: in the unchanged portions of Jarrett's work the inverted comma stands for the letter *āliph* (in names like—*ud-din*), while in my portion it stands for the letter 'ain'; and the mark over the long *A* (capital) could not be inserted owing to some technical difficulty in linotype composition.

Calcutta,
30th December, 1949.

JADUNATH SARKAR.

EXTRACTS FROM JARQUET'S PREFACE

among his own countrymen, not a beautiful image that the mind delights to recall, not a description that rises to great power or pathos, nor the unconscious simplicity redeeming its wearisome length which lends such a charm to Herodotus, and which in the very exordium of Thucydides, in Lucian's happy phrase, breathes the fragrance of Attic thyme. His narrative affects a quaint and stiff phraseology which renders it often obscure, and continues in an even monotone, never rising or falling save in reference to the Emperor whose lightest mention compels the adoring prostration of his pen, and round whom the world of his characters and events revolves as its central sun. Whatever its merit as a faithful representation, in a restricted sense, of a reign in which he was a capable and distinguished actor, it lacks the interesting details and portraiture of the life and manners of the nation which are commonly thought to be below the dignity of history but which brighten the pages of Eastern historians less celebrated than himself, and are necessary to the light and shade of a perfect picture.

His statistical and geographical survey of the empire which this volume comprises is a laborious though somewhat lifeless compilation, of the first importance indeed as a record of a past and almost forgotten administration to guide and instruct the historian of the future or the statesman of to-day, but uninformed by deductive comment and illustration which might relieve the long array of bald detail. His historical summaries of dynasties and events in the various Subahs under their ancient autonomous rule, are incoherent abridgements, often so obscurely phrased as not to be understood without a previous knowledge of the events to which they relate and his meaning is rather to be conjectured than elicited from the grammatical analysis of his sentences. The sources from which he drew his information are never acknowledged. This of itself would have been of no moment and their indication might perhaps have disturbed the unity of his design had he otherwise so incorporated the labours of others with his own as to stamp the whole with the impress of originality, but he not seldom extracts passages word for word from other authors undeterred by the fear or heedless of the charge, of plagiarism.

Such, in my opinion, is the reverse of the medal which represents Abul Fazl as unrivalled as a writer and beyond the reach of imitation. The fashion of exaggerating the importance and merits of a subject or an author by those who make them their special study, especially when that study lies outside the common track of letters, inevitably brings its own retribution and ends by casting general discredit on what in its place and of its kind has its due share of honour or utility. The merit and the only merit of the *Ain-i-Akbari* is in what it tells and not in the manner of its telling which has little to recommend it. It will deservedly go down to posterity as a unique compilation of the systems of administration and control throughout the various departments of Government in a great empire, faithfully and minutely recorded in their smallest detail, with such an array of facts illustrative of its extent, resources, condition, population, industry and wealth as the abundant material supplied from official sources could furnish. This in itself is praise and fortune of no common order and it needs not the fictitious ascription of

unparalleled powers of historiography in its support. The value of the *Ain* in this regard has been universally acknowledged by European scholars and it may not be out of place to quote here the opinion* of the learned Reinaud on this work in his 1st vol. of the *Géographie d' Abulfeda*, as it accurately represents its nature and worth and the style and quality of its literary composition. He writes :—

“Muslim India offers us, at the commencement of the 17th century, a work of compilation, which is of great interest for geography ; it is a Persian treatise composed by Abul Fazl, the minister of the Mughal Emperor Akbar, and entitled the *Ain-i-Akbari* or the Institutes of Akbar. . . . The empire founded in India by Babur, had attained, under the reign of Akbar, a great extension, and stretched from Afghanistan up to the head of the Gulf of Bengal, from the Himalaya up to the Deccan. Due to the excellent government established by Akbar, the provinces, long ravaged by intestine wars, had acquired a new shape. On the other hand, the liberal views of the Emperor and of his ministers, had nothing in common with the narrow and exclusive spirit which characterises Islam, and they had caused to be translated into Persian the best works of Sanskrit literature. Abul Fazl, putting himself at the head of a body of scholars, undertook a geographical, physical and historical description of the empire, accompanied by statistical tables. Each of the sixteen *subahs* or Governments of which the Mughal empire was then composed, is there described with minute exactitude ; the geographical and relative situation of the cities and boroughs (market towns, *gasba*) is there indicated ; the enumeration of the natural and industrial products is carefully traced there ; as also the names of the princes, both Hindu and Musalman, to whom the *subah* had been subject before its inclusion in the empire. We next find an exhibition of the military condition of the empire and an enumeration of those who formed the household of the sovereign, &c. The work ends in a summary, made in general from indigenous sources, of the Brahmanic religion, of the diverse systems of Hindu philosophy, &c.

The author, by the pursuit of a misplaced erudition has accomplished the style of the ancient Persian authors ; it is often difficult to understand it. In 1783, Francis Gladwin, encouraged by the Governor-General Hastings, published an abridged English version of the work. (He then condemns Gladwin's defects,—inaccuracy, confusion, and ‘horrible alteration’ of indigenous, particularly Sanskrit, words in transcribing them in the Arabic Alphabet, and calls for a new edition as a very useful service to students.)

In the table of the names of places confusion exists in the original text. Evidently, the person who in that early age was charged with the drawing up of the table had little knowledge of geography.”

H. S. JARRETT.

Calcutta,
1891

* Translated from French into English by J. Sarkar for the second edition.

CONTENTS

	PAGE
Divine Era	1
Era of the Hindus	15
Turkish Era	20
Hijera Era	25
Ilāhi Era	29
Ain 1. Provincial viceroy	37
2. Faujdar	41
3. Mir Adl & Qazi	42
4. Kotwal	43
5. Collector of Revenue	46
7. Treasurer	52
Islamic land tax	60
8. Ilahi gaz	64
9 & 10. Tanāb and Bighā	66
11. Land, its classification, dues of the State	68
Imposts abolished by Akbar	72
14. Nineteen Years' revenue rates	75
15. The 'Ten Years' Settlement	94

Account of the Twelve Subhas

Bengal	129
Orissa	138
Sovereigns of Bengal	157
Behar	162
Allahabad	169
Qudh	181
Agra	190
Malwa	206
Sovereigns of Malwa	221
Khandesh	232
Berar	236
Gujarat	246
Rulers of Gujarat	264
Ajmer	273
Delhi	283
Sovereigns of Delhi	302
Lahor	315
Multan	329
Kings of Multan	336
Sarkar Tatta	338
Princes of Tatta	343
Kabul Subah	349
Sarkar Kashmir	349
Sovereigns of Kashmir	370
Notes on places in Kashmir	389
Sarkars Pakli & Swat	397
Sarkar Qandahar	399
Sarkar Kabul	404
16. The Kos	417

BOOK THIRD

IMPERIAL ADMINISTRATION

Since somewhat of the recent imperial institutions regulating the Army and the Household have been set down, I shall now record the excellent ordinances of that sagacious intellect that energizes the world.

'A IN I

. THE DIVINE ERA

The connection of monetary transactions without fixity of date would slip from the grasp, and through forgetfulness and falsehood raise a tumult of strife; for this reason every community devises a remedy and fixes an epoch. Since thought fosters well-being and is an aid to facility (*of action*), to displace obsolete chronology and establish a new usage is a necessity of government. For this reason, the prince regent on the throne of felicity in the 29th year of the *Ilāhi* Divine Era,¹ for the purpose of refreshing that pleasure-ground of dominion and revenue, directed its irrigation and rendered blooming and lush the palace-garden of the State.

Compassing events within a determinate time, the Persian calls *māhroz* (date); the Arab has converted this into *mu'arrakh* (*chronicled*), and thence "*tārikh* (*date*) is a household word. Some derive the Arabic from *irākh*, a wild bull.² This conjugation of the measure of *tafa'il* means, to polish. As ignorance of the time of an event grew less, it

¹ *Akbarnāmah* (Beveridge's trans), iii. 644; this era was introduced at the beginning of the 29th regnal year, 8 Rabi A. 992=10th March 1584.

² *Encyclopaedia of Islam*, Supplement, p. 230: "The root of the word *tārikh* (meaning era, date) is *w-r-kh*, common to the Semitic languages, which we find for example in the Hebrew *yerah*, month. . . . The survival of a tradition in al-Bīrūnī is interesting; according to this, the word is an arabisation of the Persian *māhrūz*; here again there is the vague consciousness that the word has something to do with fixing the beginning of the month. al-Khwarizmi in his *Mafātih al-'Ulum* expressly states that this tradition is to be rejected." Abul Fazl's etymology is sometimes as bad as his geography. [J. S.]

wealth, and the philosophic treatises of the past and the institutions of the ancients cannot be secured without the most strenuous endeavours of the sovereign. With all this, thirty years are needed to observe a single revolution of the seven planets.⁶ The longer the period and the greater the care bestowed upon a task, the more perfect its completion.

In this time-worn world of affliction Divine Providence has vouchsafed its aid to many who have attained considerable renown in these constructions, such as Archimedes, Aristarchus and Hipparchus in Egypt, from whose time to the present, the 40th year of the divine era, 1769 years have elapsed;⁷ such as Plotemy in Alexandria who flourished some 1410 years ago; as the Caliph Māmun in Baghdad, 790 years past, and Sind⁸ bin 'Ali and Khālid⁹ bin 'Abdul Malik al Marwazi 764 years since at Damascus. Hākim and Ibn¹⁰ Aa'lam also laid the foundations of an observatory at Baghdad which remained unfinished, 712 years, and Battāni¹¹ at Raqqa 654 years previous to this time. Three

⁶ The ancients gave the name of *planets* to the five planets visible to the naked eye, and the sun and moon. The names of the five—Mercury, Venus, Mars, Jupiter, and Saturn first occur in the cosmical scheme of Philolaus. (Lewis. *Astron. of the Ancients*) The thirty years must refer to that planet of the seven occupying the longest period in its revolution, namely, Saturn which was the most remote then known. It takes 29 years and 5½ months (very nearly) to return to the same place among the fixed stars, whether the centre of motion be the Sun or the Earth.

⁷ It is needless to say that all these figures are very inexact. Archimedes flourished 287-212 B.C., Aristarchus somewhere about 280-264 B.C. and Hipparchus is placed by Suidas at from B.C. 160 to 145, and yet they are all bracketed together. The date of Plotemy, illustrious as he is as a mathematician, astronomer and geographer, is uncertain. He observed at Alexandria, A.D. 139 and was alive in A.D. 161. Mamun succeeded to the Caliphate on the 24th September 813. He caused all Greek works that he could procure to be translated, and in particular the *Almagest* of Plotemy. *Almagest* is a compound of the Greek with a prefix of the Arabic article. (*Encycl. Metropolitana*, Art. Astron.)

⁸ Abu Tayyib Sind-b-'Ali was a Jew converted to Islam in the Caliphate of Māmun and was appointed his astronomer and superintendent of observatories.

⁹ Khālid-b-'Abdul Malik, A.H. 217 (832) a native of Merv. He is included among three astronomers who first among the Arabs, instituted observations from the Shammāsiyah observatory at Baghdad.

¹⁰ Ibn ul 'Aa'lam A.H. 375 (A.D. 985), stood in great credit with Adhad ud daulah, but finding himself in less estimation with his son Shamsud Daulah, he left the court but returned to Baghdad a year before his death. His astronomical tables were celebrated not only in his own time but by later astronomers.

¹¹ Muhammad b. Jābir al Battāni (Albatenius), a native of Harrān and inhabitant of Raqqa. His observations were begun in A.H. 264 (A.D. 877-8) and he continued them till A.H. 306. *Ency. Islam*, i. 680, "one of the greatest of Arab astronomers," (where details about his writings and achievement); he died in 317 A.H. He was surnamed the Ptolemy of the Arabs. He corrected the determination of Ptolemy respecting the motion of the stars in longitude, ascertaining it to be one degree in 70 instead of 100 years; modern observations make it one degree in 72 years. He also determined very exactly the eccentricity of the ecliptic and corrected the

hundred and sixty-two solar years have passed since Khwājah¹² Nasir of Tus built another at Murāgha near Tabriz and 155 is the age of that of Mirzā Ulugh Beg¹³ in Samargand.

Rasad signifies 'watching' in the Arabic tongue and the watchers, therefore, are a body who, in a specially-adapted edifice, observe the movements of the stars and study their aspects. The results of their investigations and their discoveries regarding these sublime mysteries are tabulated and reduced to writing. This is called an astronomical table (*zij*). This word is an Arabicized form of the Persian, *zik* which means the threads that guide the embroiderers in weaving brocaded stuffs. In the same way an astronomical table is a guide to the astronomer in recognising the conditions of the heavens, and the linear extensions and columns, in length and breadth, resemble these threads. It is said to be the Arabic rendering of *zih* from the frequent necessity of its use, which the intelligent will understand. Some maintain it to be Persian, signi-

length of the year, making it consist of 365 days, 5 hours, 46 minutes, 24 seconds, which is about 2 minutes short of but 4 minutes nearer the truth than had been given by Ptolemy. He also discovered the motion of the apogee.

¹² *Nasirū'ddin* is the surname of Abu Ja'far Md. b. Muhammad-b-Hasan or Ibn Muhammad at Tusi, often simply called Khwājah Nasirū'ddin (A.H. 597-672). Hulāku the Tartar chief placed him at the head of the philosophers and astronomers whom his clemency had spared in the sack of Moslem towns, and gave him the administration of all the colleges in his acquired dominions. The town of Marāgha in Azarbayjān was assigned to him and he was ordered to prepare the astronomical tables which were termed Imperial (*Elkhān*). [*Enc. Islam*, iv. 980, under al-Tusi.]

¹³ Ulugh Beg, (name Muhammad Turghāi) born 1393, died 1449 A.D., was the son of Shah Rukh and grandson of Tamerlane. In 810 he possessed the government of some provinces of Khorasān and Mazanderān and in 812, that of Turkistān and Transoxania. He, however, quickly abandoned politics and devoted himself passionately to his favourite studies. He desired that his tables should be scrupulously exact and procured the best instruments then available. These at this period, were of extraordinary size. The obliquity of the ecliptic was observed in A.D. 995 with a quadrant of 15 cubits' radius (21 feet 8 inches). The sextant of Abu Muhammed al Khojandi used in 992 had a radius of 40 cubits (57 feet 9 inches). The quadrant used by Ulugh Beg to determine the elevation of the pole at Samargand, was as high as the summit of St. Sophia at Constantinople (about 180 feet). The astronomical tables were first published in A.H. 841 (A.D. 1437). The ancient astronomy had produced only one catalogue, of the fixed stars, that of Hipparchus. Ulugh Beg, after an interval of sixteen centuries, produced the second. His observatory at Samargand (begun in 1428 under the architect Ali Qushji), in its day was regarded as one of the wonders of the world. He corrected Ptolemy's computations and compiled the *Zij-i-Jadid Sultāni*. These tables became celebrated in Europe—trans. by Hyde in 1665, by Sedillot (prolegomena only) in 1847, and by Knobel in 1917." With him the period of astronomical works in the East finishes." [*Ency. Islam*, iv. 994-996.]

For the compilation of Astronomical Tables by Muslims (*zif*), see *Enc. Islam*, i. 498.

fying a mason's rule, and as he, through its instrumentality determines the evenness of a building, so an astronomer aims at accuracy by means of this astronomical table.

Many men have left such compilations to chronicle their fame. Among these are the Canons of.

1. MĀJUR THE TURK.

There are two of this family whom Sedillot terms the Benou Amajour. Hammer-Purgstall makes them the same person but adds another name Abul Qāsim 'Abdullah. According to him, they were brothers, and the former was the author of the Canon called al Bedia or "the Wonderful;" the latter of works on other astronomical tables with disputed titles. He appears to quote from the Fihrist and from Casiri who borrows from Ibn Jounis, but the Fihrist distinctly states that Abu'l Hasan was the son not the brother of Ali b. Amajur. Ibn Jounis speaks of Abul Qāsim also, and as a native of Herat. The Benou Amajur were astronomers of repute and made their observations between the years 885-933, leading the way to important discoveries. (Sed p. xxxv *et seq.*)

2. HIPPARCIUS.

3. PTOLEMY.

4. PYTHAGORAS.

5. ZOROASTER.

6. THEON OF ALEXANDRIA.

7. SĀMĀT THE GREEK.

Another reading is Sābāt but I cannot recognize nor trace the name satisfactorily. The epithet *Yunāni* inclines me to believe the name to be that of a Greek astronomer in Islamic times.

8. THĀBIT-b-QURRAH b Hārūn was a native of Harrān, of the Sabean sect, and rose to eminence in medicine, mathematics and philosophy, born A. H. 221 (A.D. 836), died in A. H. 288 (A.D. 901). He was much favoured by the Caliph al Muatadhid who kept him at Court as an astrologer. He wrote on the Spherics of Theodosius, and retranslated Euclid already turned into Arabic by Hunain-b-Ishāq al Ibādi. He was also author of a work in Syriac on the Sabean doctrines and the customs and ceremonies of their adherents. Ibn Khall. D'Herb. Sedillot. p. xxv. *et seq.* For a list of his works, see the Fihrist, p. 272.

9. HUSĀM b. SINAN (var. Shabān.)

I believe the first name to be an error. The Fihrist mentions a son of Sinan with the patronymic Abul Hasan who is no doubt here meant. He was grandson of Thābit-b-Qurrah, and named also Thābit according to D'Herb. as well as Abul Hasan after his grandfather. (Sedillot). Equally proficient in astronomy with his grandfather, he was also a celebrated physician and practised in Baghdad. He wrote a history of his own time from about A.H. 290 to his death in 360. Abul Faraj speaks of it as an excellent work. See also Ibn Khall. De Slane. Vol. II. p. 289 and note 7. His father Sinān the son of Thābit-b-Quarrah, died at Baghdad A.H. 331. They were both Harranians, the last representatives of ancient Greek learning through whom Greek sciences were communicated to the illiterate Arabs.

Sinān made a collection of meteorological observations called the *Kitāb ul anwā*, compiled from ancient sources, incorporated by Albiruni in his *Chronology*, and thereby preserved to us the most complete Parapegma of the ancient Greek world. See Albiruni, *Chronol.*, Sachau's Transl. p. 427. n.

10. THĀBIT-b-MUSA.

I can find no such name. The *Fihrist* gives Thābit-b-Alusa, head of the Sabean sect in Harrān.

11. MUHAMMAD-b-JABIR AL BATTĀNĪ. See p. 3, note 11.

12. AHMAD-b-'ABDULLAH JABĀ.

Jaba is a copyist's error for Habsh. He was one of Al Māmun's astronomers, and distinguished by the title of Al Hāsib or the Reckoner. He was employed by Māmun at Sinjar to observe the obliquity of the Ecliptic and to test the measurements of geometrical degrees. He compiled a set of tables by the Caliph's order. Ham. Purg., B. III, p. 260. Abul Faraj (ed. 1663, p. 247) says that he was the author of three Canons; the first modelled on the Sindhind, the second termed Muntahan or Proven (after his return from his observations) and the third the Lesser Canon, known as the 'Shāh'.

13. ABU RAYHĀN.

Abu Rayhān-Muhammad-b-Ahmad Albiruni, born 362. A. H. (A. D. 973), d. 440. (Ar. D. 1048). For further particulars I refer the reader to Sachau's preface to the *Indica* and the *Chronology* of this famous savant.

14. KHĀLID-b-'ABDUL MĀLIK. See p. 3, note 9.

15. YAHYA-b-MANSUR.

More correctly Yahya-b-Abi Mansur, was one of Al Māmun's most famous astronomers. Abul Faraj (p. 248), says that he was appointed by that Caliph to the Shammāsiyah observatory at Baghdad and to that of Mount Qāsiun at Damascus. The *Fihrist* gives a list of his works (p. 275) and (p. 143) his genealogy and descendants who appear to have shared and augmented their father's fame. He died about 833, (A. H. 218) in Māmun's expedition to Tarsus and was buried at Aleppo. *Enc. Islam*, iv. 1150.

16. HĀMID MARWARUDĪ.

This is doubtless, Abu Hāmid, Ahmad-b-Muhammad as Sāghānī. Sāghān is a town near Marw. Ibn Khallikān's derivation of Marwarrud will explain the difference in the titular adjectives of place. I transcribe De Slane, V. I, p. 50. "*Marwarrudī* means native of *Marwarrud*, a well known city in Khorāsān, built on a river, in Persian *ar-rud*, and situated 40 parasangs from Marw as Shāh-jān; these are the *two Marws* so frequently mentioned by poets: the word Shāh-jān is added to the name of the larger one from which also is derived the relative adjective *Marwazi*; the word *rud* is joined to that of the other city in order to distinguish between them. *Marwarud* has for relative adjective *Marwarrudī* and *Marwazi*, also, according to as Samānī." Shāh-jān is, of course, Sāghān. Abu Hāmid was one of the first geometricians and astronomers of his time (d. 379, A. H. 898), and a maker of astrolabes at Baghdad and was employed to certify the correctness of the royal astronomical reports. Ham. Purg. B. V. 313.

17. MUGHITHI. Perhaps, Mughni tabulae astronomicae sufficientes, mentioned by Hāji Khalifa, p. 568, Art. Zich.

18. SHARQI. (Var. Sharfi.) probably Abul Qāsim as Saraqi of whom Casiri writes. 'Abulcassam Alsaraki Aractensis (of Raqqa), Atrologiæ judiciaræ et astronomiæ doctrina, uti etiam Tabularum et Sphæræ peritia laud ignobilis, inter familiares atque intimos Saifeldaulati Ali-ben-Abdalla-ben Hamdan, per ea tempora Regis, habitus est, quibuscumque Sermones Academicos frequens conferebat (Saifeldaulatus Syriæ Rex, anno Egiræ 356 obiit. (Sedillot, p. xlviii.)

19. ABUL WAFĀ-NURHĀNI. An error for Buzjāni. Buzjān is a small town in the Nisābur district in the direction of Herāt. He was born A. H. 328 (939) d. 388 (998). In his 20th year he settled in Irāq. A list of his works will be found in the Fihrist, p. 283. Ham Purg. B. V. 306. His Canon was termed "as Shāmil." His most important work was the *Almagest*, which contains the formulas of tangents and secants employed by Arab geometricians in the same manner as in trigonometrical calculations of the present day. In the time of Al Battāni, sines were substituted for chords. By the introduction of tangents he simplified and shortened the expression of circular ratios. His anticipation of the discoveries of Tycho Brahe may be seen in Sed. p. ix. *Enc. Isl.* i. 133, s.v. *Abu-l-Wafa*.

20. THE JAMI'. (Plura continens)

21. THE BALIGH. (Summum attingens)

22. THE 'ADHADI.

} Kyahushyar.

Kushyār-b-Kenān al Hanbali, wrote three Canons, according to Hāji Khalifa. Two were the *Jāmi'* and the *Sāli'* (Bāligh is however confirmed by D'Herbelot, art. *Zig*). These works were on stellar computations, on almanacs, the motions of the heavenly bodies and their number, supported by geometrical proofs. His compendium (*mujmal*) summarises their contents (p. 564.) The *Jāmi'* is again mentioned lower down as a work in 85 chapters applied by the author to rectify or elucidate the Persian era. He added to it a supplement in illustration of each chapter of the *Jāmi'*. The third Canon is called simply *Zij Kushyār* translated into Persian by Md-b-'Umar-b-Abi Tālib at Tabrizi. This was probably dedicated to Adhad ud Daulah Alp Arslan, lord of Khorāsān, who had condescended to accept this title from his creature the feeble Qāim bi amri llāh at Baghdad. Hence, I conjecture, the name Adhadi.

23. SULAYMĀN-b-MUHAMMAD. Untraceable. This name does not occur in one of the MSS. of the *Ain*.

24. ABU HĀMID ANSĀRI.

The only descendant of the Ansārs that I can find among the astronomers is Ibn us Shatir. d. 777 A. H. (1375); the name was Alāuddin, patronymic not given. See Haj. Khal. pp. 557, 566. It is possible that the celebrated Abu Hāmid al Ghazzālī may be meant.

25. SAFĀIH. Evidently the name of a Canon and not of its author.

26. ABUL FARAH SHIRĀZI.

27. MAJMU'Ā. Apparently the name of a Canon mentioned by Hāji Khalifa, auctore Ibn Shari', collecta de astrologia judiciaria.

28. MUKHTĀR auct. Shaikh Abu Mansur Sulaiman b. al Husain-b-Bardowaili. Another work of the same name (*Dilectus 'e libris*

electionis dierum, astrologiere) was composed by the physician Abu Nasr Yahya b. Jarir at Takriti for Sadid ud Daulah Abul Ghanaim Karim.

29. **ABUL HASAN TUSI.** This name occurs in the *Fihrist* (p. 71) as that of a scholar learned in tribal history and poetry. A son of the same name is mentioned as a distinguished doctor, but there is no notice of his astronomical knowledge.

30. **AHMAD-b-ISHAQ SARAKHSI.**

The name of Ishaq does not occur in the genealogy of any Sarakhsi that I can discover. The text probably refers to Ahmad-b-Md. b. at Tayyib, the well known preceptor of the Caliph al Muatadhid by whom he was put to death in A. H. 286 (899) for revealing his pupil's confidences. D'Herb. states that he wrote on the *Eisagoge* of Porphirius, and Albiruni (*Chronology*) mentions him as an astrologer and cites a prophecy of his where he speaks of the conjunction of Saturn and Mars in the sign of Cancer.

31. **GHARARI.** Probably Al Fazari. Abu Ishaq Ibrahim-b-Habib the earliest maker of astrolabes among the Arabs, who was the author of a canon and several astronomical works. *Fihrist*, p. 273, date not given.

32. **AL HARUNI.**

It is difficult in such bald mention of names, where so many are alike, to be sure of the correctness of allusion. This is, probably, Harun-b-al Munajjim, an astrologer, native of Baghdad and an accomplished scholar. His great grandfather was astrologer to the Caliph al-Mansur and his son Yahya served al Fadhl-b-Sahl in the same capacity, died A. H. 288 (901). Ibn Khall. IV, p. 605.

33. **ADWAR I KIRAIN** (Cycles of conjunctions) the name of a Canon whose author I cannot discover.

34. **YAKUB-b-TAUS.**

I may safely hazard the emendation Tariq for Taus. This astronomer is mentioned by Albiruni. *Ham. Purg.* gives his date A. H. 218 (833) and a list of his works apparently copied from the *Fihrist*, p. 278.

35. **KHWARAZMI.**

Muhammad-b-Musa, by command of al Mamun, compiled an abridgement of the *Sindhind* (*Siddhanta*); better known as a mathematician than as astronomer—see Sedillot, I. xvi. He was the author of a Canon according to the *Fihrist*, p. 274. *Enc. Isl.* ii. 912.

36. **YUSUFI.** The secretary of Al Mamun, Abut Tayyib-b-'Abdillah is the only name I discover in this relative form. The *Fihrist*, (p. 123) mentions no astronomical works of his. Perhaps, Yusuf-b-Ali Thatta (1043) or Ibn Yusuf al Massisi may be meant: the text is too vague to determine accurately.

37. **WAFI**—the work of Ulugh Beg "*fi Ma'arifi ul samai un Najumiya*" (de transiitibus operationum astronomicarum) is the only title approaching that of the text that I discover.

38. **JAUZHARAYN**—Jauzhar the Arabic form of Gauzhar, is the head and tail of Draco. The two points in the Ecliptic which mark its intersection by the orbit of a planet in ascent and descent, are called its Nodes or two Jauzhars—(*Istilābāt ul Funon*.) There is a Canon called *Fi Maqarim al Juzhar de motu vero capitis et caudae draconis*, by Shaikh Ibn ul Qadir al Barallusi—see Haj-Khall, p. 561.

39. SAMA'ĀNI. D'Herbelot mentions under this surname Abu Saad Abdul Karim Muhammad, the author of a work on Mathematics entitled *Adāb fi istimāl il Hisāb*. A. H. 506—62. The Fihrist p. 244, records another Samaān as a commentator on the Canon of Ptolemy, and a third Ibn Samaān, the slave of Abu Mashar, and author of an astronomical work.

40. IBN SAHRA.

The variants of this name suggest its doubtful orthography. Ibn Abi Sahari is mentioned by Ham. Purg. as an astrologer of Baghdad whose predictions were fortunate. He lived in the latter half of the century, 132—232, (749—846) the most brilliant period in the annals of Arab literature.

41. ABUL FADHL MĀSHALLAH, incorrectly Māshada in the text. —Born in Al Mansur's reign, he lived to that of Al Māmun. His name "What God wills" is simply a rendering of the Hebrew Mischa. The Fihrist calls him Ibn Athra and notes his voluminous writings, copied by Ham, Purg. B. III. 257.

42. 'AĀSIMI—untraceable.

43. KABIR OF ABU MA'SHAR—a native of Balkh, a contemporary and envious rival of Al Kindi.—At first a traditionist, he did not begin the study of astronomy till after the age of 47. He died at Wāsit exceeding the age of 100, A. H. 272, (885)—An astronomer and astrologer of great renown. In the latter capacity, he paid the penalty of success in a prediction by receiving a flogging at the command of Al Musta'in; upon which his epigram is recorded. "I hit and got hit." Thirty-three of his works are named in the Fihrist, p. 277. He was known in Europe as Albumaser and his works translated into Latin, see Sachau's Albiruni (Chronol.) p. 375,—also Haj. Khal. art. zij.

44. SIND-b-'ALI. See note p. 3.

45. IBN AĀLAM. See note p. 3.

46. SHAHRYĀRĀN.

This Canon occurs in Albiruni (Chronol.) with the addition of the word Shāh.—Sachau confesses his ignorance of it. Haj. Khal. gives a Canon called Shahryar which is well-known—translated into Arabic by At Tamimi from the Persian. Fihrist, 244. v. also Sachau's preface to Albiruni's *India*, p. xxx.

47. ARKAND.—In Albiruni called "the days of Arkand." The more correct form according to Reinaud, *Memoire sur l Inde*, p. 322, would be the Sanskrit *Ahargana*—See Sachau's note p. 375 of Albiruni's *Chronol.* from which I quote.

Albiruni made a new edition of the Days of Arkand, putting into clearer words and more idiomatic Arabic, the then existing translation which followed too closely the Sanskrit original.

48. IBN SUFI.

Al Shaikh Md. b. Abil Fath as Sufi al Misri wrote an epitome of the Canon of: Ulugh Beg with additional tables and notes. It was with reference to this epitome that the work of Al Barallusi, *Bihjat ul Fakr fi Hall is Shams Wāl Qamr* was written, of which the Jauzhar, one of its three parts, is alluded to in 38.

49. SEHALĀN KĀSHI.

Sehelān, Sehilān or Ibn Sehilān according to D'Herbelot was the name of the Minister of Sultān ud Daulah of the Buyide family, whose enmity with his brother Mushrafud Doulah was due to the policy or personal feeling of that statesman. A canon might have been published under his patronage and name.

50. **AIHWĀZI.** D'Herbelot alludes to several authors under this name ; one a commentator on Euclid. The *Fihrist* names Md-b-Ishāq al Ahwazi, without date. He appears to have written on agriculture and architecture.

51. **THE 'URUS OF ABU JAFAR BUSHANJ.**

Bushanj, according to Yaqut (*Mujam il Buldān*) is a small town about 40 miles from Herat, which has given birth to some eminent scholars, but I can find no astronomer among them.

52. **ABUL FATH**—Shaikh Abul Fath as Sufi who amended the tables termed Samarqandi. Hajj Khal. 566, III.

53. **A'KKAH RĀHIBI**—untraceable.

54. **MASAUDI.**—The *Canon Masudicus* is extant in 4 good copies in European libraries, and waits for the combination of two scholars, an astronomer and an Arabic philologist, for the purpose of an addition and translation, v. Sachau, pref. to Alberuni's *India*, p. xvi. *Enc. Islam*, iii. 403.

55. **MUATABAR OF SANJARI.** The surname of Abul Fath Abdur Rahman, called the treasurer ; he was a slave of Greek origin, in the service of A'li al Khāzin al Marwazi and much in his favour. On the completion of his Canon, the Sultan Sanjar sent him a thousand dinars which he returned. Hajj Khal. III. 564.

56. **WĀJIZ-I-MUATABAR** is doubtless, as its name imports, an epitome of the foregoing.

57. **AHMAD ABDUL JALIL SANJARI**, author of two treatises on stellar influences. D'Herbelot mentions him as an astrologer of note, but adds no particulars.

58. **MUHAMMAD HASIB TABARI.**

Untraceable.

59. **'ADANI.**

60. **TAYLASĀNI.**

61. **ASĀBAI.**

62. **KIRMĀNI.**

These are names of tables which I do not find mentioned. By the term *Taylasān* is meant a paradigm showing astronomical calculations, in the shape of half an oblong quadrangular field divided by a diagonal. It is named after the form of the Scarf (*Taylasān*) worn by learned men in the East. A model will be found in Albiruni's *Chronology*. (Sachau), p. 133.

63. **SULTAN 'ALI KHWĀRAZMI.** Ali, Shah-b-Md-b-il Qāsim commonly known as 'Alāuddin Al Khwārazmi, the author of a Canon called *Shāhi*—the royal ; also of a Persian epitome from the Elkhāni Tables, called the *Umdat ul Elkhāniya*. Hajj Khal. p. 565, III.

64. **FĀKHIR 'ALI NASĀBI.**

The variants indicate a corrupt reading—untraceable.

65. **THE 'ALAI OF SHIRWĀNI.** Fariduddin Abul Hasan Ali-b-il Karim as Shirwani, known as Al Fahhād, eminent among the later astronomers, the author of several canons besides the one mentioned—See Hajj Khal. p. 567, in two places.

There are two other Canons called 'Alai, H. K. 556-7.

66. RĀHIRI—var. Zahidi—untraceable.

67. MUSTAWFI—mentioned by Haj. Khal. without author's name.

68. MUNTAKHAB (Selectus) OF YAZDI.

69. ABU RAZĀ YAZDI.

Yazd is a town between Naysabur and Shirāz. I find no record of either the canon or the astronomer.

70. KAYDURAH.

71. IKLIL.

Al Iklil is the 17th Lunar Station—three stars in the head of Scorpio. I infer from the absence of any mention of such astronomers that these canons are named after stars. I can learn nothing of Kaydurah.

72. NĀSIRI—perhaps called after Nāsirud-Daulah-b-Hamdān, temp. Mutii billah, A.H. 334. (946 A.D.)

73. MULAHHKHAS. (Summarium).

74. DASTUR. *Dastur ul Aml fi Tashih il Jadwal*—a Persian commentary by Mahmud-b-Mahd.-b-Kādhizāda (known as Meriem Chelebi, in H. K. and D'Herb.) of the Canon of Ulugh Beg. See H. K. p. 560, III, and Sedillot, clv. I.

75. MURAKKAB. (Compositus).

76. MIKLAMAH. (Calamarium).

77. 'ASĀ. (Baculas)

78. SHATSALAH. Var. Sashtalah.

79. HASIL. (Commodum).

80. KHATĀI. A name of N. China: its people possessed an Astronomical Calendar in common with the Aighur Tribe, v. D'Herb. Art. *Igur*.

81. DAYLAMI.

This is a bare list of tables of whose authors there is no certain record. Two of them, Khatāi and Daylam point to the countries where they were in vogue. Kublai Khan the brother of Hulāku after his conquest of China, introduced into the Celestial Empire the astronomical learning of Baghdad, and Cocheon-king in 1280, received the tablēs of Ibn Yunas from the hands of the Persian Jamāluddīn. For the extent of Chinese science at this time, see Sedillot. ci. I.

82. MUFRAD. (Simplex) OF MD.-b-AYYUB.

This Canon is in H. K. without the author's name.

83. KĀMIL (Integer) OF ABU RASHID.

There is a commentary of the *Shamil* of al Buzjani by Hasan-b-Ali al qumnāti, entitled the *Kāmil*, mentioned in H. K. p. 565. III.

84. ELKHĀNI.

There are the tables of Nasiruddin Tusi.

85. JAMSHIDI. Ghiyāthuddin Jamshid together with the astronomer known as Kadhizadah, assisted Ulugh Beg in the preparation of his Canon. The former died during the beginning of the work, the latter before its completion. H. K. 559. D'Herbelot (Art. *zig. Ulug. Beg.*) reverses this order and asserts that Jamshid finished it. I suspect that he has copied and mistaken the sense of H. K.

86. GURGANI. Another name for the Canon of Ulugh Beg. See Sed. p. cxix.

Whatever they set down, year by year from an astronomical table, as to the particular motions and individual positions of the heavenly bodies, they call an Almanac. It embodies, in fact, the diurnal progression of a planet from its first entrance into Aries to a determinate point in the ecliptic, in succession, and is in Hindi called *patrah*. The Indian sage considers astronomy to be inspired by divine intelligences. A mortal endowed with purity of nature, disposed to meditation, with accordant harmony of conduct, transported in soul beyond the restraints of sense and matter, may attain to such an elevation that earthly and divine forms, whether as universals or particularized, in the sublime or nethermost regions, future or past, are conceived in his mind. From kindness of disposition and in the interests of science they impart their knowledge to enquirers of auspicious character, who commit their lessons to writing, and this writing they term *Siddhānt*. Nine such books are still extant; the *Brahm-Siddhānt*, the *Suraj-Siddhānt*, the *Som-Siddhānt*, the *Brahaspat-Siddhānt*, inspired by Brahma, the sun, moon, and Jupiter respectively. Their origin is referred to immemorial time and they are held in great veneration, especially the first two. The *Garg-Siddhānt*,¹⁴ the *Nārad-Siddhānt*, the *Parāsar-Siddhānt*, the *Pulast-Siddhānt*, the *Bashista-Siddhānt*,—these five they ascribe to an earthly source. The unenlightened may loosen the tongue of reproof and imagine that these mysteries acquired by observation of *Stellar* movements, have been kept secret and revealed only in such a way as to ensure the gratitude of reverential hearts, but the keen-sighted and just observer will, nevertheless, not refuse his assent, the more especially as men of innate excellence and outward respectability of character have for myriads of years transmitted a uniform tradition.

¹⁴ These last are named after five celebrated Rishis or Munis. The antiquity of Indian astronomy is a matter of dispute among the learned. The curious inquirer may refer to the 8th Vol. of the Asiatic Researches where Mr. Bentley reduces its age, maintained by Monsieur Bailly to date back to the commencement of the Kali Yug, 3102 B.C.—to within a few hundred years, and fixes the date of the *Suraj-Siddhānt*—the most ancient astronomical treatise of the Hindus and professed to have been inspired by divine revelation 2,164,899 years ago,—to 1038 of our era. Mr. Bentley is in turn learnedly answered by a writer in the *Edinburgh Review* for July 1807. Sir W. Jones' essay on the Chronology of the Hindus may be read in conjunction with the preceding papers, v. Alb. India, Chap. XIV, where the names of the *Siddhānts* and their sources are differently given.

Among all nations the Nychthemeron¹⁵ is the measure of time and this in two aspects, *firstly*, Natural, as in Turān and the West, from noon to noon, or as in China and Chinese Tartary¹⁶ from midnight to midnight; but the reckoning from sunset to sunset more universally prevails. According to the Hindu sages, in Jagmot¹⁷—the eastern extremity of the globe, they reckon it from sunrise to sunrise; in Rumak—the extreme west, from sunset to sunset; in Ceylon, the extreme south, from midnight to midnight and the same computation obtains in Delhi: in Siddhapur, the extreme north, from noon to noon. *Secondly*, the Equated also called Artificial, which consists of a complete revolution of the celestial sphere measured by the sun's course in the ecliptic. For facility of calculation, they take the whole period of the sun's revolution and divide equally the days thereof and consider the fractional remainder as the mean of each day, but as the duration of the revolutions is found to vary, a difference *between the natural and artificial day* arises. The tables of Al-Battāni assume it as 59 minutes, 8 seconds, 8 thirds, 46 fourths, 56 fifths and 14 sixths. Those of Elkhāni make the minutes and seconds the same, but have 19 thirds, 44 fourths, 10 fifths and 37 sixths. The recent Gurgāni tables agree with the Khwājah¹⁸ up to the thirds, but give 37 fourths, and 43 fifths. Ptolemy in the *Almagest* accords in minutes and seconds, but sets down 17 thirds, 13 fourths, 12 fifths and 31 sixths. In the same way ancient tables record discrepancies, which doubtless arise from varying knowledge and difference of instruments. The cycle of the year and the seasons depend upon the sun. From the time of his quitting one determinate point till his return to it, they reckon as one year. The period that he remains in one sign is a solar month. The

¹⁵ This term for the twenty-four hours of light and darkness was used by the later Greeks and occurs in 2 Cor. xi. 25. Its precision of meaning commends its use which Sachau has adopted.

¹⁶ Uighūr is the name of a Chaghtai tribe eponymously applied to this country, see D'Herb. Art. Igur and the observations thereon Vol. IV, p. 300.

¹⁷ Cf. Albirūni's *India*, Edit. Sachau, p. 133, Chap. XXVI. This word should be "Jamkôt." Albirūni quotes from the *Siddhānta*. The 4 cardinal points mentioned are given as the names of 4 large towns—the globe is described a spheroid, half land, half water: the mountain Mīru occupies the centre, through which the Equator (*Nalkash*) passes. The Northern half of the mountain is the abode of angelic spirits, the southern that of Daityas and Nāgs and is therefore called Daitantar. When the sun is in the meridian of Meru, it is midday at Jamkôt, midnight at Rumak and evening at Siddpūr. The latter name is spelt by Albirūni with a double d. See a map of this peculiar geographical system prefixed, to Gladwin's translation of the *Aṣṭi* and in Blochmann's text edition, following the preface.

¹⁸ Naṣīru'ddīn Ṭūsī, author of the Elkhāni tables.

interval of the moon's departure from a given position to its return thereto with the sun in conjunction or opposition or the like, is a lunar month. And since twelve lunations are nearly¹⁹ equal to one *annual* revolution of the sun, they are called a lunar year. Thus both the year and the month are solar and lunar : and each of these two is Natural when the planetary revolutions are regarded and not the computation of days, and Equated when the computation is in days and not in the time of revolution. The Hindu sage divides the year, like the month, into four parts, allotting a particular purpose to each. Having now given a short account of the night, the day, the year and the month which form the basis of chronological notation, we herein set down somewhat of the ancient eras to complete our exposition.

A note on Islamic astronomy (compiled from the *Encyclopaedia of Islam*, i. 497-501.) For the Muslims, as for the Greeks, astronomy only aims at studying the apparent movements of the stars and giving a geometrical representation of them ; it comprises therefore what we call spherical astronomy and the "theory of the instruments". . . . The sum total of the practical knowledge necessary for determining by calculation or instruments the hours of day and night, having especially in view the fixing of the times of the five canonical prayers in the mosques, is called *'ilm al mawaqit* or science of the fixed times. In the beginning of Islam the Arabs already possessed some knowledge of practical astronomy. . . . But it was only in the 2nd century of the Hijra (=8th century A.D.) that the scientific study of astronomy was entered on, under the influence of two Indian books : the *Brahma-sphuta-Siddhānta* of Brahmagupta (628) which was brought to the Court at Baghdad in 771 and was used as a model in Arabic by Ibrahim b. Habib al Fazari and Yaqub b. Tariq ; and the treatise of Aryabhatta composed in 500, from which Abul-Hasan al Ahwazi derived his tables of the planetary movements. . . .

To these selections from Indian books there was soon added the Arabic translation of the Pahlavi tables entitled *Zik-i-shatroayar* ("royal astronomical tables") compiled in

¹⁹ A synodical month, the interval between two conjunctions of the sun and moon, is 29 d. 12 h. 44 m. It was founded on the most obvious determination of the moon's course and furnished the original month of the Greeks, which was taken in round numbers at 30 days. By combining the course of the sun with that of the moon, the tropical year was assumed at a rough computation to consist of 12 unations or 360 days. See *Astron. of the Ancients* by Lewis, p. 16.

the last period of the Sassanian empire; but about the 11th century A.D. they ceased to be used.

The Greek influence was the last in order of time, but first in order of importance. It introduced into Muslim astronomy the geometrical representation of the celestial movement. The first (and unsatisfactory) Arabic translation of the *Almagest* dates from about 800 A.D.; it was followed by two other versions much superior (in 828 and c. 850.) Translations of other Greek works on astronomy, esp. Tables were made later in large numbers.

(The author of the above account, Signior C. A. Nallino, has treated the subject much more fully in Hastings's *Encyclopædia of Religion and Ethics*, xii. 94-101, under "Sun Moon and Stars".

—[J. Sarkar.]

ERA OF THE HINDUS

The creation of Brahmā is taken as its commencement and each of his days is an epoch. They assert that when 70 *kalps* are completed, each consisting of 4 Yugs²⁰ and the total of these being 4,320,000 years, a Manu appears. He is the offspring of the volition of Brahma and his co-operator in the creation. In each of his days fourteen *successive* Manus arise. At this time which is the beginning of the 51st year of the age of Brahma, there have been six Manus, and of the seventh, 27 *kalps* have elapsed, and three Yugs of the 28th, and of the fourth Yug, 4,700 years. In the beginning of the present Yug, Rājā Judhishtira conquered the universe and being at the completion of an epoch, constituted his own reign an era and since that time to the present which is the fortieth of the Divine era, 4,696 years have elapsed. It continued in observance 3,044 years. After him Bikramājīt²¹ reckoned from his own accession to

²⁰ I.e., the Satya or Krita, Tretā, Dwāpar and Kali; the first comprises 1,728,000 years; the second, 1,296,000, the third, 864,000, the fourth, 432,000—being a total of 4,320,000. For Hindu Cosmogony and Cosmology, Hastings's *Encyclo. of Religion*, iv. 155-161 (H. Jacobi) and Hindu Calendar, *ibid.*, v. 870 (Hopkins.) The best and most detailed practical table is Swami-Kannu Pillai's *Indian Ephemeris*, 7vols. (1922), which supersedes all earlier and smaller works, but it covers only 700—1999 A.D. [J. Sarkar.]

The first is Svayambhuva (as sprung from Svayam-bhu, the self-existent,) the author of the famous Code: the next five are Svarochesha, Uttama, Tāmasa, Raivata, Chakshusha; the seventh is called Vairasvata, or the Sun-born and is the Manu of the present period,—conjectured to be Noah, as the first is thought to be Adam.—Prinsep's *Useful Tables*.

²¹ This era to which the luni-solar system is exclusively adapted is called Sanvat, Vulg. Sambat. It began when 3044 years of the *Kali Yug* had elapsed, i.e., 57 years before Christ, so that if any year, say 4925 of the *Kali*

the throne and thus in some measure gave relief to mankind. He reigned 135 years. In this year 1652 years have since then gone by. They relate that a youth named Śālbāhan,²² was victorious through some supernatural agency and took the Rājā prisoner on the field of battle. Since the captive was not deserving of death, he treated him with consideration and asked him if he had any request to make. He replied that though all his desire was centred in retirement from the world and in the worship of the one Supreme Creator, he still retained the wish that his era might not be obliterated from the records of the age. It is said that the boon was granted, and although he introduced his own era, he did not interfere with the observance of the other. Since this era, 1517 years have expired, and they believe that it will continue in use for 18,000 years more, after which Raja Bijyābhinandan will institute a new era from his own reign which will last 10,000 years. Then Nāgā Arjun will come to the throne and promulgate another era which will continue for 400,000 years, after which Kalki,²³ whom they regard as an *avatar*, will establish a fresh era to last 821 years. These six are considered the principal eras and are called Saka, for there were many epochs and each termed "Sanpat."²⁴ After the invasion of Śālbāhan, the era of Bikramājīit was changed from "Sāka" to "Sanpat." After the expiration of these six, the Sat²⁵ Yug will re-commence and a new epoch be instituted.

The Hindu astronomers regard the months and years as of four kinds—1st, "Saurmās," which is the sun's continuance in one sign of the Zodiac, and such a year consists

Yug be proposed and the last expired year of Vikramaditya be required, subtract 3044 therefrom and the result, 1881, is the year sought. To convert Samvat into Christian years, subtract, 57; unless they are less than 58 in which case deduct the amount from 58 and the result will be the date B.C. This era is in general use throughout Hindustan properly so called.—*Useful Tables*, Part II, p. 26.

²² Śālivāhan, a mythological prince of Deccan who opposed Vikramāditya raja of Ujjain. His capital was Pratiśthāna on the Godaverī. The Sākā era, dates from his birth and commences on the 1st Bysākh, 3179. K. Y. which fell on Monday, 14th March, 78 A.D. Julian style.—*Ibid.* p. 22.

²³ Vishnu, in his future capacity of destroyer of the wicked and liberator of the world. This is to constitute the tenth and last *avatār* and is to take place at the end of the four *yugs*. He is to re-appear as a Brahman, in the town of Sambhal, in the family of Vishnu Sarmā.

²⁴ Properly 'Sanwat.' Sākā signifies an era or epoch and is generally applied to that of Śālivāhan.

²⁵ The text is here in error. The full stop after *āst* nullifies the sense. It should be omitted together with the *alif* of *āst*. The sentence is then complete and the meaning obvious and consistent. *Sat* is the ordinary Persian transliteration of the Sanskrit *satya*.

of 365 days, 15 *gharis*,²¹ 30 *pals*, and $22\frac{1}{2}$ *bipals*; 2nd, "Chāndramās," which is computed from the first day of the moon's increase to the night of the new moon. This year is of 354 days, 22 *gharis*²² and one '*pal*.' The beginning of the year is reckoned from the entry of the sun into Aries. This month consists of 30 lunar days (*tithi*). Each twelve degrees of the moon's course, reckoning from its departure from conjunction²³ with the sun is a *tithi*: and from the slowness or speed of the moon's progress there is a difference in the number of *gharis* from a maximum of 65 to a minimum of 54. The first, *tithi* is called *Pariwā*; the second *Duj*; the third *Tij*; the fourth *Chauth*; the fifth *Panchamin*; the sixth *Chhath*; the seventh *Saptamin*; the eighth *Ashtamin*; the ninth *Naumin*; the tenth *Dasmin*; the eleventh *Ekādasi*; the twelfth *Duādasi*; the thirteenth *Tirudasi*; the fourteenth *Chaudas*; the fifteenth *Puranmāsi*; and from the 16th to the 29th, they use the same names up to the 14th. The 30th is called *Āmāwas*. From *Pariwā* the 1st to the 15th they call *Shukla-pachch*, and the other half *Kishna-pachch*. Some begin the month from the 1st of *Kishna-pachch*. In their ephemerides generally the year is solar and the month lunar.

And since the lunar year is less than the solar by ten days, 53 *gharis* 29 *pals* and $22\frac{1}{2}$ *bipals*, on the calculation of a mean rate of motion of the sun and moon, the difference, after 2 years, 8 months, 15 days and 3 *gharis*, would amount to one month, and according to the reckoning in the ephemeris would occur in not more than 3 years or in less than 2 years and one month. According to the first calculation, there is this difference in every twelve months and in such a year they reckon one month twice: according to the latter system, in every solar month when there are two conjunctions,²⁴ and this must necessarily occur between

²¹ A *ghari* is 24 minutes, a *pal* 24 seconds, a *bipal*, a second. This would give 6 hours, 12 minutes and $22\frac{1}{2}$ seconds, whereas according to our calculation, it should be 5 hours, 48 m. 47 $\frac{1}{2}$ s. very nearly.

²² This minus the *pal* is our calculation exactly.

²³ The year commences at the true instant of conjunction with the sun and moon, that is on the new moon which immediately precedes the beginning of the solar year, falling, somewhere within the 30 or 31 days of the solar month *Chaitra*. The day of conjunction (*amāvasyā*) is the last day of the expired month; the first of the new month being the day after conjunction. The *tithis* are computed according to *apparent* time, yet registered in *civil* time. For the comprehension of this perplexing notation I refer the reader to the *Useful Tables*, Part II, p. 24.

²⁴ When two new moons fall within one solar month, the name of the corresponding lunar month is repeated, the year being then intercalary or

Chait and Kuār (*āsvin*) and does not go beyond these seven months. They term this *intercalary* month *Ādhik* (*added*), vulgarly called *Laund*.

The third kind of month is *Sāwan Mās*. They fix its commencement at any day they please : it is completed in thirty days. The year is 360 days.

The fourth, *Nachhattar*, is reckoned from the time the moon quits any mansion to her return thereto. This month consists of 27 days and the year of 324.

The number of the seasons is, with them, six³⁰ and each they call *Ritu*. The period that the sun remains in Pisces and Aries, they term *Basant* : this is the temperate season : when in Taurus and Gemini, *Girckham*, the hot season ; in Cancer and Leo, *Barkha*, the rainy season ; in Virgo and Libra, *Sard*, the close of the rainy season and the beginning of winter ; in Scorpio and Sagittarius, *Hemant*, winter ; in Capricornus and Aquarius, *Shishra*, the season between winter and spring.

They divide the year likewise into three parts : to each they give the name of *Kāl*, beginning from *Phāgun*. They call the four hot months *Dhupkāl* ; the four rainy months *Barkhakāl* and the four cold months *Sitkāl*. Throughout the cultivable area of Hindustan, there are but three seasons. Pisces, Aries, Taurus and Gemini are the summer ; Cancer, Leo, Virgo, Libra, the rains ; Scorpio, Sagittarius, Capricornus and Aquarius, the winter. The solar year they divide into two parts. The first beginning with Aries to the extreme of Virgo they term *Uttargol*, which is the sun's progress to the north of the Equator, and from the beginning of Libra to the extreme of Pisces, *Dakkhangol*, the sun's course to the south of the Equator. Also from the first of Capricorn to the end of Gemini, they call *Uttarāyan*, the sun's northern declination (the summer solstice) : and from the 1st of Cancer to the end of Sagittarius *Dachchhanāyan*, or the sun's southern declination (the winter solstice). Many events, occurring in the first of these divisions, especially death, are deemed fortunate.

The *Nycthemeron* they divide into 60 equal parts and to each they give the name of *ghatis*, more commonly *ghari*. Each *ghari* is subdivided into the same number of parts,

containing 13 months. The two months of the same name are distinguished by the terms *adhika* (added) and *nija* (proper or ordinary). *U. T.* p. 23.

³⁰ Of two sidereal months each, the succession of which is always the same : but the vicissitudes of climate in them will depend upon the position of the equinoctial colure.—*U. T.* II, 18.

each of which they call *pal*. In the same way they apportion the *pal*, and each part they term *nāri* and also *bīpal*. Each *nāri* is equal to six respirations of a man of an equable temperament, undisturbed by running, the emotions of anger and the like.

A man in good health respires 360 times in the space of one *ghari*, and 21,600 times in a Nycthemeron. Some affirm that the breath which is respired, they term *Swās* and that which is inspired *Parswās*, and both together they called a *parān*. Six *parāns* make a *pal*, and 60 *pals* a *ghari*. An astronomical hour which is the 24th part of a Nycthemeron is equal to $2\frac{1}{2}$ *gharis*. Each night and each day is again divided into 4 parts, each of which is called a *pahr*, but these are not all equal.

The Khatāi era.

They reckon from the creation of the world, which in their belief took place 8,884 *Wans* and 60 years previous to the present date. Each *Wan* is 10,000 years. They believe that the duration of the world will be 300,000 *Wans*—according to some 360,000. They employ the natural solar year and the natural lunar month. They begin the year from the sun's mid passage through Aquarius. Muhiuddin³¹ Maghrebi places it at the 16th degree, others between the 16th and 18th. They divide the Nycthemeron into 12 *Chāghs*. Each of which is subdivided into 8 *Kehs*, and to every one of these they give a different name.

They divide the Nycthemeron also into *Feneks*. For this computation of time they have three cycles, viz.; *Shāng Wan*, *Jung Wan*, and *Khā Wan*, each comprising 60 years and each year of the cycle is defined by a double³²

³¹ He was a distinguished philosopher and mathematician in the service of the Sultan of Aleppo. Surnamed al Mughrebi from his having been educated in Spain and Africa, associated in A. H. 658 with Nasir-u'ddin Tusi in the superintendence of the observatory at Murāgha, and shared in the composition of the Elkhāni tables. D'Herbelot. See D'Herb. (Vol. IV. p. 42.) on this nomenclature and his tables of the cycles. For Chinese era, Hastings' *Ency.*, iii. 82.

³² The word *badu* may also grammatically but in point of fact less accurately apply to the cycle. The following explanation taken from the *Useful Tables* (Part II. p. 14-15 under 'Chinese era'), will elucidate the text. They have two series of words, one of ten and the other of twelve words; a combination of the first words in both orders is the name of the 1st year; the next in each series are taken for the 2nd year, and so to the 10th; in the 11th, the series of 10 being exhausted, they begin again with the first combining it with the eleventh of the second series; in the 12th year, the second word of the first series is combined with the twelfth of the second;

notation. The revolution of the cycle is marked by a series of ten and a series of twelve *symbols*. The first is employed for the notation of the year and the day; the second is similarly applied and is likewise horary. By the combination of these two series, they form the cycle of 60 and work out detailed calculations.

The Turkish Era.

Called also the Uighuri. It is similar to the foregoing, except that this cycle is based on the series of 12. They reckon their years and days after the same manner, but it is said that some astronomical tables also employ the series of 10. The commencement of their era is unknown. Abu Raihān (Albiruni) says³³ that the Turks add nine to the incomplete Syromacedonian years and divide it by 12: and in whatever animal the remainder terminates, counting from the Sign of the Mouse, the year is named therefrom. But weighed in the balance of experiment, this is found wanting by one year. The intention, undoubtedly, is to carry the remainder down the animal signs of the series,

for the 13th year, the third word of the first list with the first of the second list is taken, that list also being now exhausted. Thus designating the series of 10 by Roman letters, and that of 12 by italics, the cycle of 60 will stand thus.

1 a a	21 a i	41 a e
2 b b	22 b k	42 b f
3 c c	23 c l	43 c g
4 d d	24 d m	44 d h
5 e e	25 e a	45 e i
6 f f	26 f b	46 f k
7 g g	27 g c	47 g l
8 h h	28 h d	48 h m
9 i i	29 i e	49 i a
10 k k	30 k f	50 k b
11 a l	31 a g	51 a c
12 b m	32 b h	52 b d
13 c a	33 c i	53 c e
14 d b	34 d k	54 d f
15 e c	35 e l	55 e g
16 f d	36 f m	56 f h
17 g e	37 g a	57 g i
18 h f	38 h b	58 h k
19 i g	39 i c	59 i l
20 k h	40 k d	60 k m

The first cycle, according to the Jesuits, began in February 2397 B.C.; we are now, therefore, in the 72nd cycle, the 28th of which will begin in 1890. To find the Chinese time, multiply the elapsed cycle by 60, and add the odd years: then if the time be before Christ, subtract the sum from 2398; but after Christ, subtract 2397 from it; the remainder will be the year required.

³³ This reference I have not been able to trace in Albiruni's *Athār ul Baqiya*, or his *India*. [Jarrett] The Turkish era has fallen into disuse, but the names of the Cyclic years as borrowed in Indo-China, Champa and Japan, are given in Hastings, *Encycl.*, iii. 110-115. [J. S.]

and beginning from the Mouse, to adopt the name of the animal in which it terminates. Although the commencement of the era is unknown, yet we gather sufficient information regarding the year of the cycle and its name. And if 7 years be added to the imperfect years of the Maliki era, dividing by 12, whatever remains is the year of the animal reckoning from the Mouse. This will prove correct according³⁴ to the following series.

Names of the twelve years of the Cycle.

1. *Sijqān*, the Mouse. 2. *Ud*, the Ox. 3. *Pārs*, the Leopard. 4. *Tawishqān*, the Hare. 5. *Loiy*, the Dragon, 6. *Y'ilān*, the Serpent. 7. *Yunt*, the Horse. 8. *Qu*, the Sheep. 9. *Bij*, the Ape. 10. *Takhāku*, the Cock. 11. *Yit*, the Dog. 12. *Tankuš*, the Hog. They add the word *el* to each of these words, which signifies year.

The Astrological Era.

The astrologers reckon from the Creation and assert that all the planets were then in Aries. The year is solar. According to their calculation, from that time to the present 184,696 years have elapsed.

The Era of Adam.

Its beginning dates from his birth. The years are solar, the months lunar. According to the Elkhāni tables, 5,353 solar years have elapsed to the present date. But some of those possessing a book of divine revelation make it 6,346 solar years; others 6,938 solar: others again, 6,920, solar, but according to what has been reported from learned Christians, it is 6,793.

The Jewish Era.

Begins with the creation of Adam. Their years are natural, solar: their months, artificial, lunar. They reckon their months and days like the Arabians according to an intermediate system. The years is of two kinds, *viz.*, Simple, which is not intercalary, and Composite, in which

³⁴ These 12 signs of the Zodiac exactly correspond with the animals in the series of the Japanese Cycle given in the *Useful Tables*, but the vernacular names are different. The calculations based on them are vaguely stated: in Albiruni's *Chronology*, some information may be obtained from the Rules for the reduction of Eras.

an intercalation is effected. Like the Hindus they intercalate a month every three years.³⁵

The Era of the Deluge.

This era is computed from this event; the year is natural, solar, the month natural, lunar. The year begins from the entry of the Sun into Aries. Abu Ma'shar of Balkh based his calculations regarding the mean places of the stars on this era from which to the present year 4,696 years have elapsed.

The Era of Bukht Nassar (Nebuchadnezzar).

This monarch instituted an era from the beginning of his own reign. The year is solar, artificial, of 365 days without a fraction. The month, likewise, is of 30 days and five days are added at the end of the year. Ptolemy in his *Almagest* computed the planetary motions on this era. Since its commencement 2,341 years have elapsed.

The Era of Philipus (Arrhidæus).³⁶

Called also Filbus or Filqus. It is also known as the Era of Alexander of Macedon. It dates from his death. The years and months are artificial, solar. Theon of Alexandria has based his calculations of the mean places of the stars in his *Canon* on this Era, and Ptolemy has recorded some of his observations regarding it, in the *Almagest*. Of this period, 1,917 years have elapsed.

The Coptic Era.³⁷

This is of ancient date. Al Battāni states that its years are solar, artificial, consisting of 365 days without a fraction. The Sultāni tables say that its years and months

³⁵ Or 7 months in 19 lunar years. Cf. Albiruni's *Chronology*, p. 13. For the Jewish era, Hastings's *Encyclo.* iii. 117-123, after which Prinsep's *Useful Tab.* ii. 8 is unnecessary. For the era of Nebuchadnezzar, *Encyclo. of Islam*, under Bukht-Nassar (i. 784) and under Tarikh (Suppl. 231.) The Arabs have confounded Nabonassar with Nebuchadnezzar (though 143 years separate the two.) Ptolemy makes this era begin in 742 B.C. For calculating dates in this system, see Prinsep's *Useful Tab.* ii. 9. [J. S.]

³⁶ He was half brother of Alexander the Great, the son of Philip and a female dancer, Philinna of Larissa. Prinsep's *U. T.* ii. 10. *Enc. Islam*, Suppl. 231, this era began on 12 Nov. 324 B.C.

³⁷ This is the era of Diocletian or the Martyrs; was much used by the Christian writers till the introduction of the Christian era in the 6th century, and is still employed by the Abyssinians and Copts. It dates from 29th August, 284. Prinsep, ii. 7. *Ency. Isl.* iv. 1211.

resemble the Syro-Macedonian. It has the same intercalations, but the Coptic intercalary days precede those of the Syro-Macedonian by six months.

The Syro-Macedonian Era.

The years and months are artificial, solar, and they reckon the year at $365\frac{1}{4}$ days exactly. In some astronomical observations, the fraction in excess is less than $\frac{1}{4}$. According to Ptolemy, it is 14 m. 48 s. The Elkhāni observations make the minutes the same, but 32 seconds and 30 thirds. According to the calculations of the Cathayans the minutes are the same, and 36 seconds, 57 thirds; to the recent Gurgāni observations, the minutes agree, with 33 seconds; the Maghrebi has 12 m.: the Battāni, 13 m. 36 s. Muhiyuddin Maghrebi says that some of the Syro-Macedonian calculations make the fraction more than a quarter, others less than a quarter, and thus a quarter has been taken as the medium. Others assert that the Syro-Macedonians have by observation determined the fraction to be a full $\frac{1}{4}$. Consequently it is a natural solar year, although Mulla 'Ali Kushji makes it a solar year even on the first mentioned basis. This era dates from the death of Alexander the second, [corr. IV] *Bicornutus*, but was not employed till 12 years after his death. Others assert that he established it in the 7th year of his reign when he set out from Macedonia, his kingdom, bent on foreign conquest. Muhiyuddin Mughrebi on the other hand, states that it began with the reign of Seleucus (*Nicator*) who founded Antioch. This era was in use both with the Jews and Syrians. They relate that when Alexander the son of Philip marched from Greece to the conquest of Persia, he passed through Jerusalem. Summoning the learned Jews of Syria he directed them to discontinue the Mosaical era and to employ his own. They thus answered him. "Our forefathers never observed any era above a thousand years and this year our Era will complete the thousand; from next year, therefore, thy command shall be obeyed." And they acted accordingly. And this took place in Alexander's 27th year. Some maintain that this Grecian era is of Hebrew origin. Kushyar in his *Jāmi'* says that there is no difference between the Syro-Macedonian and the Syrian era, except in the names of the months. The Syrian year begins on the 1st day of Tishrin

ul Awwal. This happened formerly when the sun was in the 4th degree of Libra, and now falls on the 11th.³⁸ With the Syro-Macedonians, that date is the 1st of Qanuni i Sāni, when the sun is near the 20th degree of Capricorn. Battāni mentions this era³⁹ as beginning with Philip, father of Alexander Bicornutus, but that he called it after his son to exalt his fame; and he has based on it the calculation of the mean places of the planets in his Canon. Of this era 1905 years have elapsed.

The Augustan Era.

He was the first of the Roman Emperors. The birth of Jesus Christ happened in his reign. The era begins with his accession. The year is the same as the Syro-Macedonian, and the months are Coptic; the last month in the common years has 35 days and in leap years 36. Of this era 1623 years have elapsed.⁴⁰

The Christian Era.

Begins with the birth of Jesus Christ. The year consists, like the Syro-Macedonian, of 365 d. 5 h. At the end of 4 years, they add a day to the end of the second month. The beginning of their Nycthemeron is reckoned from midnight. Like the Arabians, they name the days of the week, beginning with Sunday. The commencement of their year, some take to be the entry of the sun in Capricorn: others, from the 8th degree of the same.

The Era of Antoninus of Rome.

It begins with his accession [138 A.D.]. The years are Syro-Macedonian, the months Coptic. Ptolemy deter-

³⁸ Another reading is 15th. Gladwin has 16th. Better known as the Seleucid era, began on 1 Oct. 312 B.C. (acc. to Ginzel.) *Ency. Islam*, Supp. 231; also iv. 1211.

³⁹ There is a discrepancy among chronologers as to the commencement of this era. Some determine it to the 1st October 312 B.C. (W. Smith, *Cl. Dic.* art Seleuc); the *U. T.* (ii. 11) places it, 311 y. 4 m. B.C. The Syrian Greeks began their years in September, other Syrians in October: the Jews, about the autumnal equinox. It is used in the book of Maccabees and appears to have begun in Nisan. Supposing it to begin on 1st September 312 B.C.; to reduce it to our era, subtract 311 y. 4 m.

⁴⁰ The Spanish era of the Caesars is reckoned from 1st January, 38 B.C., being the year following the conquest of Spain by Augustus. It was much used in Africa, Spain, and the south of France. By a Synod held in 1180, its use was abolished in all the churches dependent on Barcelona. Pedro IV of Arragon abolished it in 1350. John of Castile in 1382. It continued to be used in Portugal till 1455.—*U. T.*, ii. 11. But *Enc. Islam*, Supp. 231, differs; "its epoch 14 Feb. 27 B.C.",

mined the position of the fixed stars in his *Almagest* on this era of which 1,457 years have elapsed.

The Era of Diocletian⁴¹ of Rome.

He was a Christian emperor. The era begins with his accession. The years are Syro-Macedonian, the months Coptic; 1,010 years have since elapsed.

The Era of the Hijra.

In pre-Islamic times, the Arabs had various eras, such as the building of the Ka'bah, and the sovereignty of Omar⁴² b. Rabi' a to whom was due the rise of idolatry in Hijāz, and this continued in use till the year of the Elephant,⁴³ which they, in turn, observed as a fresh epoch. Every Arab tribe constituted any important event in their history, an era. In the time of the prophet this thread of custom had no coherence, but from the date of the Hijra, they gave each year a special name. Thus that year was called the "year of Permission," that is, the permission to go from Mecca to Medina. The second year was named the "year of Command," i.e., to fight the unbelievers.⁴⁴

⁴¹ The name in the text is Diocletian. Abul Fazl evidently meant Constantine, but probably following the text of Albiruni, (*Chronol*) he copied the heading of the Era of Diocletian, without noticing in the body of the passage, the change of name to Constantine, as the 1st Christian Emperor. The number 1010 is an error. Gladwin has 1410. If Abul Fazl counts from the era of Diocletian A.D. 284, the intermediate years would be about 1310; if from A.D. 324, the date of Constantine's sole mastership of the empire 1270, if from his proclamation as Emperor by the legions in 306, the number would be 1290. His father Constantius was proclaimed Caesar by Diocletian in A.D. 292.

⁴² An error (taken from Albiruni) for 'Amr-b-Lohayy, born about 167 A.D., was king of Hijaz; for his genealogy see *Ency. Isl.* i. 336, and Caus. de Perc. *Essai Sur l'hist. Arab.* Tabl. II, VIII. The great tribe of Khuzaa'h trace their descent from him. Whilst at Balkā in Syria, he had seen its inhabitants practising idolatry; their idols, they averred, protected and favoured them, granting rain at their prayers. At his request they presented him with the idol, Hobal, which he set up in Mecca and introduced its worship.

⁴³ 570 A.D. the year in which Mahomed was born, and the name of which commemorates the defeat of Abrahā, the Ethiopian king of Yaman. *Qurān*, Sura 105.

⁴⁴ The 3rd year was called, the year of the trial.

4th	"	"	"	year of Congratulation on the occasion of marriage.
5th	"	"	"	year of the earthquake.
6th	"	"	"	year of inquiring.
7th	"	"	"	year of victory.
8th	"	"	"	year of equality.
9th	"	"	"	year of exception.
10th	"	"	"	year of farewell.

Chronol. Albiruni, Sachau, p. 35.

At the accession of the second Caliph (Omar), Abu Musa Asha'ri,⁴⁵ governor of Yaman made the following representation: "Your despatches have arrived dated the month of Shabān. I cannot discover what date is understood by Shabān." The Caliph summoned the learned. Some of the Jews advised the use of their era. The sage Hurmuzān⁴⁶ said; "the Persians have a computation which they call Māhroz" and this he explained. But as there were intercalations in both, their skill in calculation was slight, he did not accept either but adopted the era of the Hijrah. The month according to their system is reckoned from the sight of one new moon, after the sun has completely set; till the next is visible. It is never more than 30 nor less than 29 days. It sometimes occurs that four successive months are of 30 days, and three of 29. Chronologers putting aside calculations based on the moon's appearance, reckon lunar months in two ways, viz., Natural, which is the interval of the moon's departure from a determinate position, with the sun in conjunction or opposition or the like to its return thereto; 2ndly, Artificial; since the motions of the moon are inconstant and their methodisation as well as an exact discrimination of its phases difficult, its mean rate of motion is taken and thus the task is facilitated. In the recent (*Gurgāni*) tables, this is 29 days, 12 hours and 44 minutes.⁴⁷ The rule is this, that when the fraction is in excess of half, it is reckoned as one day. Thus when the excess is over a half, they take the month of Muharram as 30 days, and the second month 29, and so on alternately to the last. In common years, therefore, Dhil Hijjah is 29 days. The mean lunar year consists of 354 d. 8 h. 48 m.⁴⁸ which is less than a solar artificial year by

⁴⁵ Abu Musa Al Asha'ri was one of the Companions, a native of Kufah. He joined the prophet at Mecca and was a convert before the Flight to Medina. He was also one of the fugitives to Abyssinia and including his journey from Yaman to Mecca, shared in the unusual distinction of three flights. *Ency. Islam*, I. 481.

⁴⁶ Hurmuzan was a learned Persian, taken prisoner by Abu Musa and sent to the Caliph Omar by whom his life was spared, though the grace was obtained with some difficulty. He subsequently became a convert. *Ency. Islam*, ii. 333. Nawawi, *Tahzib-ul-Asmā*.

⁴⁷ This is a lunation or synodical month, the interval between two conjunctions of the Sun and Moon. The periodical month, as distinguished from this, is the time taken in transit by the moon from any point of the Zodiac back to the same point: it consists of 27 d. 7 h. 43 m. Hence a lunar month is sometimes taken in round numbers at 28 d. and this is the length of a lunar month according to the law of England. Lewis. *Astr. of the Anc.* p. 20.

⁴⁸ And 36 seconds. *Ibid*.

10 d. 21 h. 12 m. Mirza Ulugh Beg has based his new Canon on this era of which 1002 years have elapsed to the present time.

The Era of Yazdajird.

He was the son of Shahryār Aparwez⁴⁹ b. Hurmuz b. Noshirwān. It began with the accession of Jamshid. After him every succeeding monarch renewed his designation by his own accession and Yazdajird also re-instituted it from his assumption of sovereignty.⁵⁰ The years are like the Syro-Macedonian; but the fraction in excess was reserved till at the end of 120 years, it amounted to a whole month, and that year was reckoned at 13 months. The first intercalation was after *Farwardin*, and it was called by the name of that month. Then *Urdibihisht* was twice counted and so on. When the era was renewed under the name of Yazdajird, and his authority terminated in disaster, the continuity of intercalation was neglected. The years and months are artificial, solar. 963 years have since elapsed.⁵¹

Note on the Hijera era. "The question on what day the 1st Muharram of the year 1 A.H. fell is not yet decided." (Discussion of different theories; *Encyclopædia of Islam*, Suppl. 231).

"Authorities are not agreed on the exact date of the Hidjra. According to the most usual account, it took place on the 8th Rabi' I (20th Sept. 622 A.D.). But this would not be the date of the departure from Mecca but of the arrival in Medina. According to other versions, it was the 2nd or the 12th Rabi' I The 8th was preferred as it was a Monday. According to a tradition, the Prophet is said to have answered when asked why he observed Monday especially, 'on this day I was born, on this day I received my prophetic mission, and on this day I migrated'. The fixing of the Hidjra as the beginning of the Muhammadan era dates from the Caliph 'Omar. The traditions which try

⁴⁹ In Albiruni, Shahryār-b-Parwez. Parwez or Aparwez signifies Victorious. Era of Yazdajird, *Ency. Islam*, Supp. 232, also Prinsep's *Useful T.* ii. 12. *Ency. Islam*, iv. 178, gives Yazdigird III. (r. 632-651 A.D.) after Ardashir III. (r. 628-630), with "several ephemeral rulers" between them. J. S.

⁵⁰ A.D. 632.

⁵¹ "In Persia, since the age of Zoroaster, the revolution of the sun has been known and celebrated as an annual festival, but after the fall of the Magian empire, the intercalation had been neglected: the fractions of minutes and hours were multiplied into days, and the date of the spring was removed from the sign of Aries to that of Pisces." Gibbon. *Decl. and Fall*, Vol. X. p. 367, Rd. 1797.

to trace it to the Prophet himself are devoid of all probability." (*Ency. Islam*, ii. 302).

In *Ency. Islam*, iv. 1210 (under *Zamān*), there is a full discussion of the calendar adopted by the Muslims.

"Although the era of Islam begins with the 15th (16th) of July, 622 A.D., the lunar year, peculiar to the Muslims, was not established till the year A.H. 10. When Muhammad in that year (A.D. 631) made his last pilgrimage to Mecca, . . . he arranged . . . that the year should consist of 12 lunar months of 29, (28, 30) days each, and that intercalation (*nasi'*) was to be forbidden (*Quran*, ix. 36 ff.) . . . The Meccans had had a more or less perfect solar year (before this, as) the names of the months in part indicate clearly certain definite seasons of the year—a situation, in the case of a changeable lunar year, evidently out of the question. . . . The Arabs adopted the week of the Jews and Christians." (K. Vollers in Hastings's *Encyclopædia of Religion*, iii. 126-127).—*J. Sarkar*.

The Maliki Era.

It is also called Jalāli. The Persian Era was used at that period. Through the interruption of continuity in intercalation, the commencements of the years fell into confusion. At the instance of Sultān Jalāluddīn⁵² Malik Shāh Saljuki, Omar Khayyam and several other learned men instituted this era. The beginning of the year was determined from the sun's entry into Aries. The years and months were *at first* Natural, but now the month is the ordinary Artificial. Each month consists of 30 days and at the end of *Isfandārmuz*, they add 5 or 6 days. Of this era, 516 years have elapsed.

The Khāni Era

dates from the reign of Ghāzān⁵³ Khān and is founded on the Elkhāni tables. The years and months are Natural,

⁵² A brilliant sketch of his life may be read in Gibbon, Ch. 57, and *Enc. Isl.* iii. 211. For his era *Ency. Islam*, i. 1006 (under *Djalāli*), also iv. 672 (under *Tarikh*) and iii. 888 (under *Nawruz*.) The era begins on 15 March 1079 A.D.

⁵³ Ghazan Khan, Mahmud, eldest son of Arghun, the 8th from Mangu Khan son of Jenghiz, of the Moghul Tartar or Ilkhanian Dynasty of Persia. He ascended the throne in A. H. 694 (A.D. 1294) and was succeeded by Ghiasu'ddin Au-gaptu Khuda bandah Muhammad, A. H. 703 (A. D. 1303). *U. T. P. II*, p. 146. The Ilkhani era, in *Ency. Isl. Supp.* 232. Ghāzān Kh. in *ibid.* ii. 149.

of ancient sages, the paragon of the house of wisdom, set himself to the fulfilment of this object, and taking as his base the recent Gurgāni Canon, began the era with the accession of his Imperial Majesty. The splendour of visible sublimity which had its manifestation in the lord of the universe commended itself to this chosen one, especially as it also concentrated the leadership of the world of spirituality, and for its cognition by vassals of auspicious mind, the characteristics of the divine essence were ascribed to it, and the glad tidings of its perpetual adoption proclaimed. The years and months are natural, solar, without intercalation and the Persian names of the months and days have been left unaltered. The days of the month are reckoned from 29 to 32, and the two days of the last are called *Roz o Shab* (Day and Night). The names of the months of each era are tabulated for facility of reference. [Tr.'s note. The Uighur and Coptic months are spelt differently by Albiruni from Abul Fazl. The spelling of the Jewish month names also is incorrect in the printed text of the *Ain*.]

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.
Hindu months.	Khatāi months.	The Uighur Era.	The Era of the astrologers.	The Era of Adam.	The Era of the Jews.	The Era of the Deluge.	The Era of Nabonasar.	The Era of Philipus Arrhi-dæus.	The Era of the Copts.
Chait Baisākḥ	Chanweh Zhezhehewh	Arām Ay. Ikandi Ay.	" "	" "	Tishri Marhesh-wān	" "	Thoth Bāpeh	Thoth Bāpeh	Thoth Pāopi
Jeth	Sāmweh	Ochanj Ay.	" "	" "	Kislew	" "	Hātor	Hator	Athyr
Asārḥ	Harweh	Dardanj Ay.	" "	" "	Tebeth	" "	Kahak	Kehak	Khawāk
Sānwān	Uweh	Beshanj Ay.	" "	" "	Shebāt	" "	Tubah	Tubah	Tybi
Bhādon	Luweh	Altinj Ay.	" "	" "	Adhār	" "	Amsher	Amsher	Makhir
Kunwar	Cheweh	Yetinj Ay.	" "	" "	Nisān	" "	9	Barmahāt	Phamanoth
Kātik	Bāweh	Saksanj Ay.	" "	" "	Iyār	" "	9	Barmulah	Pharmuthi
Aghān	Kheweh	Tuksanj Ay.	" "	" "	Siwān	" "	9	Bashans	Pachon
Pus	Shabweh	Onnanj Ay.	" "	" "	Tammuz	" "	9	Bonah	Payni
Māgh	Shayayweh	Onbaranj Ay.	" "	" "	Āb	" "	9	Abib	Epiphi
Phāgun	Sirweh	Haksabāt Ay.	" "	" "	Elul	" "	9	Misri	Mesori

11.	12.	13.	14.	15.	16.	17.	18.	19.	20.
Syro-Macedonian Era.	The Angustun Era.	The Christian Era.	The Era of Antoninus.	The Era of Diocletian.	Era of the Hijrah.	Era of Yazdijird.	The Maliki Era.	The Khāni Era.	The Divine Era.
Tashrinul Awwal	January				Muharram	Farwadin Māh. Old Style	Farwar-din Māh. i Jalāli	Arām Ay. Khani	Farwar-din Māh. i Ilāhi
Tashrinu'l Ākhir	February				Safar	Ardibihisht Māh. O. S.	&c.	&c.	&c.
Kānun'1 Awwal	March				Rabia' I.	Khurdād Māh. O. S.	&c.	&c. like 3	like 18,
Kānun'1 Ākhir	April				Rabia' II.	Tir Māh. O. S.	&c.	with the word "Khāni"	substi-tuting "Ilāhi"
Shebāt	May				Jumāda I.	Amurdād Māh. O. S.	like 17, with the word	after "Ay."	for "Jalāli."
Āzār	June				Jumāda II.	Sharewar Māh. O. S.	In the 4th month	In the 4th month	
Nisān	July				Rajab	Mīhr Māh. O. S.	"Jalāli" after "Mah."	the word "Tor-tanj"	
Ayyār	August				Sha'bān	Ābān Māh. O. S.		occurs, where in Col. 3, it is "Dar-danj."	
Huznrān	September				Ramadhān	Āzar Māh. O. S.			
Tamuz	October				Shawwāl	Day Māh. O. S.			
Āb	November				Dhi Ka'da	Bahman Māh. O. S.			
Aylul	December				Dhi Hijjah	Isfandārmaz Māh. O. S.			

The events of the world recorded in chronological sequence, are accounted the science of history, and he who is proficient in them, is a historian. Many writings in this branch of knowledge regarding India, Khatā, the Franks, Jews and other peoples are extinct. Of the Muhammadan sect, the first who in Hijaz occupied himself with this subject was Muhammad-b-Ishāq, then follow Wahab-b-Murabbih, Wāqidi, Asma'i, Tabari, Abu A'bdullah Muslim-b-Qutaybah, Aa'tham of Kufa, Muhammad Muqanna, Hakim A'li Miskawaih, Fakhruddin Muhammad-b-Ali, Dāud Sulaiman Binākiti, Abul Faraj, 'Imadu-ddin-b-Kathir, Muqaddasi, Abu Hanifah Dinawari, Muhammad-b-Abdullah Masa'udi, Ibn Khallākān, Yāfa'i, Abu Nasr Utbi; amongst the Persians, Firdausi Tusi, Abul Hasan Baihaqi, Abul Husain author of the *Tārikh-i-Khusrawi*, Khwājah Abul Fazl 'Baihaqi, A'bbās-b-Musa'b, Ahmad-b-Sayyār, Abu Ishāq Bazz'az, Muhammad Balkhi, Abul Qāsim Ka'bi, Abu'l Hasan Fārsi, Sādruddin Muhammad author of the *Tājul-Maāsir*, (*Corona monumentorum*), Abu Abdullah Juzjāni (author of the *Tabaqāt-i-Nāsiri*), Kabiruddin Irāqi, Abul Qāsim Kāshi, author of *Zubdah* (*Lactis flos*), Khwājah Abul Fazl, author of the *Makhzan ul Balāghat* (*Promptuarium eloquentiæ*) and *Fadhāil-ul-Muluk* (*Virtutes principum præstantes*) A'lauddin Juwaini, brother of the Khwājah Shamsuddin, author of a *Diwān*, (he wrote the *Tārikh Jahānkushā*, *Historia orbis terrarum victrix*), Hamdullah Mustaufi Qazwini, Qādhi Nidhām Baydhāwi, Khwājah Rashidi Tabib, Hāfiz Abru, and other trustworthy writers.

For a long time past, likewise, it has been the practice to record current events by a chronogram and to make the computation of years appear from a single word, a hemistich and the like, and this too they term a date; as for instance, for the accession of his Majesty, they have devised the words *Nasrat-i-Akbar* (*victoria insignis*) and *Kām Bakhsh* (*Optatis respondens*), but the ancients practised it little: thus the following was written on Avicenna,—

The Demonstration of Truth, Abu A'li Sina,
Entered in Shajā' (373) from non-existence into being.
In Shasā (391) he acquired complete knowledge.
In Takaz (427) he bade the world farewell,

BIOGRAPHICAL NOTES

"The whole of this series of authors is taken bodily and in the same order by Abul Fazl from the *Raudhat-us-Safā* without acknowledgement." (*H. S. Jarrett.*)

For convenience of printing and also of study, Jarrett's notes on the ancient authors, a bare list of whose names is given by Abul Fazl, have been here collected in one place, instead of being dispersed as separate footnotes. For more modern and detailed information consult the *Encyclopædia of Islam* under each name." (*J. Sarkar.*)

Ad.-b-Ishāq,—author of the well-known work *Al Maghāzī wa's Siyar* (expeditiones bellicæ et biographiæ); he was a native of Medina and as a traditionist held a high rank, and regarded by Al-Bukhārī and As-Shāfa'i as the first authority on the Muslim conquests. He died at Baghdad A.H. 151 (A.D. 768). It is from his work that Ibn Hishām extracted the materials for his life of the Prophet.

Wahab-b-Murabbih,—was a native of Yaman and one of the "Abnā", i.e., a descendant of one of the Persian soldiers settled there. He died at Sana'ā in Yaman A.H. 110, in Muharram (April-May A.D. 728)—(others say in 114 or 116) at the age of 90. He was a great transmitter of narrations and legends. A great part of the information given by Moslem historians regarding the pre-Islamic history of Persia, Greece, Yaman, Egypt, etc., comes from him. He was an audacious liar, as Moslem critics of a later period discovered. Ibn Khall. De. Sl. IV. p. 672-3.

Wāqidi,—Abu A'bdu'llah, Muhammad-b-Omar. Wāqid, al Wāqidi, a native of Mecca, author of the well-known "*Conquests*" of the Moslems, born A.H. 130 (Sept. A.D. 745), died on the eve of Monday 11 Zul Hijjah, A.H. 206 (27th April A.D. 823).

Asma'i,—Abu Sa'id A'bdu'l Malik-b-Kuraib al Asma'i, the celebrated philologist, a complete master of Arabic. He was a native of Basra, but removed to Baghdad in the reign of Hārūn-ar-Rashid. It is said he knew by heart 16,000 pieces of verse; born A.H. 122 (A.D. 740) and died in Safar A.H. 213 (March-April A.D. 728). *Ency. Isl.* i. 490.

Tabari,—Abu Jafar M-b-Jarir at-Tabari, author of the Great Commentary of the *Qurān* and of the celebrated history. He is regarded as an exact traditionist, born A.H.

224 (A.D. 838-9) at Amol in Tabaristān and died at Baghdad A.H. 319 (A.D. 923). *Ency. Isl.* iv. 578.

Abu Abdūllah Muslim,—(213-270 A.H.) A native of Dinawar, some say of Marw, author of the *Kitāb-ul-Ma'ārif* and *Adāb-ul-Kātib* (=the Writer's Guide): the first a work of general knowledge, from which Eichhorn extracted his genealogies of the Arabs published in his *Monumenta historię Arabum*: it contains a number of short biographical notices of the early Moslems.

Aa'tham Kufi,—Muhammad-b-A'li, known as Aa'sim Kufi; his work the *Futuh Aa'thim* (H.K.) is a short account of events from the death of the prophet to the death of Husain at Karbalā. It was translated into Persian by Ahmad-b-Mustaufi.

Md. Muqanna',—Freytag gives his name from the Scholia as Muhammad-b-Ōhmaizah. He is said to have been called Muqanna' from the veil he wore to protect the beauty of his person. He squandered his wealth in lavish gifts and in the time of the Omayyads was still living, of much account with his people, but in poverty. Not to be confounded with Abu 'Amr (afterwards Abu Md.) *Ibn al Muqaffa'* (*Ency. Islam* ii. 404), who was known as the Kātib or Secretary and was the author of some celebrated epistles, and also translated *Kalila and Damna* into Arabic.

Abu Ali Ahmad-b-Miskawaih,—a Persian of good birth and distinguished attainments. He was treasurer to Malik Adhd-ud-daulah-b-Buwaih, who placed the utmost trust in him. He was the author of several works. Abul Faraj relates (*Hist. Dynast.* p. 328) that Avicenna consulted him on a certain abstruse point; and finding him slow of intelligence and incapable of solving his difficulty, left him. His death is placed about A.H. 420.

Daud Sulaiman Binakiti,—author of the *Raudhat-ul-Albāb* (*Viridarium cordatorum*) a compendium of Persian history. He lived tempore Jinghiz Khan and wrote on the history of Khātāi kings at the request or command of Sultan Abu Said Bahādur.

Abul Faraj,—(1) 897-967 A.D., author of the great *Kitāb al Aghani*. (2) Barhebraeus, 1226-1286, author of a famous Universal History (See *Ency. Isl.* under the above two names).

Hafidh I'māduddin,—Ismail-b-A'bdu'llah ad Dimashqi died in A.H. 774 (A.D. 1372). The name of his history is

ʿAl-Bidāyah wa'l Nihāyah (*Initium et finis*) and is continued to his own time.

Muqaddasi,—There are several of this name. Shams-uddin Abdullah was the author of a geography entitled *Ahsanu'l taqasim fi Ma'rifati'l aqalim*, a description of the seven climates, died A.H. 341 (A.D. 1049, *Ency. Isl.* iii. 708); a second Husāmuddin Md. b. A'bul Wāhid author of a work on judicial decisions; died A.H. 642 (A.D. 1245); a third, probably the one alluded to, Shahābuddin Abu Mahmud as Shāfa'i author of the work *Muthirul Gharam ila' Ziāratil Quds wāl Shām* (*Liber cupidinem excitans Hierosolyma et Damascum visendi*). He died in 765 (A.D. 1363). H. K.

Abu Hanifa Ahmad-b-Dāud ad Dinawari, author of a work *Islah ul Mantiq* (*Emendatio sermonis*). He died 290 (A.D. 902) H. K.

Masāudi,—author of the *Muruj-ud-Dahāb*. (*Prata Auria*) which he composed in the reign of the Caliph Mutia' Billah and many other works. It begins with the creation of the world, and is continued through the Caliphs to his own time. He died in Cairo in 346 A.H. (A.D. 957). *Ency. Isl.* iii. 403.

Ibn Khallakan,—the famous biographer: his work the *Wafayātul Aa'yān* containing the lives of illustrious men is well-known. It was composed in Egypt under Sultān Baybars of the Mameluke dynasty. He has given a few particulars of his life at the close of this work which was finished in A.H. 672 (A.D. 1273-4). He was born in 608 (A.D. 1211) and died in 681 (A.D. 1282, *Ency. Isl.*, ii. 396).

Abdullah-b-Asa'd al Yafa'i al Yamani, died 768 A.H. (A.D. 1266). He wrote the *Mirat ul Janān wa I'brat ul Yakdhān* (*speculum cordis et exemplum vigilantis*), a historical work beginning with the Flight and continued to his own time. Another is the *Raudhatul Riahin* (*Viridarium hyacinthorum*) containing lives of Moslem saints. *Ency. Isl.*, iv. 1134.

Utbi,—author of the *Tārikh Yamini* which contains the history of the Ghaznvide Sultan Yamin ud Daulah Mahmud-b-Subuktigin of whom he was a contemporary: it is brought down to the year 427 (A.D. 1036-7).

Baihaqi,—(1) Abu Hasan' Ali-b-Zayd al Baihaqi author of the *Wishāhi Dumyatil Qasr*: a supplement to the *Dumyat ul Qasr* of al Bakharzi the poet, who died A.H. 467

(A.D. 1075), and author of work called *Tārikhi Baihaq*. *Ency. Isl.*, i. 592.

Baihaqi,—(2) Abul Fazl Md. b. Husain, author of a history of the Ghaznavids in more than 30 vols., of which only five volumes covering the reign of Masa'ud b. Mahmud has been preserved. *Ency. Islam*, i. 592-593.

Abul Husain,—Muhammad-b-Sulaiman Al Asha'ri; the *Tārikh Khusrawi*, is a history of the Persian kings.

Abbas b. Musa'b,—author of the *Tārikh Khorāsān*.

Ahmad-b-Sayyār-b-Ayyub,—the Hāfidh, Abul Hasan al Marwazi, a traditionist of great repute and accuracy. Died A.H. 268, A.D. 881. *Abul Mahasin* V. II. p. 45.

Abu Ishaq-Muhammad-b-al Bazzāz was the author of a history of Herat.

Muhammad-b-Akil al Balkhi-d—A.H. 316 (A.D. 928). (*Abul Mahasin* II. p. 235) author of a history of Balkh. H. K.

Abu'l Qāsim Ali-b-Mahmud, author of a history of Balkh.

Abu'l Hasan,—Abdul Ghāfir-b-Ismail *Al Fārsi*, author of the *Siyāq fi daili tārikh Nishabur* (*Cursus orationis appendix ad historiam Nishaburae*). He died A.H. 527 (A.D. 1132). H. K.

Juzjāni,—The *Tabaqāt-i Nāsiri* is on the military expeditions of Nāsiruddin Mahmud Shāh-b-Iltamish of Delhi. The name of the author is Abu Omar, Othman-b-Muhammad al Minhāj, Sirāj al Juzjāni. Translated by Raverty in *Biblio. Indica* series.

Kabiruddin Irāqi,—son of Tajuddin Irāqi, who wrote of the conquests of Sultan Alāuddin Khilji. He was a skilled rhetorician, and writer; see a slight sketch of him in the *Tārikh Firoz Shāhi*, of Ziauddin Barni, p. 361.

Abul Qāsim Jamāluddin Muhammad,—d. 836 (A.D. 1432), author of the *Zubdatut Tawārikh*, in Persian.

Abul Fadhl Ubaidullah—(H.K. : in *Raudhat us Safa*, 'Abdullah) -b-Abi Nasr Ahmad-b-Ali-b-al Mikāl; both the works mentioned are historical.

Alauddin Ata Malik al Juwaini,—the author of the *Jahān Kushā'* a Persian history, *Ency. Isl.*, i. 1067-1070, under *Djuwaini*.

Hamdullah Qazvini,—author of the *Tārikh Guzida* (*Præstantissima ex historia*) which ranks among the best general histories of the East, written for the Wazir Ghiāt-uddin Muhammad. It was first composed in 50,000 verses,

and then turned into prose about A.H. 730 (A.D. 1329-30). *Ency. Isl.*, ii. 844.

Qadhi Nasiruddin Abdullah-b-Omar al Baidhāwi-d—A.H. 684 (A.D. 1285), author of the *Nidhamut Tawārikh* (*Ordo historiarum*), a compendium of Persian history with an account of Moslem dynasties from the house of Umayyah to that of Khwārazm and the Mongols (1275 A.D.). *Ency. Isl.*, i. 590.

Khj. Rashidi,—Khwājah Rashiduddin Fadhlullah, Tabib, "one of the greatest historians of Persia (put to death in 718, A.D. 1318), author of the *Jamiut Tawārikh* (*Historia universalis*). He began it just before the death of Ghāzān Khan A.H. 704 (1304 A.D.). His successor Khudabandah Muhammad ordered him to complete it and preface it with his name and to add to the history of the Jingiz dynasty, a more general account, *Ency. Isl.*, iii. 1124.

Hāfidh Abru,—Shihābuddin Abdullah b. Lutfullah b. Abdur Rashid al Khwāfi (and not *al-Haravi*), author of the *Zubdatut Tawārikh* composed for Baisonghor Mirzā, an account of the principal events and strange or extraordinary occurrences recorded in the history of the world, carried down to A.H. 829 (1425 A.D.). He died in 834 (A.D. 1430). *Ency. Isl.*, ii. 213.

Avicenna,—The full name of this philosopher is Abu Ali Husain-b-Abdullah-b-Sina, as Shaikh, ar-Rāis. He is therefore known in the East as *Ibn Sina* and *Pur-i-Sina*, from his father's name. *Ency. Isl.*, ii. 419-420 (under *Ibn Sina*). He was born in Bukhārā A.H. 370 (A.D. 980) and died in 428 (A.D. 1036) at the age of 58.

A'IN I.

The Provincial Viceroy, Sipah Sālār, literally,
*Commander of the Forces.*⁵⁵

He is the vicegerent of His Majesty. The troops and people of the provinces are under his orders and their welfare depends upon his just administration. He must seek the

will of God in all that he undertakes and be constant in praise and supplication. He must never lay aside the consideration of the people's prosperity nor suffer his zeal to sleep. He must not be prompt to vain converse or asperity of manner. Vigilance and the due distinction of ranks must be his care, especially towards subordinates near his person and officials at a distance. What is the duty of dependents must not be committed to his sons, and what these can perform he should not execute himself. In all transactions he should confide in one wiser than himself and if he can find none such, he should confer with a few chosen individuals and weigh carefully their deliberations.

It haps at times, the hoary sage
May fail at need in counsel right,
And unskilled hands of tender age
A chance shaft wing within the white.

[S'adi, *Gulistān*, Ch. 3.]

He should not admit many men to his secret councils, for the prudent, zealous, warm, disinterested adviser is rare, lest one of them should provoke dissension, and opportunities for timely action escape. He should regard his office of command as that of a guardian, and exercise caution, and making a knowledge of the disposition of men a rule of government, live as it behoves his office. Levity and anger he should keep under the restraint of reason. He should reclaim the rebellious by a just insight into the conduct of affairs and by good counsel, failing which, he should be swift to punish by reprimands, threats, imprisonment, stripes or amputation of limb, but he must use the utmost deliberation before severing the bond of the principle of life. He should not pollute his tongue with abuse which is the manner of noisy vagabonds of the market place. He should refrain from the use of oaths in speech for this is imputing falsehood to himself by implication and distrust in the person he addresses. In judicial investigations, he should not be

viceroys (*sipāh sālār*) and the revenue-head (*shāhīn*) is as old as the first government set up by the Arabs after the conquest of Egypt: "In the early centuries of Arab rule (in Egypt) two political functions are sharply distinguished, the governorship and the treasury. The governor, *Amir*, had control over the military and police only. . . . Alongside of him was the head of the treasury the *Amīl*. . . . These two officials had to keep a strict watch on one another." (C. H. Becker in *Ency. Islam*, ii, 13.) These provincial viceroys were afterwards called *nāẓims* and *subah-dārs*. Akbar divided his empire into 12 provinces and appointed a uniform set of officials to each, first in his 24th regnal year (1579). See *Akbarnāmah*, tr. ii. 413. [J. Sarkar.]

satisfied with witnesses and oaths, but pursue them by manifold inquiries, by the study of physiognomy and the exercise of foresight, nor, laying the burden of it on others, live absolved from solicitude.

Beware lest justice to that judge belong,

Whose own ill-deed hath wrought the suppliant's wrong.

Let him not inflict the distress of expectation upon supplicants for justice. He should shut his eyes against faults and accept excuses, and adopt such a course of conduct as will not disparage his good breeding and dignity. He should not interfere with any man's creed. A wise man, in worldly affairs that are transient, seeks not his own loss, why then should he knowingly abandon the spiritual life that is eternal, for if it be true, disturbance is criminal and if otherwise it is the malady of ignorance and is deserving of kind treatment. Each division of the kingdom, he should entrust to zealous upright men and provide for the safety of the roads by the establishment of trusty guards and from time to time receive reports of them. He should select for purposes of secret intelligence honest, provident, truthful and unavaricious men, and if such needful individuals are not to be obtained, in every affair he should associate several who are unknown to each other and inspecting their several reports thus ascertain the truth. His expenditure should be less than his income, and from his treasury he should supply the needy, especially those who loose not their tongues in solicitation. He should never be negligent of the supplies and accoutrements of the troops. He should not refrain from the practice of horsemanship, and should use the bow and the matchlock and command this exercise to his men. In attaching individuals to his own person and in the increase of confidence, he should employ a cautious circumspection. Many are the evil disposed and licentious of nature who profess sincerity and sell themselves at a high price. He should turn his attention to the increase of agriculture and the flourishing condition of the land and earn the gratitude of the people by the faithful discharge of his obligations and account the befriending of the agriculturists as an excellent service to the Almighty. He should retain impartial collectors of revenue and from time to time obtain information regarding their actions. Let him store for himself a goodly reward in the making of reservoirs, wells, watercourses, gardens, serais and other pious foundations, and set about the repairing of what has fallen into

ruin. He should not be given to retirement nor be unsettled in mind which is the manner of recluses, nor make a practice of associating with the common people nor be ever surrounded by a crowd which is the fashion of blind worshippers of outward appearances.

Court not the world nor to it wholly die;
Walk wisely : neither phoenix be nor fly.

Let him hold in honour the chosen servants of God, and entreat the assistance of spiritually-minded anchorites and of mendicants of tangled hair and naked of foot. The imploring of blessings from the sun and the solar lamp, he should not consider as its deification or a worshipping of fire.⁵ Let him accustom himself to night vigils and partake of sleep and food in moderation. He should pass the dawn and the evening in meditation and pray at noon and at midnight. When he is at leisure from worldly affairs and introspection of conscience, he should study works of philosophy and act according to their precepts. If this does not satisfy his mind, he should peruse the spiritual admonitions of the Masnawi [of Jalāl-ud-dīn Rūmī] and regardless of the letter imbibe its spirit. He should entertain his mind with the instructive stories of Kalila and Damna, and thus gaining a knowledge of the vicissitudes of life, regard the experience of the ancients as his own. Let him apply himself to the cultivation of true knowledge and put aside childish tales. Let him associate with a discreet and trusty friend and give him permission to look carefully into his daily conduct in order that he may privately represent whatever, in the balance of his discretion, appears blameworthy and if at any time his penetration should be at fault he should not be thereat displeased for men have ever been backward in uttering a displeasing truth especially in a season of anger when reason slumbers and the spirit is aflame. Courtiers, for the most part, seek pretexts of evasion and lend a false colouring to error, and if perchance one of them should be really concerned, he will hold his peace for fear, for he is indeed difficult to find who would prefer another's benefit to his own injury. Let him not be roused to anger by the representations of detractors, but rest in the path of circumspection, for men of evil nature, dissemblers in speech, palm off their tales with the semblance of truth and representing themselves as disinterested, labour to in-

⁵ See Vol. I, pp. 200-202.

jure others. He should not consider himself as fixed of residence but hold himself ever ready for a summons to the presence. Let him not be malevolent, but prefer courtesy and gentleness. He should not subvert ancient families but let an illustrious ancestry redeem unworthy successors. Let him see that the younger among his followers when they meet, use the greeting *Allahu ākbar*,³⁸ 'God is greatest', and the elder reply *Jalla-jalāluhu*, 'His majesty is eminent'. Let him not take as food a sheep or a goat of under one year and he should abstain from flesh for a month after the anniversary of his birthday. He shall not eat of anything that he has himself killed. He should restrict himself in sensual gratification and approach not a pregnant woman. The food which is bestowed in memory of the deceased, he should prepare each year on his birthday and regale the needy.

With heavenly treasures store thy grave—provide
While yet in life—none may when he hath died.

[*Gulistan.*]

When the sun advances from one sign of the zodiac to another, let him offer up a thanksgiving and discharge cannon and musketry to arouse the slumberers in forgetfulness. At the first beams of the world-illuminating sun and at midnight which is the turning point of its re-ascension, let him sound the kettle-drum and enforce vigilance.

A'IN II.

The Faujdār.

In the same way that His Majesty, for the prosperity of the empire, has appointed a Commander of the forces for

³⁸ *Allahu akbar*.—This formula, as the briefest expression of the absolute superiority of the One God (Allah) over the idols of the pagan Arabs, is used in Muslim life in different circumstances, in which the idea of Allah, His greatness and goodness is suggested. . . . The call to the daily prayer (*azan*) is opened with a four-fold *takbir* (=the cry *Allahu ākbar*.) The Prophet is said to have uttered very frequently the *takbir* during the Hajj. (*Ency. Islam*, iv. 627 under *takbir*.)

Akbar's order for its general use as a form of salutation among the public in the place of the customary *salām 'alaikum* (sanctified by its frequent occurrence in the *Qurān*, xvi. 34, xxxix. 73 &c.), led the ignorant populace to believe that he wished to be acknowledged as God. "This caused great commotion." (Badayuni, tr. ii. 308.) For Abul Fazl's vexation at this misrepresentation, *Akbar-nāmāh*, tr. iii. 397. V. Smith's *Akbar*, p. 177 ("ambiguous phrase"), 218 and n. [*J. Sarkar.*]

each province, so by his rectitude of judgment and wise statesmanship he apportions several pargannahs to the care of one of his trusty, just and disinterested servants,⁵⁹ appreciative of what is equitable, and faithful to his engagements; and him they style by the above name. As a subordinate and assistant he holds the first place. Should a cultivator or a collector of the crown lands or an assignee of government estates prove rebellious, he should induce him to submit by fair words, and if this fail, he shall take the written evidence of the principal officers and proceed to chastise him. He should pitch his camp in the neighbourhood of the body of rebels and at every opportunity inflict loss upon their persons and property but not risk at once a general engagement. If the affair can be concluded with the infantry he should not employ cavalry. He should not be rash in attacking a fort, but encamp beyond bowshot and the reach of its guns and musketry, and obstruct the roads of communication. He should be vigilant against night attacks and devise a place of retreat, and be constant in patrolling. When he has captured the rebel camp, he must observe equity in the division of the spoil and reserve a fifth for the royal exchequer. If a balance of revenue be due from the village, this should be first taken into account. He should constantly inspect the horses and accoutrements of the troops. If a trooper be without a horse, his comrades should be assessed to provide for him and if a horse be killed in action, it should be made good at the expense of the State. He must duly furnish a roll of the troops present and absent, to the royal court and ever bear in mind the duty of carrying out its sacred ordinances.

A'IN III.

The Mir A'dl and the Qāzi.

Although the supreme authority and the redress of grievances rests with sovereign monarchs, yet the capacity of a single person is inadequate to the superintendence of

⁵⁹ For the duties of the *faujdar* (modern district magistrate *cum* superintendent of police and commandant of local forces but not collector), see Sarkar's *Mughal Administration*, 3rd. ed., IV. § 4.

the entire administration. It is therefore necessary that he should appoint one of his discreet and unbiassed servants as his judiciary delegate. This person must not be content with witnesses and oaths, but hold diligent investigation of the first importance, for the inquirer is uninformed and the two litigants are cognisant of the facts. Without full inquiry, and just insight, it is difficult to acquire requisite certitude. From the excessive depravity of human nature and its covetousness, no dependence can be placed on a witness or his oath. By impartiality and knowledge of character, he should distinguish the oppressed from the oppressor and boldly and equitably take action on his conclusions. He must begin with a thorough interrogation and learn the circumstances of the case; and should keep in view what is fitting in each particular and take the question in detail, and in this manner set down separately the evidence of each witness. When he has accomplished his task with intelligence, deliberation and perspicacity, he should, for a time, turn to other business and keep his counsel from others. He should then take up the case and reinvestigate and inquire into it anew, and with discrimination and singleness of view search it to its core. If capacity and vigour are not to be found united, he should appoint two persons, one to investigate whom they call a Qāzī;⁶⁰ the other the Mir A'dl to carry out his finding.

A'IN IV.

*The Kotwāl.*⁶¹

The appropriate person for this office should be vigorous, experienced, active, deliberate, patient, astute and humane. Through his watchfulness and night patrolling the citizens should enjoy the repose of security, and the evil-disposed lie in the slough of non-existence. He should keep a register of houses, and frequented roads, and engage the citizens in a pledge of reciprocal assistance, and

⁶⁰ Qazi in Sarkar's *Mughal Administration*, Ch. II; § 7.

⁶¹ Kotwal in *ibid.*, Ch. IV, § 5, *Mirat-i-Ahmadī*, i. 168. In the later Mughal Empire the inspection of markets was often entrusted to the *muh̄tasib* (from Aurangzib's reign).

bind them to a common participation of weal and woe. He should form a quarter by the union of a certain number of habitations, and name one of his intelligent subordinates for its superintendence and receive a daily report under his seal of those who enter or leave it, and of whatever events therein occur. And he should appoint as a spy one among the obscure residents with whom the other should have no acquaintance, and keeping their reports in writing, employ a heedful scrutiny. He should establish a separate *serāi* and cause unknown arrivals to alight therein, and by the aid of divers detectives take account of them. He should minutely observe the income and expenditure of the various classes of men and by a refined address, make his vigilance reflect honour on his administration. Of every guild of artificers, he should name one as guildmaster, and another as broker, by whose intelligence the business of purchase and sale should be conducted. From these also he should require frequent reports. He should see to the open thoroughfare of the streets and erect barriers at the entrances and secure freedom from defilement. When night is a little advanced, he should prohibit people from entering or leaving the city. He should set the idle to some handicraft. He should remove former grievances and forbid any one from forcibly entering the house of another. He shall discover thieves and the goods they have stolen or be responsible for the loss. He should so direct that no one shall demand a tax or cess (*bāj wa tamghā*) save on arms, elephants, horses, cattle, camels, sheep, goats and merchandise. In every Subah a slight impost shall be levied at an appointed place. Old coins should be given in to be melted down or consigned to the treasury as bullion. He should suffer no alteration of value in the gold and silver coin of the realm, and its diminution by wear in circulation, he shall recover to the amount of the deficiency. He should use his discretion in the reduction of prices and not allow purchases to be made outside the city. The rich shall not take beyond what is necessary for their consumption. He shall examine the weights and make the *scr* not more nor less than thirty *dāms*. In the *gas* hereinafter to be mentioned, he should permit neither decrease or increase, and restrain the people from the making, the dispensing, the buying or selling of wine, but refrain from invading the privacy of domestic life. Of the property of a deceased or missing person who may have no heir, he shall take an

inventory and keep it in his care. He should reserve separate ferries and wells for men and women.

He should appoint persons of respectable character to supply the public watercourses, and prohibit women from riding on horseback. He should direct that no ox or buffalo or horse, or camel be slaughtered, and forbid the restriction of personal liberty and the selling of slaves. He should not suffer a woman to be burnt against her inclination, nor a criminal deserving of death, to be impaled, nor any one to be circumcised under the age of twelve. Above this limit of age, the permission may be accorded. Religious enthusiasts, calenders, and dishonest tradesmen he should expel or deter from their course of conduct, but he should be careful in this matter not to molest a God-fearing recluse, or persecute barefooted wandering anchorites. He should allot separate quarters to butchers, hunters of animals, washers of the dead, and sweepers, and restrain men from associating with such stony-hearted gloomy-dispositioned creatures. He shall amputate the hand of any who is the pot-companion of an executioner, and the finger of such as converse with his family. He should locate the cemetery outside of, and to the west of the city. He should prohibit his adherents from wearing sombre garments in mourning and induce them to wear red. From the first till the nineteenth of the month of Farwardin, during the whole month of Abān, the days of the sun's passage from one sign of the zodiac to another, *viz.*, the first of every solar month, the sixteenth of the same, the Ilāhi festivals, the days of the eclipse of the sun and moon, and on the first day of the week, he shall prohibit men from slaughtering animals, but hold it lawful as a necessity for feeding animals used in hunting and for the sick. He shall remove the place of execution to without the city and see that the Ilāhi festivals are observed. He shall have lamps lit on the night of the Nauroz (New Year's day) and on the night of the 19th of Farwardin. On the eve of a festival, as well as on the festival itself he shall cause a kettle-drum to be sounded at each watch. In the Persian and Hindu almanacs, he shall cause the Ilāhi era to be adopted and the beginning of the month according to the Hindu nomenclature he shall place in *Shukla-pachh*.

A'IN V.

The 'Aml-guzār or Collector of the Revenue.

Should be a friend of the agriculturist. Zeal and truthfulness should be his rule of conduct. He should consider himself the representative of the lord paramount and establish himself where every one may have easy access to him without the intervention of a mediator. He should deal with the contumacious and the dishonest by admonition and if this avail not, proceed to chastisement, nor should he be in apprehension of the land falling waste. He should not cease from punishing highway robbers, murderers and evildoers, nor from heavily mulcting them, and so administer that the cry of complaint shall be stilled. He should assist the needy husbandman with advances of money and recover them gradually. And when through the exertions of the village headman the full rental is received, he should allow him half a *biswah*⁶² on each *bigha*, or otherwise reward him according to the measure of his services. He should ascertain the extent of the soil in cultivation and weigh each several portion in the scales of personal observation and be acquainted with its quality. The agricultural value of land varies in different districts and certain soils are adapted to certain crops. He should deal differently, therefore, with each agriculturist and take his case into consideration: He should take into account with discrimination the engagements of former collectors and remedy the produce of ignorance or dishonesty. He should strive to bring waste lands into cultivation and take heed that what is in cultivation fall not waste. He should stimulate the increase of valuable produce and remit somewhat of the assessment with a view to its augmentation. And if the husbandman cultivate less and urge a plausible excuse, let him not accept it. Should there be no waste land in a village and a husbandman be capable of adding to his cultivation, he should allow him land in some other village.

He should be just and provident in his measurements. Let him increase the facilities of the husbandman year by year, and under the pledge of his engagements, take nothing beyond the actual area under tillage. Should some

⁶² The 20th part of a *bigha*.

prefer to engage by measurement and others by appraisement of crops, let him forward the contracts with all despatch to the royal presence. Let him not make it a practice of taking only in cash payments but also in kind. This latter is effected in several ways. First, *kankut*: *kan* in the Hindi language signifies grain, and *kut*, estimate. The whole land is taken either by actual mensuration or by pacing it, and the standing crops estimated in the balance of inspection. The experienced in these matters say that this comes little short of the mark. If any doubt arise, the crops should be cut and estimated in three lots, the good, the middling and the inferior, and the hesitation removed. Often, too, the land taken by appraisement, gives a sufficiently accurate return. Secondly, *bātāi*, also called *bhāoli*, the crops are reaped and stacked and divided by agreement in the presence of the parties. But in this case several intelligent inspectors are required, otherwise the evil-minded and false are given to deception. Thirdly, *khet batāi*, when they divide the fields after they are sown. Fourthly, *lūng batāi*; after cutting the grain, they form it in heaps and divide it among themselves, and each takes his share home to clean it and turn it to profit. If it be not prejudicial to the husbandman, he may take the value of the corn-bearing land in cash at the market rate. If on this land they sow the best kinds of produce,⁶³ in the first year he should remit a fourth of the usual assessment. If at the time of collection, the better produce is found to be larger in quantity than the previous year, but less land cultivated, and the revenue be the same, let him not be provoked or removed to contention. He should always seek to satisfy the owner of the crops. He should not entrust the appraisement to the headman of the village lest it give rise to remissness and incompetence and undue authority be conferred on highhanded oppressors, but he should deal with each husbandman, present his demand, and separately and civilly receive his dues.

He must take security from land surveyors, assessors and other officers of revenue. He should supply the officials engaged in the land measurements, for each day on which

⁶³ *Jūs-i-Kāmil* such as sugar, *pān*, indigo, opium or cotton in contradistinction to *jūs-i-ādna*, inferior crops, such as maize.

they are employed, with 16 *dāms* and 31 *ser*s, and as a monthly ration, on the following scale :

	Flour. ser	Oil. ser	Grain. ser	Vegetables &c. dām
Superintendent of survey ...	5	$\frac{1}{2}$	7	4
Writer ...	4	$\frac{1}{2}$	4	4
Land surveyor and four thanadars, each ...	8	1	5	5

He shall affix a mark to the land surveyed and shall take a bond from the headman that there shall be no concealment regarding the land, and the various crops shall be duly reported. In the process of measurement if any inferior portion of land be observed, he shall at once estimate its quantity, and from day to day take a note of its quality and this voucher he shall deliver to the husbandman. But if this discovery be made after the collection of the revenue, he shall gather information from the neighbours and from unofficial documents and strike an average. In the same way as the *kārḱun* (registrar of collections) sets down the transactions of the assessments, the *muqaddam*⁶⁴ (chief village revenue officer) and the *patwāri* (land-steward) shall keep their respective accounts. The Collector shall compare these documents and keep them under his seal and give a copy thereof to the clerk. When the assessment of the village is completed, he shall enter it in the abstract of the village accounts, and after verifying it anew, cause its authentication by the *kārḱun* and *patwāri*, and this document he shall forward weekly to the royal presence and never delay it beyond fifteen days. After the despatch of the draft estimates to the imperial court, should any disaster to the crops occur, on ascertaining the exact particulars on the spot, he shall calculate the extent of the loss and recording it in writing, transmit it without delay in order that it may be approved or a commissioner despatched. He should collect the revenue in an amicable manner and extend not the hand of demand out of season. He should begin the collection of the spring harvest from the *Holi*, which is a Hindu festival occurring when the sun is about to pass from Aquarius and is entering or has reached mid-way in Pisces and the Autumn harvest from the *Dasharah*, which is a festival falling when the sun is in the middle or

⁶⁴ For *muqaddam*, Wilson, 351.

last days of Virgo or the first ten of Libra. Let him see that the treasurer does not demand any special⁶⁵ kind of coin, but take what is of standard weight and proof and receive the equivalent of the deficiency at the value of current coin and record the difference in the voucher. He should stipulate that the husbandman bring his rents himself at definite periods so that the malpractices of low intermediaries may be avoided. When there is a full harvest, he should collect the appropriate revenue and accept no adjournment of payments on future crops.

Whosoever does not cultivate land liable to taxation but encloses it for pasturage, the Collector shall take for each buffalo six *dāms*, and for an ox, three *dāms* yearly, but for a calf or a buffalo which has not yet calved, he shall make no demand. He shall assign four oxen, two cows and one buffalo to each plough and shall lay no impost on these. Whatever is paid into the treasury, he shall himself examine and count and compare it with the day-ledger of the *kārkun*. This he shall verify by signature of the treasurer and placing it in bags under seal, shall deposit it in a strong room and fasten the door thereof with several locks of different construction. He shall keep the key of one himself and leave the others with the treasurer. At the end of the month, he shall take from the writer (*bitikchi*) the account of the daily receipts and expenditure and forward it to the presence. When two lakhs of *dāms* are collected, he shall remit them by the hands of trusty agents. He shall carefully instruct the *pātwari* of each village to enter in detail in the memorandum which he gives to the husbandman, the amount he receives from the same; any balances he shall enter under each name in a book and forward it attested by the signatures of the headmen; and these, at the next harvest, he shall recover without distress. He shall carefully inspect the *suyurghal*⁶⁶ tenures, sending copies of them to the registry office to be compared. He should ascertain the correctness of the *chaknāmah*,⁶⁷ and resume the share of a deceased grantee or one who is an

⁶⁵ *Zar-i-khās* in the text should be translated as His present Majesty's coin. Jarrett took it to mean 'any special kind of coin', but this interpretation is wrong. It is not necessary to read *Khālis* for *Khās* (from a variant) as suggested by Jarrett (= "fine gold"). J. S.

⁶⁶ An assignment of land revenue for charitable purposes: also a grant of land without stipulation of any condition or service. Wilson, 495.

⁶⁷ This is a grant of alienated lands specifying the boundary limits thereof. *Chak*, according to Elliot, is a patch of rent-free land detached from a village. Wilson, 97.

absentee or actually in service of the state. He should take care that land cultivated by the farmer himself and not by the tenant, as well as resumed lands, should not be suffered to fall waste; the property of the absentee or of him that dies without an heir he should duly keep under ward and report the circumstances. He should see that no capitation-tax be imposed nor interfere with the remission of dues granted by former governments.

He shall not make the occasions of journeying, feasting or mourning an opportunity for exactions, and refrain from accepting presents. Whenever a *muqaddam* or *patwāri* shall bring money or, advancing to the dais, shall present a *dām* in obeisance, he shall not accept it. In the same way he shall renounce *balkati*, which is the practice of taking a small fee from each village when the harvest is ready for reaping. He shall also waive all perquisites on handicrafts, market-booths, police, travelling passports, garden produce, temporary sheds, enclosure, fishing rights, port-dues, butter, oil of sesame, blanketing, leather, wool, and the like malpractices of the avaricious who fear not God. He shall provide for the periodic appointment of one among those best acquainted with the district, to reside at the royal court and furnish it with the minutest particulars. Every month he shall submit a statement of the condition of the people, of the *jāgirdārs*, the neighbouring residents, the submission of the rebellious, the market prices, the current rents of tenements, the state of the destitute poor, of artificers and all other contingencies. Should there be no *kotwāl*, the Collector must take the duties of that office upon himself.

A'IN VI.

*The Bitikchi*⁶⁸

Must be conscientious, a good writer, and a skilful accountant. He is indispensable to the collector. It is his duty to take from the *kanungo*⁶⁹ the average decennial state

⁶⁸ A word of Turkish origin, signifying a writer or scribe. *Enc. Isl.* i. 734.

⁶⁹ An officer in each district acquainted with its customs and land-tenures and whose appointment is usually hereditary. He receives report from the *patwāris* of new cases of alluvion and diluvion, sales, leases, gifts of land &c. which entail a change in the register of mutations. He is a revenue officer and subordinate to the tahsildār. Carnegy, *Kachh. Technical*. Wilson, 260.

of the village revenues in money and kind, and having made himself acquainted with the customs and regulations of the district, satisfy the Collector in this regard, and lend his utmost assistance and attention. He shall record all engagements made with the agriculturists, define the village boundaries, and estimate the amount of arable and waste land. He shall note the names of the *munsif*,⁷⁰ the superintendent (*zābit*), the land-surveyor and *thānadār*, also that of the cultivator and headman, and record below, the kind of produce cultivated. He should also set down the village, the *pergunnah* and the harvest, and subtracting the deficiency take the value of the assets, or after the manner of the people of the country, inscribe the name, the kind of produce, and the deficiency below the date of cultivation.

When the survey of the village is complete, he shall determine the assessment of each cultivator and specify the revenue of the whole village. The Collector shall take the revenue on this basis, and forward a copy of the survey, called in Hindi *khassra* to the royal court. When drawing out the rolls, if the former documents are not available, he should take down in writing from the *patwāri* the cultivation of each husbandman by name and thus effect his purpose, and transmit the roll together with the balances and collections punctually, and he shall enter the name of the *tahsildar* below each village, in the day-ledger. He shall record the name of each husbandman who brings his rent and grant him a receipt signed by the treasurer. Copies of the rolls of the *patwāri* and *muqaddam* by means of which they have made the collections, together with the *sarkhat*, that is the memorandum given to the husbandman, he shall receive from the *patwāri*, and inspecting them, shall carefully scrutinize them. If any falsification appears, he shall fine them and report to the Collector daily and the collection and balances of each village and facilitate the performance of his duty. Whenever any cultivator desires a reference to his account, he shall settle it without delay and at the close of each harvest he shall record the collections and balances of each village and compare them with the *patwāri*'s, and enter each day in the ledger the receipts and disbursements under each name and heading, and authenticate it

⁷⁰ *Munsif*.—An officer employed to superintend the measurement of the lands of a village in concert with the villagers. [Wilson, 356]. For the position of the *munsif* in Sher Shah's revenue system, see 'Abbās Sarwānī, near the end. [J. S.]

by the signature of the Collector and treasurer. At the end of the month, he shall enclose it in a bag under the seal of the Collector and forward it to the presence. He shall also despatch daily the price-current of mohurs and rupees and other articles under the seals of the principal men, and at the end of each harvest, he shall take the receipts and disbursements of the treasurer, and forward it authenticated by his signature. The abstract and settlement of the assessment, at the close of each year, he shall transmit under the signature of the Collector. He shall enter the effects and cattle plundered in any village, in the day-ledger, and report the circumstances. At the year's end, when the time of the revenue-collections has closed, he shall record the balances due from the village and deliver the record to the Collector and forward a copy to the royal court. When removed from office, he shall make over to the Collector for the time being his account under the heads of balances, advances &c., and after satisfying him in this regard, take the detail thereof and repair to the Court.

ĀIN VII.

- *The Treasurer (Khazānadār)*

Called in the language of the day *Fotadār*.⁷¹ The treasury should be located near the residence of the governor and the situation should be such where it is not liable to injury. He should receive from the cultivator any kind of mohurs, rupees or copper that he may bring, and not demand any particular coin. He shall require no rebate on the august coinage of the realm but take merely the equivalent of the deficiency in coin-weight. Coinage of former reigns he shall accept as bullion. He shall keep the treasure in a strong room with the knowledge of the *shiqdār*⁷² and the registrar, and count it every evening and

⁷¹ The term *fota* is applied in Arabic, to cloths used as waist wrappers brought from Sind, and the word itself is supposed to be derived from that country and not to be of Arabic origin. The office was no doubt originally named from this distinguishing portion of apparel; whence the common name *Poddār* applied to, a banker, cash-keeper, or an officer in public establishments for weighing money or bullion. See Wilson's *Gloss.*, 160 and 422.

⁷² *Shiqdār*, an officer appointed to collect the revenue from a certain division of land under the Moghul government; it was sometimes applied to the chief financial officer of a province or to the viceroy in his financial capacity.—Wilson's *Glossary*, 480. For this officer in Sher Shah's system, see 'Abbās Sarwāni, near the end.

cause a memorandum thereof to be signed by the Collector and compare the day-ledger with the registrar's account and authenticate it by his signature. On the door of the treasury as sealed by the Collector, he should place a lock of his own, and open it only with the cognisance of the Collector and registrar. He shall not receive any monies from the cultivator save with the knowledge of the Collector and registrar, and he shall grant a receipt for the same. He shall cause the *patwāri's* signature to be affixed to the ledger known in Hindustan as *bahi*, so that discrepancy may be avoided. He shall consent to no disbursements without the voucher of the *diwān*,⁷³ and shall enter into no usurious transactions. If any expenditure should be necessary that admits of no delay, he may act under the authority of the registrar and *shiqdār* and represent the case to government. The aforementioned duties, from those of the commander of the troops up to this point, are primarily under the direct cognisance of the sovereign authority and as no one individual can perform them, a deputy is appointed for each function and thus the necessary links in administration are strengthened.

Currency of the means of Subsistence.

Since the benefit and vigour of human action are referrible to bodily sustenance, so in proportion to its purity is the spirit strengthened; the body, were it otherwise, would grow corpulent and the spirit weak: the thoughts too under such a regimen, incline to refinement and actions to virtue. The seekers of felicity, sober in conduct, are before all things particularly careful in the matter of food and do not pollute their hands with every meat. To the simple in heart who fear God, labour is difficult and their means of living straitened. They have not that luminous insight which penetrating to the essence of things, dwells in repose, but through fear of the displeasure of God, are sunk in exhaustion of soul from the pangs of hunger. As for instance in the case of the man who possessed a few cows, his legitimate property, and subsisted on their milk. By the accident of fortune, it chanced that they were

⁷³ *Diwān*, This term was especially applied to the head financial minister whether of the state or of a province, being charged in the latter with the collection of the revenue, its remittance to the imperial treasury and invested with extensive judicial powers in all civil and financial causes. Wilson's *Glossary*, 144-145. For a full description, see *Sirāj's Mughal Administration*, Ch. 3, § 1-5.

carried off, and he passed some days fasting. An active fellow after diligent pursuit brought them back, but he would not accept them and replied, "I know not whence those dumb animals have had food during these past few days." In a short space this simple soul died. Many tales are told of such dull-witted creatures who have thus passed away. There are also avaricious worldlings who do not recognize the difference between other people's property and their own, and gratify themselves at the expense of their spiritual and temporal good. The ignorant and distraught in mind, making their own necessities an occasion of spoliation and seizure, prepare for themselves eternal punishment.

Simple, innocent-minded folk consider that there are no unappropriated waste lands and were they obtainable, it would be difficult to furnish the implements of cultivation, and if these could be had, the means of providing food which would enable them to labour, are not manifest. They can discover no mine to excavate, and if one were pointed out to them which had no owner, it would be extremely onerous to obtain a living therefrom. They are averse too, from the profession of arms, lest dear life be the exchange for base lucre. They withdraw themselves also from commerce for this reason that many ask a high price for their goods, conceal their deficiencies and praise them for qualities which are not in them, while they close their eyes to the evident excellencies of what they purchase and disparage it for faults it does not possess, preferring their own benefit to another's loss. And they disapprove also of those who are content to hold lawful the sequestration of the goods of rival sectaries, and they affirm that if the fautor of such pretension be discerning and wise, it will seem an occasion for additional anxiety rather than a sanction to retain the property of another; for how can the illicit seizure of what is another's be commendable on the score of a difference of faith? On the contrary, it is a suggestion of the evil one, a phantasy of the dreams of the avaricious and unfit for the ears of the good. At the present time His Majesty has placed a lamp upon the highway before all men, that they may distinguish the road from the pitfalls, and sink not into the slough of perdition, nor pass their dear lives in unprofitableness.

Since there is infinite diversity in the natures of men and distractions, internal and external, daily increase, and

heavy-footed greed travels post haste, and light-headed rage breaks its rein, where friendship in this demon-haunted waste of dishonour is rare, and justice lost to view, there is, in sooth, no remedy for such a world of confusion but in autocracy, and this panacea in administration is attainable only in the majesty of just monarchs. If a house or a quarter cannot be administered without the sanctions of hope and fear of a sagacious ruler, how can the tumult of this world-nest of hornets be silenced save by the authority of a vicegerent of Almighty power? How, in such a case can the property, lives, honour, and religion of the people be protected, notwithstanding that some recluses have imagined that this can be supernaturally accomplished, but a well-ordered administration has never been effected without the aid of sovereign monarchs. That fiery wilderness of talismanic power, too, is haunted by spells and sorcerers, and storms of confusion from this sea of undiscernment have arisen and arise, and many souls, through simplicity and shortsightedness, in the turbulent billows of inexperience have been and are still ever engulfed, while those who by the light of wisdom and through the grace of acceptance have bridled their desires and garnered provisions for the long journey to come, have, in the cross-roads of distraction, become the reproach of high and low, for their folly, irreligion and unbelief. In that assembly of ignorance should a philosopher of experience enter, he must needs take up the fashion of fools and so escape from the contumely of the base.

It is evident that in all cultivated areas, the possessors of property are numerous, and they hold their lands by ancestral descent, but through malevolence and despite, their titles become obscured by the dust of uncertainty and the hand of firmness is no longer stretched above them. If the cultivator hold in awe the power of the Adorner of the universe and the Elixir of the living, and the merchant turn back from evil designing and reflect in his heart on the favour of the lord of the world, the depository of divine grace, his possessions would assuredly be approved of wisdom. Thus the virtue of property lies in the pledge of intention, and a just ruler, like a saltbed, makes clean the unclean, and the evil good. But without honest coadjutors, abundant accessories of state and a full treasury even he could effect nothing and the condition of subserviency and obedience would lack the bloom of

discipline. Now the man of robust frame should, in the first place, choose the profession of arms and reflect on the assistance which he is capable of rendering, so as to regard his life as devoted to the task of preserving human society from dissolution. The means of sustenance are likewise as abundant to the labourer as forage for his cattle. But if a man is unequal to this, he should endeavour, in some way, to enter into the number of state servants. Thus the currency of the means of subsistence rests on a twofold basis, *viz.*, the justice of sovereign monarchs and regard to the welfare of well-disposed dependents. The base materialist understands not the language of reason and never transcends the limits of bodily sense. This unfertile soil needs the water of the sword, not the limpid spring of demonstration. In the presence of the majesty of the prince, the proud and perverse of disposition sink into obscurity while the prosperity of the good who seek after justice is ever continuous.

Of a truth, whatever be the recompense of the guardianship over the four⁷⁴ priceless elements of the constitution, it is both meet and expedient and according to the Almighty will. To the watchmen over the house, the lord thereof appoints the guerdon, and to the watchmen of the universe, its shepherds. If the whole of a man's possessions were spent for the protection of his honour, it would be but fitting if in gratitude he further pledged his whole credit, how much the more when it is a question of the guardianship of the four great elements of State polity? But just monarchs exact not more than is necessary to effect their purpose and stain not their hands with avarice; and hence it is that this principle varies, as has been stated, according to diversities of age and country. From this suggestive digression, it will be evident that whatever circumspect rulers exact from their subjects after due deliberation and to subserve the interests of justice and grant to their submissive dependents, has a perfect propriety and is universally in vogue. It is also clear that the maintenance of the soldier should be ampler and more choice. Next follow the cultivators and then other artisans.

⁷⁴ In Vol. I. Abul Fazl's preface, they are named as (1) the warriors, (2) the artificers and merchants, (3) the learned, and (4) the husbandmen and labourers,—who are respectively likened to the four elements, fire, air, water and earth. [J. S.]

Ancient Greek⁷⁵ treatises affirm that professions are circumscribed to three classes, the Noble, the Base, and the Intermediate. The former refers to the mind and is, also, of not more than three kinds: the first concerns the pure intellect, as sagacity and capability of administration; the second, acquired knowledge, as composition or eloquence. the third personal courage, as military duty. The Base also is of three kinds: the first is opposed to the common weal of mankind, such as the hoarding of grain; the second is the contrary of any one virtue, as buffoonery; the third is such as the disposition is naturally averse from, as the trade of a barber, a tanner or a sweeper. The Intermediate comprises various callings and trades; some that are of necessity, such as agriculture; others which could be dispensed with, as dyeing; others again simple, as carpentry and ironmongery; and some compound, as the manufacturing of scales or knives.

From this exposition the distinguished character of the military profession is evident. In short, the noblest source of maintenance is to be found in a profession which is associated with just dealing, self-restraint and bravery and apart from evil doing and sensuality. The good regard three things as necessary in a profession—avoidance of tyranny, refraining from what is dishonourable, abstinence from all that is mean; by what is dishonourable, is meant buffoonery and the like low pursuits; by what is mean, is understood an inclination to base callings.

When an appropriate means of maintenance is secured, it is a requisite condition of economy to husband a portion of one's means, provided that the household is not thereby straitened. The mendicant should not be turned away disappointed nor subjected to the reproof of covetousness and greed. The proper control of an estate is conditional on the expenditure being less than the income; it is permitted to indulge a little in commercial speculation and engage in remunerative undertakings, reserving a part in coin and valuables, a part in goods and wares, and somewhat invested in the speculations of others, and yet a por-

⁷⁵ The reference is, no doubt, to Aristotle's *Politics* 2. (Δ) the true sense of which has been lost by filtration through some Arabic version or paraphrase. [H. S. J.]

The reader will find most of these ideas in a rather different form in Aristotle's *Politics*, Walford's translation in Bohn's Classical Library (1898), Bk. IV. Ch. IV (pp. 130 sqq.) Bk. III. Ch. V (p. 91). [J. S.]

tion in lands and immoveable estates, and a share may be entrusted to borrowers of credit, and expenditure regulated with circumspection, justice and modesty. Let such a one be frank in his commercial dealings and give no place in his heart to self-reproach. He should keep in view of his purpose, the will of God, not the hope of gratitude, the increase of reputation or the expectation of reward. He should also give freely to the needy whose destitution is unexposed. There is also a twofold manner of munificence which if exercised in just measure, is meritorious. Firstly, what is given in pure generosity or largesse such as a present and the like. This should be done quickly and secretly and without setting store on its amplitude or abundance, nor yet so as to cripple one's resources or exhaust them.

Secondly what is called for by occasional exigencies, either in procuring comforts or removing grievances, such as what is given to oppressors or to the profligate in order that person, property and honour may escape their injury. But in this he should use moderation. In procuring the conveniences of life, however, it is better that the bounty should be liberal.

People of the world in the matter of living are to be resolved into three classes. One class are fallen into such heedlessness that spiritual needs do not enter their comprehension, much less are practically considered. Another through their luminous fortune are so immersed in the consideration of essential truths that they give no thought to their means of sustenance. But those who seek the felicity to come, the circumspect in conduct, neglect not a just appreciation of life but make external conditions the instrument of interior well being in the hope of admission among those absorbed in divine love, and so attaining to the third degree of felicity, whence after traversing the arid waste of deliverance, they may repose in the second.⁷⁶

The dues of sovereignty have thus been set forth. The circulation of the means of sustenance, thus, is seen to rest on the justice of prudent monarchs and the integrity of conscientious dependents. And because the conditions of

⁷⁶ That is, according to the theology of the mystics, the third stage in the progressive spiritual life is the attraction of the soul to God *Allah*; the second is immersion in the Divine love *f-Allah*; the supreme stage is the unitive *Ma' Allah* reserved for his chosen saints.

the royal state and prerogative vary in different countries, and soils are diverse in character, some producing abundantly with little labour, and others the reverse, and as inequalities exist also, through the remoteness or vicinity of water and cultivated tracts, the administration of each state must take these circumstances into consideration and fix its demands accordingly. Throughout the whole extent of Hindustan where at all times so many enlightened monarchs have reigned, one-sixth of the produce was exacted; in the Turkish empire, Irān and Turān a fifth, a sixth, and a tenth respectively. In ancient times a capitation tax was imposed called, *khirāj*. Kubād disapproved of this practice, and resolved that the revenue should be fixed upon arable land accurately surveyed. But his death occurred before he could accomplish his design. Noshirwān (his son) carried it to completion and made the *jarib* of ten square reeds.⁷⁷ This was sixty royal yards square. One fourth of this was taken as a *qafiz*⁷⁸ and valued at three dirhams,⁷⁹ and the third part was fixed as the contribution due to the state. *Qafiz* is a measure, called also *sā'* weighing eight *ratl*,⁸⁰ and, some say, more. The dirham is equal in weight to one *misqāl*. When the Caliphate fell to Omar, at the suggestion of the learned, he adopted the plan of Noshirwān but through the vicissitudes of temporal conditions, he introduced some alterations which may be gathered from ancient volumes. In Turān and Irān from ages past, they have exacted a tenth, but the exactions have increased to more than a half which does not appear exorbitant to a despotic government. In Egypt they take for a

<i>Faddān</i> of the best soil,	3	<i>Ibrahimis</i>
„ „ „ middling,	2	„
„ „ „ worst,	1	„

⁷⁷ In the original, the word *qabzah* is written erroneously for *qasbah* which is corrected in the subsequent page with the following note. "According to the glossaries, 6 barleycorns make an *asba'*, (finger breadth): 4 *asba'*, a *qabzah*: 8 *qabzah*, a *zarā'* (cubit): 10 cubits, a *qasbah*: 10 *qasbah*, an *ashl*: a *jarib* is 1 square *ashl*, i.e., 10 square *qasbah* or 100 square cubits. According to the *qudāmāh*, 4 *asba'* is equal to a *qabzah*, and 10 *qabzah* a cubit, and 60 cubits an *ashl*. According to this, a *jarib* would be 60 square cubits."

⁷⁸ *Qafiz*.—A space of ground containing from about 124 to 144 cubits square. It is also a dry measure. *Enc. Isl.* ii. 622.

⁷⁹ *Dirham* in *Ency. of Islam*, i. 978; and *Ain-i-Akbari*, Vol. I. Ain II.

⁸⁰ *Ratl* is variously rated at 12 to 16 oz. At Bombay it is said to be equal to 36 Surat rupees. In the Red Sea littoral the Rottolo, as it is corruptly called, varies from 10 to 24 oz. avoirdupois. *Wilson's Gloss.*, 441.

The *faddān*^{80a} is a measure of land of 100 square reeds, each of which is equal to one *bāa'*. An *Ibrahimi* is current for 40 *kabirs* and 14 *kabirs* is equal to a rupee of Akbar Shāh. In some parts of the Turkish empire, they exact from the husbandman 30 *Ākchehs* for every yoke of oxen. The *Ākcheh* is a silver coin equal to 81 *Ibrahimis*. And from crown lands the demand is 42 *Ākcheh*, and from each soldier 21, besides which the governor of the Subah takes 15 more. In some parts for each plough 20, and from each soldier 7 *Ākcheh*, while the Governor takes six. In others, the *Sanjaqbegi*⁸¹ receives 27 and the *Subashi* (kotwāl) twelve. Other systems are also given which obtain in that empire.

Note on Islamic land-tax.

The very obscure and complicated subject of the land system of early Islam can be best studied in the *Encyclopædia of Islam* by piecing together information scattered under the following words:—*Kharadj* (ii. 902), *Muqasama* (Suppl. 154), *Ushr* (iv. 1050-1052), *Dār-al-Sulh* (i. 919), and *Fai'* (ii. 38). Abu Yusuf Ibn Yaḡūb's *Kitāb-ul-Khirāj* (Fr. tr. by E. Fagan) is not very helpful. The application of the system to India in Aurangzib's reign is discussed in detail in Jadunath Sarkar's *Mughal Administration*, 3rd ed., ch. XI.

The term *sulhiy*, for the meaning of which Abul Fazl refers us to "ancient documents," will be understood from the following passages of the *Ency. Islam* (i. 919, under *Dār ul Sulh*): "With the Christian population of Najran Muhammad himself entered on treaty relationships, guaranteeing their safety and laying on them a certain tribute. See on the whole story, Baladhuri, *Futuh-al-Buldān*. The constitutional situation on the matter is thus

^{80a} *Faddān*, a certain measure of land, subdivided into 24 *qirāt*—loosely reckoned as the quantity which a yoke of oxen will plough in one day and commonly defined as consisting of $333\frac{1}{4}$ *gasabehs*, the latter being 24 *qabḍah*, and the *qabḍah* being the measure of a man's fist with the thumb erect, or about $6\frac{1}{4}$ inches. Lane's *Arab. Lex. Ency. Islam*, ii. 36.

⁸¹ *Sanjaq* is a word in Turkish, signifying a flag or standard: it also means a minor province of which several form one *Eyālat* or Government. It is in this latter sense that the word should probably be taken, signifying the provincial governor. An *Ākcheh* is $\frac{1}{2}$ of a *pāra* and consequently the $\frac{1}{2}$ of a piastre or the $\frac{1}{2}$ of a penny; it is frequently mentioned under the name of *asḡer*, a corruption of the Greek equivalent for the proper Turkish word. [*Ency. Islam*, iv. 148. *Aqcha*, in *ibid.*, i. 229].

formally laid down by Mawardi : All territories : . . under Muslim control . . . fall into three divisions : (i) those taken by force of arms ; (ii) those taken without fighting after the flight of their previous owners ; (iii) those taken by treaty (*Sulh*). . . In the last (class) if the title to the soil remains with the original owners, . . . the terms of the treaty are that the owners retain their lands and pay a *Kharāj* from their produce ; that this *kharāj* is regarded as a *jizya* which falls away when they embrace Islam ; that their lands are absolutely their own to sell or pledge ; and that their country is neither *Dār-ul-Islām* nor *Dār-ul-Harb* but *Dār-ul-Sulh*. When these lands pass to a Muslim, *Kharāj* can no longer be collected . . . Mawardi includes among the *Bilād al Islām* this *Dār-ul-Sulh*." Also, *ibid.*, ii. 38 under *Fai'* :—"Verses lix. 6, 3 and 10 of the *Qur'ān* were revealed when Muhammad had resolved not to divide the fields and orchards left by the Ban u'l Nādir, who had been driven out of the country, as booty of war among those who had taken part in the siege, but to give them to the Muhājirs exclusively. He justified this action by arguing that these were really obtained not by fighting, but in a peaceful fashion, by surrender."

the owner has voluntarily embraced that faith. 3rd, Lands which have been conquered and apportioned: 4th, Land on which an adherent of that faith has built a mosque or planted a vine or laid out a garden or fertilized it with rain water; otherwise other conditions apply. 4th, Waste land which has been brought into cultivation by permission of the owner. *Khīrāji* 1st kind; Persia proper and Kirmān. 2nd, Land which a tributary subject has laid out as grounds round about his house. 3rd, Land which a Muslim has reclaimed and irrigates from a source constructed from the public revenues. 4th, Land which has been acquired by convention. 5th, Land cultivated by means of water that pays revenue. *Sulhiy*, Lands of the Bani Najrān and Bani Taghlib;⁸³ the details of these may be learnt from ancient documents. Likewise, in some treatises, land is regarded under three heads. 1st, Land cultivated by Muslims which they deem *U'shr*.⁸⁴ 2nd, Land of which the proprietors have accepted that faith. According to some, this is *U'shri*, and others say that it is *U'shri* or *Khīrāji*, according to the determination of the Imām. 3rd, Land acquired by conquest, which some make *U'shri* and others *khīrāji*, and others again affirm that its classification rests with the Imām. 4th, Land which those outside the faith retain on convention. This they call *khīrāji*. Tribute paid by *khīrāji* lands is of two kinds. 1. *Muqāsamah* (divided), is the 5th or 6th produce of the soil. 2. *Wazifah*⁸⁵ which is settled according to the capability and convenience of the tributaries. Some call the whole produce of the revenue *khīrāj*, and as the share of the producing body is in excess of their expenditure, the *Zakāt*⁸⁶ is taken from the amount under certain stipulations and this they call a tithe, but on

of the limits of *U'shri* are laid down exactly as in the text with the omission of Rabah. The *Fatāwa* i A'lamgiri follows Qāzi Khān. From the variants of this doubtful reading given in the notes, it is clear that there is some corruption and perhaps the variant of M.S. *Dal* is correct.

⁸³ The text has Tha'lab, a misprint. The details of the submission of these two tribes may be gathered from Caussin De Perc. *Essai sur l'histoire des Arabes*. *Ency. Islam*, iii. 825 (under *Nadīrān*), *Sup.* 254 (under *Uqail*), *Sup.* 223 (under *Taghlib*).

⁸⁴ This word signifies a tenth and is the tithe assessed on lands under Muslim rule. *U'shri* are therefore those lands subject to the tithe.

⁸⁵ *Wazifah* signifies a stipend or any thing stipulated or agreed upon; hence, revenue collected at a stipulated or fixed rate for a certain quantity of land. *Wilson's Gloss.*, 557.

⁸⁶ *Zakat*, the poor rate, the portion therefrom given as the due of God by the possessor that he may purify it thereby, the root of the word, *zakā*, denoting purity. The proportion varies, but is generally a fortieth or 2½ p.c. provided that the property is of a certain amount and has been in possession eleven months. See *Ency. Isl.* iv. 1202-1204.

each of these points there is much difference of opinion. The Caliph Omar, during his time, taxed those who were not of his faith at the rate of 48 dirhams for persons of condition, 24 for those of the middle class, and 12 for the lowest class. This was called the *Jaziyah* (capitation tax).

In every kingdom government taxes the property of the subject over and above the land revenue and this they call *Tamghah*.⁸⁷ In Irān and Turān they collect the land tax from some, from others the *Jihāt* and from others again the *Sāir Jihāt*, while other cesses under the name of *Wajuhāt* and *Farua'āt* are exacted. In short, what is imposed on cultivated lands by way of quit-rent is termed *Māl*. Imports on manufactures of respectable kinds are called *Jihāt*, and the remainder *Sair*⁸⁸ *Jihāt*. Extra collections over and above the land tax if taken by revenue officers are *Wajuhāt*; otherwise they are termed *Farua'āt*.

In every country such demands are troublesome and vexatious to the people. His Majesty in his wise statesmanship and benevolence of rule carefully examined the subject and abolished all arbitrary taxation, disapproving that these oppressions should become established by custom. He first defined the *gaz*, the *tanāb*, and the *bihah* and laid down their bases of measurement: after which he classed the lands according to their relative values in production and fixed the revenue accordingly.

A'IN VIII.

The Ilāhi Gaz

Is a measure of length and a standard gauge. High and low refer to it, and it is the desire of the righteous and the unrighteous. Throughout Hindustan there were three such measures current, *viz.*; long, middling and short. Each was divided into 24 equal parts and each part called *Tassuj*.^{ss} A *Tassuj* of the 1st kind was equal to 8 ordinary barley-corns placed together breadthways, and of the other two respectively, to 7 and 6 barley-corns. The long *gaz* was used for the measurement of cultivated lands, roads, distances, forts, reservoirs and mud walls. The middling was employed to measure buildings of stone and wood, bamboo-built houses, places of worship, wells and gardens, and the short *gaz* for cloth, arms, beds, seats of state, sedan chairs, palanquins, chairs, carts and the like.

In some other countries, although they reckon the *gaz* as consisting of 24 *Tassuj*, they make

1 Tassuj	equal to	2 Ḥabbah (grain).
1 Ḥabbah	„	2 Barley-corns.
1 Barley-corn	„	6 Mustard seeds.
1 Mustard seed	„	12 Fals.
1 Fals	„	6 Fatila.
1 Fatila	„	6 Naqir.
1 Naqir	„	8 Qitmir.
1 Qitmir	„	12 Zarrāh.
1 Zarrāh	„	8 Habā.
1 Habā	„	2 Wahmah.

Some make 4 *Tassuj* equal to 1 Dāng.
6 Dāng „ 1 Gaz.

Others reckon the *gaz* as 24 fingers, each finger equal to the breadth of 6 barley-corns, and each barley-corn equal in thickness to 6 hairs from the mane of a cob. In some ancient books they make the *gaz* equal to two spans and twice round the joint (*giriḥ*) of the thumb, and they divided it into 16 *giriḥ* and each *giriḥ* was subdivided into 4 parts

^{ss}a *Tassuj* is an arabicized word from the Pers. *tasu*, a weight of 4 barley-corns, the 24th part of a weight measure or day. *Ency. Islam*, iv. 692 (under *Tasudj*).

which they called 4 *pahr*, so that a *pahr* was the sixty-fourth part of a *gaz*.

In other ancient records the *gaz* is reckoned of seven kinds. 1st, The *Gaz i Sauda* (*Gaz* of traffic) consisting of 24 digits and two-thirds of a digit. Harun ur Rashid of the House of 'Abbās took this measure from the hand of an Abyssinian slave who was one of his attendants: the Nilometer^{88b} of Egypt is on this measure, and houses and cloths are also measured by it. 2nd, *Zirāa' i qasbah*, (Reed-yard) called also *A'āmah*, and *Daur*, of 24 digits: this was introduced by Ibn Abi Laila.⁸⁹ 3rd, The *Yusufiyah*, used by the provincial governors of Baghdad for the measurement of houses: it consisted of 25 digits. 4th, The short *Hāshimiyah*, of 28 digits and a third. Bilāl⁹⁰ the son of Abi Bardah introduced it: according to some it was Abu Musa Ash'ari his grandfather. 5th, The long *Hāshimiyah* of 29 digits and two-thirds which Mansur the A'bbaside favoured. It is also called the *Maliq* and *Ziyādiyah*. Ziyād⁹¹ was the so-called son of Abu Sufiyān who used it to measure the lands in Arabian Irāq. 6th, The *Omariyah* of 31 digits. During his Caliphate, Omar carefully considered the long, short and middling *gaz*. He took the three kinds together and to one-third of the aggregate he added the height of the closed fist and the thumb erect. He closed both ends of the measure with tin and sent it to Hudaifah⁹² and Othmān⁹³-b-Hunaif which they used for the measurement of the villages in Arabian Irāq. 7th, The *Māmuniyah* of 70 digits less a third. Mamun brought it into use, and it was employed for measuring rivers, plains and road distances.

^{88b} The cubit of the Nilometer is supposed to be the same as that of the Jews, which is exactly two feet English: if so the 24 digits will be precisely inches. A finger's breadth may be safely taken as three quarters of an inch. *Useful Tables*, pp. 87, 88. For *Zirā'* see *Ency. Isl.* i. 959 (under *Dhirā'*).

⁸⁹ *Muhammad-b-Abdur Rahmān*, surnamed Ibn Abi Layla, was a distinguished jurisconsult and one of the *Tābiis*. He was Qadhī of Kufa where he was born A.H. 74, and died in A.H. 148. D'Herb.

⁹⁰ *Bilāl*.—The grandson of Abu Musa al Ashari, Qadhī of Basrah, of which his grandfather had been Governor. See a brief notice of him in Ibn Khall. Vol. II, p. 2.

⁹¹ *Ziyād*, the governor of Irāq. (*Enc. Isl.* iv. 1232).

⁹² *Hudaifah*, one of the most eminent of the Companions of Muhammad. Omar appointed him to the government of Madāin, where he died after the assassination of Othmān and 40 days after the accession of 'Ali. Ibn Hajar. *Biog. Dict.*

⁹³ *Othmān*.—He was governor of Basrah under the Caliph 'Ali. Ibn Khall, p. 391, Vol. IV.

Some in former times reckoned the cloth-measure (*gaz*) to be seven times the fist, and the fist was equal to four fingers closed; according to others, one finger less. The survey *gaz*, according to some, was the same seven fists: others made it seven fists together with one finger (thumb?) erect added to the seventh fist. Others again added another finger to that fist; while some made it seven fists with one finger adjoined to each fist.

Sultan Sikander Lodi in Hindustān introduced another *gaz* of the breadth of 41 *Iskandarīs* and a half. This was a copper coin mixed with silver. Humayun added a half and it was thus completed to 42. Its length was 32 digits. But some authors anterior to his time make mention of a similar measure. Sher Khān and Salim Khān [Sur], under whom Hindustān was released from the custom of dividing the grain and its apportionment, in measuring land used this *gaz*. Till the thirty first-year of the Divine Era, although the *Akbar Shāhi gaz* of 46 fingers was used as a cloth-measure, the *Iskandari gaz* was used for cultivated lands and buildings. His Majesty in his wisdom, seeing that the variety of measures was a source of inconvenience to his subjects, and regarding it as subservient only to the dishonest, abolished them all and brought a medium *gaz* of 41 digits into general use. He named it the *Ilāhi gaz* and it is employed by the public for all purposes.

A'IN IX.

*The Tanāb.*⁹⁴

His Majesty fixed for the *jarib* the former reckoning in yards and chose the measurement of sixty square, but adopted the *Ilāhi gaz*. The *Tanāb* (tent rope) was in Hindustān a measure of hempen rope twisted which became

⁹⁴ The *Tanāb*, *jarib* and *Bigha* seem to have been indiscriminately used as nearly interchangeable terms. The *jarib* in its original use, according to Wilson. (*Glossary*), was a measure of capacity equal to 60 *qasiz* or 384 *madd*, about 768 pounds. It then became applied to a land measure, or as much land as could be sown with a *jarib* of seed-corn, and then appears to have been loosely used for a *bigha*. In course of time it occurs as a measure of land of various extent, and as the chain or rope for measuring. In the N. W. P. the measurements were made by a chain, and the *jarib* is = to 5

shorter or longer according to the dryness or moisture of the atmosphere. It would be left in the dew and thus fraudfully moistened. Oftentimes it would be employed in the early morning when it had got damp and had shrunk, and by the end of the day it had become dry and had lengthened. In the former case, the husbandmen suffered loss, in the latter the royal revenues were diminished. In the 19th year of the Divine era, the *jarib* was made of bamboos joined by iron rings. Thus it is subject to no variation, and the relief to the public was felt everywhere while the hand of dishonest greed was shortened.

A'IN X.

The Bigha

Is a name applied to the *jarib*. It is a quantity of land 60 *gaz* long by 60 broad. Should there be any diminution in length or breadth or excess in either, it is brought into square measure and made to consist of 3600 square *gaz*.⁹⁵ They divide the *bigha* into 20 parts, each of which is called *biswah*, and this is divided into 20 parts each of which is termed *biswānsah*. In measuring they reduce no further. No revenue is required from 9 *biswānsah*, but ten they account as one *biswah*. Some, however, subdivide the *biswānsah* into 20 parts, each of which they called *taswān-*

chains of 11 yards each, or to 60 *gaz* or 20 gathas or knots. A square of one *jarib* is a *bigha*. Before the new system of survey, it was usual to measure lands paying revenue with a *jarib* of 18 knots only, two being coiled round the measurer, but free lands were measured with the entire rope of 20 knots. In Sindhi a *jarib* is a measure of a 150 square feet. In Telegu, it is applied to garden land or its produce. The standard *bigha* of the revenue surveyors of the N. W. P. is = to 3,025 sq. yds. or $\frac{1}{4}$ of an acre. In Bengal the *bigha* contained only 1,600 sq. yds. or a little less than $\frac{1}{2}$ of an acre. In Benares at the time of the settlement, it was determined at 3,136 sq. yds. In other *perganahs* it was equal to 2,025 to 3,600 or 3,925 sq. yds. A *kachha bigha* is in some places a third, in others only a fourth of a full *bigha*. Akbar's *bigha* of 3,600 *Ilahi gaz* was considered = to 3,025 sq. yds. of the *bigha* of Hindustān. In Cuttack the *bigha* is now considered to be an English acre. The Maratha *bigha* is called 20 *pānds* or 400 sq. *kālhis* or rods of (each) 5 cubits and 5 hand-breadths. The Guzerāt *bigha* contains only 284 $\frac{1}{2}$ sq. yds. Mr. Elliot specifies six variations found in the Upper Provinces. See Wilson's *Gloss.* under *Bigha* and *Jarib*. *Ency. Islam*, iii. 530-539 (under *al-Mizān*) and i. 1018 (under *Ujarib*). Elliot *Memoirs*, ii. 189 (*jarib*).

⁹⁵ The text has an error of 60 for 600. 3600 sq. *gaz* = 2,600 sq. yards = 0.538 or somewhat more than half an acre. *U. T.*, p. 88.

sah, which they again divide into 20 parts, calling each *tapwānsah*. This again they partition into 20 portions, and name them severally *answānsah*. A *bigha* as measured by the *tanāb* of hemp, was two *biswah* and 12 *biswānsah* smaller in extent than the *bigha* measured by the *tanāb* of bamboo. This makes a difference of 10 *bigha* in a hundred. Although the *tanāb* of hemp was of 60 *gaz*, yet in the twisting it shrank to 56. The *Ilāhi gaz* was longer than the *Iskandari* by one *biswah*, 16 *biswānsah*, 13 *taswānsah*, 8 *tapwānsah*, and 4 *answānsah*. The difference between the two reduced the *bigha* by 14 *biswah*, 20 *biswānsah*, 13 *taswānsah*, 8 *tapwānsah*, and 4 *answānsah*. In one hundred *bighas* the variation in the two measures amounted to 22 *bighas*, 3 *biswah* and 7 *biswānsah*.

A'IN XI.

Land and its classification, and the proportionate dues of Sovereignty.

When His Majesty had determined the *gaz*, the *tanāb*, and the *bigha*, in his profound sagacity he classified the lands and fixed a different revenue to be paid by each.

Polaj is land which is annually cultivated for each crop in succession and is never allowed to lie fallow.

Parauti is land left out of cultivation for a time that it may recover its strength.

Chachar is land that has lain fallow for three or four years.

Banjar is land uncultivated for five years and more.

Of the two first kinds of land, there are three classes, good, middling and bad. They add together the produce of each sort, and a third of this represents the medium produce, one-third part of which is exacted as the royal dues. The revenue levied by Sher Khān, which at the present day is represented in all provinces as the lowest rate of assessment, generally obtained, and for the convenience of the cultivators and the soldiery, the value was taken in ready money.

*Produce of Polaj Land.⁹⁶ Spring Harvest, called in
Hindi Asādhi..*

	Produce of a <i>bigha</i> of the best sort of <i>Polaj</i> .		Produce of a <i>bigha</i> of the middling sort.		Produce of a <i>bigha</i> of the worst sort.		Aggregate produce of three <i>bighas</i> of different sorts.		One third of the proceed- ing, being the medium produce of a <i>bigha</i> of <i>polaj</i> .		One third of the medium produce, being the pro- portion fixed for the revenue.	
	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.
Wheat ...	18		12		8	35	38	85	12	88 $\frac{1}{2}$	4	12 $\frac{3}{4}$
<i>Nukhud</i> —(Vetches) ...	13		10	20	7	20	81	0	10	19 $\frac{1}{2}$	8	18
<i>Adas</i> —Pulse (Cicer lins) in Hindi. <i>Masur</i> ...	8	10	6	20	4	25	19	15	6	18 $\frac{1}{2}$	2	6
Barley ...	18	0	12	20	8	15	38	85	12	38 $\frac{1}{2}$	4	12 $\frac{1}{2}$
Linseed ...	6	20	5	10	8	80	15	20	5	7	1	29
Safflower—(<i>carthamus tinctorius</i>) ...	8	30	6	30	5	10	20	80	6	86 $\frac{1}{2}$	2	12
<i>Arzan</i> —Millet (<i>Penicum</i> <i>miliaceum</i> (in Hindi <i>China</i>) ...	10	20	8	20	5	5	24	5	8	11 $\frac{1}{2}$	2	27 $\frac{1}{2}$
Mustard ...	10	20	8	20	5	5	24	5	8	11 $\frac{1}{2}$	2	27 $\frac{1}{2}$
Peas ...	13	0	10	20	8	25	32	5	10	23	3	28
Fenugreek (<i>Methi</i>) ...	14	0	11	0	9	85	34	35	11	25	3	85
Kur rice ...	24	0	18	0	14	10	56	10	18	80	6	10

The revenue from musk melons, *ajwāin* (*Ligusticum ajowan*), onions and other greens not counted as produce, was ordered to be paid in ready money at the rates herein-after mentioned.

⁹⁶ I have copied the *form* of the 4 following tables from Gladwin. Abul Fazl makes the calculation for the 4th and 5th columns for wheat only. For vetches and pulse he omits the 4th column and omits the 4th and 5th of all the remainder. The fractions below a quarter of a seer are discarded in calculating the proportion fixed for revenue: the thirds are not always mathematically exact, and fractions are sometimes raised to a unit or altogether omitted.

Polaj Land.

The Autumn Harvest, called in Hindi SĀWANĪ.

	Produce of a <i>bigha</i> of the best sort of <i>Polaj</i> .		Produce of a <i>bigha</i> of the middling sort.		Produce of a <i>bigha</i> of the worst sort.		Aggregate produce of three <i>bighas</i> of different sorts.		One third of the preceding, being the medium produce of a <i>bigha</i> of <i>polaj</i> .		One third of the medium produce, being the proportion fixed for the revenue.	
	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.
Molasses ⁷⁷ ...	13	0	10	20	7	20	31	0	10	13½	3	18
Cotton ...	10	0	7	20	5	0	22	20	7	20	2	20
<i>Shālī Mushkin</i> —Dark coloured, small in grain and white, fragrant, that ripens quickly and pleasant to taste ...	24	0	18	0	14	10	56	10	18	80	6	10
Common rice, not of the above quality ...	17	0	12	20	9	15	38	35	12	38½	4	13
<i>Māash</i> —in Hindi <i>Mung</i> (<i>Phaseolus mungo</i>) ...	10	20	7	20	5	10	28	10	7	80	2	23½
<i>Minsh</i> <i>Siāh</i> —H. <i>Urīdh</i> (a kind of vetch) ...	10	20	7	20	5	10	28	10	7	80	2	23½
<i>Moth</i> (lentils), coarser than the white <i>mung</i> and better than the dark ...	6	20	5	10	3	30	15	20	5	6½	1	29
<i>Jowār</i> (<i>Andropogon Sorghum</i> . Roxb.) ...	13	0	10	20	7	20	31	0	10	13½	3	18
<i>Shamākī</i> —H. <i>Sanwān</i> (<i>Panicum frumentaceum</i> . Roxb.) ...	10	20	8	20	5	5	24	5	8	1½	2	27½
<i>Kodron</i> ⁷⁸ (like <i>Sanwān</i>) but its outer husk darkish red ...	17	0	12	20	9	15	38	35	12	38½	4	12½
Sesame ...	8	0	6	0	4	0	18	0	6	0	2	0
<i>Kanguni</i> (<i>Panicum italicum</i>) ...	6	20	5	10	3	30	15	20	5	7	1	29
<i>Turiya</i> , like mustard seed, but inclined to red ...	6	20	5	10	3	30	15	20	5	7	1	29
<i>Arzan</i> (<i>Panicum miliaceum</i>) generally a spring crop	16	0	13	20	10	25	40	5	18	1½	4	19½
<i>Lahdarah</i> grows in ear, the grain like <i>Kanguni</i>	10	20	7	20	5	10	28	10	7	80	2	23½
<i>Mandīkah</i> (<i>Cynosurus corocanus</i>) the ear like <i>Sanwān</i> , the seed like mustard seed, but some red, some white ...	11	20	9	0	6	20	27	0	9	0	3	0

⁷⁷ The 4th and 5th columns have been omitted by Abul Fazl.⁷⁸ A variant gives *Kodron* and *Koderam* probably the same as *Kodo*—a small grain (*Paspalum frumentaceum*). Wilson's *Glossary*, 292.

The Autumn Harvest, called in Hindi SĀWANI.—Contd.

	Produce of a <i>bigla</i> of the best sort of <i>Polaj</i> .		Produce of a <i>bigla</i> of the middling sort.		Produce of a <i>bigla</i> of the worst sort.		Aggregate produce of three <i>biglas</i> of different sorts.		One third of the preceding, being the medium produce of a <i>bigla</i> of <i>polaj</i> .		One third of the medium produce, being the proportion fixed for the revenue.	
	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.
<i>Lobiya</i> (<i>Dolichos sinensis</i>), resembles a bean, somewhat small ...	10	20	7	20	5	10	28	10	7	30	2	20½
<i>Kudiri</i> , like <i>Sāman</i> but coarser ...	6	20	5	10	3	30	15	20	5	7	1	29
<i>Kull</i> , (<i>Dolichos uniflorus</i>) like a lentil somewhat darker, its juice good for camels: it softens stone and renders it easy to cut ...	10	20	7	20	5	10	23	10	17	30	2	20½
<i>Batti</i> , like <i>Sāman</i> but whiter (a species of <i>Panicum</i>) ...	6	20	5	10	3	30	15	20	5	7	1	29

As a consideration for watching the crops a quarter of a seer (per maund) is allowed in some places and in others more, as will be shown.

The revenue from indigo, poppy, *pān*, turmeric, water chestnut⁹⁹ (*trapa bispinosa*), hemp, *kachālu* (*arum colocasia*) pumpkin, *hinna* (*Lawsonia inermis*) cucumbers, *bādrang* (a species of cucumber), the egg-plant (*solanum melongena*), radishes, carrots, *karelā* (*momordica charantia*) *kakura* (*Momordica Muricata*), *tendas*,¹⁰⁰ and musk-melons,

⁹⁹ This is the *Singārah* or Singharah. In the month of November, the nut ripens and such of the fruit as remains ungathered, falls off and sinks to the bottom of the pond. When the water dries up in May or June, these nuts or bulbs are found to have thrown out a number of shoots. They are then carefully collected and placed in a small hole in the deepest portion of the tank and covered with water. In the rains when the ponds begin to fill, the bulbs are taken up, each shoot is broken off, enveloped in a ball of clay to sink it and thrown into the water at different distances. They at once take root and grow rapidly until in a short time the surface of the water is covered with leaves. The fruit forms in October. The produce of a standard *bigla* is about 2½ *mans* which at the selling price of 10 *seers* for the rupee, represent a total value of Rs. 10. It is much more extensively consumed by the Hindus than the Mahomedans. Carnegie's *Kachhari Technicalities*.

¹⁰⁰ Also called *tendu*: resinous fruit of the tree *Diospyros glutinosa*,

not counted as produce, was ordered to be paid in ready money at the rates hereafter mentioned.

Parauti land when cultivated, pays the same revenue as *polaj*.

His Majesty in his wisdom thus regulated the revenues in the abovementioned favourable manner. He reduced the duty on manufactures from ten to five per cent. and two per cent. was divided between the *patwari* and the *qānungo*. The former is a writer employed on the part of the cultivator. He keeps an account of receipts and disbursements, and no village is without one. The latter is the refuge of the husbandman. There is one in every district. At the present time the share of the *qānungo* (one per cent.) is remitted and the three classes of them are paid by the State according to their rank. The salary of the first is fifty rupees: of the second, thirty; of the third, twenty; and they have an assignment for personal support equivalent thereto. It was the rule that the commissaries of the *shiqdar*, *karkun*,¹⁰¹ and *Amin* should receive daily 58 *dāms* as a perquisite, provided that in spring they did not measure less than 200, nor in autumn less than 250 *bighas*. His Majesty whose heart is capacious as the ocean, abolished this custom and allowed only one *dām* for each *bigha*.

Many imposts, equal in amount to the income of Hindustān were remitted by His Majesty as a thank-offering to the Almighty. Among these were the following:

The capitation tax, *jizya*.

The port duties, *mir-bahari*.

Tax¹⁰² per head on gathering at places of worship, *kar*.

A tax on each head of oxen, *gāo-shumārī*.

A tax on each tree, *sar-i-darakhtī*.

Presents, *peshkash*.

Distraints, *qurq*.

A tax on the various classes of artificers, *peshawar*.

Dārogha's fees, *dāroghānah*.

Tahsildār's fees, *tahsildārī*.

Treasurer's fees, *foṭahdārī*.

¹⁰¹ *Kārkun*, the registrar of the collections under a *Zamindar*. The *Amin* was an officer employed either in the revenue department to take charge of an estate and collect the revenues on account of government, or to investigate and report their amount: or in the judicial department, as a judge and arbitrator in civil causes: Wilson's *Gloss.*, 261.

¹⁰² The word is *kar* in the text, and is probably from the Sansk. कर an impost, fee or cess. These imposts are called *wajuhāt* in the text, and *ābwābs* in the later Mughal days. For a full account of the *ābwābs*, see Sarkar's *Mughal Adm.*, 3rd ed., ch. v. § 8 and 9.

Complimentary offerings on receiving a lease and the like, *salāmi*.

Lodging charges, *wajih kirāya*.

Money bags, *kharitah*

Testing and exchanging money, *sarrāfi*.

Market duties, *hāsīl-i-bāzār*.

Sale of cattle (*nakhās*); also on hemp, blankets, oil, raw hides, weighing (*Kayyālī*), scaling; likewise butcher's dues, tanning, playing at dice,¹⁰³ passports for goods, turbans,¹⁰⁴ hearth-money [*dudi*, *har ke ātish āfruzad chize bar dehad*, i.e., fee for illumination?] fees on the purchase and sale of a house, on salt made from nitrous earth, *balkati* on permission to reap the harvest, felt, manufacture of lime, spirituous liquors, brokerage, catching fish, the product of the tree *Āl* (*Morinda citrifolia*);¹⁰⁵ in fine all those imposts which the natives of Hindustān include under the term *Sair Jihāt*,¹⁰⁶ were remitted.

ĀIN XII.

Chachar land.

When either from excessive rain or through an inundation, the land falls out of cultivation, the husbandmen are, at first, in considerable distress. In the first year, therefore, but two fifths of the produce is taken: in the second three-fifths; in the third,¹⁰⁷ four-fifths and in the fifth, the ordinary revenue. According to differences of situation, the revenue is paid either in money or in kind. In the third year the charges of 5 per cent. and one *dām* for each *bigha*¹⁰⁸ are added.

¹⁰³ Two words follow which are marked in the text as doubtful, there is doubtless an omission.

¹⁰⁴ The word is *pag*, contraction of *pagri*, a turban. It was a kind of poll tax levied on every turban.

¹⁰⁵ From which a dye is extracted.

¹⁰⁶ See p. 63.

¹⁰⁷ There is probably an error in the text as the fourth year is omitted. Gladwin has "the third and fourth years fourth-fifths each."

¹⁰⁸ I take the *wa* between *dah wa nim* to be an error, as by retaining it the percentage would rise to 15 or at least to 10½. Five per cent. was levied on manufactures; it may therefore have been an extra charge on land though I do not see its reason or its justice. Gladwin translates as I have done.

AIN XIII.

Banjar land.

When through excessive inundations production has seriously diminished, the revenue is collected in the following proportions :

*Spring Harvest**Proportion of revenue from one Bigha of Banjar land for five years.*

				1st year		2nd year		3rd year		4th year		5th year
				Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	
Wheat	I.	0	20	1	0	2	0	8	0	as <i>polaj</i>
Mustard	R.	0	5	0	25	0	35	1	10	"
Vetches	Nukhud	...	I.	0	10	0	30	1	10	2	10	"
Do.	R.	0	5	0	80	1	10	2	10	"
Barley	I.	0	20	1	0	2	0	8	0	"
Do.	R.	0	5	0	85	1	20	2	20	"
Pulse	(<i>Cicer lens</i>)	Adas	I.	0	10	0	30	1	10	1	80	"
Do.	R.	0	5	0	80	1	10	1	80	"
Millet	(<i>Panicum miliaceum</i>)	...										
	Arzan	...	I.	0	10	0	25	0	35	1	0	"
Do.	R.	0	5	0	25	0	85	1	0	"
Linseed	I.	0	10	0	20	0	30	1	10	"
Do.	R.	0	5	0	5	0	80	1	10	"

Note. I stands for inundated land, and R for that which has suffered from rain.

*Autumn Harvest.**Proportion of revenue from one Bigha of Banjar land for five years.*

				1st year		2nd year		3rd year		4th year		5th year
				Md.	Sr.	Md.	Sr.	Md.	Sr.	Md.	Sr.	
Māsh	I.	0	20	1	0	1	20	2	10	as <i>polaj</i>
Do.	R.	0	5	0	20	1	0	1	20	"
Jowār	I.	0	20	1	0	2	0	8	0	"
Do.	R.	0	5	0	20	1	0	2	0	"
Moth	R.	0	5	0	20	0	30	1	10	"
Lahdarah	R.	0	5	0	20	1	10	2	0	"
Kodron	I.	0	20	1	0	2	0	3	0	"
Do.	R.	0	5	0	20	1	20	2	20	"
Mandwah	I.	0	20	1	0	2	0	3	0	"
Do.	R.	0	5	0	80	1	10	2	10	"
Kudiri	I.	0	10	0	25	0	85	1	10	"
Do.	R.	0	5	0	25	0	85	1	10	"
Kanguni, (Pers. <i>kāl</i>)	I.	0	10	0	25	0	35	1	10	"
Do.	R.	0	5	0	25	0	35	1	10	"
Turiya	I.	0	20	1	0	1	10	1	20	"
Do.	R.	0	5	0	25	0	35	1	10	"
Sarwān (Pers. <i>Shamākh</i>)	I.	0	10	0	25	0	35	1	10	"
Do.	R.	0	5	0	25	0	85	1	10	"
Arzan	I.	0	10	0	80	1	0	1	10	"
Do.	R.	0	5	0	30	1	0	1	10	"
Sesame	R.	0	5	0	20	0	80	1	10	"

In the 4th year the charges of 5 per cent. and one *dām* for each *bigha* were collected and this is still in force.

In *Banjar* land for the 1st year, one or two *sers* are taken from each *bigha*; in the 2nd year, 5 *sers*; in the 3rd year, a sixth of the produce; in the 4th year, a fourth share together with one *dām*: in other years a third suffices. This varies somewhat during inundations. In all cases the husbandman may pay in money or kind as is most convenient. *Banjar* land at the foot of the hills and land subject to inundations in the districts of Sanbhal and Bahrāich, do not remain as *banjar*, for so much new soil is brought down with the overflow that it is richer and more productive than *polaj*. His Majesty, however, in his large munificence places it in the same class. It is in the option of the cultivator to pay in ready money or by *kankut* or *bhaoli*.

ĀIN XIV.

*The Nineteen Years' Rates.*¹⁰⁹

Intelligent people have from time to time set themselves to record the prices current of the Empire, and after careful inquiry the valuation of grain was accepted on this basis.

The revenue rates for a *bigha* of *polaj* land were fixed as has been stated. From the 6th year of the Divine Era which runs with the Novilunar year 968 (A. D., 1560-1) and concluding with the 24th year of this reign, the statistics were collected and have been tabulated for reference after the most diligent investigation. The figures are entered under the heading of each year.

¹⁰⁹ Nineteen years correspond with a cycle of the moon during which period the seasons are supposed to undergo a complete revolution. Gladwin, p. 292, Vol. I.

Spring Harvest of the Subah of Agra. Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat	90 dams D.	80 to 90 D	90 D.	50 to 60 D.	56 to 60 D.	56 to 60 D.	56 to 60 D.	52 to 60 D.	38 to 48 D.	86 to 52 D.	86 to 74 D.	43 to 54 D.	32 to 50 D.	40 to 58 D.	42 to 80 D.	64 to 94 D.	40 to 58 D.	52 to 116 D.
Cabul Vetches	88-57	38-57	38-57	38-57	38-57	88-57	88-57	88-57	26-52	50-55
Indian do	80	76-80	80	44-56	44-56	44-56	44-56	82-10	20-88	20-30	20-48	19-28	19-20	21-38	19-44	26	22-37	40-36
Barley	80	60-76	60	38-50	38-50	40-54	40-54	36-40	21-28	21-34	21-54	28-30	20-40	26-40	28-52	86-54	28-86	40-90
Pot-herbs	80	80	80	80	80	80	80	80	52-60	50-70	50-60	40-54	40-60	44-62	44-60	44-60	46-60	46-60
Poppy	160	160	160	140	140	140	140	140	180	100-180	100-180	100-180	100-180	100-180	100-180	100-180	100-180	100-180
Safflower	20 sers	20 sers.	20 sers.	80	80	80	80	70-76	60-70	60-70	52-70	50-70	40-78	54-78	54-78	54-78	54-73	54-73
Linseed	60-80	60-80	60-80	60-80	50-56	24-30	18-30	18-28	23-26	24-28	24-26	16-34	16-34	18-26	24-42
Mustard	80	80	80	60-80	60-80	60-80	60-80	50-56	22-30	20-30	24-32	22-30	22-26	19	19-32	20	18	30-48
Adas (Pulse)	60	60-68	50	82-50	82-50	82-50	82-50	26-32	15-24	15-28	15-80	15-22	15-28	17-25	16-40	16-20	16-24	25-50
Arsan (Millet)	44	44	20	30	80	80	80	26-28	14-20	15-22	15-24	14-18	14-17	16-19	11	12	12-24	16-34
Pear	...	68	44	15-26	15-42	15-42	15-42	19-24	17-28	17-80	17-80	17-80	18-28	32
Persian Musk-melons	120	86-120	86-120	86-120	86-120	86-120	86-120	82-120	82-120	82-120	82-120
Indian do	10	10	16	16	15-16	15-16	8-16	15-16	15-16	10-16	12-16	12-16	12-16
Kur rice	60	60	60	50-60	54-60	60	60	4-70	86-48	86-44	86-54	32-50	32-42	82-54	84-56	84-48	84-48	50-70
Ajwain
Lig-usticum ajo-wan	80	80	80	80	80	80	80	70	70	70-90	70-71	60-90	70	50-80	70-90	70-90	70-74	72-74

Note. In these tables D stands for *dām* and J for *jēal* the 25th part of a *dām* which is the 40th part of a rupee.

Spring Harvest of the Subah of Allahabad. Nineteen years' Rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat	90	90	90	60-64	80-100	80-100	...	62	48-70	42-100	42-100	48-70	40-70	42-64	48-86	62-86	40-62	40-75
Cabul Vetches	38-50	50	50	50	50	33-50	33-50	83-75	26-75	40-68
Indian do.	24-70	18-40	82-45	20-45	20-45	80-74	48-57	38-50	22-44	24-43
Barley	70	80	80	56-64	76-90	76-90	76-90	76-90	50-106	50-100	50-100	40-100	40-100	40-100	44-60	46-60	43-60	87-60
Pot-herbs	80	80	80	80-120	80	80	80	70-76	44	28-70	32-50	30-50	21-50	22-50	22-47	45-83	38-56	24-56
Poppy	160	160	160	140	140	140	140	130	100-130	100-130	100-130	100-130	100-130	100-130	100-130	100-130	100-130	100-130
Safflower	1 man	1 man	1 man	70-80	80	80	80	76	60-70	60-70	60-70	52-70	50-70	48-70	56-70	56-70	56-70	56-70
Linseed	80	80	80	70-80	80	80	80	64	80-80	26-64	80-64	18-64	20-64	22-81	28-28	20-28	18-22	18-24
Mustard	80	80	80	70-80	80	80	80	20-60	30-80	26-44	26-44	22-44	24-44	25-48	26-48	28-36	22-80	22-44
Adas	60	60	50	40-54	54-60	54-60	54-60	42	17-60	18-40	24-40	15-40	15-40	18-43	24-86	21-35	25-28	17-38
Arzan	44	44	20	30	40	30-40	26-86	19-86	17-36	17-86	14-86	16-86	16-23	14-28	16-28	14-23	14-28	14-80
Pens	15-60	18-43	17-40	14-40	15-40	17-3	17-44	17-44	17-44	17-28	18-41
Persian Musk-melons	120	120-160	120-160	120-160	80-160	66-160	43-160	86-120	86-120	86-120	86-120
Indian do.	10-12	12-16	12-16	12-16	8-16	9-16	12-40	12-16	12-16	12-16	12-16
Kur rice	40-60	44-46	40-48	40-48	36-46	88-46	22-42	36-42	82-42	40-42	42-50
Atwain	80	70-100	70-100	70-100	60-100	52-100	52-70	52-73	70-73	52-78	52-78
Onions	70-100	70-100	70-100	70-100	70-100	70-100	62-76	72-76	72-76	70-95
Pennegreek	36-70	36-70	36-70	36-70	36-70	50-73	52-72	52-72	28-80	40-80
Carrots	1 man	do.	do.	do.	do.	do.	do.	do.	24-30	24-80	24-80	28-40	20-40	20-52	20-26	20-25	14-25	16-24
Lettuce	24	24	24	24	25	25	25	25	16	25

Autumn Harvest of the Subah of Allahabad. Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Sugar-cane (<i>panda</i>) ..	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.
Common sugar-cane	180	180	180	180	200	200	200	200	200	200	200	200	170-200	160-200	180-200	180-200	180-200	180-200
Dark coloured rice (<i>Shālī</i> <i>Mushkin</i>)	80-90	80-90	80	80	80-90	80-90	80-90	80-90	50-76	54-77	49-77	49-77	56-76	56-76
Common rice	70	70	70	70	86-80	86-80	70	48	86-80	36-50	36-57	84-57	37-57	37-58	42-59	40-50	86-44	86-44
Munji rice	48	48	48	48	48	48	48	60	44	65	65	65
Cotton	120	120	180	110	90-120	90-120	120	96	90-120	70-100	70-120	70-120	70-120	70-120	70-128	80-102	70-102	50-70
Pot herbs ..	70	60	80	80	70	70	80	80	70	70-100	60-100	50-100	50-100	60-94	60-94	60-94	60-86	60-99
Sesame seed	60	60	80	80	50-100	50-100	80	64	50-100	39-50	89-40	28-40	28-40	26-38	22-82	24-82	24-52	24-46
Moth (lentils)	48	48	54	44	22-60	22-60	50	36	22-60	29-46	22-46	20-46	18-46	18-80	22-28	16-20	16-27	16-28
Māsh ..	48	48	54	44	28-70	28-70	48	96	28-70	28-42	28-42	24-42	25-42	27-44	21-44	21-40	24-45	24-45
Mung ..	48	48	54	44	82-72	82-46	44	44	82-72	82-46	32-46	30-46	38-46	82-48	28-56	34-56	80-50	26-56
Jowār ..	50	50	60	48	26	26	48	40	26	26	26	26-27	22-26	29-46	22-54	30-54	82-40	24-44
Laharāh ..	48	48	48	44	20	20	50-56	40-56	20	20	20	20-22	16-40	20-48	20-48	24-40	28-40	28-61
Lobiya	56	42	50-56	..	56	42	82-42	82-42	92-42	21-48	34-44	28-58	20-86	20-44
Kodaram ..	44	44	44	44	21-60	21-83	54-64	36	21-60	21-83	20-44	20-22	16-86	20-98	76-48	81-48	22-80	20-44
Kori ..	40	40	50	24	10	10	30	20	10	10	10	10	7-22	7-14	7-14	10	10	7-14
Shamākh ..	86	36	50	80	30	30	36-54	80	30	20	10-40	10-22	10-22	7-22	8-22	7-14	10-18	10-17
Gul ..	44	44	50	40	18-44	13-24	50-56	28	18-44	13-24	18-24	10-24	8-24	10-21	15-23	15-23	14-24	12-22

Autumn Harvest of the Subah of Allahabad (continued). Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Arzan	44	41	50	40	40	40	40	86	20-86	20-86	20-86	20-36	18-36	20-88	14-28	14-28	14-28	14-30
Mandwah	46	48	50	40	40	52-56	52-56	84	22-56	22-29½	22-29½	17-29½	18-29	19-39½	25-82	25-32	22-28	18-28
Indigo	140	140	160	140	140	140	140	186	150-160	130-160	120-160	130-160	130-160	180-140	132-140	132-140	182-140	182-160
Elemp	80	80	80	80	80	80	80	77	70-120	70-80	70-80	76-80	76-80	60-88	60-90½	80	80	80
Turiya	80	80	80	32-80	32-44	32-44	24-44	24-44	82-40	26-40	26½-40	26½-40	26½-40½
Turneric	100	100	100	100	100	100	100	100	100	100
Kachalu	70	70	60	60	60	60	60	60	60	60
Kull	20	86	86	36	36	24	24	24	18	29½
Hinna	58	58	58	58	58	60-80	60-80	60-80	60-80	60-80
Watermelons	10-12	10-12	10-12	10-12	19½-12	10-14	10-14	10-14	10-14	10-14
Pan	180	180	180	180	180	160	200	200	240	240
Singhara	100	100	100	100	100	100	100	100	100	100
Arhar (Cytisus
Cajan)	20	20	20	20	20

Spring Harvest of the Subah of Oudh. Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat ...	D. 90	D. 90	D. 90	D. 52-60	D. 52-80	D. 52-80	D. 52-70	D. 46-65	D. 48	D. 42-50	D. 50-52	D. 33-46	D. 33-48	D. 46-50½	D. 46-70	D. 54-74½	D. 32-44	D. 38-46
Cabul vetches	50	50	50	50	50	50	50	50	50	50
Indian do. ...	80	80	80	40-56	48-76	48-76	48-74	84-58	24-88	26-33	26-38	20-27	20-28	80-41	42-57	30-57½	19-44	21-40
Barley ...	80	70	60	42-50	42-60	52	48-50	36-44	28-82	30-32	32-61	20-27	20-28	29½-45	48-62	34-56½	2-30	24-10
Pot-herbs ...	80	80	80	80	80	80	80	62-72	56-60	50-61	50-61	40-62	40-60	40-52	40-52	40-52	44-60	24-60
Poppy ...	160	160	160	140	140	140	140	130	130	180	100-180	100-130	100-130	100-180	100-180	100-130	100-180	100-180
Safflower ...	man ½	man ½	man ½	80	80	80	80	60-70	80-81	60-70	61-70	52-70	52-70	54-60	54-60	54-70	54-70	54-70
Linseed ...	80	80	80	68-80	68-80	68-80	68-80	50-68	80-81	26-81	26-81	80-31	18-31	20-27	21-81	17½-28	17-20	17-24
Mustard ...	80	80	80	68-80	68-80	68-80	68-80	54-60	80-33	28-33	26-38	22-83	22-83	25-39	19-31	25-31	20-28	21-22
Adas ...	60	60	50	40	40-54	40-54	50-54	82-40	18-27	19-20	20	14-19	14-18	17-24	20-24	19-28	19-22	18½-25
Arzan ...	44	44	20	80	80-40	80-40	80-40	26	15-17	17-20	17-20	14-18	14-16	16-18	14-17	16-17	14-16	14-17
Peas	28	28	16-28	15-31½	15	16-28	16-22	16-24	16-81
Persian Muskmelons	120	120	160-180	66-120	86-120	86-120	86-120	86-120	86-120
Indian do. ...	10	10	10	10	8-10	8-10	8-10	8-10	16	8-16	16	19-16	8-16	15-16	12-16	12-16	12-16	12-16
Kur rice ...	66	66	66	50-60	50-60	50-60	60-72	52-60	44-46	36-46	36-46	86-46	28-46	22-42	82-42	85-42	85-42	86-58
Ajwain ...	80	80	80	80	80	80	80	70	70	70	70-71	60-70	70	52-70	52-78	70-78	70-78	52-73
Onions	70-73	70	70-78	70-73	70	70-74	70-74	70-74	70-74	70-74
Fenugreek	70	70	70	70	70	52-80	52-80	50-80	52-80	50-80
Carrots ...	1 man	do.	do.	80	24	24	50-90	24	20-25	20-28	20-28	14-28	17-28
	24	24	24	24	25	25	25	25	16	25

Autumn Harvest of the Subah of Oudh. Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Sugar-cane (<i>paunda</i>)
Common Sugar-cane	180	180	180	160	200	200	200	200	200	124-144	200	200	200	200	200	200	200	200
Dark coloured rice
(<i>Shadli Mushkin</i>)
Common rice	70	70	70	60	80	80	80	60	56	56-68	56	56-70	50-70	54-70	49½-68	44-76	40-76	36-60
<i>Munji</i> rice
Cotton	120	120	130	110	110-130	110-120	110-120	88	...	90	70-90	70-74	72-130	72-130	65-79	64-70	50-60	46-90
Pot-herbs	80	80	80	80	80	80	80	70	70	60-70	50-76	60-70	64-94	64-94	64-94	64-94	60-70	60-64
Sesame seed	60	60	80	70	70-80	70-80	70-80	64	56	50	40-50	28-50	24-50	28-32	29-90½	21½-33	21½-30	19-26
<i>Moth</i>	48	48	54	44	44	44	44	44	22	22-36	22	20-22	20-22	13-21½	18-25	16-25	12-20	16-28
<i>Mush</i>	48	48	54	44	44-54	44-50	50-54	36	28	28-36	28	27-28	26-28	23-35	28-42½	28-34	19-36	16-28
<i>Mung</i>	48	48	48	44	44	44	44	44	32-40	32-40	32-40	32-40	32-40	32-48	28½-44	30-52	36-46	25-30
<i>Jowar</i>	50	50	60	48	48-60	46-60	48-60	40	26	26-40	26	26-27	24-26	23-48	25½-48	30-40	30-40	24-46
<i>Lahdarah</i>	48	48	48-50	44	16-44	44-50	44-50	20-70	20-40	20	20-40	18-48	18-48	20-40	18-48½	30-40	18-30	18-30
<i>Lobiya</i>	16-44	44	44-54	24	15-50	32	32	30	36½	35	20	20	20
<i>Kodaran</i>	44	44	44-50	44	44-54	44-54	50-54	36	21-23	21-36	20-21	20-21	16-24	22-30	28-41	22-34	18-28	15-28
<i>Kori</i>	40	40	50	24	24-30	24-30	30	20	10	10	8-10	10	10	9-10	9-12½	9-12½	9-12½	10½-18½
<i>Shamakh</i>	36	36	50	30	30-36	30	36	20	10	10-20	10	9-10	9-10	9-12½	8½-18	10-16	8-12	11-16½
<i>Gāl</i>	44	44	50	40	40-50	40-50	44-50	26	13	13-28	13	10-13	10-13	11-15	12-23	12-23	14-14½	12-14
<i>Arzan</i>	44	44	50	40	40	40	40	34-36	20	20	20	20	18-28	18-28	14-28	14-28	14-22	14-25
<i>Mandwah</i>	48	48	50	40	40	40-52	50-52	34	22-23	22-23	22-23	16-22	18-20½	18-31½	22-31	18-28	14-28	14-28
Indigo	140	140	160	140	140	140	140	136	132	130-136	130-136	136	130-136	140	140	140	140	140
Hemp	80	80	80	80	80	80	80	70-78	70	70-78	70	70	70	70-80	80	80	60-80	60-80
<i>Turiya</i>	80	80	80	32	32	32	24-32	24-32	20-32	18-32	20-32	20-32	14½-24

Autumn Harvest of the Subah of Oudh (continued). Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Turmeric	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.
Kachālu
Kult
Hinna
Water melons
Pān
Singhārāh
Arlar

Spring Harvest of the Subah of Delhi. Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.	D.
Cabul vetches	90	84-90	90	44-60	48-56	56	56	50-56	44-57	36-48	37-64	40-48	24-40	31-50	45-83	36-82	20-56	65-102
Indian do.
Barley	70	70-86	80	44-56	40-44	40-50	40-50	30-44	20-30	21-30	21-30	21-40	19-30	19-50	19-24	21-30	24-38	57-60
Pot-herbs	80	60-70	60	32-50	32-40	40	40	36	16-37	16-39	20-44	12-37	12-30	12-30	20-34	19-37	26-42	19-37
Peppy	70	80	80	80	80	80	80	70	40-70	40-70	40-60	40-54	40-60	40-60	40-60	40-69	40-60	40-72
Safflower	108	108	108	108	140	140	140	130-140	100-130	100-130	100-130	100-130	100-130	100-130	100-130	100-130	100-130	100-130
Linseed	man	man	man	80	80	80	80	76-80	60-70	60-70	60-70	50-70	50-70	50-70	54-70	54-70	54-70	54-70
Mustard	60-80	60	..	60-70	50	20-30	20-30	20-30	19-30	19-30	19-30	28-70	14-28	8-19	26-30
	80	80	80	60-70	60	60-70	60-70	48-60	22-30	19-30	27-28	19-26	19-27	19-27	14-24	19-30	19-24	28-48

Spring Harvest of the Sabah of Delhi (continued). Nineteen years' rate.

[illegible]

Autumn Harvest of the Subah of Delhi. Nineteen years' note.

[illegible]

Spring Harvest of the Subah of Lahore—(continued). Nineteen years' rates.

	6th & 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat	...	80	90	50	56	56	60	60	44-52	48-52	D. D.	D. D.	D. D.	D. D.	D. D.	D. D.	D. D.	D.
Cabul Vetches	43½-53	57½-3½	D. J.	D. J.	D. J.	40-43	28-38	44-55	38-64	55-68
Indian ditto	...	70	80	48	48	48	50	50	26-30	32-33	do.	57-16	57½-3½	57	57½-3½	57-3½	57½-63	do.
Barley	...	70	60	40	40	40	40	40	26-34	32-36	24	16	20	24½-28	16-21	28-34	28-34	40-53
Potterbs	...	80	80	80	80	80	80	80	60-70	50-60	60	50	50	22-27	18-24	26-40	30-51	40-51
Poppy	...	160	160	130	120	100	100	100	100	104	104	104	104	104	54-74
Safflower	...	do.	do.	76	70	60	60	70	64	64	64	64	104
Linseed	50	60	60	60	50	50	28-30	28-30	25	19	24	20-23	14-23	15-30	16-30	25-40
Mustard	...	80	80	60	60	60	60	60	28-30	25	19	30	22-23	16-23	18-28	18-28	20-26	30-42
Adas	...	60	60	86	86	36	40	40	27-28	24-27	20	12	16	12½-19	13-16½	19-26	26-42	29-42
Arzan	...	44	44	30	30	30	30	24	19-22	20-22	16	13	20	16-18	7½-10½	7½-14	12-20	18-24
Peas	15	15	19-28	28-36	15	19-23	19	19-28	19-30	28-36
Persian Muskmelons	50-100	120	120	120	120	80	66	86	86	86
Indian ditto	...	10	8	8	12-24	12-24	13	13	13	15	15	11-12	12	12	12	12
Kar rice	...	60	60	54	54	60	54	40-44	40-44	24	24	27	27	26-27	26-27	34-40	36-50	36-50
Ajwahn	...	80	80	80	80	80	70	70	70	70	70	70	70	70-74	70-76	70-76	73-74	73-74
Onions	73	73	73	73	73	70-74	70-74	70-74	70-74	70-74
Penugreek	70	70	70	70	70	42-54	20-74	20-32	30-64	40-64
Carrots	...	man ½	man ½	24	24	24	24	20-21	20-21	20-21	20-21	18-26	21-32
Lettuce	25	25	25	25	21	21	18½	18½	16-20	25-50

* D stands for *Dām* and J for *Jetal*. In these six columns, the J applies only to the Cabul Vetches and not to the following figures.

Spring Harvest of the Subah of the Multān. Nineteen years' rates.

	6th and 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat	..	D.	..	D.	52	52	52	36	D.	36	21½-40	D.	40-52	46-64
Kabul Vetches	57-16	ditto	ditto	ditto	ditto	ditto	ditto	ditto	ditto	ditto
Indian ditto	D. J.	32	23-25	16	20	21½-40	13½-40	20½-40	20-48	26-48
Barley	30	36	22	12	21	20½-40	16-40	20½-40	20-48	26-48
Potherbs	34	60	58-60	50	50	53-60	44-50	31-40	52-60	52-60
Poppy	130	130	100	100	100	60-104	60-104	60-104	60-104	60-104
Safflower	76	70	60	60	70	60-64	40-64	64-70	64-70	60-70
Linseed	30	30	20	19	24	24	23	23	16-30	28-30
Mustard	30	30	25	19	30	18-60	15½-40	14½-28	20-36	36
Arzan	28	28	19	12	16	6-20½	12½-40	18½-40	10-42	27-42
Peas	22	22	16	13	13	16-37	13½-40	10-16	13-24	17-24
Persian Muskmelons	15	15	19-20	26-30	15½	19	19	18½	9-22	26-30
Indian ditto	120	120	120	82	66	60-80	86	86	86	86
Kur rice	13	13	13	11	11	12-19	12-40	11-12	11-16	12
Afzāh	44	44	44	44	27	26	28-36	40	40	40
Onions	73	70	70	70	70	64-70	44-70	52-74	56-74	44-60
Pennegreek	70	70	70	70	70	60-74	40-74	52-74	58-74	44-60
Carrots	72	70	70	70	70	60	35-40	14½-52	40-70	40-70½
Lettuce	24	24	24	24	20-21	20-21	20-21	20	16	24-26
	25	25	25	25	21	20	18½	18½	20	25

	6th & 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Sugarcane (<i>paunda</i>)	200	200	200	200	200	200	200	200	200	200
Common sugarcane	150	120	100-120	100-120	100-120	100-120	100	100-110	70-100	100
Dark coloured rice	60	46	46	40	40	*60	45-62	45-62	51-62	65-72
Common rice	50	40	40	32	32	48-18	28-40	28-40	32-40	38-48
Munji do.	65	65	65	65	65	50	50	50	50	52
Cotton	120	104	70	64	80	70-86	10-95-1	70-76	44-90	66-90
Botherbs	76	70	60-70	60	50	40-76	10-70	70	60-70	60-70
Sesame seed	58	48	40	36	36	40-18	19-40	21-26	20-26	26-10
Molh	31	25	25	21	20	23-40	13-40	13-40	14-18	24-26
Mash	36	30	30	25	24-25	34-18	18-40	20-32	20-26	26-10
Mung	32	32	32	27	27	34-18	26-36	26-36	32-23	32-50
Jowār	39	32	32	32	25	39-18	15-40	24-26	25-32	32-18
Lahdarah	30	28	28	26	21	23-18	23-40	13	16	26-30
Lobya	32	32	32	32	25	23-16	22-40	26-27-1	22-26	26-38
Kodaram	32	32	32	32	32	23-16	22-40	26-27-1	22-26	26-38
Kori	32	32	32	32	26	24-30	18-40	18-30	16	26
Shamalkh	18	10	16	10	5	10-16	9-10	9-10	10-12	5-12-1

* Gladwin has 40½ but the text has no variant.

Autumn Harvest of the Subah of Multān—(continued). Nineteen years' rates.

	6th & 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Gāl	16	10	10	10	7	10-12½	9-10	9-10	8-10½	12-12½
Arzan	20	24	24	24	14	20½-48	20½-40	10-21	10-20	15-20
Mandwah	80	28	28	24	21	25	25	25	18-25	26-30
Indigo	136	136	136	120	120	130-134	184	134	184	184
Hemp	78	78	78	70	70	48-72	48-72	48-72	60-70	70-82
Turiya	82	82	32	82	82	84	84	34	24-84	28-84
Turmeric	120	120	120	104	104	104	104	104	104	104
Kāchālu	76	70	70	60	60	68-70	68-70	68-70	70	70
Kut	28	26	26	22	22	28	24	24	24	24-30
Hinna	58	58	58	58	58	48-70	40-70	70	70	70
Water melons	10	10	10	10	10	11	11	11	11	11
Pūn	180	10	do.	do.	do.	300	200	200	200	200
Singhārah	100	100	100	100	100	100	100	100	100	100
Arhar	20	20	20	20	20

Spring Harvest of the Subah of Mālwah. Nineteen years' rates.

	6th & 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Wheat ...	D.	D.	D.	D.	D.	D.	D.	D.	D.		do.	do.	do.	do.	do.	do.	do.	do.
Cabul Velches	...	50	50	50	50	50	50	50	50	Muzaffaris ¹ 2 to 50	do.	do.	do.	13M to 43½	do.	do.	do.	do.
Indian do.	...	50	50	50	50	50	50	50	50	13M to 43½	do.	do.	do.	do.	do.	do.	do.	do.
Barley	70	70	70	70	70	70	70	70	2M to 50D	do.	do.	do.	13M to 43½	do.	do.	do.	do.
Pot-herbs	...	75	75	75	75	75	75	75	75		do.	do.	do.		do.	do.	do.	do.
Poppy	50	50	50	50	50	50	50	50		do.	do.	do.		do.	do.	do.	do.
Safflower	...	50	50	50	50	50	50	50	50		do.	do.	do.		do.	do.	do.	do.
Linseed	...	50	50	50	50	50	50	50	50		do.	do.	do.		do.	do.	do.	do.
Mustard	...	50	50	50	50	50	50	50	50		do.	do.	do.		do.	do.	do.	do.
Alas and Arran	...	50	50	50	50	50	50	50	50		do.	do.	do.		do.	do.	do.	do.
Peas	...	50	50	50	50	50	50	50	50		do.	do.	do.		do.	do.	do.	do.
Persian muskmelons		do.	do.	do.		do.	do.	do.	do.
Indian do.	...	10	10	10	10	10	10	10	10		do.	do.	do.		do.	do.	do.	do.
Kur rice	...	60	60	60	60	60	60	60	60		do.	do.	do.		do.	do.	do.	do.
Ajwain	...	80	80	80	80	80	80	80	80		do.	do.	do.		do.	do.	do.	do.
Onions, Fenugreek		do.	do.	do.		do.	do.	do.	do.
Carrots, lettuce		do.	do.	do.		do.	do.	do.	do.

Muzaffaris to 75 dams.

Muzaffaris to 50.

Muzaffaris to 75.

Muzaffaris to 50.

¹ See Vol. I, p. 23. There were three Sovereigns of Gujarāt of the name of Muzaffar : the 1st reigned A.H. 799 (A.D. 1396) : the 2nd in A.H. 917 (A.D. 1511) : the 3rd in 969 (A.D. 1561). The last named abdicated in favour of Akbar in 980 (A.D. 1572), but in 991, he collected a force, defeated Akbar's general and re-ascended the throne. His second reign was brief and the kingdom became a province of the Empire. Mālwah was united to Gujarāt under Bahādur a king of the latter dynasty A.H. 937, (A.D. 1530). I take these details from Mr. Oliver's note on the coins of the Muhammadan kings of Gujarāt. In the list of coins there are two of copper of Muzaffar Shāh II, of 169 and 160 grains respectively, and three of silver of Muhammad Shāh III, of 73 and 175 grains. The latter, No. XXXI, of the Catalogue, is remarkable as having been struck during the second brief accession of this monarch to power. See also History of Gujarāt, Bayley, Index, Muzaffar.

	6th & 7th years.	8th year.	9th year.	10th year.	11th year.	12th year.	13th year.	14th year.	15th year.	16th year.	17th year.	18th year.	19th year.	20th year.	21st year.	22nd year.	23rd year.	24th year.
Sugarcane (<i>paunda</i>) ..	D.	150	150	150	150	M. D.	D.	D.	D.	D.	M. D.	D.	D.	D.	D.
Common Sugarcane ..	150	do.	do.	do.	do.	do.	do.	do.	6-150	do.	do.	do.	do.	7 to 75 M.	do.	do.	do.	do.
Dark coloured rice	62½	do.	do.	do.	do.	2½-62½	do.	do.	do.	do.	8 to 75 M.	do.	do.	do.	do.
Common rice ..	50	do.	do.	do.	do.	do.	do.	do.	2-50	do.	do.	do.	do.	1 to 48½ M.	do.	do.	do.	do.
<i>Munji</i>	2-50	do.	do.	do.	do.	do.	do.	do.	do.	do.
Cotton ..	50	do.	do.	do.	do.	do.	do.	do.	2-50	do.	do.	do.	do.	2½-62½ M.	do.	do.	do.	do.
Pot-herbs ..	75	do.	do.	do.	do.	do.	do.	do.	3-75	do.	do.	do.	do.	do.	do.	do.	do.	do.
Sesame seed
<i>Moth</i>
<i>Mūsh</i>
Pears
<i>Jowār</i>
<i>Laharāh</i>
<i>Labiya</i>
Kodaram
Korā
<i>Shandāh</i>
<i>Gāl</i>
<i>Arzan</i>
<i>Mandrah</i>
Indigo ..	150	do.	do.	do.	do.	do.	do.	do.	M. D.	do.	do.	do.	do.	...	do.	do.	do.	do.
Flump ..	50	do.	do.	do.	do.	do.	do.	do.	6-150	do.	do.	do.	do.	...	do.	do.	do.	do.
<i>Tusya</i> ..	50	do.	do.	do.	do.	do.	do.	do.	2-50	do.	do.	do.	do.	...	do.	do.	do.	do.

AIN 15.

The Ten Years' Settlement.

From the beginning of this immortal reign, intelligence and void of rapacity, together with zealous men of experience, have been annually engaged in noting the current prices and reporting them to His Majesty, and taking the gross produce and estimating its value, they determined the rates of collection, but this mode was attended with considerable inconvenience. When Khwajah Abdul Majid Asaf Khan was raised to the dignity of Prime Minister, the total revenue was taken at an estimation, and the assignments were increased as the caprice of the moment suggested. And because at that time the extent of the empire was small, and there was a constant increase of dignities among the servants of the State, the variations were contingent on the extent of corruption and self-interest. When this great office devolved on Muzaffar Khān and Rajah Todar Mull, in the 15th year of the reign, a redistribution of the imperial assessment was made through the *qanungos*, and estimating the produce of the lands, they made a fresh settlement. Ten *qanungos* were appointed who collected the accounts from the provincial *qanungos* and lodged them in the imperial exchequer. Although this settlement was somewhat less than the preceding one, nevertheless there had been formerly a wide discrepancy between the estimate and the receipts.

When through the prudent management of the Sovereign the empire was enlarged in extent, it became difficult to ascertain each year the prices current and much inconvenience was caused by the delay. On the one hand the husbandman complained of extensive exactions, and on the other the holder of assigned lands was aggrieved on account of the revenue balances. His Majesty devised a remedy for these evils and in the discernment of his world-adorning mind fixed a settlement for ten years: the people were thus made contented and their gratitude was abundantly manifested. From the beginning of the 15th year of the Divine era to the 24th, an aggregate of the rates of collection was formed and a tenth of the total was fixed as the annual assessment; but from the 20th to the 24th year the collections were accurately determined and the five former ones accepted on the authority of persons of probity.

The best crops were taken into account in each year and the year of the most abundant harvest accepted, as the table shows.

(A Note on *Dastur-ul-'aml* : Sarkar, &c.)

For a full description and discussion of the official manuals called *Dastur-ul-'aml*, see J. Sarkar's *Mughal Administration* 3rd. ed., ch. XIV. § 2.

Sir Henry Elliot writes, in his *Supplemental Glossary*, revised ed. by J. Beames, entitled *Memoirs of the History &c. of N.W.P.* (1869), :—"Dastur-ul-aml, a body of instructions, and tables for the use of revenue officers under the Native Government. . . . No two copies can ever be found which correspond with each other, and in most respects they widely differ. Those which profess to be copied from the *Dastur-ul-'aml* of Akbar, are found to contain on close examination sundry interpolations of subsequent periods.

"Besides the *Dastur-ul-'aml*, another book, called the '*Aml Dastur*, was kept by the Qanungoes, in which were recorded all orders which were issued in supersession of *Dastur-ul-'aml*." (ii. 156-157.)

"A *Sarkār* is a subdivision of a *subah*. Each *subah* is divided into a certain number of *sarkārs*, and each *sarkār* into *parganahs* or *mahals* (which are used as equivalent expressions), and the *parganahs* again are aggregated into *Dasturs* or districts. . . .

"*Dastur* besides signifying a rule, is also a minister, a munshi. *Parganah* means tax-paying land; the *Burhan-i-Qati'* gives the meaning *Zamine ke āz ān māl wa kharāj bagirand*. . . .

"The words used before Akbar's time to represent tracts of country larger than a *parganah* were *shiqq*, *Khita*, '*arsa diyār*, *vilāyat*, and *iqta'*, but the latter (term) was generally applied when the land was assigned for the support of the nobility or their contingents." (See *Ikta'* in *Encyclopaedia of Islam*, ii. 461, for a fuller treatment. J.S.)

"I have endeavoured to restore the *sarkars*, *dasturs*, and *parganahs* (in the N. W. Provinces of Allahabad and Agra) as they stood in the time of the Emperor Akbar. The copies of the *Ain-i-Akbari* vary so much, and such ignorance is frequently exhibited by the transcribers, that to verify the names of *parganahs* has been a work of great labour. . . .

“But it is in separating the *sarkārs* into *dasturs* that the ignorance of the copyists has been chiefly exhibited, for all the *parganahs* are frequently mixed together, as if there were no meaning at all attached to *dastur*.” (ii. 201-203.)

The word *dastur* in the sense of a subdivision of land for revenue purposes, went out of use in the official histories of the Mughal empire after Akbar's time. It may have lingered on in the N.W. Provinces up to the Mutiny, but only in the village records, as it does not occur in any history or revenue-manual of the Central Government of the later Mughals known to me. (*Jadunath Sarkar*.)

The *Subah* of *Allahabad* comprises nine *sarkārs* (districts) and possesses fifteen separate revenue codes. (*dastur-ul-ʿaml*.)

1. The *Sarkār* of *Allahabad* includes fifteen mahals and has three revenue codes.

The suburban district of *Allahabad* comprises three mahals, viz., the suburbs of *Allahabad*, *Kantit*, and a tract on the extreme limits of the *subah* of *Agra*, and possesses one revenue code.

Jalālābād [i.e., *Arail*] has three mahals and a revenue code.

Bhadoi, seven mahals, viz., *Bhadoi*, *Sikandarpur*, *Sorāon*, *Singror*, *Mah*, *Kewāi*, *Hādiābās* [= *Jhusi*]*—*and a revenue code.

2. The *Sarkār* of *Benāres* has eight mahals and a revenue code. The detail is as follows—the suburban district of *Benares*, the township of *Benares*, *Pandrah*, *Kaswār*, *Harhwā*, *Byālisi*.

3. The *Sarkār* of *Jaunpur* has 41 mahals and two codes.

The suburban district of *Jaunpur*, 39 mahals, one code, viz. :—

Aldimao, *Angli*, *Bhileri*, *Bhadāon*, *Talhani*, *Jaunpur*, *Suburban Jaunpur*, *Chandipur Badhar*, *Chāndah*, *Chiriyā Kot*, *Chakesar*, *Kharid*, *Khāspur Tāndah*, *Khānpur*, *Deogaon*, *Rāri*, *Sanjholi*, *Sinkandarpur*, *Sagdi*, *Sarharpur*, *Shādi-ābād*, *Zafarābād*, *Karyāt Mittu*, *Karyāt Dostpur*, *Karyāt-Mendia*, *Karyāt Swetah*, *Gheswah*, *Ghosi*, *Kodiya*, *Gopālpur*, *Karākat*, *Mandiāho*, *Muhammad-ābād*, *Majhorā*, *Mau*, *Nizāmābād*, *Naigun*, *Nathupur*.

4. The *Sarkār* of *Chanādah* [= *Chunār*], 14 mahals and one revenue code, viz., the suburban district of *Chanadah*, *Aherwārah*, *Bholi*, *Badhol*, *Tāndah*, *Dhos*, *Rāghupur*¹¹⁰—the villages on the western bank of the river, *Majhwārah*, *Mahācch*, *Mahwāri*, *Mahoi*, *Silpur*, *Naran*.

5. The *Sarkār* of *Ghāzipur*, 18 mahals, one code, viz., the suburban district of *Ghāzipur*, *Baliā*, *Pachotar*, *Balhābās*, *Bhariābād*, *Barāich*, *Chausā Dehma*, *Sayyidpur Namdi*, *Zahurābād*, *Karyāt Pali*, *Kopā Chhit*, *Gadhā*, *Karandah*, *Lakhnesar*, *Madan Benāras*, *Muhammadābād*, *Parhābāri*.

6. The *Sarkār* of *Karrah*, 12 mahals, one code, viz., the township of *Karrah*, its suburban district, *Aichhi*, *Atharban*, *Ayāsā*, *Rāri*, *Karāri*, *Kotla*, *Kaunra* commonly called *Karson*, *Fatchpur Hanswah*, *Hatgaon*, *Hanswah*.

7. The *Sarkār* of *Korah*, 8 mahals, 3 codes, viz., thus detailed. The suburban district of *Korah* has one code and 2 mahals, viz., itself and *Ghātampur*; *Kotiā*, 3 mahals, *Kotiā*, *Goner*, *Keranpur Kinār*,¹¹¹ and one code; *Jajmau*, 3 mahals, viz., *Jājmau*, *Muhsinpur*, *Majhāon*, and one code.

8. The *Sarkār* of *Kālinjar*, 10 mahals, one code, viz., *Kālinjar* with its suburbs, *Ugāsi*, *Ajigarh*, *Sihonda*, *Simoni*, *Shādipur*, *Rasan*, *Khandeh*, *Mahobā*, *Maudhā*.

9. The *Sarkār* of *Mānikpur*, 14 mahals, 2 codes. The suburbs of *Mānikpur* have 10 mahals and one code, viz., *Mānikpur* together with its suburban district, *Arwal Bhalol*, *Salon*, *Jalālpur Balkhar*, *Karyāt Karārah*, *Karyāt Paegāh*, *Khatot*, *Nāsirābād*.

Rāc Bareli, etc., 4 mahals, one code, viz., *Rāc Bareli*, *Talhandi*, *Jāes*, *Dalmau*.

¹¹⁰ A note to the text gives *Rālhupūr* as the present name of this mahal—the other names have nearly all variants in the MSS., no doubt due as much to dialectic variations in pronunciation as to errors of copyists. Tiefertenthaler adds to the above, the fortress of *Tschinarghar* (*Chanār*) built of stone, on an eminence on the western bank of the Ganges.

¹¹¹ Thus in all MSS. but Elliot has *Kiralpur Kananda*.

Spring Harvest of the Subah of Allahabad—Ten Years' rates.

	Suburban district of Allahabad. 3 Mahals.	Jalaibās, &c. 5 Mahals.	Bhadoi, &c. 7 Mahals.	Sarkar of Benares 8 Mahals.	Suburban district of Jaunpur. 39 Mahals.	Pargana of Mongra, &c. 2 Mahals.	Sarkar of Chandah 14 Mahals.	Ghazipur, &c. 18 Mahals.	Pargana of Karrah 12 Mahals.	Pargana of Kora-rai. 2 Mahals.	Pargana of Kotia. 3 Mahals.	Tajman, &c. 3 Mahals.	Sarkar of Kailnjar. 10 Mahals.	Sarkar of Manik-pur. 10 Mahals.	Rae Bareilly. 4 Mahals.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Wheat	...	60-9	64-21	64-1	64-1	58-4	64-21	64-21	60-3	60-18	60-3	60-23	63-15	58-4	62-15
Chul Vetches	71-14	71-14	...	71-14	71-14	...	55-23	55-23	...	71-14
Indian do.	...	38-0	...	41-9	41-9	39-3	41-9	41-9	38-0	34-17	38-0	...	34-17	39-3	39-3
Barley	48-2	47-2	40-12	47-2	47-2	...	40-6	40-6	40-6	40-6	42-12	45-21
Green barley not in ear	...	40-6	...	67-3	67-2	...	68-2	68-2	67-2
Adas	38-0	38-0	23-12	38-0	38-0	24-15	24-15	24-15	25-16	24-15	23-14	35-8
Safflower	...	83-15	...	70-3	70-3	83-21	70-3	83-3	83-21	70-17	83-21	69-22	72-17	83-21	82-3
Poppy	...	150-13	...	115-20	115-20	150-13	115-20	115-20	150-13	127-15	153-13	128-0	55-23	156-18	115-8
Potherbs	...	27-2	...	80-13	80-13	67-5	82-13	80-13	67-2	55-23	67-20	21-0	30-15	68-5	76-1
Linseed	...	31-8	...	40-6	40-6	32-15	40-6	40-6	31-8	32-15	31-20	30-5	32-15	32-15	35-8
Mustard	...	35-8	...	40-6	40-6	27-24	40-6	40-6	35-8	32-15	35-8	31-21	20-3	38-21	38-21
Arzan	...	20-3	...	6-21	26-21	16-19	26-21	26-21	20-3	20-3	20-3	20-3	20-2	16-19	24-15
Peas (Mashang)	...	24-15	...	40-6	40-6	29-2	40-6	40-6	24-15	22-6	24-0	20-2	26-21	29-2	38-0
Carrots	...	25-18	...	26-21	26-21	16-21	26-21	26-21	25-18	32-21	25-18	31-21	70-18	20-21	26-21
Onions	...	83-21	...	54-29	80-13	79-10	80-13	80-13	83-21	82-18	83-21	82-18	...	84-10	80-33
Fenugreek	...	74-23	...	54-29	54-24	54-24	54-24	54-24	74-23	...	74-23	82-18	109-14	58-4	54-20
Persian muskmelons	...	144-6	...	134-4	134-11	150-1	134-4	134-4	144-6	109-14	144-6	119-16	115-16	150-1	134-4
Indian ditto	...	19-0	...	14-14	14-14	17-20	14-14	14-14	19-0	15-16	19-0	14-13	...	17-7	14-13
Cumin seed	83-15	89-15	61-12	89-15	89-15	...	82-18	82-18	61-12	89-15
Coriander seed	105-2	105-2	...	105-2	105-2	105-2
Kur rice	...	52-14	...	50-24	46-24	46-24	46-24	46-24	52-14	50-20	52-14	46-24	50-20	46-24	46-24
Aywan	...	83-21	...	89-15	89-15	89-15	89-15	89-15	83-4	86-15	83-21	83-21	86-2	83-10	97-7

* In these tables, D stands for dām and J for jetal, the 25th part of a dām which is the 40th part of a rupee.

	Sub-District of Allahabad.	Jalaiah.	Bhadoi.	Sarkar of Benares.	Sub-District of Jaunpur.	Pargannah of Mongra.	Sarkar of Chanda.	Chazipur.	Pargannah of Karrah.	Pargannah of Kora-rah.	Pargannah of Kotia.	Jajman.	Sarkar of Kalinjhar.	Sarkar of Manikpur.	Rae Bareilly.
Sugarcane (<i>paundah</i>)
Common Sugarcane	240-9	...	230-20	208-15	223-15	234-20	223-15	223-15	240-3	223-15	240-9	231-15	223-15	232-20	223-15
Dark coloured rice	126-9	123-0	123-0	126-9	123-9	123-0	109-17	143-3	103-17	143-3	143-17	126-6	123-0
Common rice	71-14	...	71-14	71-14	71-14	71-14	71-14	71-14	81-14	67-2	81-14	73-20	67-2	71-14	71-14
<i>Al</i> (<i>morinda citrifolia</i> , from which a red dye is extracted)	44-18	...	42-12	49-5	49-5	43-12	49-5	49-5	44-18	46-24	44-28	43-24	46-24	42-12	46-24
Cotton	205-18	...	205-18
<i>Moth</i>	89-15	...	91-18	96-4	96-4	91-17	96-4	96-4	89-15	91-18	89-0	93-3	91-18	91-18	93-23
<i>Arzan</i>	25-18	...	26-21	33-14	33-14	26-21	33-14	33-14	25-18	24-15	25-18	22-23	14-11	26-21	31-8
Indigo	33-12	...	18-24	26-21	26-21	17-22	32-21	26-21	23-12	24-15	23-16	26-21	24-15	17-20	24-18
<i>Hinna</i>	163-6	...	162-3	162-3	162-3	162-3	162-3	162-3	163-5	163-5	163-6	163-6	163-6	162-6	162-6
Hemp	76-0	...	89-15	89-15	89-15	89-15	89-15	89-15	76-0	79-20	86-0	86-1	69-20	82-6	89-15
Potherbs	84-24	...	84-24	84-24	84-24	84-24	84-24	84-24	84-24	89-24	84-24	84-24	89-15	84-4	84-24
Pan	80-0	...	87-5	83-15	83-15	87-5	89-15	89-15	82-17	84-23	82-18	87-7	84-20	87-5	87-0
<i>Singhārah</i>	210-0	...	244-21	268-20	268-20	244-21	268-14	268-14	210-3	267-20	210-4	268-20	267-20	267-20	267-20
<i>Jawāri</i> , (<i>Jawār</i>)	120-18	...	115-2	115-20	115-20	115-20	115-20	115-20	120-18	120-20	115-20	115-20	115-20	115-20	115-20
<i>Kari</i> (a kind of wild grain)	34-17	...	35-20	40-6	40-6	35-20	40-6	40-6	34-4	33-7	34-17	32-15	37-7	35-8	38-0
Persian muskmelons	13-15	13-15	...	13-15	15-15	...	13-15	18-15	...	13-15
Sesame seed	105-2	105-2	...	205-2	105-2	105-2
<i>Mung</i>	40-0	...	43-15	44-18	44-15	44-18	44-18	42-12	42-12	42-12	41-9	101-9	43-15	43-15	43-15
Turneric	42-12	...	48-2	49-5	49-5	48-5	49-5	49-5	42-12	42-6	42-12	41-9	40-6	48-2	48-2
	115-20	115-20	...	115-20	115-20

The Subah of *Oudh* comprises five *sarkārs* and possesses twelve codes.

1. The *Sarkār* of *Oudh*, 21 mahals, 3 codes. The suburban district has 19 mahals and one code. Two parganahs are comprised in *Khairābād*. They are as follows :

Oudh with its suburban district; *Anbodha*, *Anhonah*, *Pachhamrāth*, *Bilehri*, *Basodhi*, *Thānah Bhadaon*, *Bakthā*, *Daryābād*, *Rudauli*, *Selak*, *Sultānpur*, *Sātanpur*, *Supahah*, *Sarwāpāli*, *Satrakah*, *Gawārchah*, *Manglasi Naipur*.

Ibrahimābad and *Kishni* are each a parganah with one code.

2. The *Sarkār* of *Bharāitch* has 11 mahals, one code. The suburban district of *Bharāitch*, &c. 8 mahals, one code. *Bharāitch* with its suburbs 6 mahals, *Bahrah*, *Husampur*, *Wankdun*, *Rajhāt*, *Sanjhauli*, *Fakhrpur*, *Fort Nawāgarh*.

Firuzābād, &c., two parganahs, one code, viz., *Firuzābad*, *Sultānpur*.

Kharosna, one mahal, one code.

3. The *Sarkār* of *Khairābad*, 2 mahals, 3 codes. *Khairābād*, &c., 12 parganahs, one code, viz., suburbs of *Khairābād*, *Basārā*, *Baswah*, *Basrah*, *Chhitāpur*, *Khairigarh*, *Sadarpur*, *Kheri*, *Kharkhela*, and *Laharpur*, two mahals; *Machharhattah*, and *Hargarāon*, two mahals. *Pāli*, &c. has 8 mahals, one code, viz., *Pāli*, *Barurānjnah*, *Bāwan*, *Sāndi*, *Sirah*, *Gopamau*, *Khankatmau*, *Nimkhā*; *Bharwārah*, &c. two mahals, included in *Oudh*, viz. *Bharwārah* and *Pilā*,—and one code.

4. The *Sarkār* of *Gorakhpur*, 24 parganahs, one code. The suburban district of *Gorakhpur* with the town, 2 mahals, *Atraulā*, *Anholā*; *Bināekpur* &c. 4 mahals, *Bāhmini-pārah*, *Bhāwāpārā*, *Tilpur*, *Chilupārā*, *Dharyapara*, *Dhewapārā* and *Kotlah* [*Kuhānā*] 2 mahals, *Rihli*; *Ramgarh* and *Gauri* 2 mahals, *Rasulpur* and *Ghaus* 2 mahals; *Kathlā*, *Khilāpārā* [= *Rihlāpara*] *Maholi*, *Mundwah*, *Mandlah*; *Maghar* and *Ratanpur*, 2 mahals; *Maharanthoi*.

5. The *Sarkār* of *Lucknow* has 55 mahals, 2 codes. The suburban district of *Lucknow*, &c., 47 parganahs, one code. *Abethi*, *Isāuli*, *Asiyun*, *Asohā*, *Unchah Gāon*, *Balkar Bijlour*?—[*Bijnor*], *Bāri*, *Bharimau Pungwan*, *Betholi*, *Panhan*, *Parsandhān*, *Pātan*, *Bārāshākor*, *Jhaloter*, *Dewi*, *Deorakh*, *Dadrah*, *Ranbirpur*, *Rāmkot*, *Sandilah*, *Saipur*, *Sarosi*, *Sahāli*, *Sidhor*, *Sidhupur*, *Sāndi*, *Saron*, *Fatehpur*,

Fort of *Ambhati*, *Kursi*, *Kakori*, *Khanjrah*, *Ghātampur*, *Karanda*, *Konbhi Lucknow* with its suburbs, *Lashkar*, *Malihābād*, *Mohān*, *Morāon*, *Madiāon*, *Maḥonah*, *Manawi*, *Makrācd*, *Hadha*, *Inhār*.

Onām &c., 8 parganahs, one code, viz., *Onām*, *Bilgrāon*, *Bangarmau*, *Hardoi*, *Sātanpur*, *Fatehpur*, *Chaurāsi*, *Kachhāndu*, *Malāwah*.

11948

Spring Harvest of the Subah of Oudh.

	Parganah of the subah district of Oudh, &c.	Ibrahimabad, &c.	Kishni, &c.	Bharāitch, &c.	Firuzabad, &c.	Kharānsah, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Wheat ...	54-20	62-15	58-4	54-20	55-23	55-20
Indian Vetches ...	34-17	39-3	39-3	33-14	32-11	33-14
Mustard seed (<i>Khar-dal</i>)	40-6
Barley ...	39-3	45-21	42-12	38-0	35-20	38-0
Adas ...	23-12	35-20	23-12	22-9	21-6	22-10
Safflower ...	71-14	72-0	83-21	71-14	69-8	71-14
Poppy ...	127-15	115-20	156-13	127-12	127-11	127-11
Potherbs ...	69-9	76-1	68-5	56-12	54-20	56-12
Linseed ...	29-0	35-20	32-15	27-24	26-21	27-24
Mustard seed (<i>Saishaf</i>) ...	30-5	38-0	27-24	29-2	29-2	29-2
Arzan ...	20-3	24-15	16-19	15-3	7-22	23-4
Peas ...	29-2	38-0	29-2	25-8	24-15	25-15
Carrots ...	30-5	36-21	36-21	28-7	29-2	29-2
Onions ...	78-0	80-18	79-10	78-7	78-7	78-7
Fenugreek ...	55-22	54-20	58-4	58-4	78-20	...
Persian Muskmelons ...	115-20	230-4	150-1	110-20	115-20	115-30
Indian do. ...	4-13	14-23	17-22	15-16	15-16	15-16
Cumin seed ...	79-15	61-12
Coriander seed	150-2
Kur rice	46-24	46-24	45-21	44-18	45-21
Ajwādh	97-5	79-10	83-21	83-21	82-21

Note.—The difference in the two classes of mustard seed is in the size and colour of the grain.

Autumn Harvest of the Subah of Oudh.

	Parganah of the sub- ban district of Oudh, &c.	Ibrahima bad, &c.	Kishni, &c.	Bharatich, &c.	Firuzabad, &c.	Khatronsah, &c.	Suburban district of Khairabad.	Pail, &c.	Bharwārah, &c.	Suburban district of Gorakhpur.	Lucknow, &c.	Onāni, &c.
Sugarcane (<i>paundak</i>)	D. J. 240-9	D. J. 223-15	D. J. 230-8	D. J. 240-9	D. J. 203-15	D. J. 240-9	D. J. 220-15	D. J. 231-15	D. J. 240-9	D. J. 240-9	D. J. 231-15	D. J. 231-35
Common sugarcane	190-15	123-0	126-0	123-0	134-4	123-0	134-4	131-23	190-15	123-0	127-15	131-3
Dark coloured rice	67-2	71-14	42-12	62-5	65-4	62-15	65-24	73-20	67-2	62-15	74-20	73-20
Common rice	43-15	46-24	40-6	40-6	41-9	40-6	41-9	46-24	43-17	40-6	44-18	46-24
<i>Māsh</i>	33-15	34-17	31-8	31-8	32-15	31-8	32-15	34-17	33-15	31-8	34-24	34-17
Cotton	83-21	93-23	91-18	89-15	89-11	89-15	89-15	93-23	83-21	89-15	93-18	93-23
<i>Moth</i>	35-18	41-20	26-21	24-15	23-12	24-15	23-12	22-23	25-18	24-15	24-15	22-23
<i>Gāl</i>	16-19	21-6	15-16	15-16	15-16	15-16
<i>Turiya</i>	31-8	38-0	35-20	31-8	33-14	31-6
<i>Arzan</i>	25-18	24-15	17-22	22-9	24-15	22-9
Indigo	123-15	162-3	163-6	163-6	163-6	162-6
<i>Hinna</i>	70-15	79-15	79-15	69-8	71-14	69-20
Hemp	89-15	84-24	84-24	85-21	89-15	89-15
Potherbs	89-2	84-5	87-5	82-18	82-16	83-21
<i>Kachrah</i> (<i>Cucumis melo</i>)	12-20	4-3	13-15	12-8	14-4	12-8
<i>Pān</i>	230-14	260-3	244-21	223-15	223-15	223-15
<i>Singhārah</i>	115-8	115-8	115-8	115-8	115-8	115-8
<i>Lobiya</i>	...	38-0
<i>Jowāri</i> , (millet)	35-20	38-0	35-8	38-0	33-14	38	...	32-15	35-2	38-0	95	32-15
Carrots	...	81-15
<i>Kiri</i> (a kind of wild grain)	...	13-15	...	15-5
Persian* watermelon	105-2
<i>Arlar</i>	22-9	...	22-9	...	25-4
<i>Lahdarah</i>	24-15	25-18	24-15	23-12	24-15	23-12	23-12	25-18	24-18	23-12	25-4	25-18
<i>Kodaran</i>	28-20	31-8	29-2	26-22	25-18	26-15	24-15	31-8	28-8	26-21	28-24	41-8
<i>Mandwah</i>	25-18	31-8	26-21	25-18	24-15	25-18	24-15	29-2	35-18	55-18	32-21	23-2
Sesame seed	41-9	31-8	43-15	44-18	45-1	44-18	45-21	41-9	41-1	44-18	40-20	13-10
<i>Shandakh</i>	18-15	19-0	12-8	12-8	12-8	12-8	12-8	13-10	13-11	12-8	12-8	13-10
<i>Mung</i>	43-15	48-2	48-3	41-2	43-15	41-9	43-15	41-9	43-15	41-10	43-15	41-9

* So the text, but it is probably a misprint of tarbuja for kharbuja.

1. The *Sarkār of Agra*—the royal residence. 44 parganahs, 4 codes. The suburban district of Agra, &c., 6 mahals, one code, viz., *Agra* and its suburbs, *Chanwār*, *Jalesar*, the city of *Agra*, *Dholpur*, *Mahāwan*, *Beānah* &c., 33 mahals, one code; the suburbs of *Beānah*, 2 mahals, *Oudchi*, *Od*, *Ol*, *Bhasāwar* *Todahbhim*, *Bināwar*, *Chausath*, *Khānwā*, *Rajhohar*, *Fatchpur* known as *Sikri*, *Sconkar* *Sconkri*, *Mathura*, *Maholi*, *Mangottah*, *Bhaskar*, *Wazirpur*, *Helak*, *Hindon*, *Rāpari*, *Bāri*, *Bajwārah*. *Etāwah* &c. 3 mahals, one code, viz., *Etāwah*, *Rūpri*,¹¹² *Hatkānt*. *Mandāwar* &c. 2 mahals, one code, viz., *Mandāwar*, *Kakhonmar*.

2. *Sarkār of Alwar*. 43 paragraphs, 3 codes. The parganahs of *Alwar* &c. 33 mahals, one code, viz., the suburbs of *Alwar*, *Dharā*, *Dadkar*, *Bahādurpur*, *Panāin*, *Khelohar*, *Jalālpur*, *Bihrozpur*, *Rāth*, *Bālhattah*, *Bahrkol*, *Hājipur*, *Budahthal*, *Anthulah* *Hābru*, *Parāt*, *Balhār*, *Barodah* *Fathkhan*, *Barodahmco*, *Basānah*, *Hasanpur*, *Badohar*, *Hasanpur Gori*, *Deoli* *Sājāri*, *Sakhan*, *Kiyārah*, *Ghat* *Scon*, *Kohrana*, *Mfonkonā*, *Mandāwarah*, *Naugāon* *Nāhargarh*, *Harsori* and *Harpur*, 2 mahals, *Harsānā*. *Bachherah*, &c. 5 mahals, one code, viz., *Bachherah*, *Khohariranā*, *Bhīwān*, *Ismailpur*, *Amran*, *Mubārakpur*, &c., 5 mahals, one code, viz., *Mubārakpur*, *Harsoni*, *Mandāwar*, *Khirtahali*, *Mojpur*.

Shamshābād, Pati 'Alīpur, Kanpal, Bhojpur. Sinkandar-pur, one code. Phapund, one code.

6. *Sarkār of Sahār. Sahār, &c. 6 madals, one code, viz., Sahār, Pahāri, Bhadoli, Kāmah, Koh Majahid, Hodal. Nonhera, one code.*

7, 8, 9. *Sarkār of Gwalior, &c., one code. Sarkār of Gwalior, 13 mahals, one code. Sarkār of Narorpanj, 5 mahals, one code. Sarkār of Beanwan, 28 mahals, one code.*

10. *Sarkār of Kalpi, 16 parganahs, one code. Ulai, Bilāspur, Badhneth Derāpur, Deokali, Rāth, Rāipur, Saganpur, Shāhpur, suburbs of Kālpi, Kenār, Khandot, Khandela, city of Kālpi, Muhammadābād, Hamirpur.*

11. *Sarkār of Kol, 4 codes. Thānah Farida, &c. 10 mahals, one code, viz., Thānah Farida, Pahāsu, Danbhāi, Malikpur, Shikārpur, Nuh, Chandos, Khurjah, Ahār, Tapal. Suburban district of Kol, &c., 4 mahals, one code, viz., Kol, Jalāli, Sikandar rāo, Gangeri. Mārharah, &c., 5 mahals, one code, viz., Mārharah, Balrām, Soron, Pachlānah and Sidhpur, 2 mahals. Akbarābād, 2 mahals, one code, viz., Akbarābād, Atrauli.*

12. *Sarkār of Nārnol, 4 codes. Suburban district of Nārnol, &c., 8 mahals, viz., suburbs of Nārnol and city, Bārhi, Kot Potli, Bābāi, Khandela, Saṅkhāna, Kānori, villages at the foot of the hill. Barodah rana, &c. 2 mahals, viz., Barodah ranā Lāpoti. Chāl Kalānah, &c. 2 mahals, Chālkālānah, Khodānā. Kanodah, &c. 3 mahals, Kanodah, Narharah, Jhojeon.*

	Suburban district of Agra.	Etāwah.	Suburban district of Bayānah.	Mandāwar.	Alwar.	Bachherah.	Mubarakpur.	Kraj.	Tijarah.	Thānah of Kālīwār.	Bestur.	Sahar.	Pahārī.	Nonhera.	Kanauj.
1.															
Wheat	67-2	0-9	67-2	67-2	67-2	64-21	63-10	63-17	64-21	67-2	67-2	67-2	64-21	68-2	60-21
Cabul Vetches	67-9	55-23
Indian do.	44-18	35-20	42-12	40-6	40-6	36-23	35-20	34-17	36-23	40-6	36-23	36-23	36-23	40-6	37-15
Barley	49-5	40-6	44-17	44-18	44-18	42-12	41-9	46-0	42-12	44-17	42-12	42-12	42-12	44-17	40-0
Adas	29-2	25-17	29-17	26-21	26-21	26-21	26-21	26-21	26-21	26-21	26-21	26-21	26-21	26-21	25-17
Safflower	127-11	120-1	127-11	123-0	123-0	127-0	127-0	127-0	127-0	120-0	127-11	127-11	127-11	123-0	69-22
Poppy	127-11	120-20	127-11	123-0	127-0	127-11	127-11	127-11	127-11	123-0	127-11	127-11	123-0	123-0	128-0
Potherbs	67-2	58-4	61-12	60-9	60-9	59-7	60-9	55-23	59-8	60-9	59-8	59-8	59-8	60-9	61-12
Mustard seed	31-14	31-8	31-14	33-14	33-14	31-8	31-8	32-11	31-8	33-14	31-8	31-8	31-8	33-14	31-21
Arzan	24-15	23-3	20-3	21-6	21-6	22-9	23-3	23-9	21-6	22-9	22-9	22-9	22-9	21-6	20-6
Pens	31-8	29-2	33-14	32-11	32-11	31-20	29-2	29-2	31-8	32-11	31-8	31-8	31-8	32-15	39-2
Carrots	29-2	29-2	33-14	29-2	29-2	25-18	26-21	26-21	25-18	29-2	25-18	25-18	25-8	29-2	31-21
Onions	84-24	80-12	80-11	80-18	82-17	81-16	81-16	82-17	81-16	80-2	31-16	31-16	31-16	82-17	82-17
Fenugreek	44-18	50-8	84-24	55-8	55-29	84-24	81-16	...	83-24	55-23	84-24	55-23	82-18
Persian muskmelons	111-20	87-17	111-20	111-20	111-20	100-16	100-16	100-16	100-14	100-16	...	100-16	100-16	111-20	119-16
Indian ditto	15-11	14-13	15-16	15-16	15-16	14-14	15-16	15-16	14-14	15-16	15-16	15-16	14-14	15-16	14-13
Cumin seed	84-24	83-21	82-24	84-24	84-24	81-18	84-24	82-17	...	84-24	81-16	84-24	...
Kur rice	55-23	59-5	87-8	51-11	51-11	53-17	51-11	50-8	50-18	50-18	53-17	53-17	56-17	51-11	46-24
Ajwain	84-24	83-21	84-24	84-24	84-24	81-17	84-24	86-2	81-16	84-24	81-16	81-16	81-16	84-24	83-21

Supplement to the Spring Harvest of the Subah of Agra.

	Saketh.	Bhagdon.	Sikandarpur.	Phapund.	Gwalior, &c.	Kaippi.	Kol.	Thannah Farida.	Akbarabad.	Mahrarah.	Narnool.	Barodaharana.	Chal Kalaunah.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Wheat	64.21	58.4	60.9	63.18	69.8	63.18	63.9	58.4	63.18	60.9	62.15	63.18	61.12
Cultiv. Vetches	55.23	...	55.23
Indian do.	39.3	33.14	38.0	34.18	42.12	34.17	35.20	34.17	35.20	38.0	36.22½	35.20	35.20
Barley	40.12	38	40.6	40.6	40.6	40.6	40.6	38.0	40.12	40.6	41.9½	41.9	41.9
Chickpeas	26.21	24.15	24.15	24.15	20.2	24.15	26.21	22.9	24.15	24.15	24.15	23.15	24.15
Peas	73.20	73.20	74.23	72.17	69.8	72.17	71.14	83.21	81.14	74.23	72.17	71.14	71.14
Mustard	127.15	127.15	127.15	127.15	127.15	127.15	123.0	124.9	123.0	128.12	119.17	127.15	123.0
Groundnuts	60.9	57.4	57.4	55.23	60.9	50.23	58.4	64.21	63.2	58.4	65.4	60.9	60.9
Oilseeds	32.15	30.5	30.15	30.15	33.14	32.15	29.2	30.5	29.2	30.15	37.4	31.8	31.8
Peas	21.6	20.3	21.6	20.3	16.12	20.3	20.9	19.0	22.9	21.6	20.9	22.9	20.3
Barley	31.20	24.15	29.2	20.9	31.8	22.9	26.21	29.2	29.2	29.2	27.23	29.21	26.21
Peas	31.20	39.20	31.20	26.21	26.24	26.21	24.15	24.15	26.21	31.8	26.1	24.20	24.15
Groundnuts	37.5	30.18	37.5	32.18	34.24	32.18	39.15	81.15	81.16	47.15	84.12	81.16	77.7
Oilseeds	97.15	...	89.11	49.5	...	89.15
Peas	10.15	101.18	...	109.14	115.20	109.14	100.16	145.9	111.8	...	102.21	100.16	...
Barley	14.14	15.16	...	15.16	15.16	15.16	17.22	15.16	14.14	...	15.16	15.16	1 (?) 16
Chickpeas	37.5	37.5	37.5	32.18	84.14	80.18	...	86.2	84.24	87.5	84.2	84.24	...
Peas	51.15	50.8	51.15	50.8	59.8	50.20	49.5	59.23	53.17	51.15	46.2	51.11	60.9
Groundnuts	87.5	82.2	87.5	82.2	86.2	86.2	84.24	86.2	84.24	87.23	84.12	84.24	84.24

	Saketh.	Bhugan.	Sikandarpur.	Phapand.	Gwalior, &c.	Kalpi.	Kol.	Thana Farida.	Akbarabad.	Alatharah.	Narnol.	Barodahra.	Chai Kalanah.
Sugarcane (<i>paunda</i>)	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Common Sugar- cane	..	223-5	..	223-15	229-6	..	223-18	219-2	223-15	..	216-22	223-15	205-18
Dark coloured rice	138-16	146-3	147-16	143-3	147-15	143-0	134-4	134-4	134-4	138-16	134-4	127-11	125-6
Common rice	70-14	59-7	71-14	67-2	70-12	67-2	64-21	67-2	64-21	74-2	77-6½	76-1	73-20
<i>Al</i>	0-5	44-18	49-5	46-24	55-20	46-24	46-24	46-20	46-24	49-5	60-90	63-18	53-17
<i>Masli</i>	4...	205-18	...	205-18
Cotton	35-20	34-18	34-18	35-19	40-6	35-19	33-14	23-14	33-14	34-17	38-0	35-20	33-14
<i>Moth</i>	93-23	84-24	93-23	91-17	87-5	91-18	89-15	93-23	89-15	93-23	89-11	89-11	89-11
<i>Gai</i>	25-18	22-18	24-15	24-5	26-21	24-15	22-9	23-12	22-9	24-15	29-3	22-3	23-12
<i>Turiya</i>	16-19	15-16	16-19	15-16	20-9	15-16	15-16	14-14	15-16	16-19	16-19	15-19	15-16
<i>Arzan</i>	38-0	34-17	35-20	38-0	40-8	38-0	38-0	33-14	38-0	35-20	42-12	35-9	46-½
Indigo	21-15	21-6	23-12	40-6	27-24	24-15	24-15	21-6	24-11	23-12	23-12	24-11	22-9½
<i>Hinna</i>	160-3	158-19	160-3	160-6	160-3	162-1	163-1	160-24	161-0	165-15	156-0	161-0	161-0
Hemp	...	77-4	...	69-8	69-8	69-8	77-4	76-17	77-4	...	76-½	78-7	77-4
Potherbs	82-11	86-2	87-5	89-11	84-20	89-11	84-24	77-5	84-24	87-5	89-15	89-11	84-24
<i>Kachrah</i>	78-7	78-7	78-7	74-23	76-1	74-21	76-0	88-8	76-0	77-7	71-13	71-14	11-14
<i>Pan</i>	13-11	12-8	13-11	12-7	12-7	12-7	12-7	12-8	12-8	13-11	13-11	13-11	12-8
<i>Singharah</i>	...	267-20	...	268-8	223-15	268-8	223-13	223-15	223-15	...	223-15	223-15	223-15
<i>Lobya</i>	...	102-22	...	111-20	111-20	111-20	111-20	111-20	108-11	...	115-20	111-20	111-20
<i>Jowari</i>	30-5	27-24	131-8	33-17	31-8	33-14	36-21	36-21	35-19	31-8	35-19	31-8	26-21
<i>Kuri</i>	39-3	35-20	39-3	38-7	34-18	38-7	35-19	35-14	35-19	39-3	35-19	33-20	38-14
<i>Lahdarah</i>	15-16	11-14½	(?) 11	12-8	...
<i>Kodaran</i>	26-21	24-5	26-21	26-21	31-8	26-21	24-15	24-15	24-15	26-21	27-23	26-23	26-23
<i>Mandwah</i>	30-5	27-24	30-5	27-24	31-8	27-24	29-2	32-5	29-2	30-5	29-1	33-14	29-2
<i>Shanah</i>	30-5	26-21	29-2	26-2	31-8	25-21	27-24	27-14	27-24	29-2	20-8	25-18	27-24
Peas	25-18	12-8	24-11	11-5	14-0	11-5	12-8	11-8	12-8	24-15	12-7	13-15	15-19
Turneric	49-6	42-24	49-5	40-6	49-5	40-6	40-6	33-0	40-6	49-5	35-19	35-20	35-20
...	89-11	...	111-20	111-20

Subah of Ājmere, 7 Sarkārs, 9 codes.

1. *Sarkār of Ājmere, 2 codes. Suburban district of Ājmere, &c. 24 Parganahs, 1 code. City and suburbs of Ājmere, 2 mahals, Arāine, Parbat, Bahnāi,¹¹³ Bharānah, Barwāl, Bāhal, Bāndhan Sandheri, Bharonda, Tusina,¹¹⁴ Johnair,¹¹⁵ Deogāon, Roshanpur, Sānbhar, Sarwār, Sathelā, Sulaimānābād, Kekri, Kherwah, Māhrot, Masaudābād, Narāina, Harsor, Amber, &c., 4 Parganahs, 1 code, viz., Amber, Bhakoi, Jhāg, Muzābād.*

2. *Sarkār of Jodhpur, 21 Parganahs, 1 code. Suburbs and city of Jodhpur, Asop, Eindrāoti, Bhodhi, Palpārah, Belārā, Pāli, &c., 3 mahals, Bāhilah, Podhi, Bhadrājaun, Jetāran, Dotārā, Sujhat, Sātalmir, Sewāna, Kherwa, Khconsar, Kundoj, Mahewah.*

3. *Sarkār of Chitor, 28 Parganahs, 1 code. Suburbs and city of Chitor, 2 mahals, Islāmpur commonly Rāmpur, Udaipur, &c., 3 mahals, Aparmāl,¹¹⁶ Artod, Islāmpur commonly Mohan, Bodhnur, Phuliā, Banhera, Pur, Bihin Surur, Bāgon, Begun, Pati Hājipur, Jeran, Sānwarkhāti, Sāndri, Samel with the cultivated land, Kosiānah, Māndalgah, Māndal, Madāriya Nimach &c., 3 mahals.*

4. *Sarkār of Ranthambor, 4 codes, Ranthambor &c., 36 Parganahs, 1 code. Suburban district of Ranthambor, Alhanpur, Etāda, Aton, Islāmpur, Iwān Bosamer, Barodah, Bhadrāon, Baklānt, Palātiāh, Bhosor, Belonah, Bālakhatri, Bhoripahāri, Bārān, Talād, Jetpur, Jhāin, Khaljipur, Dhari, Sanhusāri, Kotā, Khandār, Khatoli, Kadaud, Lakhri, Londah, Lahaud, Māngror, Momcdānah &c., 16 mahals. Chātsu &c., 16 Parganahs, 1 code, viz., Chātsu, Barwārah, Uniyārā, Pātan, Banhatā, Sarsup, Boli, Bejri, Kharni, Nawāhi, Jhalāwah, Khankharah, Sui Supar, Malārnah, Karor, Bondi, Delhwārah, &c., 7 Parganahs, 1 code, viz., Delhwārah, Rewāndhnah, Nagar, Antrorah, Delānah, Amkhorah, Loharwārah, Todā, &c., 3 Parganahs, 1 code, viz., Todā, Tonk, Tori.*

5. *Sarkār of Nāgor, 30 Parganahs, 1 code. Suburban district of Nāgor, Amar Sarnain, Indānah, Bhadānah,*

¹¹³ Bahacoi, Tieff.

¹¹⁴ Bossina, Ibid.

¹¹⁵ Zounbora, Ibid.

¹¹⁶ Aparpāl, Ibid.

Baldubalām,¹¹⁷ *Batodhā*, *Baroda*, *Bārah gāin*, *Chāel*, *Charodah*, *Jākhrah*, *Khārijkhātu*, *Dendwānah*, *Donpur*, *Rewāsā*, *Ron*, *Rasulpur*, *Rahot*, *Sādelah*, *Fathpur Jhanjmun*, *Kāsli*, *Khāelah Kojurah*, *Kolewah*, *Kumhāri*, *Keran*, *Lādon*, *Merath*, *Manohar nagar*, *Nokhā*.

6 & 7. *Sarkārs* of *Sarohi* and *Bikāner*. The codes of these two *Sarkārs* are not laid down.

Spring Harvest of the Subah of Ājmere.

	Suburban district of Ājmere, &c.	Parganah of Amber, &c.	Parganah of Jodhpur, &c.	Parganah of Chitor, &c.	Parganah of Rantambhor &c.	Parganah of Chātsu, &c.	Parganah of Delhwārah, &c.	Parganah of Tōdah, &c.	Parganah of Nāgor, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Wheat ...	49-5	31-8	100-16	55-23	55-23	53-18	67-2	46-24	100-16
Indian Vetches ...	33-14	20-3	55-23	31-8	31-8	38-0	42-12	27-24	55-23
Barley ...	33-14	20-3	67-2	33-14	33-14	38-0	49-5	32-11	67-2
Adas ...	22-3	13-11	...	22-9	22-9	24-15	20-3
Safflower ...	62-15	38-9	67-2	55-23	55-22	58-9	59-4	36-29	67-2
Poppy ...	85-15	60-9	115-20	89-24	84-24	115-20	116-8	77-4	115-20
Potherbs ...	55-23	35-20	62-15	55-23	55-23	46-8	55-22	36-24	62-15
Linseed ...	31-8	20-3	31-8	26-21	26-21	26-21	29-2	...	31-8
Mustard seed ...	44-18	26-21	55-23	26-21	24-15	...	27-24	18-11	55-23
Arzan ...	20-9	13-11	55-23	13-11	13-11	17-22	17-22	14-15	55-23
Peas ...	26-9	20-3	...	22-2	20-9
Carrots ...	26-21	15-16	...	22-9	22-21	...	27-24	18-11	...
Onions ...	67-2	44-18	67-2	59-21	59-21	80-13	89-13	53-17	68-2
Fenugreek	55-0	...	67.	55-23	...
Persian Musk-Melons	100-16	67-2	...	83-11	89-11	...	89-11	89-8	...
Indian ditto	11-5	6-18	...	13-11	13-11	13-11	13-11	13-11	8-24
Cumin ...	70-7	53-17	77-8	67-2	67-2	80-13	80-13	53-17	...
Kur rice ...	51-11	33-0	...	52-14	52-24	40-6	33-14
Ajwāin	70-7	53-17	78-7	67-2	67.	80-13	80-13	53-17	88-7

¹¹⁷ In the text *Bakdu*, but the above is the name in the account of this Subah which occurs later on.

Autumn Harvest of the Subah of Ajmere.

	Suburban district of Ajmere, &c.	Parganah of Amber, &c.	Parganah of Jodipur, &c.	Parganah of Chitor, &c.	Parganah of Rantambhor &c.	Parganah of Chitsa, &c.	Parganah of Delhwārah, &c.	Parganah of Toda, &c.	Parganah of Nāgor, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Sugarcane (<i>paundah</i>)	239.6	239.6
Common sugarcane	1153.20	86.1	115.8	115.8	115.8	134.4	115.20	81.16	115.20
Dark coloured rice	55.23	35.20	55.23	67.2	68.2	72.20	67.22	44.18	...
Common rice ...	44.20	23.2	44.2	53.17	50.17	67.2	46.24	31.8	44.18
Māsh ...	33.14	29.2	31.7	33.14	33.14	39.3	27.24	18.15	31.8
Cotton ...	60.15	40.6	67.2	76.1	76.1	78.8	72.17	54.0	67.0
Moth ...	24.15	15.16	36.3	26.1	26.1	22.9	40.6	26.21	20.3
Gāl ...	13.15	8.24	38.21	13.15	13.15	15.16	16.16	10.16	38.8
Turiya ...	38.1	24.16	...	33.14	33.14	15.5
Arzan ...	17.22	12.7	55.21	17.22	17.22	17.22	22.9	17.24	55.6
Indigo ...	134.4	85.11	134.4	111.20	134.4	134.4	134.4	89.11	134.4
Hinna ...	67.2	44.18	67.2	55.23	55.23	67.2	62.15	40.21	67.2
Hemp ...	82.19	53.8	87.7	78.8	78.7	89.15	76.13	76.13	53.17
Potherbs ...	55.22	35.20	62.15	55.23	55.23	62.15	76.13	26.9	62.15
Kachran ...	13.2	8.24	13.11	11.5	15.5	13.11	18.11	8.24	13.11
Singhārah ...	115.20	116.20	115.20	115.20	115.20	115.20	115.20	118.20	115.20
Lobiya ...	31.20	20.9	22.9	31.8	31.8	32.11	22.9	13.14	22.9
Jowāri ...	24.15	11.16	31.8	29.2	29.12	32.22	42.2	30.0	31.8
Lahdarah ...	20.3	12.8	17.20	22.9	22.9	25.18	31.8	19.0	17.22
Kodarama ...	22.3	11.5	...	22.9	22.9	33.14	33.14	27.24	...
Mandwah ...	22.2	14.4	...	22.3	22.9	26.21	26.21	17.22	...
Sesame seed ...	33.14	20.3	33.4	33.14	33.14	24.16	34.17	22.24	33.14
Shamākh ...	15.5	6.18	...	11.5	11.5	11.5	11.5	6.0	...
Mung ...	24.11	15.16	26.21	40.6	40.6	36.22	42.12	27.10	26.21
Kuri ...	21.5	6.18	...	8.24	8.24	...	11.5	6.3	...
Kalt	33.14	22.9	...

The rates of the *Sarkārs* of Bikāner and Sarohi are not given.

The Subah of Delhi, 8 *Sarkārs*, 28 codes.

1. The *Sarkār* of Delhi, 48 Parganahs, 7 codes. The old suburban district, the new ditto *Pālam*, *Jhārsah*, *Masaudābād*, *Tilpat*, *Luni*, *Shakarapur*, *Bāghpat*, *Kāsnah*, *Dāsnah*, *Sulaimānābād*, *Kharkhudah*, *Sonipat*, *Talbegampur*, *Talālpur*.

Pānipat, &c., 2 Parganahs, 1 code, viz., *Pānipat*, *Karnāl*, *Safedun*, *Kutānah*, *Chhaproli*, *Tāndah Bhagat*, *Gonor*, *Jhanjhānah*, *Kāndhlah*, *Gangerkhara*.

Baran, &c., 8 Parganahs, 1 code. *Baran*, *Sikandarābād*, *Jewar*, *Dankor*, *Adh*, *Pothh*, *Seniānah*, *Sikandarābād*.

*Merath, &c., 7 Parganahs. 1 code. Merath, Hāpur, Barnāwah, Jalālābād, Sarwārah, Garh Muktesar, Hatnāwar.*¹¹⁸

Jhajhar, &c., 4 Parganahs, 1 code. Jhajhar, Dādri-Tāha. Māndothi, Beri Dobaldhan.

Rohtak, 1 Parganah, 1 code.

Paloh. 1 Parganah, 1 code.

2. *Sarkār of Badāon, 16 Parganahs, 1 code. Ajāon, Aonla, Badāon and suburbs, Bareilly, Barsar, Pond, Telhi, Sahsāwn, Sonāsi Mandehah. Saniyā, Kānt, Kot Sālbahan, Golah.*

3. *Sarkār of Hisār Fīrozah, 18 mahals, 4 codes. Suburbs of Hisār Fīrozah, &c., 7 parganahs, 1 code. Suburbs and city of Hānsi, Barwalah, Barwā. Toshām and Agrohah, 2 mahals, Fatehābād. Gohānah, &c., 4 parganahs, 1 code. Gohānah, Ahroni, Bhattu and 16 villages. Sirsā, 1 parganah. 1 code. Muhim, &c., 6 parganahs, 1 code. Muhim. Rohtak, Jind, Khāndah, Tahānah, Athkerah.*

4. *Sarkār of Rewāri, 11 mahals, 4 codes. Rewāri, &c., 8 parganahs. 1 code. Rewāri, Bāwal, Kot Kāsim Ali, Pātaudi, Bhoharah, Ghelot, Ratāi Jatāi, Nimrānah. Tāoru, 1 parganah, 1 code. Suhmah, 1 parganah, 1 code. Kohānah, 1 parganah, 1 code.*

5. *Sarkār of Sahāranpur, 36 mahals, 4 codes. Deoband, &c. 26 mahals, 1 code. Deoband, Sahāranpur, Bhatkhanjāwar, Manglor, Nānoth Rāmpur, Sarot, Purchhapūr, Jorāsi, Sikri Bhukarhari, Sarsāwali, Charthūwal. Rurki, Baghra, Thānah Bhevan, Muzuffarābād, Raepurtātūr, Ambeth. Nakor and Toghlaqpur, 2 mahals, Bhogpur. Bhattah, Thānah Bhim, Sanbalhera, Khodi and Gangwah, 2 mahals. Lakhmāuti Kerunah, &c., 2 parganahs. 1 code. Kerānah. Bedoli.*

Sardhanah, &c., 7 parganahs, 1 code. Surdhanah, Bhomh, Suranpalri, Badhānah, Joli, Khatoli and Baghra, 2 mahals. Indri. 1 mahal, 1 code.

6. *Sarkār of Sirhind. 2 mahals, 4 codes. Suburbs of Sirhind, &c. 13 parganahs. Suburbs of Sirhind. Rupar,*

Pācl, Bcnor, Jahat, Dhotah, Dorālah, Dcorānah, Kuhrām, Mascukan, villages of Rāc Samu, Ambālah and Kaithal. Thānesar, &c., 8 parganahs. Thānesar, Sadhurah, Shāhābād, Khizrābād, Mustafā-ābād, Bhodar, Sultanpur, Pundri. Thārah, &c., 2 parganahs. Thārah, Ludhiānah, Samānah, &c., 9 parganahs. Samānah, Sunnām, Mansurpur, Mālner, Hōpuri, Pundri, Fatehpur and Bhatindah, Machhipur.

8. *Sarkār of Sambal, (Sambhal) 47 mahals, 3 codes. City of Sambal, &c., 23 parganahs. City of Sambal, suburbs of Sambal, Sarsi, Naroli, Manjholah, Jadwār, Gonor, Neodhanah, Deorah, Dabhārsi, Dhakah, Rajabpur, Amrohah, Ujhāri, Kachh, Āzampur, Islampur Dargu, Islampur Bharu, Afghānpur, Chotālah, Kundarki, Bachharaon, Gunder, Chāndpur, &c., 16 parganahs. Chāndpur, Sherkot, Bijnaur, Mandāwar, Keratpur, Jalālābād, Sahanspur, Nihitor, Naginah, Akbarābād, Islīmābad, Seohāra and Jhala, 2 mahals. Lakhnōr, &c., 11 parganahs. Lakhnōr, Shāhi, Kābar and Kānkhati 2 mahals. Hatamnah, Rājpur, Dodelah, Leswah, Sarsāwah, Basārō, Parohi [=Barohi].*

Sarkār of Kumāon. (The names of its parganahs are not entered in the MSS.)

Spring Harvest of the Subah of Delhi.

	Old suburban district.	Panipat, &c.	Merali, &c.	Baran, &c.	Jhajhar, &c.	Palol.	Rohatak.	Sarkar of Badaun.	Suburban district of	Gohannah, &c.	Sirsa.	Muhim.	Rewari.	Thorn.
Wheat	63-0	58-4	58-4	58-4	61-12	64-21	58-4	50-8	62-15	57-4	58-4	58-4	63-10	D. J. 64-16
Cabul Vetches	67-2	D. J. ...
Indian ditto	36-3	36-23	40-6	32-11	33-14	33-14	29-16	30-5	29-2	29-16	30-5	7-19	35-20	31-20
Harley	42-12	40-6	38-0	38-0	41-9	42-12	34-17	45-20	40-6	42-12	42-12	42-12	24-11	22-12
Adas	24-15	24-15	25-11	22-9	24-15	26-1	24-11	15-23	24-15	22-9	24-16	24-16	24-11	26-21
Safflower	71-14	71-14	84-24	83-21	71-14	72-14	68-20	70-11	67-2	67-0	67-2	60-20	71-14	71-14
Poppy	123-0	125-3	145-9	120-35	123-11	119-16	127-11	128-0	119-16	119-16	119-16	127-16	127-11	127-11
Potherbs	67-2	55-23	64-21	64-21	60-9	59-7	48-0	57-1	60-2	55-23	51-12	57-0	60-9	50-7
Linseed	31-20	31-7	29-20	33-14	33-14	32-11	36-21	24-0	25-13	25-17	24-15	23-21	29-2	34-17
Mustard seed	29-2	29-2	31-20	35-5	31-20	31-20	30-20	26-7	31-20	29-2	29-2	30-5	31-20	31-20
Aran	22-9	20-3	19-0	19-0	20-3	22-2	20-3	17-9	20-3	17-20	20-3	20-3	22-9	22-9
Pears	29-2	26-21	24-16	29-2	26-21	31-20	26-21	...	29-9	29-9	29-9	26-21	29-2	29-2
Carrots	21-23	24-15	23-12	24-11	24-11	53-17	29-2	26-21	23-5	39-2	29-2	29-2	26-21	25-18
Onions	81-16	78-7	81-16	81-16	77-7	81-16	80-0	80-8	85-0	85-0	85-0	81-16	81-16	81-16
Pengreek	...	62-15	49-5	49-5	100-16	100-16	96-4	...	35-0	38-0	100-16	81-16
Persian Musk Melons	111-20	100-16	45-9	145-9	100-16	100-16	96-4	13-12	98-10	96-4	98-2	96-4	100-16	100-16
Indian ditto	11-16	15-16	117-16	17-22	15-16	15-16	13-11	11-16	15-16	13-11	13-11	13-14	11-16	14-14
Kur rice	53-17	53-17	53-17	55-23	60-9	50-17	46-24	38-0	46-24	45-21	46-24	46-24	21-11	53-17
Afradin	84-24	89-12	84-24	86-2	84-24	81-16	85-0	85-0	85-0	85-0	84-24	85-0	...	81-16

	Old suburban district.	Panipat, &c.	Meerut, &c.	Baran, &c.	Jhajhar, &c.	Palol.	Rohatak.	Sarkar of Badoun.	Suburban district of Hisar.	Gohana, &c.	Sirsa.	Muhim.	Rewari.	Tharu.
Sugarcane (paundah)	D. J. 210-5	D. J. 204-17	D. J. 216-22	D. J. 219-3	D. J. 250-18	D. J. 218-5	D. J. 217-0	D. J. 216-9	D. J. 214-20	D. J. 214-20	D. J. 214-20	D. J. 217-0	D. J. 220-11	D. J. 223-11
Common sugarcane	127-11	123-0	123-0	134-4	125-6	138-11	127-19	125-6	125-6	128-2	127-24	127-4	137-11	125-6
Dark coloured rice	78-7	67-0	43-18	67-2	73-8	76-1	62-11	64-21	62-15	63-18	64-21	76-1	76-1	77-7
Mash	55-7	44-18	48-2	46-20	53-17	58-14	49-5	38-15	51-14	...	45-21	48-20	63-18	63-18
Cotton	35-20	33-14	34-17	33-14	33-14	31-23	38-0	31-20	38-0	35-20	38-0	38-0	35-20	35-20
Moth	89-11	91-17	89-11	93-23	89-11	95-1	89-21	96-4	89-11	89-11	89-11	89-12	89-11	89-11
Gul	16-15	15-9	16-19	14-14	15-16	11-16	16-12	15-3	16-19	15-16	15-16	16-12	16-12	16-12
Indigo	20-3	20-3	29-9	21-6	22-9	23-12	23-12	23-3	23-12	23-12	23-12	23-12	22-0	22-9
Henna	121-0	121-0	121-0	121-0	121-0	121-0	120-12	121-14	125-12	125-12	125-12	156-0	156-3	161-0
Hemp	77-4	76-1	71-14	72-17	78-3	78-7	76-0	42-14	76-0	76-0	76-0	76-0	76-0	77-7
Potherbs	84-24	89-18	83-21	87-5	84-24	81-0	80-18	89-11	80-18	80-18	87-5	86-18	89-11	88-8
Kachrah	70-17	71-14	78-7	78-7	71-14	71-7	73-20	73-20	71-14	71-14	71-14	73-20	71-14	72-17
Pan	11-0	11-0	12-7	12-20	13-11	13-11	12-20	13-11	13-11	13-11	12-11	13-11	13-11	13-11
Singharah	223-15	200-15	220-11	220-11	220-11	220-11	220-11	220-11	220-11	220-11	220-11	220-11	220-11	220-11
Lobiya	111-15	111-20	111-20	111-20	111-20	111-20	111-20	111-20	111-20	111-20	111-20	111-20	111-20	111-20
Jowari	31-0	...	26-21	26-21	26-21	33-14	33-14	27-10	35-20	34-17	38-0	38-0	35-20	30-5
Kari	33-14	33-14	33-14	33-14	33-14	26-20	35-20	34-17	38-0	38-0	38-0	35-0	35-20	35-20
European radish	11-5	11-5	12-20	11-5	13-11	11-5	...	11-5	11-5	...	11-20	...	12-8	12-8
Lahdarah	500-0	500-0	12-20	12-20	13-11	13-11	12-20	13-20	13-11	...	13-11	13-11
Kodaran	26-21	26-21	22-9	24-11	26-21	26-21	29-2	22-9	28-0	27-24	26-21	29-2	...	21-21
Mandurah	32-11	33-4	29-2	32-5	29-2	33-14	29-2	27-24	29-2	29-2	33-14	23-8	...	34-17
Sesame seed	29-2	31-20	23-2	27-14	27-24	27-10	28-0	25-17	26-21	26-21	25-17	28-0	25-17	29-9
Shanakh	42-12	40-0	44-18	44-18	52-12	49-5	46-24	39-3	44-18	45-21	41-24	46-24	...	44-18
Mung	11-5	11-5	12-8	11-5	11-19	12-20	11-19	11-19	11-5	11-4	11-5	11-5	13-11	13-11
	38-0	42-0	43-11	38-6	35-20	40-6	36-23	36-22	36-22	35-2	36-23	36-23	35-20	36-23

Supplement to the Spring Harvest of the Subah of Delhi.

	Subnah.	Kohānah.	Deoband, &c.	Sardhanah, &c.	Keranah, &c.	Indri.	Suburban district of Sirhind.	Thanesar, &c.	Tharah, &c.	Samanah, &c.	Suburban district of Samblal.	Chāndpur, &c.	Lakhnor, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Wheat	34-21	67-2	55-23	58-4	58-0	51-11	51-11	59-5	51-11	51-11	55-21	54-20	50-8
Cabul Vetches
Indian do.	35-0	33-14	33-14	34-17	35-8	32-23	35-0	31-22	33-3	33-14	33-14	35-20	35-20
Barley	42-12	44-18	35-8	38-0	40-6	36-23	35-0	31-22	39-3	33-14	33-14	35-20	35-20
Adas	24-15	24-15	25-11	29-9	23-15	26-1	24-11	11-23	22-9	15-23	24-15	24-15	24-18
Safflower	76-17	71-14	84-24	84-24	71-14	76-0	176-0	76-0	76-0	76-0	71-14	69-20	70-11
Poppy	...	123-0	150-7	145-9	125-3	126-9	126-9	126-9	126-9	126-9	127-11	127-1	120-0
Potherbs	...	60-9	64-21	64-21	55-21	58-7	59-7	59-7	58-5	57-5	57-3	57-1	58-1
Linseed	32-11	30-14	27-24	29-9	31-8	25-18	26-21	25-18	25-18	26-21	24-11	24-15	24-16
Mustard seed	...	33-14	29-2	31-20	29-2	21-21	26-21	25-17	26-0	26-21	29-2	27-24	26-7
Arzan	...	21-6	20-9	19-0	20-9	17-22	17-22	17-22	17-22	17-22	17-22	17-9	17-9
Peas	31-20	31-20	32-11	30-5	26-21	20-9	22-9	22-3	22-20	25-0	30-5	30-0	...
Carrots	...	29-2	26-21	23-12	24-16	26-21	26-21	22-7	26-1	26-1	26-1	26-1	26-1
Onions	82-19	84-24	81-16	87-7	82-18	82-18	82-18	83-21	...	82-18	82-18
Fennugreek	...	55-23	...	49-0	60-13	51-11	...	40-6	51-11	41-2	...	62-11	...
Persian Musk Melons	...	111-20	145-0	145-9	100-16	115-20	112-23	113-12	111-20	111-20	114-1	111-20	113-12
Indian ditto	11-16	11-16	19-0	17-22	11-16	14-9	14-14	14-14	14-14	15-16	15-16	11-20	11-16
Kur rice	...	51-11	60-9	53-17	53-17	41-9	41-9	49-17	41-9	42-12	42-12	...	38-0
Ajwain	...	84-24	84-24	84-24	89-15	84-24	85-0	84-24	84-24	85-0	84-24	42-12 (?)	24-24 (?)

Supplement to the Autumn Harvest of the Subah of Delhi.

	Sahnah.	Kohat.	Deband,	Sardhana,	Karnah,	Indra	Subaham dist.	Thaneer, &c.	Tharsh, &c.	Sammah, &c.	Subaham dist.	Chandpur, &c.	Lakhmor, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Sugarcane (pandah)	2180	...	21620	21620	2144	21012	21012	21012	21012	21012	2206	2206	2160
Common Sugarcane	13416	13416	1230	1230	1230	11813	12122	12019	11813	11812	12917	13020	12029
Common rice	584	3317	4212	489	4148	1212	1212	1218	1414	1915	4212	419	4212
Mash	3623	3520	3211	3147	3314	3215	3314	330	3212	318	3112	3519	3120
Cotton	951	8911	8911	8911	9117	1078	1078	1502	5820	1052	102214	9710	4614
Moth	2415	269	209	220	2621	2164	229	229	211	216	229	229	223
Gai	1516	1619	1516	1619	169	1311	1414	1414	1311	1414	1516	1516	153
Arzan	2312	229	209	229	233	233	233	233	233	213	216	229	1914
Indigo	1630	1610	15713	1610	1610	1610	1610	1610	1610	1610	1616	15613	16114
Hing	7820	887	774	7114	831	7011	6920	7011	7011	7011	73201	7217	7217
Hemp	...	8911	8218	8321	8218	8212	8212	8212	8212	8212	8911	8911	8911
Potherbs	777	7114	7114	787	7011	7111	7111	7011	7114	7114	786	787	7320
Kachrah	1311	1311	128	128	128	115	1119	115	1119	1119	115	11143	1220
Pan	22311	22315	24524	22315	22315	22315	22315	22315	22315	22315	22315	22315	...
Singhārah	11120	11120	11120	11120	11120	11120	11120	11120	11120	...
Lobiya	3314	2721	305	2521	2623	2621	2710
Jowari	3623	3520	2621	3514	3314	3314	3314	3417	3314	3314	3622	3818	3623
Kuri	1311	1311	115	128	103	1223	1320	1222	1222	128
European radish	1311	1311	128	128	1220	115	1119	115	1119	1119	115	11143	1220
Lahdarah
Kodaram	2621	2621	229	229	2621	2115	254	2415	2415	2415	2415	2415	229
Mandarah	3314	3520	3824	299	3314	267	2518	2621	237	2415	2723	2620	267
Sesame seed	2710	2724	2415	299	3020	2415	2518	2415	2415	2415	2664	2724	2518
Shamakh	495	4418	3417	4418	406	406	413	419	406	406	4118	482	393
Mung	128	1311	115	1220	115	115	115	115	115	115	4118	115	1119
Turmeric	406	380	380	3415	406	406	406	406	406	380	406	406	3622
	2724	11120

The *Subah* of *Lāhore* contains 8 populated areas¹¹⁹ (*Tieff. pagi et oppida*).

1. The area of *Lāhore*, &c. has 20 mahals, 1 code. Area of *Lāhore*, &c. 4 mahals; metropolitan area, *Bāri Doāb*; *Barhiāsāt*;¹²⁰ lands of *Panj Bari Shāhpur*: lands of *Kālapand*, *Rachnāu Doāb*.

Panjāb, 16 mahals: *Tappah*¹²¹ *Bheluwāl* of the *Bari Doāb*, *Tappah Bharli*, *Tappah Phulwāri*, *Punjgarāmi*, *Sandhwāl*, *Sāhu Mali*, *Sidhpur*, *Mankatwālah*, *Ghāzipur*, *Chandanwarak*, *Amrāki Bhatah*, *Parsaror*, *Rachnau*, *Sidhpur Panchnagar*, *Garbandwāl*.

2. *Sarkār* of *Jālandhar*, 30 mahals. 1 code. *Jālandhar*, *Sultānpur*, *Shaikhpur*, *Melsi*, *Lohi Dheri*, *Nakodar*, *Talon*, *Muhammadpur*, *Miani Nuriya*, *Kharkharaon*, *Rahimabad*, *Jalalabad*, *Hādiābād*, *Bajwārah*, *Harhānah*, and *Akbarabad*, 2 mahals, *Balot*, *Bhonkā*, *Hājipur*, *Patī Dhināt*, *Dardak Sāhimalot*, *Andwarah*, *Dadiāl*, *Kard Jālar?* *Sarkar (?) Deswahali*, *Chaurāsi*, *Naunankal*, *Nobi*.

3. *Sarkār* of *Batālah*, &c. 14 mahals, 1 code. *Battālah*, *Kanuwāhan*, *Kalānor*, *Jamāri*, *Hanwād* and *Baba*, 2 mahals, *Thandot*, *Dābhāwālah*, *Khokhowāl*, *Paniyal*, *Bhalot*, *Katwahā* and *Bethān*, 2 mahals, *Salimābād* separate from *Battālah*.

4. *Patī Haibatpur*, &c., 6 mahals, 1 code. *Haibatpur*, *Hoshiār Karnālah*, *Firozpur*, *Qasur*, *Muhammadot*, *Deosah?*

5. *Sarkār* of *Parsaror*, &c., 7 mahals, 1 code. *Parsaror*, *Maukri*, *Mahrar*, *Patī Zafarwāl*, *Patī Bārmak*, *Haminagar*.

6. *Sarkār* of *Rohtās*, &c., 9 mahals. 1 code. *Rohtās*, *Kari*, *Kariāli*, *Bahni*, *Andarhal*, *Losdah*, *Sardahi*, *Malotrai Kedāri*, *Nandanpur*.

7. *Sarkār* of *Siālkot*, &c., 11 mahals, 1 code. *Siālkot*, *Mānkot*, *Wan Sodrah*, *Narot*, *Renhā*, *Jimah Chatah*, *Marāt*, *Mankoknor Sialkot?*

¹¹⁹ The term *sawād* is usually applied to the towns and villages of Arabian Irāq [i.e., the sown or cultivated area, as distinct from the desert], as those in *Khurasān* are called *rustāk*, and in Arabia Felix *makhālif*.

¹²⁰ This name does not occur in the account of *Lāhore* later on. The variants are *Barhiāl*, *Barhāt*, *Barsāhāt*, *Barsahasāt*. It is scarcely necessary to note that the words *Bāri* and *Rachna* in connection with *Doāb* are formed by the crasis of *Beās* and *Rāvi*, in the former case, and *Rāvi* and *Chenāb* in the latter.

¹²¹ *Tappah* denotes a small tract or division of country smaller than a *parganah*, but comprising one or more villages. In some parts of the North-West, it denotes a tract in which there is one principal town or a large village with lands and villages acknowledging the supremacy of one amongst them and forming a sort of corporate body, although not otherwise identical. *Wilson's Gloss.*

8. Sarkār of Hazārah, &c., 16 mahals, 1 code. Hazārah, Chandanwat of the Chenāu Doāb. Bherah, Khokharwāl. Khushāb, Kal Bhelak,¹²² Khār Darwāzah, Tāral, Shor, Shamshābūd, separate from Bherah. Shorpur separate from Chandanwat, Shakarpur separate from Shor.

Spring Harvest of the Subah of Lahore.

	Lahore, &c.	Batalah, &c.	Parasror, &c.	Pati Mahatpur, &c.	Jalandhar, &c.	Rohās, &c.	Siālkot, &c.	Hazārah, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Wheat ...	50-18	49-5	53-17	55-17	53-17	44-18	39-17	55-23
Cabul Vetches ...	64-21	60-10	70-15	...
Indian do. ...	85-20	34-14	85-20	83-14	...	31-8	95-20	34-17
Barley ...	46-0	35-20	38-0	38-0	...	31-8	38-0	38-0
Adas ...	26-21	24-15	24-15	24-15	...	22-9	28-21	26-2
Safflower ...	79-10	79-10	78-10	79-2	...	67-2	78-7	79-10
Poppy ...	129-17	129-17	129-17	129-17	...	115-20	129-18	129-17
Potherbs ...	71-14	67-2	67-2	67-2	...	55-20	67-0	67-2
Linseed ...	31-8	27-24	27-24	31-8	...	22-9	29-22	81-8
Mustard seed ...	81-8	29-2	31-8	31-8	...	26-21	81-8	35-21
Arzan ...	21-6	19-0	19-0	21-6	...	15-16	20-3	20-8
Peas ...	24-15	26-21	27-4	26-21	...	26-21	81-8	27-24
Carrots ...	24-15	25-18	24-15	24-15	...	19-0	24-15	24-15
Onions ...	88-21	83-21	86-18	83-21	...	71-13	88-21	84-24
Fenugreek ...	50-8	46-24	61-12	40-6	...	60-10	67-2	36-28
Persian Water Melons ...	115-20	115-20	115-20	115-20	...	89-15	111-20	111-20
Indian ditto ...	15-16	15-16	15-16	15-16	...	11-18	15-16	15-16
Cumin ...	87-5	84-24	84-5	87-5	...	81-4	84-24	87-5
Ajwādh ...	87-5	84-24	84-0	87-0	...	71-4	84-24	87-5

Autumn Harvest of the Subah of Lahore.

	Lahore, &c.	Batalah, &c.	Parasror, &c.	Pati Mahatpur, &c.	Jalandhar, &c.	Rohās, &c.	Siālkot, &c.	Hazārah, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Sugarcane (paundah) ...	240-12	240-12	240-12	240-12	240-12	183-12½	...	240-12
Common Sugarcane ...	145-9	186-10	145-0	184-4	123-0	123-0	...	170-15
Dark coloured rice ...	64-21	60-9	60-15	60-15	58-4	50-8	67-0	66-0
Common rice ...	49-5	40-6	40-6	46-24	46-12½	39-14	41-9	49-5
Kall ...	32-11	31-8	31-8	80-5	32-15	26-21	81-8	29-2
Māsh ...	35-20	83-4	35-20	39-14	39-14	31-8	85-20	36-23
Cotton ...	80-15	85-0	87-5	88-5	89-15	76-5	77-5	91-18

¹²² In the account of Lahor, Bhalak,

Autumn Harvest of the Subah of Lahore.—continued.

	Lahore, &c.	Battālah, &c.	Parsaror, &c.	Pati Haibatpur, &c.	Jālandhar, &c.	Rohtās, &c.	Sialkot, &c.	Hazārah, &c.
	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.	D. J.
Moth	20-9	22-9	23-23	22-9	22-9	20-3	23-12½	23-12½
Gāl	17-22	15-16	17-20	17-20	15-16	13-12	16-15	19-0
Turiya	...	33-14	35-20	26-21	...	31-8	38-0	...
Arzan	20-9	17-0	17-22	22-9	15-22	14-14	17-22	29-2
Indigo	156-23	156-13	156-13	156-13	156-13	134-4	134-18	158-19
Hinna	70-0	70-0	74-23	76-0	74-23	67-6	74-23	77-24
Hemp	93-23	93-23	93-23	93-23	89-15	80-12	93-23	93-23
Potherbs	80-12½	80-17	80-17	80-12½	80-17	60-9	70-17	80-12½
Kachrah	12-8	12-8	12-8	12-8	12-8	10-6	12-8	13-11
Pān	123-15	123-15	...	123-15	123-15
Singhārah	115-20	115-20	...	115-20	115-20
Jowāri	40-6	35-20	38-0	38-0	35-20	31-8	38-0	38-0
Lahdarah	31-8	29-2	30-5	29-2	26-21	24-15	23-2	31-8
Kodaram	33-14	35-20	34-17	31-8	33-14	31-8	35-20	35-20
Mandwah	33-14	31-8	31-8	32-15	26-21	26-21	21-20	32-15
Sesame	46-24	42-12	42-12½	44-18	40-6	33-14	48-12½	46-24
Shamākh	13-15	12-20	12-8	12-8	12-9	10-2	12-8	13-15
Mung	40-12½	40-6	26-21	44-18	44-18
Kori	13-15	12-8	12-8	12-8	15-5	10-2	12-8	12-8
Turmeric	133-0	133-0	138-0	134-4	133-0	115-20	184-4	133-20

Subah of Mālwah.

1. Sarkār of Ujjain, 10 mahals. City of Ujjain with suburban district, Dipālpur, Ratlām, Nawlāi, Badhnāwar, Kanel, Anhal, Khāchrod, Sānwer, Pānbihār.

2. Sarkār of Hindiah, 22 mahals.

3. „ „ Kotri, 9 do.

4. „ „ Sārangpur, 23 do.

5. „ „ Bijagarh, 32 do.

6. „ „ Gāgron, 11 do.

7. Sarkārs of Raisin and Chanderi, 1 code. Sarkār of Raisin, Asāpori, &c. 6 mahals. Bhilsah, Bhorī, Bhojpur, Bālābhat, Thānah Mir Khān, Jājoi, Jhatānawi, Jalodah, Khiljipur, Dhāmōni, Dekhwārah, Deorod, Dhāniah, Raisin with suburban district, Sewāni, Sarsiah, Shāhpur, Khimlāsah, Khēra, Kesorah, Khāmgarh, Kargarh, Korai, Laharpur, Māhsamand. Sarkār of Mando, 12 mahals. City of Mando, Amjharah, Mahesar, Dikthān, Dharmagāon, Sānkor, Panmān, Dhār, Barodah, Hāsīlpur, Sanasi, Kotrah, Manāwarah Nalchah and Nawali, 2 mahals.

Subah of Multān.

Sarkār of Dipālpur. Dipālpur, &c., 14 mahals; one *Dastur*; Dipālpur, Lakhi bālā Bhoj, Lakhi Kalnārki, Lakhi Yusfāni,¹²³ Lakhi. Khokharāin, Kabulah, Lakhi Rahimābād, Lakhi Chahni, Lakhi Qiyāmpur, Lakhi Jangli, Lakhi Aālampur, Jalālābād, Tappah Sadkarah, 2 mahals. Tappah Sadkarah, Shahzādah Baloj, Karal, Khānpur, Rasulpur, Shahzādah Hajrau, Mundi.

*Spring Harvest of the
Subah of Multān.*¹²⁴

*Spring Harvest of the
Subah of Mālwah.*

	Multān, &c. 26 mahals.	Dipālpur, &c. 14 mahals.	Sadkarah, &c. 11 mahals.	Ujjain, &c.	Raisen, &c.	Māndo, &c.
	D. J.	D. J.	D. J.	M.123 D. J.	D. J.	D. J.
Wheat ...	58-17	44-18	51-11	...	29-20	...
Cabul Vetches	40-12	...
Barley ...	49-5	30-5	30-20	...	46-24	...
Adas ...	44-5	24-15	47-14	...	30-5	...
Safflower ...	73-20	78-20	70-8*	3½ 2 13	69-20	...
Poppy ...	115-20	128-15	129-0	4½ 5 20	127-15	...
Pot-herbs ...	67-2	70-15	67-2	8½ 2 13	60-9	...
Linseed	29-2	31-8	...	31-8	...
Mustard seed ...	44-18	29-2	31-2	3½ 2 13
Arzan ...	29-2	20-17	20-8	...	16-12	...
Peas	23-12	25-17	...	31-8	...
Carrots	22-9	36-1	...	27-24	...
Onions ...	71-14	74-7	72-18
Fenugreek ...	69-20	89-8	44-18
Persian musk melons	116-0	115-20	8½ 1 3	115-20	...
Indian do. ...	22-9	15-16	15-16	...	15-0	...
Cumin ...	73-20	74-8	77-11	...	46-2	...
Kur rice	85-0	...
Ajwāin	86-2	...

*Autumn Harvest of the
Subah of Multān.*

*Autumn Harvest of the
Subah of Mālwhā.*

	Multān & c. 22 mahals.	Dipālpur & c. 14 mahals.	Sadkarah & c. 11 mahals.	Ujjain, & c.			Raisen, & c.	Mando, & c.		
	D. J.	D. J.	D. J.	M.	D.	J.	D. J.	M.	D.	J.
Sugarcane (paundah)	240-12	240-11	7½	1	21	239-6
Common Sugarcane	134-4	126-9	143-3	4½	5	8	48-15	6	1	0
Dark coloured rice	...	60-3	64-21	70-18
Common rice	49-5	49-15	49-5	55-3
Kalt	...	27-24	31-3	46-6
Māsh	40-0	32-11	35-20
Cotton	93-23	87-5	89-11	2½	1	2	87-5	2½	3	1
Moth	38-0	22-9	23-12	26-21
Gāl	26-21	17-22	19-0	8-8
Arzan	31-20	23-12	22-9
Indigo	145-9	150-19	159-22	2½	1	2	4-24
Hitna	...	76-0	76-0	2½	1	1
Hemp	85-0	91-17	93-23
Pot-herbs	73-20	77-4	82-18
Pān	...	123-0
Singhārah	...	111-0	...	4½	5	20	115-20	6½	4	7
Lobiya	38-0	38-0	33-14
Jowāri	42-12	35-20	38-0	44-18
Kuri	...	13-11	12-8	15-16
Lahdarah	44-18	29-2	81-2
Kodaram	...	33-14	33-14
Mandwah	...	30-19	31-8	31-8
Sesame	41-9	43-15	44-18	40-12
Shamākh	12-8	12-8	13-11
Mung	40-5

Note.—I cannot understand nor explain the notation in Muzaffaris and am not sure if I have interpreted it correctly.

EDITOR'S NOTE

On the correction of place-names and dynastic lists in Jarrett's translation, vol. II.

In tracing the Hindu personal names and the numerous less important place-names, the variant readings given in the printed Persian text of the *'Ain-i-Akbari* are of no help to us, unless we know the correct names from other sources, such as (in the case of topography) large-scale maps and the records in the modern revenue and judge's courts of those areas. Similarly, Tieffenthaler's *Geography of Hindustan* (Fr. trans. by Bernoulli, 1786) is of no real use to us; he merely translated from Persian mss of the *'Ain*, and where his names differ from those in our printed text of the *'Ain*, he can be correct only in the rare instances of his having had a more correct and legible ms. of the book before him and his having transcribed these names in Roman letters without a mistake. Most of the mistakes in the proper names are due to the ignorance or carelessness of the Muslim clerks of Abul Fazl and the later copyists of his book. Students of Persian mss know that the usual sources of mistake in mss are the confusion, in writing, of the letters *R*, *D*, and *W*, (and sometimes also *HU* for *DU*) and the wrong placing (or omission) of dots (*nuqta*) by which *B*, *T*, *N*, *Y*, *P* and *H* are confounded together.

The only dependable means of correcting the place-names in the *'Ain-i-Akbari* is to use the Survey of India maps (quarter-inch or even one inch to the mile sheets), and this I have done. But absolute certainty on this point can be gained only by carefully verifying these names from the old revenue and civil court records of each particular subdivision included in the *'Ain*. I wish that local inquirers would do this work and send the result to the Royal Asiatic Society of Bengal (Calcutta) for incorporation in a future edition of this translation.

Unlike his brother Faizi who was a Sanskrit scholar, Abul Fazl did not know that difficult language. So, the author of Akbar's *Imperial Gazetteer* had to engage a number of Brahman pandits and Kayasth scribes, and they read out and summarised in Urdu the legendary Hindu history from the Sanskrit epics and Purānas and quasi-historical works like the *Rajatarangini* and the guide-books

to famous Hindu shrines (i.e., *māhātmyas* and *khandas*.) These summaries were put down in Persian by Abul Fazl's clerks. Pickings from these Persian notes went to the making of ancient Hindu history as given by Abul Fazl in the final shape of the *'Ain-i-Akbari*.

When Col. Jarrett made his translation of the second volume of the *'Ain-i-Akbari* in the Eighteen-eighties, his only sources for ancient Hindu history were Wilson's *Vishnu Purāna* and Prinsep's *Useful Tables*, and for early Muslim history, Firishtah, *Riyāz-us-Salātin* and similar uncritical early works. During the sixty years and more that have passed since then, the study of Indian history has made such a great advance that it would be an injustice to the modern reader—and also to Jarrett's memory,—to reprint his notes from obsolete authors. I have therefore felt it necessary to sweep away his heaps of dead leaves (as I have called them in my introduction to the revised edition of the third volume of the *'Ain*), and to give extracts only from modern authorities, such as the Dacca University *History of Bengal* (vol. I. Hindu period, vol. II. Muslim Rule), R. D. Banerji's *History of Orissa* in 2 volumes (1930-1931, replacing the ante-diluvian Hunter's *Orissa* of 1872, which Jarrett cited,), the *Cambridge History of India*, Elliot and Dowson, &c.

In fact, Abul Fazl's Hindu history is of no real value, as it was entirely drawn from traditions and myths, long before the age of critical historiography based upon inscriptions, coins and records. Hence, I have not wasted paper by trying to refute every error in this portion of the *'Ain*, but I have given exact references to modern sources, where the reader will find the necessary correct information on the subject.

The pandits employed by Abul Fazl have made a hotch-potch of the old history of Hindustan by mixing together legendary and historical kings, inserting real royal names of one dynasty or province into the dynastic list of another, and thus inextricably mingling truth and fancy together, e.g., Anangabima was a real king of Orissa (three of the dynasty bearing that name) shortly before the Muslim invasion, but Abul Fazl makes him the son of the pre-historic Bhagadatta, the comrade of Duryodhan of the *Mahābhārat* and a king of Bengal! So also, Bhoja, who reigned elsewhere than in Bengal and was a Kshatriya, is

made in the *Ain* a Kāyastha and the founder of the second line of Bengal kings.

As for Raja *Naujah*, Abul Fazl is confused, making him the last king of the Sena dynasty in one place, and the father of Lakshman Sena in another. I cannot conceive how *Nārāyan* can be misspelt in Persian writing as *Naujah*. I suggest the emendation *Budh-sen* (a real king at the end of the Senas) for *Naujah* in the list, and *Raja of Nudja* for *Raja-i-Naujah* at the first mention.

Correct list of the Pala kings of Bengal—

Gopāla I., accession c. 750 A.D.
Dharma-pāla	...	770
Deva-pāla	...	810
Vigraha-pāla I or Sura-pāla I	...	850
Nārāyana-pāla	...	854
Rājya-pāla	...	908
Gopāla II.	...	940
Vigraha-pāla II	...	960
Mahi-pāla I	...	988
Naya-pāla	...	1038
Vigraha-pāla III	...	1055
Mahi-pāla II	...	1070
Sura-pāla II	...	1075
Rāma-pāla	...	1077
Kumāra-pāla	...	1120
Gopāla III	...	1125
Madana-pāla	...	1140
Govinda-pāla	...	1155

(D.U. Bengal, i. 176-177.)

Correct list of the Sena kings of Bengal—

Vira-sena (progenitor, not Raja)

Sāmanta-sena

Hemanta-sena, 1st Raja, in Rārhi acc. c. 1080.

Vijaya-sena, conquered all Bengal except Gaur, (r. 1125-58)

Vallāla-sena, r.c. 1158-1179

Lakshman-sena, r.c. 1179-1206. His sons Vishwa-rupa-sena and Keshav-sena ruled in East Bengal till c. 1230. Surya-sena and Purushottama-sena were probably the sons of Vishwa-rupa, and were in power till c. 1245. Among the

chiefs with names ending in Sena, in Eastern India in the 13th century, are Buddha-sena (of Pithi) and his son Jaya-sena, and Madhu-sena (date prob. 1289); but they were mere local barons or zamindārs and not ruling sovereigns. (D.U. *Bengal*, i. 205-228.)

Correct list of the Pre-Mughal Muslim rulers of Bengal (leaving out the viceroys and rebel sultans from Qutbuddin Aibak to Md. Tughluq Shah, 1202-1339.)—

Ala-ud-din Ali (Mubārak) accession 1339 A.D.

Early Ilyās Shāhi dynasty

Shams-ud-din Ilyās (Bhangāra), ...	r. 1348-'57
Sikandar Shah r. 1357-c. '91
Ghiyās-ud-din Ā'zam Shāh ...	c. 1391-1409
Ghiyās-ud-din Ā'zam Shāh ...	c. 1391-1409
Saifuddin Hamza Sh. ...	1409-10
Shihābuddin Bāyezid Sh. (title	
Shams-ud-din) ...	1411-13
'Alauddin Firuz Sh. ...	1414

Hindu dynasty

Ganesh (<i>var.</i> Kans) ...	1414-1418
Jalāluddin, s. of Ganesh ...	1418-31
Shams-ud-din Ahmad ...	1431-42

Later Ilyās Shāhi dynasty.

Nāsir-ud-din Mahmud I ...	1442-59
Rukn-ud-din Bārbak Sh. ...	1459-74
Shams-ud-din Yusuf Sh. ...	1471-81
Jalāl-ud-din Fath Sh. ...	1481-87

Abyssinian dynasty.

Bārbak Shah ... 6 months,	1487
Saif-ud-din Firuz Sh. ...	1487-90
Nāsir-ud-din Mahmud II ...	1490-91
Shams-ud-din Muzaffar ...	1491-93

(Arab) Husain Shāhi dynasty.

A'la-ud-din Husain Shāh, ...	1493-1510
Nāsir-ud-din A. M. Nasrat Sh. ...	1519-32
A'la-ud-din Firuz ...	1532-33
Ghiyās-ud-din Mahmud, ...	1533-38

Sur dynasty.

Sher Shāh	1539-45
Islām Shāh	1545-53
Shams-ud-din Md. Sh.	1553-55
Ghiyās-ud-din Bahādur (Khizr Kh.)	1556-60
Ghiyās-ud-din II	1561-63
His son	...	7 months,	1563
Ghiyās-ud-din III	...	one year	1564

Karrāni dynasty (Afghan).

Tāj Kh. Karrāni r.	1564-65
Sulaiman Karrāni	1565-72
Bāyezid Karrāni	1572
Dāud Karrāni	1573-76

(See D.U. Bengal, vol. II)

Note on the sarkars of Bengal in Akbar's time.

In view of the frequent changes in the administrative geography of Bengal under British rule and the radical change resulting from the partition of Bengal in August 1947, it is impossible to indicate briefly the extent of any of the *sarkārs* of the *Ain* in terms of the districts of the two parts of Bengal as they are today. Among the striking points of difference are that under Mughal rule (a) southern and western Midnapur belonged to Orissa and not to Bengal, (b) the district of Purnia and the eastern portion of Bhagalpur were attached to Bengal and not to Bihar, and (c) Sikhar-bhum (old name of Pachet), Dhaval-bhum, and Singbhum formed parts of the *Sarkār* of Mandaran belonging to Bengal.

The following table of approximate equivalents between Akbar's *sarkārs* and the Bengal districts in the last stage of British rule may be of some help to the modern reader.

<i>Sarkars</i>		<i>Districts</i>
Udambar	...	Rajmahal subdivision, N.W. Murshidabad, and N. Birbhum.
Jannatābād	...	Malda (mainly)
Fathābād	...	Faridpur, South Bakarganj and the islands at the mouth of the Ganges.
Mahmūdābād	...	North Nadia, North Jessore, and West Faridpur.
Khilāfatābād	...	South Jessore and West Bakarganj.

<i>Sarkars</i>		<i>Districts</i>
Baklā	North and East Bakarganj and S.-W. Dacca.
Tājpur	...	East Purnia and West Dinajpur.
Ghorāghāt	...	S. Rangpur, S.-E. Dinajpur, and N. Bogra.
Pinjāra	...	Dinajpur and parts of Rangpur and Rajshahi.
Bārbakābād	...	mainly Rajshahi, S.W. Bogra and S.E. Malda.
Bāzuhā	...	partly Rajshahi, Bogra, Pabna and Dacca.
Sonārgāon	...	West Tippera and Noakhali.
Sharifatābād	...	mostly Burdwan.
Sulaimanābād	...	North Hugli, and adjacent parts of Nadia and E. Burdwan.
Sāt-gāon	...	24 Parganas, W. Nadia (?) and Howrah.
Mandāran	...	Bankura, Vishnupur, S.E. Burdwan and W. Hugli.

Bāzuhā—This word is the Persian plural of *bāzu* meaning 'an arm', *i.e.*, the direction of a locality with reference to a central point such as the capital town. In early times the provinces of a kingdom were indicated as its different directions (*e.g.*, *Tarf*, *subah* from *sub*, whence the titles of provincial governors *Tarf-dār*, *subah-dār*, &c.) As will be noticed in the lists of the *Ain*, in Orissa locality-names are compounded with the word *dik* meaning direction of the compass, and in Bengal and elsewhere with the word *dast*, meaning the right arm or the left arm, of the speaker. In Akbar's time the portion of Bengal known as *Bāzuhā* had not yet been consolidated into a compact area, but lay sprawling over many neighbouring districts and having no clear-marked boundaries. *Rāst* and *chap* mean the right and left hands respectively.

J. SARKAR.

ACCOUNT OF THE TWELVE SUBAHS.

In the fortieth year of the Divine Era [1594] His Majesty's dominions consisted of one hundred and five *Sarkārs* (divisions of a Subah) subdivided into two thousand seven hundred and thirty-seven townships (*gasba*). When the ten years' settlement of the revenue was made (which amounted to an annual rental of three *Arbs*, sixty-two *krors*, ninety-seven *lakhs*, fifty-five thousand two hundred and forty-six *dāms* [Rs. 9,07,43,881] and twelve *lakhs* of betel leaves), His Majesty apportioned the Empire into twelve divisions, to each of which he gave the name of *Subah* and distinguished them by the appellation of the tract of country or its capital city. These were Allahabad, Agra, Oudh, Ajmer, Ahmadābād, Behār, Bengal, Delhi, Kābul, Lāhor, Multān, Mālwah : and when Berār, Khandesh and Ahmadnagar were conquered, their number was fixed at fifteen. A brief description of each is here set down, and an account of their rulers together with the periods in which they flourished, duly recorded.

BENGAL SUBAH.

Since the conceptions of sovereign rule embrace the universe, I propose to begin with Bengal which is at one extremity of Hindustān and to proceed to Zabulistān¹ and I hope that Turān and Irān and other countries may be added to the count. The country lying to the east will be first described, followed by the north, the south, and the west.

This *Subah* is situated in the second clime.² Its length

from Chittagong to *Garhi*³ is four hundred *kos*. Its breadth from the northern range of mountains to the southern frontier of the *Sarkār* of *Mandāran*, is two hundred *kos*, and when the country of Orissa was added to this *Subah*, the additional length was forty-three *kos* and the breadth twenty-three. It is bounded on the east by the sea, on the north and south by mountains and on the west by the *Subah* of Behār. The tract of country on the east called *Bhāti*,⁴ is reckoned a part of this province. It is ruled by Isa Afghān and the *Khutbah* is read and the coin struck in the name of his present Majesty. In this country the mango trees grow to the height of a man or not so high and produce abundant fruit. Adjoining it, is an extensive tract of country inhabited by the Tipperah tribes. The name of the ruler is *Bijay Mānik*. Whosoever obtains the chieftainship, bears the title of *Mānik* after his name, and the nobles that of *Nārāin*. He has a force of two hundred thousand footmen and a thousand elephants. Horses are scarce. To the north is a country called *Kuch*. Its chief commands a thousand horse and a hundred thousand foot. *Kāmrup*, commonly called also *Kāonrup* and *Kāmtā*, is subject to him. The inhabitants are as a race good looking and addicted to the practice of magic. Strange stories are told regarding them. It is said that they build houses, of which the pillars, walls and roofs are made of men. Some of these they compel by the power of sorcery, and criminals deserving of death are also thus made use of. Whoever voluntarily surrenders

The Arabs adopted this system but restricted the number to seven. They considered three-fourths of the globe to be submerged and one-fourth above water. Of this latter $\frac{3}{4}$ was habitable and the remainder waste or desert. The habitable portion was 33 150,000 square miles in extent, each mile being 4000 cubits, each cubit 24 digits. It was situated between the Equator and the N. pole and was divided into 7 climates.

³ This is Teliagarhi, a pass in the Sathāl Pargana, Bihar, lying between the Rājmaḥāl hills on the S. and the Ganges on the N. Formerly of strategic importance as commanding the military approaches to Bengal proper. The ruins of a large fort still exist, through which the E. I. Railway passes. It seems never to have been completed and was constructed in the last century by the Teli *zamindār* who was forcibly converted by the Muhammadans. Hence the name of the fort and the *pargana* in which it is situated. *Imp. Gazetteer*.

The *kos* is for convenience generally taken at two English miles. The basis of all linear systems is the same, *viz.*, the cubit or human forearm. Proceeding upwards four *hāthi*s or cubits=a *danda* or staff: and 2000 *dandas* a *kos*, which by this calculation should be 4000 yards English or nearly 2½ miles. *Useful Tables*, p. 87. Also Elliot's *Memoir of Races*, N. W. P. II, 194.

⁴ The name given by the Muhammadan historians to the coast-strip of the Sundarbans from Hijili to the Meghna Lat. 20° 30' to 22° 30' N., long. 88° to 91° 14' E. The name means "low lands overflowed by the tide" and is still applied to the Sundarban tracts of Khulna and Bākarganj Districts, I. G. For Isa Kh., D.U. Bengal, ii. 194-212.

himself for this purpose, escapes retribution for a year. Various conveniences are reserved for him. In due time, men armed with swords cut them down, and from their movements or immobility or other aspects, they have cognizance of scarcity or plenty or duration of years [of the reign] or the longevity of the ruler or defeat of enemies. They also cut open a pregnant woman who has gone her full term of months and taking out the child, divine somewhat as to the future. There grows a wonderful tree whose branches when cut, exude a sweet liquid which quenches the drought of those athirst. They have also a mango tree⁵ that has no trunk; it trails like a climbing vine, over a tree and produces fruit. There is likewise a flower⁶ which after it has been gathered for two months, does not wither nor lose its colour or smell. Of this they make necklaces.

Bordering on this country are the dominions of the Rājah of Ashām (Assam) whose great pomp and state are subjects of general report. When he dies, his principal attendants of both sexes voluntarily bury themselves alive in his grave. Neighbouring this is Lower Tibet and to its left is *Khata*.⁷ This is also called *Mahāchin* which the vulgar pronounce *Māchin*. From *Khān Bāligh*⁸ its capital, to the ocean, a forty days' journey, they have cut a canal both sides of which are embanked with stone and mortar. Alexander of Greece advanced to that country by this route.⁹ Another road is also mentioned which can be traversed in four days and four nights.

⁵ The *Willoughbeia edulis*. It is known to natives of Bengal, Assam and the Chittagong Hill tracts, as the Loti Ā'm (*Loti*, for Sanskrit *latā*, a creeper) but botanically is far removed from the true mango. The fruit is said to be pleasant to taste. The leaf of the dried specimen is very similar to the ordinary mango leaf: the fruit is about $2\frac{1}{2}$ inches long and $2\frac{1}{4}$ broad (Dr. King.)

⁶ The *Tulsi*, (*Ocimum Sanctum*).

⁷ China for nearly 1000 years, writes Yule (*Marco Polo*, 2nd ed. Introd., p. 11) has been known to Asia under the name of *Khitai*, *Khata* or *Cathay* and is still called *Khitai* by the Russians. [*Ency. Islam*, ii. 737 under *Kara Khitai*.]

⁸ De Guignes (*Hist. des Huns*, gives this name to Peking, called also *Tatou* the *grand court* or *Khān Bāligh*, the *court of the Khān*. Several towns have received this name which as it signifies the royal residence is transferable to any that the monarch may honour with his presence. It is the *Cambalu* of Western geographers and historians and placed by them in Northern China or Grand Tartary, while the Orientals locate it in China Proper. (*Ency. Islam*, ii. 898).

⁹ In B.C. 329 Alexander crossed the Oxus in pursuit of Bessus and after putting him to death, he passed the Jaxartes (Sir Daria) and defeated several Scythian tribes north of that river. This was the northernmost point that he reached. A. Fazl is merely relating the Muslim legend of Alexander, for which see *Ency. Islam*, ii. 533 under *al-Iskandar*. [J. S.]

To the south-east of Bengal is a considerable tract called *Arakan* which possesses the port of *Chittagong*. Elephants abound, but horses are scarce and of small size.¹⁰ Camels are high priced : cows and buffaloes there are none, but there is an animal which has somewhat of the characteristics of both, piebald and particoloured, whose milk the people drink. Their religion is said to be different to that of the Hindus and Muhammadans. Sisters may marry their own twin brothers, and they refrain only from marriages between a son and his mother. The ascetics, who are their repositories of learning, they style *Wali* whose teaching they implicitly follow. It is the custom when the chief holds a court, for the wives of the military to be present, the men themselves not attending to make their obeisance. The complexion of the people is dark and the men have little or no beard.

Near to this tribe is *Pegu* which is also called *Chin*. In some ancient accounts it is set down as the capital city of *Chin*. There is a large military force of elephants and infantry, and white elephants are to be found. On one side of it is *Arakan*. There are mines of rubies, diamonds, gold, silver, copper, naphtha and sulphur, and over these mines there is continual contention between this country and the *Maghs* as well as the tribes of Tipperah.

The original name of Bengal was *Bang*. Its former rulers raised mounds measuring ten yards in height and twenty in breadth throughout the province which were called *Al*.¹ From this suffix, the name Bengal took its rise and currency. The summer heats are temperate and the cold season very short. The rains begin when the sun is midway in Taurus, (May) and continue for somewhat more than six months, the plains being under water and the mounds alone visible. For a long time past, at the end of the rains, the air had been felt to be pestilential and seriously affected

¹⁰ The domestic animals of the Arakan Hill Tracts according to the *Imp. Gaz.* are the *gaya*, buffalo, ox, goat, pig, dog. "The *Gaya* (*Bos Frontalis*) has interbred with the common Indian cattle; these hybrids are brought down by the Bhutiahs to the annual fair in the Darrang District : though they thrive in Shillong they soon die if kept in the plains. The *Gaya* is plentiful along the spurs of the Bhutan hills, amongst the Duffas, Lushais, and along the hilly tract well into Chittagong." *Sport in British Burma* by Lieut-Col. Follock. An alternative reading gives, "horses are scarce, and asses and camels are high-priced," which Gladwin has adopted.

¹ Sansk. *ali* a mound of earth or ridge for crossing ditches, dividing fields and the like.

animal life, but under the auspices of his present Majesty, this calamity has ceased.

Its rivers are countless and the first of them in this province is the *Ganges*: its source cannot be traced. The Hindu sages say that it flows down from the hair of *Mahadeva's* head. Rising in the mountains towards the north, it passes through the province of Delhi, and imperial Agra, and Allahabad and Behār into the province of Bengal, and near *Qāzihattah* in the *Sarkar* of *Bārbakābād*, it divides into two streams. One of these, flowing east-wards, falls into the sea at the port of Chittagong. At the parting of the waters, it takes the name of *Padmāwati* and pursues a southern course. It is divided into three streams; one, the *Sarsuti* [Saraswati]; the second the *Jamna* (Jamuna) and the third the *Ganges*, called *collectively* in the Hindi language *Tribeni*,² and held in high veneration. The third stream after spreading into a thousand channels, joins the sea at *Sātgaon* [Hugli]. The *Sarsuti* and the *Jamna* unite with it. In praise of this stream the Hindu sages have written volumes. From its source to its mouth it is considered sacred, but some spots have a peculiar sanctity. Its water is carried as an offering of price to far distant places. Believing it to be a wave of the primeval river, they hold its worship to be an adoration of the supreme being, but this is no part of the ancient tradition. Its sweetness, lightness and wholesomeness attest its essential virtues. Added to this, it may be kept in a vessel for years without undergoing change.

Another river is the *Brahmaputra*. It flows from *Khatā*³ (China) to *Kuch* and thence through the *Sarkār* of *Bāzuhā* and fertilising the country, falls into the sea.

And again there is the sea which is here a gulf of the great ocean, extending on one side as far as Basrah and on the other to the Egyptian *Qulzum*⁴ and thence it washes

² San-k. *tribeni* three braids of hair. Wilford says (*Asiatic Research*, Vol. XIV, p. 396) that the waters of these three rivers do not mix. The waters of the *Jamna* are blue, those of the *Saraswati* white and the *Ganges* is of a muddy yellowish colour.

³ Its rise is supposed to be from the S. E. base of the sacred *Kailās* hill, on the opposite side of the water-parting in which the *Sutlej* and the *Indus* also take their rise. Its course, confluents and history may be read in the *I. G.*

⁴ This is the ancient *Klysma*, the site of the modern *Suez*, in the neighbourhood of which the *Tel Qulzum* still retains the name which has been given to the Red Sea. *Encyc. Islam*, ii, 1114.

both Persia and Ethiopia where are Dahlak and Suākin, and is called (the Gulf of) Omān and the Persian Sea.

The principal cultivation is rice of which there are numerous kinds. If a single grain of each kind were collected, they would fill a large vase. It is sown and reaped three times a year on the same piece of land with little injury to the crop. As fast as the water rises, the stalks grow, so that the ear is never immersed, inasmuch as those experienced in such matters have taken the measure of a single night's growth at sixty cubits.⁵ The people are submissive and pay their rents duly. The demands of each year are paid by instalments in eight months, they themselves bringing mohars and rupees to the appointed place for the receipt of revenue, as the division of grain between the government and the husbandman is not here customary. The harvests are always abundant, measurement is not insisted upon, and the revenue demands are determined by estimate of the crop. His Majesty in his goodness has confirmed this custom. Their staple food is rice and fish; wheat, barley and the like not being esteemed wholesome. Men and women for the most part go naked wearing only a cloth (*lungi*) about the loins. The chief public transactions fall to the lot of the women. Their houses are made of bamboos, some of which are so constructed that the cost of a single one will be five thousand rupees or more and they last a long time. Travelling is by boat, especially in the rains, and they make them of different kinds for purposes of war, carriage or swift sailing. For attacking a fort they are so constructed that when run ashore, their prow overtops the fort and facilitates its capture. For land travel they employ the *Sukhāsan*. This is a crescent-shaped litter covered with camlet or scarlet cloth and the like, the two sides of which have fastenings of various metals, and a pole supporting it is attached by means of iron hooks. It is conveniently adapted for sitting in, lying at full length or sleeping during travel. As a protection against sun and rain they provide a commodious covering which is removable at pleasure. Some enjoy the luxury of riding on elephants but they rarely take to horseback. The mats made here often resemble woven silk.

⁵ Gladwin has *six* for *sixty*. The long stemmed rice, according to the I.G. is extensively cultivated in the swamps. The seed is sown when the marshes are dry or nearly so, and when the rains set in the plant shoots up with the rise of the water and can be grown in water to a depth of from 18 to 20 feet, but even this is not in one night.

Tri^a inde genera eunuchorum veniunt, quo Sandalos, Bādāmos et Kāfuros nuncupant. Priores, partibus genitalibus radicaliter exsectis, Atlises etiam nominant. Bādāmis pars solum penis relinquitur. Kāfuros adhuc teneræ ætatis, testes vel compressi conficiuntur vel exsecantur: tamen notatum est, castrationem, quæ pervicaciam cæteris omnibus animalibus tollit, hominibus solis excitare.

Salt is in great demand and is brought from long distances. Diamonds, emeralds, pearls, cornelians and apates are imported. Flowers and fruit are in plenty. The betel-nut is of a kind that stains of a red colour the lips of those who chew it.

Jannatābād is an ancient city: for a time, it was the capital of Bengal and was widely known as Lakhnauti and for a while as Gaur. His Majesty the late Emperor Humāyūn distinguished it by this title of *Jannatābād*. It has a fine fort and to the eastward of it is a lake called *Chhatīātātā* in which are many islands. Were the dam that confines it to break, the city would be under water. About a *kos* to the north of the fort, is a large building and a reservoir, monuments of great antiquity. From time immemorial, its water has been considered to be of a poisonous character. The place was called *Piyāsbāri* (abode of thirst), and criminals condemned to death, were there confined who in a short time perished from the effects of this brackish water. At present in the blessed reign of His Majesty, this practice has been discontinued.

Mahmudābād. The marshes around the fort have added to its impregnability. The ruler of this district, at the time of its conquest by Sher Khān, let some of his elephants loose in its forests from which time they have abounded. Long pepper grows in this tract.

The *Sarkār* of *Khalifatābād* is well wooded and holds wild elephants. The *Sarkār* of *Baklā* extends along the sea shore. The fort is surrounded by woods. On the first day of the new moon the sea steadily rises until the fourteenth, and from the fifteenth till the end of the month as gradually falls. In the 29th year of the Divine Era, a terrible inundation occurred at three o'clock in the afternoon, which swept

* I have imitated the example of Gladwin in veiling the following passage under the mask of a learned language and with a slight alteration have borrowed his words. (Jarrett.)

over the whole *Sarkār*. The Rājāh held an entertainment at the time. He at once embarked on board a boat, while his son Parmānand Rāe with some others climbed to the top of a temple and a merchant took refuge in a high loft. For four hours and a half the sea raged amid thunder and a hurricane of wind. Houses and boats were engulfed but no damage occurred to the temple or the loft. Nearly two hundred thousand living creatures perished in this flood.

In the *Sarkār* of *Ghoraghāt*, silk is produced and a kind of sackcloth [jute]. Numbers of eunuchs are here and hill ponies in plenty are procurable. There are many kinds of indigenous fruits, especially one called *Latkan*.⁷ It is the size of a walnut with the taste of a pomegranate and contains three seeds.

The *Sarkār* of *Bārbakābād* produces a fine cloth called *Gangājal* (*Ganges water*), and a great abundance of oranges.

In the *Sarkār* of *Bāzuhā* are extensive forests which furnish long and thick timbers of which masts are made. There are also iron mines.

The *Sarkār* of *Sonārgāon*⁸ produces a species of muslin very fine and in great quantity. In the township of *Egāra Sindur* is a large reservoir which gives a peculiar whiteness to the cloths that are washed in it.

In the *Sarkār* of *Sylhet* there are nine⁹ ranges of hills. It furnishes many eunuchs.

There is a fruit called *Suntarah*¹⁰ in colour like an orange

⁷ Dr. King of the Royal Botanical Gardens, Calcutta, considers this to be a species of *Elæcarpus*. The fruits of all the species are a good deal alike, varying in size from an olive to a walnut, having an external fleshy pulp more or less palatable (in some species of fair flavour) and containing a stone. The later is usually found to be divided into 3 cells, one of which contains a mature seed, the seeds in the other two being abortive. The taste of the pulp of the *E. serratus* and *E. lanceifolius* (both natives of Rangpūr) is a good deal like that of the pomegranate.

⁸ This was the ancient Mahammadan capital of Eastern Bengal but is now an insignificant village called Painām in the Dacca District. I.G.

⁹ In the south of the district, says the *Gazetteer*, eight low ranges of hills run out into the plain, being spurs of the Tipperah mountains. The highest is about 1000 feet above sea level. There is also a small detached group, the Ita hills, in the centre of the district.

¹⁰ Commonly *Suntarah*. The name is supposed to be a corruption of Cintra, but its mention by Baber in his Memoirs seems subversive of this derivation, for though the fruit is said to have been an eastern importation into Portugal, it is improbable that the foreign name could have been current in India at so early a date. Humayun praises it highly saying that no one cares for any other fruit who has this. He states that it is found only at Sonārgāon in Beugal and in the greatest perfection only at one place. A note to the *Memoirs* (p. 329) says that the description of the fruit by Baber suits more the *Citrus decumana* than any other, and its Bengali name *Batāri nimbu*, the Batavia lime, denotes its being an exotic.

but large and very sweet. The China root² is produced in plenty. In ancient times it had not been discovered until some scientific travellers from European Turkey introduced it to universal notice. Aloes-wood is abundant in these mountains. At the end of the rains they fell the trees to the ground, and after a certain time they give them various names according to their greenness or maturity.

The *Bhangrāj*³ is a bird of a black colour, with red eyes and a long tail. Two of the feathers extend to a length of a *gaz*. They are snared and tamed. It catches the note of any animal that it hears, and eats flesh. The *Sherganj* is of the same kind but its beak and legs are red; in imitating sounds, it matches the other and pursues sparrows and the like and eats them.

Chāt-gāon (Chittagong) is a large city situated by the sea and belted by woods. It is considered an excellent port and is the resort of Christian and other merchants.

In the *Sarkār* of *Sharifābād* is a beautiful species of cattle, white in colour, and of a fine build: like camels they are laden kneeling down and carry fifteen *man* weight. It is noted for the Barbary goat and for fighting cocks.

In the *Sarkār* of *Sāt-gāon*,⁴ there are two ports at a distance of half a *kos* from each other; the one is *Sāt-gāon*, the other *Hugli*: the latter the chief; both are in the possession of the Europeans. Fine pomegranates grow here.

² The root of a species of *Smilax* of a pale reddish colour with no smell and very little taste. The *Smilax glabra* or *lancaefolia*, not distinguishable, according to Roxburg, by the eye from the drug known as *China root*. It is a native of Sylhet and the adjacent Garrow country.

³ *Bhringa-rāj*, *Edollus paradiscus* or large racket-tailed Drongo. Plumage uniformly black with a steel-blue gloss. Length to end of ordinary tail 14 inches; wing 6½; tail to middle 6½; outer tail feather 12 to 13 inches more; the shaft having the terminal end for about 3½ inches barbed externally, but towards the tip only on the inner side, and turning inwards so that the under-side becomes uppermost. It will eat raw meat, lizards, and almost any kind of food offered to it. It imitates all sorts of sounds, as of dogs, cats, poultry. The *Bhring-rāj*, (king of the bees) is found in the dense forests of India from the Himalays to the Eastern Ghats as far S. as N.L.15°. Jerdon. *Sherganj* *Cissa Sinensis*, Brisson. *Cissa Venatoria*, Blyth—the green jay: It is found in the South Eastern Himalays and in the hill ranges of Assam, Sylhet, Arakan and Tenasserim. These birds wander about from tree to tree and pick grasshoppers, mantides and other insects, are frequently tamed and caged and are amusing and imitative. They sing lustily a loud screeching strain and are highly carnivorous. The shrike-like habit, in confinement, of placing a bit of food between the bars of their cage is in no species more exemplified than in this—Jerdon. II, 312.

⁴ The traditional mercantile capital of Bengal from the Puranic age to the time of the foundation of the town of Hugli by the Portuguese. Its decay commenced in the latter part of the 16th century owing to the silting up of the channel of the Saraswati. In 1632, Hugli being made a royal port, all the public offices were withdrawn from *Sāt-gāon* which soon sunk into ruin. *Stat. Acct. of Bengal*, III, 307–310.

In the *Sarkār* of *Mandāran* is a place called Harpah in which there is a diamond mine producing chiefly very small stones.

Orissa.

This was formerly a separate State. The climate is extremely healthy. His Majesty apportioned it into five *Sarkārs*, viz., *Jalesar*, *Bhadrak*, *Katak* (Cuttack), *Kaling Dandpāt* and *Raja Mahandrah*. These five are now included in the province of Bengal. It contains one hundred and twenty-nine masonry forts. Its ruler is entitled Gajpati.¹ The rainy season extends over eight months; there are three cold months and one month only that is hot. The staple cultivation is rice and the food of the inhabitants consists of rice, fish, the egg-plant and vegetables. When the rice is cooked, they steep it in cold water and eat it on the second day. The men are effeminate, anointing their bodies with sandal oil and wearing golden ornaments. The women cover only the lower part of the body and many make themselves coverings of the leaves of trees.² The walls of their huts are of reeds and their temples are of stone and of great height. Elephants abound. The inhabitants of Bengal do not understand the language of this country. A woman may have more than one husband. They write on palm leaves³ with an iron pen, holding it with the clenched fist, and pen and ink are rarely employed. The litters called *Sukhāsan* are much in use: cloths are manufactured and the province furnishes eunuchs: fruits and flowers are in great plenty, especially the *gul-i-nasrin*⁴ which is very delicate and sweet-scented: its outer petals are white, the inner yellow. The *keorah*⁵ grows in great abundance and there are various kinds of betel-leaf. Money transactions are in *kauris* which is a small white shell generally divided down the middle; it is found on the sea shore. Four *kauris* make a *ganda*, five *gandas*, a *budi*, four *budis*, a *pan*, sixteen or according to

¹ Lord or rider of the elephant. The suit of cards used by Akbar (Vol. I. p. 316) under the name of Gajpati, symbolised the power and reputation of Orissa in the possession of these animals.

² For the leaf-wearing tribes of Orissa, the *Juangs* or *Patwas*, see Hunter's *Orissa*, ii. 116. Banerji, *Orissa*, i. 19 et.

³ The Brahmanical archives of the temple of Jagannāth consist of bundles of palm leaves, neatly cut and written over with a sharp iron pen without ink. I. G.

⁴ In Hindi, *Scoti* the *Rosa glandulifera*. Roxb.

⁵ *Pandanus odoratissimus*, Roxb.

some twenty *pan*, a *khāwan* [*kāhan*] and ten *khāwan*, a rupee.

Katak (CUTTACK.) The city has a stone fort situated at the bifurcation of the two rivers, the *Mahānadi*, held in high veneration by the Hindus, and the *Katjuri*.⁶ It is the residence of the governor and contains some fine buildings. For five or six *kos* round the fort during the rains, the country is under water. *Rajah* Mukund Deo⁷ built a palace here nine stories in height; the first story was taken up for the elephants and the stables: the second was occupied by the artillery and the guards and quarters for attendants: the third by the patrol and gatekeepers: the fourth by the workshops: the fifth, by the kitchen: the sixth contained the public reception rooms: the seventh, the private apartments; the eighth, the women's apartments, and the ninth, the sleeping chamber of the governor. To the south is a very ancient temple. Overlooking this, in the city of Purushottama (Puri) on the sea shore stands the shrine of Jagannāth. Near to it are the images of Krishna and of his brother and sister,⁸ made of sandal-wood. It is said that over four thousand years ago Rājah Indradaman (Indradyumna) ruler of the Nilgiri hill sent a learned Brāhman to select a suitable spot for the building of a city. He wandered much in search of his object and found a fitting site which he preferred to all other places. On a sudden he beheld a crow plunge into the water and after bathing itself, pay its devotions to the sea. He was astonished at this action and as he understood the language of animals, he inquired of the crow the reason of its proceeding. He received this answer. "I was once of the number of the *devotas* and through the curse of an ascetic was transformed into this shape. A spiritual guide of high illumination affirms that the Supreme Creator has a special regard for this spot and whosoever dwells here and applies his soul to the worship of God, quickly attains his desire. For some years past I have supplicated for my deliverance in this

⁶ One of the deltaic tributaries of the *Mahānadi* dividing into two branches, one of which retains its own name while the other takes that of *Koyākhai* and supplies the Puri district.

⁷ Telinga Mukund Deo (Harichandan); in this reign the sovereignty of Orissa was overthrown by the King of Bengal. Banerji, *Orissa*, i. 342-348, palace-building not supported by history.

⁸ *Purush-ottama* means "the best of men" i.e., Vishnu or Krishna. His brother and sister are Balabhadra and Subhadra. The images are rude logs coarsely fashioned in the shape of a human bust, and are actually in the sanctuary itself. For a description of the temple and other local shrines, Banerji, *Orissa*, ii. 369-418.

manner and the time is now at hand when my prayer will be answered. Since thou art essentially meritorious, watch in expectation and comprehend the wonders of this land." The Brāhman in a short time witnessed with his own eyes the things he had heard. He apprised the Rājah of these occurrences, who built a large city and appointed a special place of worship. The Rājah, one night, after having administered justice, was reposing on the couch of divine praise when it was thus revealed to him, "On a certain day, watch in expectation upon the sea shore. A piece of wood of fifty-two fingers in length and a cubit and a half in breadth will approach : this is the special image of the deity : take it and placing it in thy house, guard it for seven days and whatever shape it then assumes, place it in the temple and enshrine it." After waking, the thing happened in the same wise, and by a divine inspiration, he named it Jagannāth and decked it with gold and jewels. It became a place of devotion to high and low and many miracles are reported⁹ regarding it. Kālā Pahār the General of Sulaymān Karrāni, on his conquest of the country, flung the image into the fire and burnt it and afterwards cast it into the sea. But it is now restored and these popular fables are related of it.

The three images are washed six times every day and freshly clothed. Fifty or sixty priests wearing the Brahmanical thread, stand to do them service and each time large dishes of food are brought out and offered to the images, so that twenty thousand people partake of the leavings [*prasād*.] They construct a car of sixteen wheels which in Hindi, they call *Rath*, upon which the images are mounted, and they believe that whosoever draws it, is absolved from sin and is visited by no temporal distress. Near Jagannāth is a temple dedicated to the Sun. [at Konārak]*. Its cost was defrayed by twelve years revenue of the province. Even those whose judgment is critical and who are difficult to please stand astonished at its sight. The height of the wall is 150 cubits high and 19 thick. It has three portals. The eastern has carved upon it the figures of two finely designed elephants, each of them carrying a man upon his trunk. The western bears sculptures of two horsemen with trappings

⁹ The legend will be found related at length in Hunter's *Orissa*, Vol. I, p. 89.

* Konārak temple, description of the Jagannath temple and images, Banerji's *Orissa*, i. 345.

* Konārak temple, description in Banerji's *Orissa*, ii. 360—392; its art, id. 410—415.

and ornaments and an attendant. The northern has two tigers, each of which is rampant upon an elephant that it has overpowered. In front¹⁰ is an octagonal column of black stone, 50 yards high. When nine flights of steps are passed, a spacious court appears with a large arch of stone upon which are carved the sun and other planets. Around them are a variety of worshippers of every class, each after its manner with bowed heads, standing, sitting, prostrate, laughing, weeping, lost in amaze or in wrapt attention and following these are divers musicians and strange animals which never existed but in imagination. It is said that somewhat over 730 years ago, Rāja Narsing Deo completed this stupendous fabric and left this mighty memorial to posterity. Twenty-eight temples stand in its vicinity; six before the entrance and twenty-two without the enclosure, each of which has its separate legend. Some affirm that Kabir Mua'hhid (monotheist) reposes here and many authentic traditions are related regarding his sayings and doings to this day. He was revered by both Hindu and Muhammadan for his catholicity of doctrine and the illumination of his mind, and when he died, the Brāhmans wished to burn his body and the Muhammadans to bury it.

The Subah of Bengal consists of 24 *Sarkārs* and 787 *Mahals*. The revenue is 59 crores, 84 lakhs, 59,319 *dāms* (Rs. 14,961,482-15-7) in money. [Of this Orissa has 5 *sarkārs*, 99 *mahals* and 1,25,732,638 *dāms*.] The *zamin-dars* are mostly *Kayaths*. The troops number 23,330 cavalry, 801,150 infantry, 1,170 elephants, 4,260 guns, and 4,400 boats.

N.B.—The *Parganahs* will now be entered in alphabetical order in long double columns to each page accompanied by a few descriptive notices.

In the list of *mahals*, the editor has given the correct name first, with the letter R* or A* added, to mean that the place has been found in Rennell's Maps or in the Atlas of the Survey of India (quarter-inch scale). The name of the place as misspelt in the Persian text or wrongly transcribed by Jarrett has been given within brackets after the word *mistake*.—J. Sarkar.

¹⁰ This now stands in front of the Lion-gate of Jagannāth. Orissa, I. 290.

The Konārak temple was built by Narasimha I. of the Eastern Ganga dynasty (r. 1238—1264.) Banerji, Orissa, I. 267—269. For Kabir, *Ency. Islam.* ii. 592 (T. W. Arnold) and Hastings, *Ency. Religion and Ethics*, vii. 632—634. (R. Burn).

Sarkār of Udambar commonly known as Tāndā.¹

Containing 52 Mahals. Rev. 24,079,399 $\frac{1}{3}$ Dāms.

	Dāms.		Dāms.
Āg mahal ...	133,017	Dāud Shāhi ...	242,802
Achlā		Dugāchhi ...	225,745
Darsanpārah } ..	404,287 $\frac{1}{2}$	Rāmpur ...	115,532
Ashrafnihāl }		Rubaspur ...	138,122
Ibrahimpur ...	360,357	Sarup Singh ...	1,368,877
Ajiyāl-ghāti ...	231,957	Sultānpur Ajiyāl	456,394
Amgāchhi ...	369,357 $\frac{1}{2}$	Sulaimān Shāhi	198,742
Barhgangal ...	666,200	Sulaimānābād ...	197,760
Bhatāl ...	415,470	Salimpur ...	187,097
Bahādurpur ...	314,870	Sambalā ...	174,550
Bāhrāri ...	24,655	Shershāhi ...	178,230
Phulbāri ...	193,025	Shams Khāni ...	361,952
Bahādur Shāhi ...	138,102	Sherpur ...	163,097
Tāndā with Subur-		Firozpur ...	347,787 $\frac{1}{2}$
ban district ...	4,326,102	Kunwar-partāb	1,607,200
Tājpur ...	291,997	Kānakjok	
Taalluq Barbhākar	11,725	[Kānkjol] ...	1,589,332
Tanauli ...	196,380	Kāthgarh ...	1,265,632
Chunaghāti ...	589,967	Gankarah ...	894,027
Chāndpur ...	190,027	Kāshipur ...	36,240
Nasibi ...	160,205	Kachlā ...	36,240
Chungnadiyā ...	145,305	Kāfurdiya ...	1,440
Hājipur ...	106,255	Mudeşar ...	1,503,352
Husainābād ...	266,545	Mangalpur ...	226,770
Khānpur ...	31,410	Receipts from	
Dhāwah ...	250,597	scattered estates*	45,837
Deviyāpur ...	559,557	Nawanagar ...	825,985
		Nasibpur ...	377,750

¹ For Udambar the reading *Udner* was accepted in the 1st ed. *Tānda* became the capital of Bengal after the decadence of Gaur: now a petty village in Maldah District; it was to the S. W. of Gaur beyond the Bāgirathi. Old Tānda has been utterly swept away by the changes in the course of the Pāglā. Sulaimān Shāh Karrānī, the last but one of the Afghan kings of Bengal, moved the seat of government to Tāndā in 1564, A.D. eleven years before the final depopulation of Gaur. It was a favourite residence of the Mughal governors of Bengal until the middle of the following century. In 1660 the rebel Shāh Shujāa' was defeated in its vicinity.

* The term *Mackurain* was applied in old revenue accounts to small and scattered estates not included in the accounts of the district in which they are situated, and of which the assessments were paid direct to the Government officers: subsequently it denoted a revenue payer, paying through the intervention of another, except in Cuttack where it implied the reverse, or the heads of villages paying the revenue immediately to the Collector. Wilson's Gloss.

Sarkār of Jannatābād or Lakhnauti.

66 Mahals. Rev. 18,846,967 Dāms.

Castes *Kāyaths* and *Brahmans*. Cavalry 500.

Infantry, 17,000.

	Dāms.		Dāms.
Jannatābād, commonly known as Gaur. It has been a brick fort	7,869,202	Darsarak ...	62,835
Adjacent villages of Ākrā forming 14 <i>Parganahs</i> as follows :	1,573,296	Rāngāmāti ...	3,200
Ajor ...	138,925	Sāir duties from Gangapat and neighbourhood of Hindui† ...	170,800
Bāzkhokrā ...	192,508	Sherpur and Gangapur 2 mahals	2,000
Baler ...	127,060	Shāhbāzpur within the city ...	400
Ākra suburban district ...	211,260	Ghiyāspur ...	41,920
Dhanpur ...	140,340	Kamalā ...	16,377
Deviya ...	112,208	Kāthachhāpā ...	12,000
Serhwar ¹ ...	71,000	Modi Mahal ...	13,000
Shāhbālā ...	98,400	Mewa Mahal ...	360
Shāhlalsari ...	8,000	Duties from the New Market ...	11,760
Khektar ...	50,200	Adjacent villages of Dihikot 7 mahals ...	869,000
Madnāwāti ...	151,890	Barāripinjar ...	698,900
Modihāt ...	6,980	Pākor ...	37,720
Nāhat ...	242,710	Dihikot ...	31,624
Hashtganjpur ...	28,515	Dahlgāon ...	130,320
Adjacent villages of Darsarak 16 mahals as follows :	2,009,344	Shāhzādahpur ...	84,360
Achārikhānah where they sell undried ginger	7,800	Māligāon ...	141,460
Bhatiya ...	826,432	Modipur ...	61,880
Belbāri ...	91,560	Adjacent villages of Ramrauti 7 mahals ...	749,795
Bāzārī Kadim (Old Bāzār) ...	3,720	Badhtahli ...	207,500
		Rāmauti ...	194,767
		Selghariya ...	103,000
		Sangkalkarā ...	93,320

¹ T. Sirapour, G. Seernoor.

† Probably a mistake for Mandari or grain-mart, emporium.

	<i>Dāms.</i>		<i>Dāms.</i>
Sultānpur ...	29,210	Makrāin ...	106,480
Sangdwār ...	14,447	Manikpur and	
Māhinagar ...	107,550	Hatanda, 2 mahals	630,770
Adjacent villages of Sarsābād rev. of 10 mahals	13,192,377	Adjacent villages of Māldah, 11 mahls.	
Akbarpur ...	9,736	Bārbakpur, Bāzār i Yusuf,	
Pārdiyār ...	85,280	Suburban district of Māl-	
Khizrpur ...	396,100	dah, Dherpur, Sujāpur,	
Sarsābād ...	553,080	Sarbādahlpur, Sankodiya,	
Kotwāli ...	788,427	Shālesari, Shāhmandawi,	
Garhand ...	334,880	Fathpur, Mui'zzu'ddin-	
Garhi ...	200,000	pur.	

Sarkār of Fathābād.

31 mahals. Rev. 7,969,568 dāms.

Zamindārs of three classes (i.e. castes).

Cavalry, 990. Infantry, 50,700.

	<i>Dāms.</i>		<i>Dāms.</i>
Isrāchāraj ...	34,024	Sarisāni ...	173,227
Bholiyābil ...	384,452	Sardiyā ...	53,882
Belor ...	124,872	Sadhwā ...	37,127
Bhāgalpur ...	2,115	Sawāil, commonly	
Bādhādiyā ...	1,442	called Jalālpur	1,857,230
Telhati ...	377,290	Shahbāzpur ...	732,172
Charnlakhi ...	35,645	Kharagpur ...	118,135
Charhāi ...	30,200	Kasodiyā ...	102,405
Suburban district and town of		Kosā ...	68,350
Fathābād ...	902,662	Makorgāon ...	3,157
Salt duties ...	277,758	Masnādpur ...	55,312
Hazratpur ...	11,640	Mirānpur ...	22,172
Market dues ...	11,467	Receipts from	
Rasulpur ...	103,767	scattered estates	133,365
Sondip ...	1,182,450	Naklesar ...	49,422
Sarhārkāl ...	787,430	Nia'matpur ...	20,960
		Hazārahāti ...	21,597
		Yusufpur ...	258,025

Sarkār of Mahmudābād.

88 mahals. Rev. 11,602,256.

Caste *Kāyath*. Cavalry, 200. Infantry, 10,100.

	<i>Dāms.</i>		<i>Dāms.</i>
Adniyā ...	76,113	Husain Ajiyāl ...	345,135
Anupampur ...	43,365	Haweli [suburb] ...	91,575
Ajiyāpur ...	37,307	Khālispur ...	56,805
Indarkalli ...	11,250	Khizrākhāni ...	1,092
Āmdah ...	192	Khurrampur ...	265
Bāzu-rāst ...	652,507	Dakāsī ¹ ...	51,740
Bāzu-chap ...	271,240	Durlabhpur ...	13,775
Barādi ...	604,122	Dhuli ...	13,665
Bisi ...	25,247	Deora ...	107
Barin Jumrah ...	102,210	Dahlat Jalālpur ...	1,200
Bethariyā ...	96,117	Dostimā ...	1,052
Bāthnūn ...	85,447	Dhomarhāt ...	42,505
Bāthān ...	41,317	Sadkiehāl Kotiyā	
Belwāri ...	80,195	or Kota ...	8,205
Bandwal ...	26,155	Sārotiyā ...	6,530
Pātika mārā ...	22,710	Sarsariyā ...	72,147
Bābhankarlā ...	14,895	Sankardiyā ...	10,212
Paūnpur ...	12,572	Salimpur ...	23,637
Barmahpur ...	6,717	Soltāra Ajiyāl,	
Patkabhāri ...	3,567	commonly Koma ...	789,220
Pipalbariyā ...	2,045	Suruppur ...	7,482
Bāghotiyā ...	217	Sālibariyā ...	6,760
Belkasi ...	123,387	Sātor ...	290,727
Tāragonā ...	675,790	Shāhajiyāl ...	644,787
Tiyāghāti ...	96	Sherpurbari ...	9,402
Tārājīyāl ...	391,365	Sherpur Utasholi ...	2,797
Chhādūiyā or		Azmatpur ...	14,422
Chhāddiyā ...	9,125	Ghaznipur ...	12,367
Jiyārūkhī ...	11,505	Farhatpur ...	301,790
Jagannāthpur ...	762	Fathpur Nosika ...	102,525
Chadibāriyā ¹ ...	44,007	Qutabpur ...	23,352
Jediya ...	44,700	Qazipur ...	2,652
Chitanbāzu ² ...	952,950	Kandaliyā ...	20,417

¹ T. and var. Jedibariya.

² G. Chytun, var. Jastan and Chain.

³ T. and var. Dakari.

Sarkār of Baklā.

Containing 4 mahals. Rev. 7,150,605.

Castes, various. Elephants, 320. Infantry, 15,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Ismailpur, commonly		Shāhzādahpur ...	977,245
Bakla ...	4,348,960	Adilpur	
Srirāmpur ...	252,000	[Idilpur] ...	1,553,440

Sarkār of Purniyah.

9 mahals. Rev. 6,408,775 dāms.

Infantry, 5,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Asonja ...	734,225	Sripur ...	390,200
Jairāmpur ...	467,785	Sāir duties from	
Suburban dist. of		elephants ...	85,000
Purniyah ...	2,686,995	Kathiyāri ...	590,100
Dalmālpur ...	671,530	Kadwān ...	280,592
Sultānpur ...	502,206		

Sarkār of Tājpur.

29 mahals. Rev. 6,483,857 dāms.

Castes, various. Cavalry, 100. Infantry, 50,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Pangat (<i>mist.</i>		Mālduār (<i>mist.</i>	
Bankat) ...	3,307,885	Tāldwār) ...	208,540
Badokhar ...	238,855	Chhāpartāl ...	243,255
Phāli ...	60,860	Suburban dist. and	
Bandol ...	190,830	town of Tājpur	886,254
Bobarā ...	23,192	Dilāwarpur ...	944,055
Bhonharā ...	118,295	Daihat ...	124,196
Badgāon ...	9,330	Sesahrā ...	376,760
Bāsigāon ...	104,492	Shujāpur ...	244,507
Bangāon ...	115,990	Shāhpur ...	126,235
Bahādurpur ...	96,012	Kuwārpur ...	406,000
Bahānagar ...	91,630	Kasārgāon ...	258,742
Badalkā ...	71,564	Gopālnagar ...	233,160

Sarkār of Tājpur—Contd.

	<i>Dāms.</i>		<i>Dāms.</i>
Goghra ...	147,392	Nilun ...	147,510
Mahur (<i>mist.</i> Mahon) ...	194,475	Yusuf ...	146,240
Nilnagar (Nilpur)	267,612	Zakāt (tax) ...	78,487

Sarkār of Ghorāghāt.

84 mahals. Rev. 8,083,072½ dāms.

Castes, various, Cavalry, 900. Elephants, 50.

Infantry, 32,800.

	<i>Dāms.</i>		<i>Dāms.</i>
Adiwā ...	91,292	Banwārkājar ...	4,452
Andhar ...	75,010	Belghāti ...	3,245
Andalgāon ...	154,337	Bāzār Chhatāghāt	387
Anwarbān ...	31,022	Palāsbari ¹ ...	
Algāon ...	171,695	Panch Mālka ...	5,340
Ambathurā, Abthurā	25,326	Tulsighāt ...	164,340
Āhmadābād ...	18,517	Taalluq Husain	35,410
Anbalāgāchhi ...	9,200	„ Bālnāth	27,962
Anwar Malik ...	8,020	„ Siwān	15,490
Āl Hāt ...	7,508	„ Kasāi	15,267
Ilāhdādpur ...	2,190	Tāchahal ...	8,290
Bāzu Zafar Shāhi,		Taalluq Ahmad	
2 mahals ...	735,835	Khān ...	238,475
Bāzu Faulād Shāhi	711,412	Hāmilā ...	6,580
Bāgdwār ...	102,440	Khairābādi ...	5,602
Phulbāri ...	6,580	Khāsbari ...	2,735
Bārbakpur ...	84,952	Rungpur [Ruknpur]	10,950
Bāmanpur ...	349,070	Sultānpur ...	108,377
Town of Nasratā-		Sikhshahar ² ...	93,071
bād ...	336,445	Sāthipur ...	49,570
Barsalā ...	233,680	Sirhata ...	344,097
Bari Sābakbālā	146,767	Sabdi ...	206,224
„ Ghorāghāt	165,827	Sitpur ...	128,775
Bāyazidpur ...	144,227	Siriya Kāndi ...	24,622
Pātāldeli ...	41,365	Sāghāt ...	16,412
Bālkā ...	30,335	Sherpur Koibāri	
Bholi ...	12,040	(S. Kafurā) ...	15,675
Bājpatāri ...	7,900	Fathpur ...	353,355

¹ In text figures wanting, G. has 7,000. Var. 5,340

² Var. Sabtakah, Beshekh, Silah. T. Sankha.

Sarkār of Ghiorāghāt—Contd.

	Dāms.		Dāms.
Khetāri ...	1,344,280	Korā, receipts from Zakāt ...	18,000
Gayapur ...	107,205	Kokaran ...	13,120
Kābulpur ...	98,465	Kābul ...	11,690
Ganj Sāklmālā ...	98,465	Garhiya ...	10,980
Khadkhadi ...	81,565	Gokanpārā ...	9,850
Gokul ...	56,865	Magatpur ...	124,005
Kothi Bāri 2 mahals ...	48,807	Muhabbatpur ...	46,512
Khalsi ...	264,322	Musjid Husain Shāhi ...	28,945
Kandibāri ...	125,797	„ Andarkhāni ...	3,447
Kuli Bāzār, com- monly Jorpurī ...	115,680	Malāir ...	24,800
Gobindpur Akhand ...	40,675	Nandahra ...	61,050
Kanhtāl ^a ...	40,367	Naupāra ...	19,202
Kanak Sakhar ...	28,065	Nāhajaun Bātor ...	49,010
Ghātnagar ...	27,922	Wakar Hazir ...	30,646
Kawā Gāchhi ...	24,600	Wachhi ...	16,832
Kālibāri ...	24,847	Wahrib ...	4,230

Sarkār of Pinjarāh.*

21 mahals. Rev. 5,803,275 dāms.

Castes, various. Cavalry, 50. Infantry, 7,000.

	Dāms.		Dāms.
Ambel ...	1,058,725	Suburban district of Pinjarah ...	93,967
Ambāri A* ...	36,525	Digha ...	146,837
Amgochah ...	101,882	Deopārā (Deorā) A* ...	107,727
Bārbakpur (Bārangpur) ...	635,390	Sadharbāri (?Jharbari) ...	273,045
Bijānagar A* ...	719,107	Sankatā (Suktigacha) ...	251,410
Bāyazidpur A* ...	255,445	Sultānpur A* ...	203,292
Baharnagar ...	119,720	Sāsber A* ...	165,180
Bāri Gher ...	84,277	Sulaimānābād ...	42,532
Bādughar (? Balurhat) ...	55,205	Khattā (?Khetlāl) ...	777,255
Tegasi (Takāsi) A* ...	374,490	Kedābārī† ...	213,382
Chaloon (Hālon) A* ...	82,142		

* Var. Gātrāl, G. Gautnāl.

* Pinjarah, evidently a copyist's error. No such name in any map. Tieffenthaler reads Bijara.

† Cannot be Godāgarī. May be Kāmdēvpur.

*Sarkār of Bārḥakābād.*38 *mahals*. Rev. 17,451,532 *dāms*.

Castes, various. Cavalry, 50. Infantry, 7,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Amrul ...	560,382	Shikārpur A* ...	327,342
City of above-mentioned (Bārḥakābād) ...	315,340	Sherpur and Bahāmpur, 2 <i>mahals</i> A* ...	391,625
Basuoul (Bāsdol) A* ...	190,885	Tāhirpur A* ...	505,825
Polārḥār ...	136,712	Qāzihatti A* ...	620,477
Pustu (Bastol) A* ...	652,367	Kardoho A* ...	1,390,572
Barbariyā ...	64,335	Guzrhāt ...	1,296,240
Bangāon ...	319,000	Khās ...	881,080
Pāltāpur A* ...	179,840	Ganj known as Jagdal A* ...	694,655
Chhandiya Bāzu ...	755,522	Gobindpur ...	410,535
Chaurā A* ...	159,832	Kāligāe Kotha ...	341,057
Jeasindh (Jahāsand) and Chaugāon, 2 <i>mahals</i> ...	407,007	Khurael (Kharāl) A* ...	210,132
Chāndlāi (Jandlāi) A* ...	289,340	Kodānagar ...	129,550
Janāsu (? Jhankur) A* ...	85,787	Kāligaon (Kāligāe) A* ...	196,932
Suburb. district of Sukh Shahar ...	1,629,175	Laskarpur ...	255,090
Dhāmin (Dhārman) A* ...	350,895	Mājilpur (Mālji-pur) ...	925,680
Dāudpur A* ...	8,902	Mosida (Masdhā) A* ...	689,712
Sankārdal, commonly Nizāmpur ...	389,975	Man Samāli ...	594,792
		Mahmudpur ...	124,532
		Wazīrpur ...	169,190

*Sarkār of Bāzuhā.*32 *mahals*. Rev. 39,516,871 *dāms*.

Castes, various. Cavalry, 1,700. Elephants, 10.

Infantry, 5,300.

Ālap Shāhi ...	760,667	Bhoriya Bāzu ...	2,820,740
Bādmār, Nasrat Shāhi, Mehraunah, Kāhār-wana, Sirali, 5 <i>mahals</i> ...	1,178,140	Bhawāl Bāzu ...	1,935,160
		Partāb-Bāzu ...	1,881,265
		Bakhariyā Bāzu ...	1,715,170
		Husain Shāhi ...	182,750

Sarkār of Bāzuhlā—Contd.

<i>Dāms.</i>		<i>Dāms.</i>	
Dashkāhaniyā		Shāh Ajiyāl Bāzu	405,120
Bāzu ...	1,945,602	Zafar Ajiyāl Bāzu	250,047
Dhakā Bāzu ...	1,901,202	Katārmal Bāzu	2,804,390
Salim Partāb		Khatā Bāzu ...	137,720
Bāzu, Chānd	4,625,475	Mihmān Shāhi,	
Partāb Bāzu,		known as Sherp-	
Sultān Bāzu }		pur Murcha ...	2,207,715
Sonāghāti Bāzu	1,910,440	Mumin Singh,	
Sonā Bāzu ...	1,705,290	Nasrat Shāhi,	
Silbaras ...	1,484,320	Husain Singh,	1,867,640
Dues on produce		Nasrat Ajiyāl	
and piscary of		4 mahals	
river's, tanks,		Mubārak Ajiyāl	468,780
&c. ...	261,280	Hariyāl Bāzu ...	344,440
		Yusuf Shāhi ...	1,670,900

Sarkār of Sonārgāon.

52 mahals. Rev. 10,331,333 dāms.

Castes, various. Cavalry, 1,500. Elephants, 200.

Infantry, 46,000.

<i>Dāms.</i>		<i>Dāms.</i>	
Uttar Shāhpur	388,442	Chhokhañdi, from	
Al Jihāt ...	53,090	shop dues ...	17,827
Uttar Usmānpur	24,880	Chand Bāzār ...	30,322
Bikrampur ...	3,335,052	Chāndpur ...	120,000
Bhulwā-jowār ...	1,331,480	Suburban district	
Baldākhāl ...	694,090	of Sonārgāon with	
Bawāliyā ...	237,320	city ...	459,532
Barchandi ...	120,100	Khizrpur ...	40,308
Bāth Karā ...	4,080	Dohār ...	458,524
Palās-ghāti, &c.	43,265	Dānderā ...	421,380
Baradiyā ...	19,000	Dakhin Shāhpur	239,910
Phulari ...	19,000	Dilāwarpur : re-	
Pānhatta ...	7,367	ceipts from zakāt	127,207
Torā ...	104,910	Dakhin Usmānpur	8,840
Tājpur ...	60,000	Rāepur ...	4,535
Tarki ...	18,270	Sekhargāon ...	340,365
Jogidiyā ...	512,080	Sakri ...	184,780
Environs of Port	82,632	Salimpur ...	91,090

Sarkār of Sonārgāon—Contd.

	<i>Dāms.</i>		<i>Dāms.</i>
Salisari with produce and piscary of rivers, tanks, &c., <i>raiyaṭi</i> * and the like	40,724	Kothri (Kothari) Gāthi Nadhi (G. Dañai)	35,160
Sakhwā from <i>raiyaṭi</i>	280,000	Mehrkol	20,000
„ „, <i>sāir</i> dues	28,000	Muazzampur	1,039,470
Sakhādia	28,000	Mehār	236,830
Sejoāl†	13,000	Manoharpur	60,800
Shampur	22,000	Mahijāl	53,301
Kerāpur	293,402	Narāenpur, from <i>sāir</i> dues, <i>zakāt</i> and <i>raiyaṭi</i>	25,000
Gardi	89,590	Nāwākot	940,760
Kārtikpur	80,000	Hamṭā Bāzu	16,080
Khāndi	40,140	Hāt Ghāti	281,280
			10,285

Sarkār of Sylhet.

8 mahals. Rev. 6,681,308 dāms.

Castes, various. Cavalry, 1,100. Elephants, 190.
 Infantry, 42,920.

	<i>Dāms.</i>		<i>Dāms.</i>
Partābgarh, called also Panjkhand	370,000	Suburban district of Sylhet	2,290,717
Baniā Chang	1,672,080	Sarkhandal	390,472
Bajwa Biyāju	804,080	Laur	246,202
Jesa (Jaintiya?)	272,200	Harnagār, <i>raiyaṭi</i> and <i>sāir</i>	1,010,857

Sarkār of Chittagong.

7 mahals. Rev. 11,424,310 dāms.

Castes, various. Cavalry, 100. Infantry, 1,500.

	<i>Dāms.</i>		<i>Dāms.</i>
Tālāgāon [?Mālgaon]	506,000	Sulaimānpur, commonly Shaikhpur	1,572,400
Chātḡāon (Chittagong)	6,649,410	<i>Sāir</i> dues from salt-pits	737,520
Deogaon	775,540	Sahwā	5,079,340
		Nawāpārā	703,300

* Applied in Bengal to lands of which the revenue is paid in money in opposition to *khamār* lands of which revenue was paid in kind: also to a settlement direct with the cultivators.—Wilson's Gloss,
 † G. and var. Sabarchāl.

Sarkār of Sharifābād.

26 *mahals*. Rev. 2,488,750 *dāms*.

Castes, various. Cavalry, 200. Infantry, 5,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Burdwān ...	1,876,142	Suburban district	
Bahrōr ...	1,736,795	of Sherpur Atāi	816,068
Barbaksail ...	540,395	Azmatpur ...	1,660,040
Bharkondah, and		Fath Singh ...	2,090,460
Akbharshāhi,		Husam Ajyāl ...	393,340
c o m m o n l y		Kargāon ...	348,260
Sāndal, 2 <i>mahals</i>	1,276,195	Kiratpur ...	220,770
Bāgnā ...	509,340	Knand [Ghosh]	190,380
Bnatsilā ...	307,340	Khanga ...	174,360
Bāzār Ibrāhimpur	15,740	Kodra ...	63,120
Janki ...	937,705	Manland ...	1,831,890
Khot Makand ...	2,315	Manohar Shāhi	1,709,920
Dhaniyān ...	1,508,800	Muzaffar Shāhi	1,502,170
Sulaimān Shāhi	721,335	Nasak ...	782,517
Soniya ...	90,370	Natrān ...	203,560

Sarkār of Sulaimānābād.

31 *mahals*. Rev. 17,629,964 *dāms*.

Castes, various. Cavalry, 100. Infantry, 5,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Indarāin ...	592,120	Husainpur ...	355,090
Ismāilpur ...	184,540	Dhārsan ...	95,250
Anliya ...	124,577	Rāenah ...	68,207
Ulā ...	89,277	Suburban district	
Basandhari ...	2,266,280	of Sulaimānā-	
Bhursat ...	1,968,990	bād ...	2,051,090
Panduah ...	1,823,292	Sātsikā† ...	757,111
Pāchnor ...	601,495	Sahspur ...	314,842
Bāli Bhangā 2		Sanghauli ...	72,747
<i>mahals</i> *	417,185	Sultanpur ...	44,575
Chhotipur ...	554,956	Umarpur ...	223,320
Chumhā ...	455,901	Aālampur ...	38,280
Jaipur ...	44,250	Qabāzpur ...	747,200

* There is a Bāli Danga in Nadiya.

† G. and var. Satsanga. Note—Now in the district of Bardwān.

Sarkār of Sulaimānābād—*contd.*

	<i>Dāms.</i>		<i>Dāms.</i>
Gobinda (Kosada ?)	357,942	Molghar	792,107
Receipts from in- dependent <i>taluq-</i> <i>dārs</i>	213,067	Nagin	910,990
Muhammadpur	48,515	Nāirā	872,945
		Nasang	500,765
		Nabiya [? Nipā]	77,017

... *Sarkār of Sāt-gāon.* ...

... 53 *mahals*: Rev. 16,724,724 *dāms*.

Castes, various. Cavalry, 50. Infantry, 6,000.

	<i>Dāms.</i>		<i>Dāms.</i>
Banwa, Kotwālī,		Sādghāti	468,058
Farāsatghar, (?)		Sakotā	204,072
3 <i>mahals</i> ...	1,540,770	Srirājpur	125,792
Ukrā	726,360	Sāir dues from	
Anwarpur	236,950	Bāndarbān and	
Arsa Tāwālī† Sāt-		Mandawī, 2	
gāon 2 <i>mahals</i>	234,890	<i>mahals</i>	1,200,000
Akbārpur	115,590	Sākhāt, Kātsāl, 2	
Bodhan	956,457	<i>mahals</i>	45,757
Panwān and		Fāthpur	80,702
Salimpur	952,505	Calcutta, Bakoya††	
Purah	652,470	Bārbakpur, 3	
Barmhattar and		<i>mahals</i>	936,215
Mānikhatti	383,803	Khārar	365,275
Belgāon	233,602	Kandāliyā	242,160
Bāliṇḍā	125,250	Kalaruā	197,522
Bāgwān and		Magrā	801,302
Bangābārī	100,000	Matīyārī	307,845
Baliyā	94,725	Medni Mal	186,242
Phalkā	38,245	Muzaffarpur	108,332
Baridhātī	25,027	Mundāgāchhā	98,565
Tortariyā	36,604	Nāhihatti	49,935
Haveli Shahr	502,330	Nadiya and Sān-	
Husainpur	324,322	tipur, 2 <i>mahals</i>	1,508,820
Hājipur, Bārbak-		Helki	90,042
pur, 2 <i>mahals</i>	142,592	Hāthi Kandhā	55,702
Dhūliyāpur	78,815	Hatīyāgarh	781,360
Rānihāt	1,358,510		

† Can it be *A'rsa haveli-e-Sāt-gān*? [J. Sarkar].

†† G. and var. Makuma. Calcutta is unlikely. I prefer the variant in

Sarkār of Māndāran.

16 mahals. Rev. 9,403,400 dāms.

Castes, various. Cavalry, 150. Infantry, 7,000.

	Dāms.		Dāms.
Panihatti ...	122,655	Shergarh, com-	
Bagri (Bālgarhi)		monly Sikhar-	
R* ...	937,077	bhum ...	915,237
Birbhum ...	541,245	Shāhpur ...	634,160
Dhawālbhum (mis.		Ket ...	46,447
Bawal) ...	495,220	Mandalghāt ...	906,775
Chitwā A* ...	806,542	Nāgor¶ ...	4,025,620
Champānagari ...	412,250	Minakbāg (T.	
Suburban district		Mansapāt) ...	279,322
of Māndāran ...	1,727,077	Hesla (mist.	
Sin[g]bhum ...	615,805	Hesoli) A* ...	263,207
Samar Sānhas			
(Sarhat) ...	274,461		

Orissa.

Sarkār of Jalesar.

28 mahals. Rev. 5,052,738 dāms.

Castes, various. Elephants, 2. Cavalry, 3,470.

Infantry, 43,810.

	Dāms.		Dāms.
Bānsanda, commonly Haft-		Parbadā. Cav. 400, Inf.	
chor has five strong		1,600; has a strong	
forts. Castes, <i>Khandait</i> ,		fort, partly on a hill,	
<i>Brāhman</i> , and <i>Bhej</i> .	4,211,430	partly fenced by forest.	640,000
Cavalry, 100. Infantry,		Bhogrāi, has a fortress of	
5,800.		great strength; Caste	
Bibli (Pipli) Cavalry, 10,		<i>Khandait</i> , Cav. 100, Inf.	497,140
Infantry, 40 ...	2,001,430	2,200, archers and	
Bāli Shāhi Cav. 200. Inf.		matchlockmen.	
2,000 ...	963,430	Bagri, <i>Rajput</i> , Cav. 100,	
Bālkoshi, has three forts :		Inf. 200 ...	39,428
1, Sokrali. 2, Bānhas		Bāzār ...	125,720
Tāli; 3, Daddhpur. Cav.	756,220	Bābbanbhum, <i>Brāhman</i> ,	
20, Inf. 300.		Cav. 20, Inf. 400 ...	114,208

¶ For Nāgor T. reads Magor. We know of a Nagar of Birbhum. For Mandalghāt, Rennell gives Mangalgulla, a little south of the Ajay river, and Atlas Mangalkot. Hesla is eight miles west by south of Purnia town, but one ms. reads Mahisdal.

Sarkār of Jalesar—*contd.*

	<i>Dāms.</i>		<i>Dāms.</i>
Taliya with town of Jalesar, has a brick fort. Caste, <i>Khandait</i> , Cav. 300, Inf. 6,250.	12,007,110	Kāsijorā, Cav. 200, Inf. 2,500, matchlock and bowmen.	893,160
Tamluk Cav. 50, Inf. 1,000, has a strong fort, <i>Khandait</i> ...	2,571,430	Kharagpur, a strong fort in the wooded hills, 500 footmen and machlockmen.	528,570
Tarkua: a fort in the jungle, Cav. 30, Inf. 170 ...	720,570	Kedārkhand, three strong forts, Cav. 50, Inf. 500	468,570
Dāwar Shorbhum, commonly Bārah, Cav. 100, Inf. 100.	1,342,360	Karāi, Infantry 100 ...	285,720
Ramuna, has five forts, 1 adjacent to city; 2, Ramchandpur; 3 Rabgā; 4, Dnt; 5, Saldah, Cav. 700, Inf. 3,500, hold the five.	5,062,306	Gagnāpur, <i>Rajput</i> , Cav. 50, Inf. 400 ...	85,720
Rayn, on the border of Orissa, has three forts, Cav. 150, Inf. 1,500.	218,806	Karohi* ...	68,570
Rāepur, a large city, with a strong fortress, Cav. 200, Inf. 1,000.	986,970	Māljhata, Cav. 500, Inf. 5,000 ...	9,312,610
Sabang, strong fort in the jungle, Cav. 100, Inf. 2,000.	1,257,140	Mednipur, a large city with two forts, one ancient and the other modern. Caste <i>Khandait</i> , Cav. 60, Inf. 500.	1,019,930
Kesiari ...	108,570	Mahākānghāt commonly Qutbpur, a fortress of great strength, Cav. 30, Inf. 1,000.	240,000
		Narāinpur, commonly Kandhār, with a strong fort on a hill, Cav. 100, Inf. 4,000.	2,280,860

Sarkār of Bhadrak.

7 mahals. Rev. 18,687,170 dāms.

Castes, various. Cavalry, 750. Infantry, 3,730.

	<i>Dāms.</i>		<i>Dāms.</i>
Barwa, two strong fortresses, Bānak and Raskoi, castes, <i>Khandait</i> , and <i>Kāyath</i> , Cav. 50, Inf. 400.	3,240,000	Sahansu, 2 strong forts, <i>Khandait</i> , Cav. 300, Inf. 1,700.	3,514,280
Jaukajri ...	57,140	Kāaimān, a strong fort of the greatest strength, <i>Khandait</i> , Cav. 100, Inf. 400.	1,515,840
Suburban district of Bhadrak, has a fort called Dhāmnnagar, with a resident governor, <i>Khandait</i> , Cav. 200, Inf. 3,500.	9,542,760	Kadsu ...	730,430
		Independent Talukdārs; three forts, Pachchhim Dik, <i>Khandait</i> , and Majori, Cav. 100, Inf. 300; the three forts, held by <i>Khandaits</i> .	85,720

Sarkār of Katak (Cuttack.)

21 mahals. Rev. 91,432,730 dāms.

Castes, various. Cavalry, 900. Infantry, 108,160.

	<i>Dāms.</i>		<i>Dāms.</i>
Al, Inf. 2,100 ...	6,429,130	Jash commonly Jāipur, a strong fort, <i>Brāhman</i> , Cav. 200, Inf. 1,800.	2,073,780
Āsakah, Inf. 15,000 ...	3,160,380	Dakhin Dik, 4 forts, Cav. 180, Inf. 13,060.	22,065,770
Athgarh, with a strong fort, <i>Brāhman</i> , Cav. 200, Inf. 7,000.	1,184,980	Sirān ...	207,830
Purab Dik, four forts, Cav. 200, Inf. 6,000 ...	22,881,580	Shergarh, <i>Brāhman</i> , Cav. 20, Inf. 200.	1,408,580
Pachchhim Dik, Cav. 100, Inf. 50,000 ...	662,490	Kotdesli with three forts, the original fort, Kasi-bagh, Caste, <i>Khandait</i> , Cav. 5,008, Inf. 300.	4,720,980
Bahār ...	5,129,820	Katak Banāres, suburban district with city, has a stone fort of great strength, and a masonry palace within, <i>Brāhman</i> and <i>Khandait</i> , Cav. 200, Inf. 1,000.	605,600
Basāi Diwariār, Inf. 1,000 ...	2,746,650	Khatrah, with strong fortress, <i>Khandait</i> , Cav. 100, Inf. 400.	1,120,230
Barang, 9 forts, among the hills and jungles, Caste, <i>ahir</i> , Cav. 20, Inf. 300.	2,132,940	Mānakpatan, a large port, where salt dues are collected.	600,000
Bhijnagar with strong fort, <i>Telingha</i> , Cav. 50, Inf. 22,000.	860,390		
Banju, <i>Rajput</i> , Cav. 100, Inf. 20,000 ...	866,206		
Parsotam ...	691,530		
Chaubiskot, 4 forts of great strength, Cav. 500, Inf. 20,000.	2,398,970		

Sarkār of Kaling Dandpāt.

27 mahals. Rev. 5,560,000 dāms.

Cavalry, 500. Infantry, 30,000.

Sarkār of Rāj Mahendrih.

16 mahals. Rev. 5,00,000 dāms.

Cavalry, 1,000. Infantry, 5,000.

A general view of the country having now been cursorily given, I proceed to record the succession of its rulers and the duration of their reigns. Twenty-four princes of the *Khatri* caste, kept aflame the torch of

	Years.		Years.
Rājā Bhopāl reigned ...	55	Rājā Bigan (Bijan)	
„ Dhipāl „ ...	95	pāl, reigned ...	75
„ Devapāl „ ...	83	„ Jaipāl „ ...	98
„ Bhupati-		Rājpal	98
pāl „ ...	70	Bhogpāl, his	
„ Dhanpati-		brother „ ...	5
pāl „ ...	45	Jagpāl, his	
		son „ ...	74

	<i>Years.</i>		<i>Years.</i>
Sukh Sen reigned ...	3	Madhu Sen reigned ...	10
Balāl Sen, who		Kesu Sen „ ...	15
built the fort		Sada (Sura)	
of Gaur „ ...	50	Sen „ ...	18
Lakhan (Lachhman)		Rājā Nāujah	
Sen „ ...	7	(?Buddha-sen) „ ...	3

From the time of Sultān Qutb u' d-dīn Aibak to Sultān Muhammad Tughlaq Shāh 17 governors ruled during a period of 156 years.

A.H.	A.D.		Years.	Months
741	1340	Malik Fakhr'uddin Silāhdār, reigned ...	2	some
743	1342	Sultān Alāu'ddin ...	1	„
744	1343	Shamsu'ddin Bhangarah Ilyās ...	16	„
760	1358	Sikandar (Shāh) his son ...	9	„
769	1367	Sultān Ghiyāsu'ddin his son ...	7	„
775	1373	Sultān 'us Salātin, his son ...	10	0
785	1383	Shamsu'ddin, his son ...	3	some
787	1385	Kānsi native of Bengal ...	7	0
794	1392	Sultān Jalālu'ddin ...	17	0
812	1409	Sultān Ahmād, his son ...	16.	0
		Nāsir his slave, a week or according to others, half a day.		

A.H.	A.D.		Years.	Months.
830	1426-7	Nāsir Shah, descendant of Sham-su'ddin Bhangarah	... 32	0
862	1457	Bārbak Shāh	... 17	0
879	1474	Yusuf Shāh	... 7	0
887	1482	Sikandar Shāh	... half a day	
887	1482	Fath Shāh	... 7	5
896	1490	Bārbak Shāh	... two and a half days.	
897	1491	Firoz Shāh	... 3	0
899	1494	Mahmud Shah, his son	... 1	0
900	1495	Muzaffar Habshi	... 3	5
903	1498	Alāu'ddin	... 27 (?)	some
927	1521	Nasrat Shāh, his son	... 11 (?)	
940	1534	Mahmud Shāh, son of Alāu'd defeated by		
944	1537	Sher Khān.		
945	1538	Humayun (held his court at Gaur).		
946	1539	Sher Khan, a second time.		
952	1545	Muhammad Khān.		
962	1555	Bahādur Shāh, his son.		
968	1560	Jalālu'ddin, his brother.		
Not in U. T.		{ Ghiyāsu'ddin.		
		{ Tāj Khān.		
971	1563-4	Sulaimān (Karāni), his brother.		
981	1573	Bāyazid, his son.		
981	1573	Dāud, his brother (defeated by Akbar's forces).		

Fifty princes ruled during about 357 years and one hundred and eleven kept alive the torch of sovereignty throughout the period, approximately; of 4,813 years and passed into the sleep of dissolution.

The first Rājā, (Bhagadatta) came to Delhi by reason of his friendship for Rājā Durjodhan, and fell manfully fighting in the war of the Mahābhārat, 4,096 years previous to the present time. When the cup of life of Rājā Naujah [correct into Rājāh of Nodia] overflowed, the sovereignty fell to Lakhmaniya, son of Rāc Lakhman. Nadiyā was at that time the capital of Bengal and the seat of various learning. Nowadays its prosperity has somewhat abated but the traces of its erudition are still evident. The astrologers predicted the overthrow of his kingdom and the establishment of another faith and they discovered in Muhammad Bakhtiyār Khilji the individual by whom these two events would be accomplished. Although the Rājā regarding these as idle tales refused to credit them, many

of his subjects sought refuge in distant provinces. At the time when Qutbu'ddin Aibak held India for Shahābu'ddin, the Khilji took possession of Bihār by force of arms, and when he marched upon Bengal, the Rājā, escaped in a boat. Muhammad Bakhtiyar, entered Bengal and having amassed enormous plunder, he destroyed the city of Nadiyā and transferred the capital to Lakhnauti. From that time Bengal has been subject to the kings of Delhi.

During the reign of Sultān Tughlaq, Qadar Khān was viceroy in Bengal. Malik Fakhru'ddin his sword-bearer through greed of power, disloyally determined upon the death of his master and plotting in secret, slew him and with pretentious allegations fraudfully possessed himself of the government and refused allegiance to the sovereigns of Delhi. Malik Ali Mubārak, who had been one of the principal adherents of Qadar Khān, assumed the title of Alāu'ddin and rose against Fakhru'ddin, and taking him alive in action, put him to death. Hāji Iliyās 'Alāi, one of the nobles of Bengal, entering into a confederacy with some others, slew him and took the title of Shamsu'ddin. He is also called *Bhangrah*. Sultān Firoz set out from Delhi to chastise him and a severe struggle ensued, but as the rainy season was approaching, he concluded a hasty treaty and returned. When Shamsu'ddin died, the chiefs of the army raised his eldest son to the throne under the title of Sikandar Shāh. Sultān Firoz again marched into Bengal but retreated after arranging terms of peace. On Sikandar's death his son was elected to succeed him and was proclaimed under the title of Ghiyāsu'ddin. Khwājah Hāfiz of Shirāz sent him an ode in which occurs the following verse :

And now shall India's parroquets on sugar revel all,
In this sweet Persian lyric that is borne to far Bengal.

A native of Bengal named Kānsi fraudfully dispossessed Shamsu'ddin who was his [Ghiyās-ud-din's] grandson. When he died, his son embraced Islām and took the name of Sultān Jalālu'ddin. It was the custom in that country for seven thousand footmen called *Pāyiks* to patrol round the palace. One evening a eunuch conspiring with these guards slew Fath Shāh and assumed the title of Bārbak Shāh.

Firoz Shāh was also slain by these guards and his son Mahmud was raised to the sovereignty. An Abyssinian slave Muzaffar with the assistance of the same guards put him to death and mounted the throne. Alāu'ddin, an

attendant of Muzaffar, in turn, in conspiracy with these guards despatched his master and established himself in power. Thus through the caprice of fortune, these low footsoldiers for a considerable time played an important part in the state. Alāu'ddin placed the administration of justice on a better footing and disbanded the *Pāyiks*. Nasrat Shah is said to have followed the example of his father in his justice and liberality and treated his brothers with consideration. When Sultān Ibrahim (Lodi) met his death in the engagement with Sultan Bābar, [1526] his brother and the chiefs of the army took refuge with this monarch and lived in security. Humayun appointed Jahāngir Quli Beg to the governorship of the province. When Sher Khān a second time rose to power, he beguiled Jahāngir under pretext of an amicable settlement and put him to death. During the reign of Salim Khān (at Delhi) Muhammad Khān his kinsman, united loyalty to his lord with justice to his subjects. When he fell in action against Mamrez Khān, his son Khizr Khān succeeded him and assumed the title of Bahādur Shāh. Mamrez Khān entered the field against him but perished in battle. Tāj Khān [Karrāni] one of the nobles of Salim Khān, slew Jalālu'ddin and assumed the government. His younger brother Sulaimān, although of a tyrannous disposition, reigned for some time, after which his sons Bāyazid and Dāud through misconduct dishonoured the royal privileges of the mint and the pulpit. Thus concludes my abstract.

Praise be to God, that this prosperous country receives an additional splendour through the justice of imperial majesty.

THE SUBAH OF BIHAR.

It is situated in the second climate. Its length from *Gadhi* to *Rhotās* is 120 *kos*; its breadth from *Tirhut* to the northern mountains, 110 *kos*. On its eastern boundary is Bengal; to the west lie *Allahabad* and *Oudh*. On the north and south it is bounded by hills of considerable elevation. Its chief rivers are the *Ganges* and the *Son*. Whatever of wood or leather and the like falls into the *Son*, becomes petrified. The head springs of these three rivers, the *Son*, the *Narbada* and the *Johila*, bubble up from a single reed-bed* in the neighbourhood of *Gadha* [Mandla]. The *Son*

* The three great rivers, Narmadā, Son and Mahānadi, rise in a sacred pond at the Amar-Kantak, a village in the Rewā State, only three miles from

is pleasant to the taste, wholesome and cool; flowing in a northerly direction, it joins the Ganges near *Maner*. The *Gandak* flows from the north and unites with the Ganges near *Hājipur*. Such as drink of it suffer from a swelling in the throat, (goitre) which gradually increases, especially in young children, to the size of a cocoanut.

The *Sāligrām*† is a small black stone which the Hindus account among divine objects and pay it great veneration. If round and small and unctuous, they hold it in the highest regard and according to the variety of its form, different names and properties are ascribed to it. The generality have a single perforation, others more and some are without any. They contain gold ore. Some say that a worm is bred within which eats its way through; others maintain that it works its way in from the outside. The Hindus have written a considerable work on the qualities of this stone. According to the Brahmanical creed, every idol that is broken loses its claim to veneration, but with these, it is not so. They are found in the *Son* for a distance of 40 *kos* between its northernmost extremity and the south of the hills.

The *Karamnāsā* flowing from the south unites with the Ganges near *Chausā*. Its waters are regarded with aversion.¹ The *Punpun* flows also from the south and joins

the eastern border of the Garh Mandlā district of the C.P., where the Maikāl range begins. The *Johillā*, a very small river, is really a feeder of the *Son* and, after flowing north and west from its source for a little more than a hundred miles as a thin stream, loses itself in the *Son*, in the north-west corner of the Rewā State, 13 miles east of Bandhu-garh. It should not, therefore, be counted as separate from the *Son*, which does not really rise from the same tank at Amar-Kantak but some distance to the east of it. The third great river with its source at the same place is the *Mahānadi*, which Abul Fazl has entirely left out. The *Mahānadi* flowing eastward across half the breadth of the Indian peninsula, falls into the Bay of Bengal in Orissa, more than 1800 miles from the mouth of its twin-sister the *Narmadā*, in the Arabian sea, though both rivers started from the same cradle.

The sacred tank at Amar-Kantak is 8 yards long and 6 yards wide, and surrounded by a brick-wall. It is situated 90 miles due east of Mandla city. (Tieffenthaler quoting an English engineer's report). "The *Narmada* in issuing from its source is only one yard in breadth. The *Son* is visible only for a distance of half a mile from the tank, and then it descends in a waterfall 25 yards high, and after a course of five miles, it loses itself in the sand, but newly acquiring greater volume it (finally) becomes a large river." (Tieffenthaler, i, 416-417.) The *Son* used to fall into the Ganges near *Maner*, when Rennell made his survey (*Bengal Atlas*, 1772), but the junction is now about ten miles higher up, at Koilwar (Rl. Stn.) *Jadunath Sarkar*.

† A species of black quartzose found in the *Gandhak* containing the impression of one or more ammonites conceived by the Hindus to represent *Vishnu*. This river is also known as the *Sāligrām*.

¹ Its name signifies 'the ruin of religious merit.' No person of any caste will drink its waters. The reason of its impurity is said to be that a Brahman having been murdered by a Raja of the Solar line, a saint purified him of his sins by collecting water from all the streams of the world and washing him

the Ganges near Patna. The smaller rivers of this Subah cannot be recorded. The summer months are intensely hot, while the winter is temperate. Warm garments are not worn for more than two months. The rains continue during six months and throughout the year the country is green and fertile. No severe winds blow nor clouds of dust prevail. Agriculture flourishes in a high degree, especially the cultivation of rice which, for its quality and quantity is rarely to be equalled. *Kisārī*² is the name of a pulse, resembling peas, eaten by the poor, but is unwholesome. Sugarcane is abundant and of excellent quality. Betel-leaf, especially the kind called *Maghi*, is delicate and beautiful in colour, thin in texture, fragrant and pleasant to the taste. Fruits and flowers are in great plenty. At *Maner*, a flower grows named *Muchakand*,³ somewhat like the flower of the *Dhātura*, very fragrant and found nowhere else. Milk is rich in quality and cheap. The custom of dividing the crops is not here prevalent. The husbandman pays his rents in person and on the first occasion presents himself in his best attire. The houses for the most part are roofed with tiles. Good elephants are procurable in plenty and boats likewise. Horses and camels are scarce. Parrots abound and a fine species of goat of the Barbary breed which they castrate: from their extreme fatness they are unable to walk and are carried on litters. The fighting cocks are famous. Game is abundant. Gilded glass is manufactured here.

In the *Sarkār* of *Bihār*, near the village of *Rājgir* is a quarry of stone resembling marble, of which ornaments are made. Good paper is here manufactured. *Gayā* the place of Hindu pilgrimage, is in this province: it is also called *Brahma Gayā* being dedicated to *Brāhma*. Precious stones from foreign ports are brought here and a constant traffic carried on.

In the *Sarkār* of *Hājīpur* the fruits *Kathal*⁴ and *Barhal* grow in abundance. The former attain such a size that a man can with difficulty carry one.

in their waters which were collected in the spring from which the *Karamnāśā* now issues. I. G.

² *Lathyrus sativus*.

³ Dr. King of the Royal Botanical Gardens, Calcutta, suggests that this may be the *Jasminum pubescens*. The flower resembles a miniature *Dhātura* flower and is very fragrant.

⁴ Known as the Jack fruit (*Artocarpus integrifolia*, Roxb.). The *Barhal* according to the dictionary is a small round fruit, also an *Artocarpus*, doubtfully distinguished as "*lécucha*."

In the *Sarkār* of *Champāran* the seed of vetch *Māsh*⁵ is cast on unploughed soil where it grows without labour or tilling. Long pepper grows wild in its forests.

Tirhut has from immemorial time, been a seat of Hindu learning. Its climate is excellent. Milk curds keep for a year without alteration. If those who sell milk adulterate it with water, some mysterious accident befalls them. The buffaloes are so savage that they will attack a tiger. There are many lakes and in one of them the water never decreases, and its depth is unfathomable. Groves of orange trees extend to a distance of thirty *kos*, delighting the eye. In the rainy season gazelle and deer and tiger frequent together the cultivated spots and are hunted by the inhabitants. Many of these with broken limbs are loosened in an enclosure, and they take them at their leisure.

Rohtās is a stronghold on the summit of a lofty mountain, difficult of access. It has a circumference of 14 *kos* and the land is cultivated. It contains many springs, and wherever the soil is excavated to the depth of three or four yards, water is visible. In the rainy season many lakes are formed, and more than two hundred waterfalls gladden the eye and ear. The climate is remarkably healthy.

This *Subah* contains seven *Sarkārs* subdivided into 199 *Parganahs*. The gross revenue is 22 *krors*, 19 lakhs, 19,404½ *dāms*. (Rs. 55,47,985-1-3). Of these *Parganahs*, 138, pay revenue in cash from crops charged at special rates.⁶ The extent of measured land is 24 lakhs, 44,120 *bighas*, yielding a revenue of 17 *krors*, 26 lakhs, 81,774 *dāms* (Rs. 43,17,044) in cash. The remaining 61 *Parganahs* are rated at 4 *krors*, 22 lakhs, 37,630½ *dāms*. (Rs. 12,30,940-12-5), out of which 22 lakhs, 72,174 *dāms* are *Suyurghāl* (Rs. 56,803-8-10). The province furnishes 11,415 Cavalry, 449,350 Infantry and 100 boats.

Sarkār of Bihār.

Containing 46 *Mahals*, 952,598 *Bighas*. Revenue, 80,196,390 *dāms* in cash from special crops, and from land

⁵ *Phascolus radiatus*.

⁶ The term *Zabli* though originally applied to lands sequestrated by the State, was used of rent free lands subjected to assessment in Bengal, to lands which had been resumed from Jagir grants by Jafar Khān : in the north-west, to money rents on the more valuable crops, such as sugar, tobacco, and cotton where rent in kind was the rule. Abul Fazl employs it loosely elsewhere for the revenue collection or assessment of a village.

paying the general *bigha* rate. *Suyurghāl*, 2,270,147 *dāms*. Castes various. Cavalry 2,115. Infantry 67,350.

	Bighas and Biswas	Revenue Dām	Cav.	Inf.	Suyurghal Dām	Castes
Arwal	57,089-5	426,780	...	1000	...	Afghān & Brāhman Do. Brāhman Afghān Kayath
Aukhri [?Khokri] ..	49,401-10	3,747,940	
Ikhal	40,404-4	335,260	...	200	...	
Amritu	24,387-19	1,821,333	16035	
Anbalu	847,920	...	250	...	Brāhman
Anchha	10,290-57	6,700,000	20	300	...	Afghān
Antri	1,998-9	147,980	20	200	...	Kayath
Behār with subur- ban district, has a fort of stone and brick	70,683-9	5,534,151	10	400	653,200	Brāhman Shaikhzādah Brāhman, Rājput
Bahlāwar	48,310-3	3,651,640	...	500	9000	
Basok	35,318-18	2,706,539	...	300	1,708,130	
Palach	30,030-18	2,270,538	...	500	59,185	
Baliā	26,000-18	2,056,502	20	400	85,747	Rājput
Patna, has two forts, one of brick and the other of mud	21,846-8	1,922,430	
Phulwāri	20,225-19	1,585,420	20	76	...	
Pahra	12,285-6	941,160	20	400	...	
Bhimpur	10,862-15	824,584	
Pandārak	727,640	300	2000	...	
Tilādah	39,053-12	2,920,366	20	300	...	
Jarar	12,930-10	979,363	50	500	...	
Chargāon	904,440	20	300	...	
Jai Champa	620,000	20	600	...	
Dādar	262,500	
Dhakner	215,680	
Ruh	250,100	20	1500	...	
Rāmpur	363,820	
Rājgir	3,756-12	288,228	
Sanot	36,780-7	2,824,180	20	500	...	
Samāi	32,514-3	2,537,080	10	200	...	
Salurah	2,079,000	...	500	...	
Sāndah	24,562-2	1,889,956	...	500	...	
Seor, has a strong fort on a hill ..	14,145-8	1,250,591	200	5000	...	
Ghiāspur	84,205-7	5,657,290	
Gidhaur, has a strong fort on a hill in the jungle	...	1,452,500	250	10,000	...	
Kātibahira	737,540	
Kābar	7,400-9	560,875	30	700	...	
Gul	374,880	100	1000	...	Rājput
Ghātisār	360,820	
Karanpur	363,820	
Gaya	951-4	74,270	14,235	
Muner	89,039-15	7,049,179	325,380	
Masodhā	68,191-10	4,631,080	
Muldah	28,128-9	2,151,575	100	3000	49,805	Brāhman
Manroā	7,706-9	585,500	20	500	...	Do.
Maher	23,937-19	1,779,540	...	200	47,700	Do.
Narhat	30,555-7	2,380,309	5	200	...	Kayath

Sarkār of Monghyr.

Containing 31 *Mahals*. Revenue 109,625,981½ *dāms*.

Castes various, 2,150 Cavalry, 50,000 Infantry.

	Revenue D.		Revenue D.
Abhipur ...	2,000,000	Angu ...	147,800
Osla ...	89,760	Aubalu ...	50,000
Bhāgalpur ...	4,696,110	Surajgarh ...	299,445
Baliā ...	3,287,320	Sakhrasāni ...	160,000
Paharkial ...	3,000,000	Satyāri ...	58,730
Pathrārah ...	140,920	Kahalgāon ...	2,800,000
Basai ...	132,000	Kharhi ...	689,044
Tanur ...	88,420	Kozrah ...	260,602
Chai ...	9,280,000	Khatki ...	160,000
Chandoi ...	360,000	Lakhanpur ...	633,280
Dharmpur ...	4,000,000	Masjidpur ...	1,259,750
Dānd Sakhwārah ...	136,000	Monghyr and suburban dis-	
Rohni ...	95,360	trict ...	808,907½
Sarohi ...	1,773,000	Masdi ...	29,725
Sukhdehra ...	690,240	Hindui ...	108,000
Saghauli ...	360,000	Hazār taki ...	9,182

Sarkār of Champāran.

Containing 3 *Mahals*, 85,711 *Bighas*, 5 *Biswas*.

Revenue 5,513,420 *Dāms*, Horsemen, 700.

Infantry 30,000.

	B.	& B.	Dāms		B.	& B.	Dāms
Samrun ...	7,200	2	500,095	Majhora	22,415	16	1,404,890
Mehsi ...	56,095	7	3,518,435				

Sarkār of Hājipur.

Containing 11 *Mahals*, 10 Villages, 436,952 *Bighas*,

15 *Biswas*. Revenue 27,331,030 *dāms*.

	B.	& B.	Revenue		B.	& B.	Revenue
Akbarpur ...	3,366	17	195,040	Rati ...	30,438	13	1,824,980
Boswāwi ...	10,851	14	624,791	Saresā ...	102,461	8	6,704,300
Basārā ...	106,370	7	6,380,000	Imādpur ...	12,987	7	795,870
Bālāgachah ...	14,638	2	913,660	Garhsarah ...			876,200
Teghra ...	58,306	13	3,518,354	Naipur ...	27,877	9	1,663,980
Hājipur with su-							
burban district	62,653	17	3,833,460				

Sarkār of Sāran.

Containing 17 *Mahals*. Measured land 229, 052 *Bighas*,

15 *Biswas*. Revenue 60,172,004½ *dāms*.

Castes various. Cavalry 1,000. Infantry 50,000.

	B.	& B.	Dāms		B.	& B.	Dāms
Indar ...	7,218	4	534,990	Pāl ...	66,320	5	4,893,378
Barāri ...	7,117	10	533,820	Bārā ...	15,059	3	383,797½
Narhan ...	8,611	8	654,508	Godah			
Pachlakhi ...	9,266	15	437,997	(Gawā ?) ...	28,049	3	2,012,950
Chanend ...	8,413	13	633,270	Kaliyānpur ...	17,437		774,696
Chaubāra ...			400,000	Kashmir ...	16,915		1,314,539
Juwainah ...	6,963	8	309,285	Māngjhi ...	8,752	19	611,813
Degsi ...	5,825		277,630	Mandhal ...	9,405	7	698,140
Sipāh ...	3,662		290,592	Maker ...	10,936	14	811,095

Sarkār of Tirhut.

Containing 74 *Mahals*, Measured land 266,464 *Bighas*
2 *Biswas*. Revenue 19,179,777½ *dāms*. Castes various
Cavalry 700. Infantry 80,000.

	B.	& B.R.	Dāms		B.	& B.	Dāms
Ahaspur ...	4,880	"	302,550	Tarāni ...	7,171	"	443,242
Uarkhand ...	2,068	"	128,412	Tilokchāwand ...	2,411	" 7	149,896
Ahlwār ...	1,001	" 1	62,212	Tājpur ...	1,351	" 14	85,434
Anbhi ...	"	"	60,000	Tāndah ...	1,038	" 4	63,768
Aughārā ...	836	" 15	53,980	Tarson ...	980	" 4	61,180
Athāis ...	559	" 17	34,356	Tirhut with su-			
Basri &c.,				burban district	21,398	"	1,307,706
4 <i>Mahals</i>	"	"	1,125,000	Jākhar ...	17,140	"	1,068,020
Bahrwārāh ...	16,176	"	942,000	Jarāyal ...	8,297	"	515,732
Bānpur ...	40,347	"	894,792	Chakmani ...	5,173	"	321,326
Barel ...	6,185	"	789,858	Jakhal [-pur]	3,092	"	196,020
Pepra ...	1,823	" 18	112,591	Jabdi ...	"	"	45,025
Padri ...	9,048	"	554,258	Dahrōr ...	3,165	"	202,818
Basotra ...	8,864	"	546,627	Darbhāngā ...	2,038	"	159,052
Panchhi				Rāmjaund ...	7,409	"	470,005½
[?Bachhi]	5,816	"	361,920	Sareshtā ...	15,474	"	941,010
Bahnor ...	5,033	"	289,773½	Salimpur ...	458	" 14	29,094
Bachhnor ...	4,956	"	275,185	Salimābād ...	44	" 15	4,184
Pachham				Sanjoli Tadrā ...	2,450	"	150,843½
Bhagu ...	4,095	"	271,826	Alāpur ...	8,796	"	442,466
Bagla ...	3,716	"	267,862½	Fakhrābād ...	1,170	" 6	72,355
Purab Bhagu	3,022	" 17	222,280	Khānanli ...	4,644	"	408,804
Pandrājah ...	3,135	" 4	195,837½	Ghar Chāwand	5,510	"	349,480½
Bādi Bhosādi	2,823	"	175,585	Kodākhand ...	3,888	"	243,677
Bhālā ...	2,840	"	145,437	Korādi ...	"	"	90,000
Bhadwār ...	2,087	"	130,471½	Khandā ...	330	" 6	21,443
Parhārpur ...	1,968	"	121,067½	Ladwāri ...	2,609	"	142,495
Bahādurpur ...	1,936	" 16	119,305	Mahlā ...	15,295	"	946,048
Barai ...	1,455	" 12	90,369½	Morwah ...	8,289	"	515,485
Parhār Rāgha	1,303	" 17	81,605	Mandal, (Ma-			
Bhaurā ...	1,170	" 9	69,608	hend ?) ...	1,077	" 12	66,693
Palwāah ...	1,060	" 9	65,628	Margā			
Borā ...	875	" 15	55,757	[?Naranga]	632	" 18	39,022
Banwā ...	"	"	40,539	Malahmi ...	151	" 1	9,728
Parhārpur,				Nauram ...	"	"	288,140
Jabdi ...	604	" 14	37,736	Nautan ...	3,381	" 7	209,153
Bagi ...	505	" 5	31,550	Hāthi ...	2,563	" 18	159,790½
Bochhāwār ...	188	" 10	12,875	Harni ...	796	" 17	50,342
Barsūni ...	200	" 18	12,695	Hābi [?Hali]	3,665	" 8	230,700

Sarkār of Rohtās.

Containing 18 *Mahals*, 47,334 *Bighas*, 15 *Biswas*.
Revenue, 40,819,493 *Dāms*.

Castes various. Cavalry 4,550. Infantry 162,000.

	B.	& B.	Dāms		B.	& B.R.	Dāms
Alrah ...	53,512	" 16	4,028,100	Ratanpur, has a			
Bhojpur ...	66,078	" 17	4,903,310	strong fort	"	"	783,425
Piru ...	"	"	3,407,840	Siris (Sarsi)	44,710	" 3	2,769,446
Panwār ...	22,733	" 3	1,677,000	Sahsaram ...	31,220	" 18	2,370,790
Baragūon ...	10,540	" 17	842,400	Fatlipur bhāiya	50,474	" 15	3,736,000
Chakund				Kotrā ...	29,167	" 15	1,829,300
(Jaund) ...	45,251	" 3	4,440,360	Kot, has a			
Jaidar ...	26,538	" 16	1,634,110	strong fort	"	"	847,920
Danwār ...	29,154	" 4	2,076,520	Mangrōr			
Dinār ...	"	"	350,000	(Munora ?)	"	"	924,000
Rohtās with su-				Nannor ...	29,621	"	2,000,000
burban dist.	34,330	" 10	2,258,620				

The Subah of Illāhābād. (Allahabad.)

It is situated in the second climate. Its length from *Sinjhauli* in the *Jaunpur* district to the southern hills is 160 *kos*; its breadth from *Chausa* ferry to *Ghātampur* 122 *kos*. On the East is *Behār*. To the North, *Oudh*. *Bāndhu** lies to the South and *Agra* to the West.

Its principal rivers are the *Ganges* and the *Jamna*, and there are other small streams such as the *Rind*, *Ken*, *Saru* (*Sarju*), *Barna*, &c.

Its climate is healthy. It produces a variety of fruits, flowers and garden herbs, and it has always an abundant supply of melons and grapes. Agriculture is in a flourishing state. *Jowāri* and *Lahdarah*, however, do not grow and *Moth* is scarce. Cloths, such as *Jholi*, and *Mihrkāl* and the like are beautifully woven, especially at *Benāres*, *Jalālābād* and *Mau*. At *Jaunpur*, *Zafarwāl* and other places woollen carpets are manufactured. A variety of game is also to be found.

Illahabād anciently called *Prayāg* was distinguished by His Imperial Majesty by the former name. A stone fort was completed and many handsome edifices erected. The Hindus regard it as the King of shrines. Near it, the *Ganges*, the *Jamna* and the *Saraswati* meet, though the latter is not visible. Near the village of *Kanitat* considerable captures of elephants are made. What is most strange is that when Jupiter enters the constellation *Leo*, a small hill appears from out of the *Ganges* and remains there during the space of one month upon which the people offer divine worship.

Bārānasi, universally known as *Benares*, is a large city situated between the two rivers, the *Barna* and the *Āsi*.† In ancient books, it is styled *Kāsi*. It is built in the shape of a bow of which the *Ganges* forms the string. In former days there was here an idol temple, round which procession was made after the manner of the *kaabah* and similar ceremonials of the pilgrims conducted. From time immemorial, it has been the chief seat of learning in *Hindustān*.

* *Bandhu* is *Rewa State*, and not *Banda* as *Jarrett* noted in the 1st edition.

† The *Āsi* is a mere brook and the city is situated on the left bank of the *Ganges*, between the *Barnā Nadi* on the N. E. and the *Āsi Nala* on the S. W. The former rises to the N. of *Allahabad* and has a course of 100 miles. From the joint names of the two which bound the city, N. and S. the *Brāhmans* derive *Varanasi*, the Sanskrit form of *Benares*. *Cunningham*, *Ancient Geog. of India*, p. 437.

Crowds of people flock to it from the most distant parts for the purpose of instruction to which they apply themselves with the most devoted assiduity. Some particulars of its history shall be related in what follows.

In A.H. 410 Sultān Mahmud of Ghazni marched hither, and some disruption of the old faith was effected. In A.H. 416, he again invaded the country. He first invested Gwalior but raised the siege under a treaty of peace. He then resolved to take the fort of *Kālīnjar*. The governor sent him 300 elephants with his respectful submission and proffered some eulogistic verses. Mahmud was so much pleased that he bestowed on him the governorship of the fort together with the charge of fourteen other places.

Jaunpur is a large city. Sultān Firoz (Tughlaq) king of Delhi laid its foundations and named it after his cousin Fakhruddin Jaunah. Its longitude is $190^{\circ} 6''$; its latitude $16^{\circ} 15''$.

Chanādah (Chanār) is a stone fort on the summit of a hill, scarce equalled for its loftiness and strength. The Ganges flows at its foot.

In its vicinity, there is a tribe of men who go naked, living in the wilds, and subsist by their bows and arrows and the game they kill. Elephants are also found in the forests.

Kālīnjar is a stone fortress situated upon a heaven-reaching* hill. No one can trace its origin. It contains many idol temples and an idol is there, called *Kāl Bhairab*, 18 cubits high, of which marvellous tales are related. Springs rise within the fort and there are many tanks. Adjoining it is a dense forest in which wild elephants, and kestrels and hawks and other animals are trapped. Ebony is here found and many kinds of fruits grow spontaneously. There is also an iron mine. In the neighbourhood, within eight *kos*, the peasants find small diamonds.

It is said that Rājā Kirat Singh the governor of the fort possessed six precious treasures, a learned Brāhman of saintly life, a youth of great beauty and amiable disposi-

* Its elevation is 1230 feet above sea level. Ferishta ascribes the fort to Kedār Rājā, a contemporary of Muḥammad, but local legend connects it with Chandra Varma, ancestor of the great Chandel family of Rajputs, who removed hither after their defeat by Prithi Rāj, the Chauhān ruler of Delhi.
I. G.

tion, a parrot that answered any questions put to it and some say, remembered everything that it heard, a musician named Bakshu unequalled in the knowledge and practice of his art, and two handmaidens lovely to behold and skilled in song. Sultān Bāhadur Gujrāti having formed a friendship with the Rājā asked him for one of these. The Rājā generously and with a provident wisdom sent him Bakshu. Next Sher Khān of the House of Sur requested the gift of the two wonderful songstresses, and when his messenger returned without them, he invested the fort. Works were erected and the besieged were reduced to great straits. In despair, the Rājā, after the manner of the Hindus who hold their honour dear, burnt his women, for in the slumbering of his reason, he had set his affections upon the things of this fleeting life, and so giving his body to ashes, according to the desire of his enemies, he became soiled with the dust of dissolution. As to Sher Khān, who had conceived this wicked design, he fell at the powder magazine when the fire opened on the fort and the harvest of his life was consumed.*

The *Subah* contains ten *Sarkārs*, and 177 *Parganahs*. Revenue 21 *krors*, 14 *lakhs* and 17,819 *dāms* (Rs. 53,10,695-7-9)), and 12 *lakhs* of betel leaves. Of these *Parganahs* 131 pay revenue from crops charged at special rates. Measured land 39, 68,018 *bighas*, 3 *biswas*, yielding a revenue of 20 *krors*, 29 *lakhs*, 71,224 *dāms* (Rs. 50,74,280-9). The remaining 46 *Parganahs* pay the general *bigah* rate. They are rated at 94 *lakhs*, 56,595 *dāms* (Rs. 2,36,424-14). Of this, 1 *kror*, 11 *lakhs*, 65,417 *dāms* (Rs. 279,135-6-6) are *Suyurghāl*. The province furnishes 11,375 Cavalry, 237,870 Infantry and 323 elephants.

Note.—In the names of the *parganahs* under the following *Sarkārs*, I have altered the spelling where the variants allow, in accordance with Elliot's list, as his personal acquaintance with their true pronunciation is probably more correct than those of my previous lists which were adapted as far as possible to reconcile the readings of Gladwin and Tieffenthaler. The discrepancies are slight and will not interfere with their recognition.

* This took place in 1545. During the siege a live shell rebounded from the walls into the battery where Sher Shāh stood and set fire to the gunpowder. He was brought out severely burnt and died next day, having previously ordered an assault which was at once made with success. K. R. Qanungo's *Sher Shah*, 339.

Sarkār of Ghāzipur, (East.)

Containing 19 Mahals, 288,770 Bighas, 7 Biswas.

Revenue 13,431,308 Dāms, in money.

Suyurghāl, 131,825 Dāms. Castes various.

Cavalry 310. Infantry 16,650.

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Baliā	28,344-15	1,250,000	...	200	2000	Rājput
Pachotar	13,679-9	6,982,040	2,250	50	2000	Do.
Billābās*	12,306	652,360	...	10	200	Do.
Bāhriābad	6,983-10	355,340	1,720	...	200	Do.
Bhālāech, (E. Barāich) ..	2,255-19	112,461	
Chausā, (E. Chaunsā) ..	15,602-11	791,653	...	10	500	Brāhman
Dihbā, (E. Dihmah) ..	2,808-15	128,815	2,077	...	50	Rājput
Savyidpur Namdi ..	25,721-3	1,250,280	18,172	20	1000	Brāhman
Zahurābād	13,802-12	657,808	29,528	500	20	Do.
Ghāzipur with subur- ban district	12,325-9	570,350	39,680	10	20	Kayath, Rājput
Kariyāt Pali	1,394-5	75,467	
Kopāchhit	19,266-11	942,190	893	20	2000	Rājput
Gandhā, (E. Garhā) ..	10,049-10	500,000	200	Do.
Karendā	6,260-15	293,551	300	Do.
Lakhner, (E. Lakhe- sar)	2,888-3	126,636	834	
Madan Benāres	66,548-7	2,760,000	1,356	50	5000	Brāhman
Muhammadābād, and Parhārbāri	48,774-16	2,260,707	4,777	2000	100	Do.

Sarkār of Benāres (East.)

Containing 8 Mahals, 36,869 Bighas, 12 Biswas.

Revenue 8,869,315 Dāms in money.

Suyurghāl 3,38,184. Castes various.

Cavalry 830. Infantry 8,400.

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Afrād	10,655-6	853,226	20,080	...	400	Brāhman,
Benāres, with suburban district	31,657-1	1,734,721	22,190	50	1000	Rājput Brāhman
Byālisi	60,961-3	547,634	...	20	300	Do.
Pandarhā, (var. and E. Pandrah)	4,610-15	844,221	15,836	10	400	Do.
Kaswār	41,184-14	2,290,160	80,120	50	2000	Do.
Katchar, has a brick fort	30,495-14	1,874,230	48,070	500	4000	Raghuvansi
Harhuā	13,098-3	713,426	8,145	...	300	Brāhman

* G. and T. Baliabass.

*Sarkār of Jaunpur (North).*Containing 41 *Mahals*, 870,265 *Bighas*, 4 *Biswas*.Revenue 56,394,107 *dāms* in money.*Suyurghāl*, 4,717,654. Castes various.

Cavalry 915. Infantry 36,000.

		Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Aldimau	46,888-12	3,099,990	88,976	50	3,000	Rājput
Angli	42,992-14	2,713,551	464,516	50	2,000	Sayyid, Rāj- put, and Rahmatul- lāhi Bachgoti
Bihari	17,703	844,357	12,520	10	100	Ansari*
Bhadāon	4,300	229,315	...	10	100	Saddiki
Tilhani	10,983-8	654,363	27,457	10	100	Rājput
Jaunpur with suburbs, has a fort, the lower part stone, and the upper constructed of brick	65,739-4	4,247,043	807,821	120	2,500	Rājput Ko- sak, Brāh- man, Kur- mi
Chāndipur Badhar, (E. Birhar)	22,826-7	1,467,205	157,641	20	400	Rahmatullā- hi, Brāh- man
Chāndah	17,590	989,286	...	20	300	Bachgoti
Chiriyākot	14,153	807,848	13,689	20	200	Rājput
Jakesar (E. Chakesar)	5,415-10	286,586	...	10	100	Saddiki
Kharid, has a brick fort on the banks of the Sarah	30,914-13	1,445,743	3,140	50	5,000	Rājput Kau- sik
Khāspur Tūndah	17,365	986,953	40,189	10	300	Kāyath
Khānpur	6,628-10	3, 06,020	5,387	...	150	Rājput
Deogāon	44,524-18	2,583,205	196,238	25	1,000	Do.
Rāri	24,360	1,326,299	84,502	10	300	Gautami†
Sanjhanli	46,815-3	2,938,209	334,932	50	100	Rājput Sayyid, Rāj- put, Bra- man
Sikandarpur, has a brick fort	32,574-10	1,706,417	5,325	10	3,000	Brāhman
Sagdi, (E. Sagri)	19,792	1,274,721	102,224	10	200	Rājput
Surharpur	18,851	1,164,095	7,094	10	20	Do.

* These according to the I.G. (Bahraich) were the descendants of the early Mussalman settlers and invaders. For their descent and history, see Beames *Memoir*, I, 7. For Bachgoti, see Elliot (*Races of the N. W. P.*) who says that all Chauhanas are Bachgotis, being of the *gotra* of Bach, but Sherring proves this to be an error, instancing the *gotras* of Vatsa and Kāsyap. *Hindu Tribes*, I, p. 164.

† A clan of Rājputs of the Chandarbans, once a powerful clan in the Lower Doab. See Elliot, p. 118, I, and Sherring, I, 202.

Sarkār of Jaunpur (North).—(Contd.)

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Shādiābād	30,848-8	1,700,742	10,020	20	400	Rājput
Zafarābād	2,822-9	156,926	13,806½	...	50	Do.
Qariyāt Mittu	8,991-11	551,410	...	10	300	Do.
.. Dostpur	8,857	481,524	42,227	...	100	Do.
.. Mendhah	7,416	394,870	21,260	...	100	Do.
.. Seothah	2,988-10	206,733	14,224	...	100	Do.
Kolah	24,231	1,363,332	14,971	10	300	Do.
Ghiswah	30,775	1,241,291	42,366	10	200	Do.
Ghosi	18,913	1,037,934	69,650	10	200	Do.
Gadwārah	2,191	513,942	2,682	50	5,000	Rājput Bach- goti
Kāndiyah, (B. Kauria)	5,761-12	341,890	200	Rājput
Gopālpur	3,266-8	18,043	4,948	...	100	Do.
Karākat	48,332-14	23,002,748	77,339	20	500	Do.
Mandiāhu, has a brick fort (B. Ma- rialu)	88,899-5	5,259,465	273,788	50	2,000	Rājput Kau- sik
Muhammadābād	56,350-14	3,229,063	220,442	30	1,000	Rājput, Brāh- man
Mungra	9,626-5	529,730	200	Rājput
Majhāura	6,417-6	420,164	14,427	...	200	Rahmatul- lāhi
Mau	2,645-3	209,067	50	Shaikh zā- dah
Nizamābād	6,074-13	602,592	478,026	200	4,000	Rājput Gau- tami, Brāh- man, Rah- matullāhi
Negun	10,145	758,796	145,350	...	200	Brāhman
Nathupur	4,948-14	278,472	21,239	10	200	Saddiki

Sarkār of Mānikpur.

Containing 14 Mahals, 666,222 Bighas, 5 Biswas.

Revenue 33,916,527 Dāms in money.

Suyurghāl, 8,446,173. Castes various.

Cavalry 2,040. Infantry 2,900.

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Arwal, has a brick fort	62,131-10	2,957,077	37,220	114	7,000	Rājput
Bhalol	32,343-3	1,832,283	175,753	20	500	Rājput Kā- yath, Bao- riya*
Tilhandi	11,721-6	383,251	54,821	10	300	Do.
Jalalpur Balkhar, has a brick fort	76,517-8	3,913,017	140,325	400	5,000	Brāhman Bachgoti,

* Par. Gauriya, Puriya: perhaps Baoria a tribe of professional thieves widely spread, and in a loose way, a distinct caste. I. G. under, Rajputana and Sherring, II. 82.

arkār of Mānikpur.—(Contd.)

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Jāes, has a brick fort, (I. G. Jais)	25,625	1,424,787	277,863	250	7,000	Various
Dalmau, has a brick fort on the Ganges ..	67,508-9	3,626,067	344,130	50	200	Turkomān
Rae Bareli, has a brick fort on the Sai	65,751-17	3,650,984	180,050	40	2,000	Rājput, Khand, Baoria
Salon, has a brick fort	56,102	2,717,391	394,774	180	8,930	Rājput Khandwāl,† Bisen.
Qaryāt Karārah	51,505-19	2,461,077	115,774	20	700	Rājput, Bisen
" Pāegāh	22,130	1,117,926	6,794	20	400	Do. do.
Kathot, has a brick fort	9,456-8	514,909	3,187	100	2,000	Bachgoti
Mānikpur with suburbs, has a brick fort on the Ganges	129,830-1	6,737,729	542,312	500	6,000	Bisen
Nasirābād	55,599-4	2,582,079	108,148	40	1,000	Rājput, Kā- yath, Gao- ria, Bais

Sarkār of Chanādah (Chanār), South.

Containing 13 Mahals, 106,270 Bighas, 8 Biswas.

Revenue 5,810,654 Dāms in money.

Suyurghāl, 109,065. Cavalry 500.

Infantry 18,000.

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Ahirwārah	1,858-8	109,073	Saddiki, Faruki, Ansāri
Bhoili, (E. Bhuili) ..	18,975-10	1,112,656	33,605	
Badhaul, (E. Barhaul) ..	6,412-11	361,364	605	
Tāndah	488,010	
Chanādah, with subur- ban district, has a stone fort	12,939-14	833,908	8,467	500	18,000	
Dhns	4,274-10	235,644	14,548	
Rāghupur, now pro- nounced Rāhupur E.)	7,267-12	451,962	17,869	
Villages, this side of the river	18,098	845,371	14,492	
Majhwārah	9,312-3	549,817	14,597	
Mahāich	7,950-2	390,609	2,069	
Mahwāri	4,878-3	227,067	
Mahoi, (E. Mawai) ..	4,301-2	205,283	3,353	

† Sherring gives the name of *Khondāchurāl* to a trading caste in Bhurtpur.

Sarkār of Bhathkhora, (South.)

Containing 39 *Mahals*. Revenue 7,262,780 *Dāms* in money.

Cavalry 4,304. Elephants 200. Infantry 57,000.

Sarkār of Kālinjar, (South.)

Containing 11 *Mahals*. ~ Measured land, 508,273 *Bighas*,

12 *Biswas*. Revenue 23,839,470 *Dāms*, in money.

Suyurghāl 614,580 *Dāms*. Castes various.

Cavalry 1,210. Elephants 112. Infantry 18,100.

	Bighas and Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Uguāsi, has a brick fort, (E. Ugāsi)	53,963-6	2,502,898	60,776	400	5,000	10	Sayyid, Gadhwāl, Parihār
Ajaigarh, has a stone fort on a hill	200,000	...	20	2,000	10	Gond
Sendha, (E. Sihondā) has a stone fort on the Ken	138,467-12	6,262,833½	129,412	20	3,000	25	Gond, Chan del, &c.
Simauuni, has a brick fort	48,866-3	2,247,346	15,300	300	3,000	...	Khandwāl
Shādipur, has a stone fort	62,755-15	2,798,329½	96,312	40	700	...	Rājput, &c.
Rasan	11,988-10	512,026	...	50	100	20	Bhar, Bais
Kālinjar with suburban district	22,494	970,259	130,490	20	500	7	
Kharelah, has a brick fort	25,940-1	1,275,325	...	50	1,500	...	Rājput, Bais
Mahobā, has a stone fort, and each side of the village is flanked by two high hills	81,567-13	4,042,014 & 120,000 <i>pān</i> leaves	860,528	100	3,000	40	Bagri* Rahmatu'l- lāhi, Pari- hār
Māudhā, has a stone fort	62,530-7	2,998,062	154,062	30	400	..	

* The Bāgri are a tribe inhabiting the Bāgar country, a tract between the S.-W. border of Hariana and the Ghāra. Bāgar is also the name of a tract in the Mālwah, but in the N.-W. P. applied to the Bāgri Jats of Hissār and Bhattiāna. Elliot, *Memoir* (Beale), I, 9-10.

Sarkār of Kurrah, (West.)*

Containing 9 *Mahals*, 341,170 *Bighas*, 10 *Biswas*.

Revenue 17,397,567 *Dāms*. *Suyurghāl* 469,350 *Dāms*.

Castes various. Cavalry 500. Elephants 10.

Infantry 15,000.

	Bighas and Biswas	Revenue D.	ghāl D. Suyur-	Cavalry	Infantry	Elephants	Castes
Jājmāo, has a fort on the Ganges ..	62,195-10	3,106,346	139,936	200	4,000	7	Afghān Lodi, Rāj- put, Rais.
Kurrah, with suburban district, has a brick fort on the Rind river	124,748-12	6,771,891	257,373	50	300	...	Brāhman
Ghātampur	73,876-3	3,667,564	48,654	100	2,000	10	Rājput Di- khit (Di- kshit) Kā- yath
Majhāwan	26,980-8	1,323,339	2,574	20	1,000	...	Brāhman
Kutīā	12,178-11	584,274	20,815	30	1,000	...	Rājput Gau- tami
Guner	10,041-16	513,457	...	20	1,000	...	Do.
Kiranpur Kinār, (Elliot Kiratpur Kanānda) ..	17,965	830,070	...	30	1,000	...	Do.
Muhsanpur	13,181	600,586	...	50	2,000	2	Rājput Chandel

* Kurrah is a decayed town in Fatehpur district; formerly the capital of this Sarkār under the Mughals: it still retains traces of its former importance. A few words follow this name which are either omitted or illegible in the other MSS. Literally they run thus: "And there is a village called Nuni which produces flowers and colour."

Karah is now a ruined town on the right bank of the Ganges, 40 miles N.W. of Allahābād. It was the scene of the famous meeting between Muir'uddin and his father in 1286 which forms the subject of Mir Khusrū's well-known Persian epic, the *Kirān's Saadain*. Two sarkārs of the Allahabad province bearing names liable to be confounded with each other in careless Persian writing, are *Korā* and *Kārā*. They were later distinguished as *Korā-Jahānābād* (situated in the Fatehpur dist. of the U. P.) and *Kārā-Mānikpur*, (*Kārā* being in the Allahabad dist., and *Mānikpur* on the north bank of the Ganges opposite to *Kārā* and therefore in the Oudh province). The two places are 70 miles apart east to west. The best device for avoiding confusion is to spell *Korā* as *Kurrah*, which form of the word we find in the Marathi and some Persian records. [J. Sarkar.]

Sarkār of Karah, (West.)

Containing 12 *Mahals*, 447,556 *Bighas*, 19 *Biswas*....
 Revenue 22,682,048 *Dāms*. *Suyurghāl*, 1,498,862 *Dāms*.
 Castes various. Cavalry 390. Infantry 8,700.

	Bighas and Biswas	D. Revenue	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Richhi, (Elliot Richhi)	35,825-11	1,624,034½	34,974	10	500	...	Do.
Atharban	18,517-14	894,036½	4,770	10	200	...	Do.
Āyāsū	15,783-11	845,766	...	10	500	...	Rājput
Haveli, (suburban dis- trict) of Kara ..	9,638-17	5,192,170	442,080	100	1,000	...	Kāyath, Rāj- put, Brāh- man, Khari Rājput Brāhman
Rāri	56,727-18	2,707,034	26,350	10	4,000	...	Rājput Brāhman
Baldah* of Kara, has a fort on the Ganges, lower part stone, up- per, brick	70,001-12	236,868	Various
Karāri, has a brick fort on the Jumna ..	39,686-19	141,953	Brāhman
Kotlā	18,043-1	909,234	122,191	10	300	...	Rājput
Kunrā, commonly Ko- son, (Elliot, Karson), has a brick fort ..	11,782-9	693,487½	...	100	2,000	...	Various
Fatchpur Hanswah, (Elliot Haswā) ..	55,915-8	2,892,705	370,420	50	1,000	...	Rājput, Brāhman
Hatgāon	55,322-12	2,723,508½	24,829	40	1,000	...	Do.
Hanswah	42,521-3	2,123,661½	15,506	30	1,000	...	Afghān, Rājput

Its rulers.

Sultānu's Sharq reigned,	16 years.
Mubārak Shāh ..	1 year and a fraction.
Sultān Ibrahim ..	40 years ..
Sultān Mahmud ..	21 years and a few months.
Mahmud [= Muham- mad] Shah ..	5 months.
Husain ..	19 years.

* Mr. Beames in a note to Elliot's Gloss., p. 83, II, distinguishes between *Haveli* and *Baldah*, the former alluding to the district close to the Capital and the latter to that at a distance.

Malik Sarwar Khwāja Jahān ...	A.H. 796/1394 A.D.
Malik Qaranful, Mubārak Sh. ...	802/1399
Shams-ud-din Ibrāhīm Sh. ...	804/1402
Mahmud Sh. ...	840/1436
Muhammad Sh. ...	862/1458
Husain Sh. ...	862-884/1458-79

—(Cambridge Hist. India, iii).

These six princes held sway for 97 years and a few months.*

This province was formerly administered by the sovereigns of Delhi. When the imperial authority devolved on Sultān Muhammad-b-Firuz Shāh, he bestowed the title of Sultān us Sharq upon Malik Sarwar a eunuch who had received from his predecessor the dignity of *Khān-i-Jahān*, and sent him to this province. He gave lustre to his reign by his judgment, clemency, justice and valour and thus garnered a provision for his life's last journey. When the cup of his days was full, the son whom he had adopted; named Mubārak Qaranful, by the assistance of the chief men of the State, raised himself to power and had the *khutbah* read and the coin struck in his own name. When the news of this event reached Mallu (*Khān*), he collected troops and marched from Delhi to oppose him and encamped in readiness for battle on the bank of the Ganges, but nothing decisive having been effected, both armies returned home.

When this prince died, his younger brother Ibrahim was raised to the throne. By his knowledge of men and capacity for affairs he administered the kingdom with justice and made the chastisement of the unruly a source of prosperity to his government. Wisdom was eagerly sought and the prospects of the intelligent in every profession was advanced. Qāzi Shahābu'ddin, a sage of Hindustan flourished about this time. He was born at Delhi and in that city acquired a comprehensive knowledge of the inductive sciences and traditional lore, and at the time of the arrival of Timur, he set out for Jaunpur in the company of his master Maulānā Khwājagi who was the successor of Nasiru'ddin Chirāgh of Delhi and there continued his progress and became the envy of his time. Shāh Madār, however, who is esteemed one of the saints of Hindustān and the chief of his contemporary series of divines, through the disagreement that ever exists between philosophers who regard the material world, and masters of the spiritual life, entertained no esteem for the Qāzi.

When the days of Ibrahim came to a close, his eldest son Bikhan Khān, under the name of Sultan Mahmud, assumed the sovereignty. As his deeds were not approved, the sentence of deposition was issued against him and his

* Six Jaunpur rulers,—97 years.

brother Husain raised to power. He made rectitude his rule of conduct and his chief object the conciliation of all hearts. Fortune favoured his desires and the world praised him but intoxicated by the maddening fumes of worldly success, he became arrogant. He was involved in war with Sultān Bahlol and was defeated. Sultān Bahlol left his son Bārbak at Jaunpur and entrusted him with the government. [1478.] On the death of Sultān Bahlol the throne of Delhi devolved on Sultān Sikandar. Sultān Husain with the connivance of Bārbak collected troops, made several attempts against Delhi, but with him the *Sharqi* dynasty closed.*

The Subah of Oudh.

It is situated in the second climate. Its length from the Sarkār of Gorakhpur to Kanauj is 135 kos. Its breadth from the northern mountains to Sidhpur on the frontier of the Subah of Allahabad is 115 kos. To the east is Bihar; to the north, the mountains; to the south, Manikpur, and to the west Kanauj. Its climate is good. Summer and winter are nearly temperate. Its principal streams are the Saru (*Sarju*), the Ghaghar (*Gogra*) the Sai and the Godi (*Gumti*). In the first mentioned, divers aquatic animals and forms of strange appearance show themselves. Agriculture is in a flourishing state, especially rice of the kinds called *Sukhdās*, *Madhkar*, and *Jhanvān*, which for whiteness, delicacy, fragrance and wholesomeness are scarcely to be matched. They sow their rice three months earlier than in other parts of Hindustān. When the drought begins, the Sai and the Gogra rise high in flood and before the beginning of the rains, the land is inundated, and as the waters rise, the stalks of rice shoot up and proportionately lengthen: the crop, however, is destroyed if the floods are in full force before the rice is in ear. Flowers, fruits and game are abundant. Wild buffaloes are numerous. When the

* Jaunpur continued to be governed by the Lodi synasty till the defeat and death of Ibrahim grandson of Bahlol and last of the line, at Panipat by Bihar in 1526. A local kingdom was for a short time established under Bahadur Khān governor of Jaunpur who asserted his independence. It was recovered by Humayun, passed again into the hands of Sher Khān and his son of Salim. Humayun on his reconquest of Hindustān died before he could master his eastern possessions. Jaunpur continued under the Afghāns until Akbar in the 4th year of his reign, took possession of it through Ali Quli Khān and incorporated it with his dominions. In 1575 the Viceregal Court was removed to Allahabad and Jaunpur was governed thenceforth by a Nizam.

plains are inundated the animals take to the high ground where the people find sport in hunting them. Some of the animals remain all day in the water and only at night approach the dry ground and breathe in freedom. *Awadh* (*Ajodhyā*) is one of the largest cities of India. It is situated in longitude $118^{\circ}, 6'$, and latitude $27^{\circ}, 22'$. In ancient times its populous site covered an extent of 148 *kos* in length and 36 in breadth, and it is esteemed one of the holiest places of antiquity. Around the environs of the city, they sift the earth and gold is obtained. It was the residence of Rāmachandra* who in the *Treta* age combined in his own person both the spiritual supremacy and the kingly office.

At the distance of one *kos* from the city, the *Gogra*, after its junction with the Sai, [*Saraju*] flows below the fort. Near the city stand two considerable tombs of six and seven yards in length respectively. The vulgar believe them to be the resting-places of Seth and the prophet Job, and extraordinary tales are related of them. Some say that at *Ratanpur* is the tomb of Kabir,† the assertor of the unity of God. The portals of spiritual discernment were partly opened to him and he discarded the effete doctrines of his own time. Numerous verses in the Hindi language are still extant of him containing important theological truths. *Bahraich* is a large town on the banks of the river Sarju. Its environs are delightful with numerous gardens. *Sālār Masud*¹ and Rajab Sālār are both buried here. The common people of the Muhammadan faith greatly reverence this spot and pilgrims visit it from distant parts, forming themselves in bands and bearing gilded banners. The first mentioned was connected by blood with Mahmud Ghaznavi, and sold his life bravely in battle and left an imperishable name. The second was the

* The 7th *avatār*, who in this capital of the solar dynasty founded on the chariot wheel of Brahma, consummated the glories of sixty generations of solar princes and as the incarnate Rāmā, is the hero of the famous epic that bears his name.

† His doctrines were preached between A.D. 1380 and 1420 and attempted the union of Hindu and Muhammadan in the worship of one God whether invoked as Ali or Rāmā. On his decease both these sects claimed the body and while they contested it, Kabir suddenly stood in their midst and commanding them to look under the shroud, vanished. A heap of beautiful flowers was there discovered, which, divided among the rival worshippers, were buried or burnt according to their respective rites. Pilgrims from upper India to this day beg a spoonful of rice water from the Kabir Monastery at Puri in Orissa.

¹ Under the orders of Mahmud of Ghazni, he penetrated the country in A.D. 1033, but was eventually defeated at Bahraich and fell fighting, *sanguine purification*, as Tieffenthaler writes, crowned with the double glories of the hero and the martyr.

father of Sultān Fīroz king of Delhi and won renown by the recitude of his life.

In the vicinity of the town, there is a village called *Dogon* which for a long time possessed a mint for copper coinage.

From the northern mountains quantities of goods are carried on the backs of men, of stout ponies and of goats, such as gold, copper, lead, musk, tails² of the *kutās* cow, honey, *chuk* (an acid composed of orange juice and lemon boiled together), pomegranate seeds, ginger, long pepper, *majith*³ root, borax, zedoary, wax, woollen stuffs, wooden ware, hawks, falcons, black falcons, merlins, and other articles. In exchange they carry back white and coloured cloths, amber, salt, assafoetida, ornaments, glass and earthen ware.

Nimkhār is a fort of considerable note and a shrine of great resort. The river Godi (Gumti) flows near it, and around are numerous temples. There is a tank called *Brahmāwartkund* in which the water boils and with such a swirl, that a man cannot sink therein,⁴ and it ejects whatever is thrown into it. In the neighbourhood is also a deep hollow, the springhead of a stream, one yard in breadth and four digits deep that flows into the Gumti. The Brāhmins tell strange tales of it and pay it worship. Its sand shapes itself into the form of *Mahādeo* which quickly disappears again and of whatever is thrown in, as rice and the like, no trace remains.

There is likewise a place called *Charāmiti*, whence, during the *Holi* festival, flames spontaneously issue forth with astonishing effect.

² It would seem from a passage of Ferishta mentioning an inroad of Tibetans into Kashmir in the reign of Ibrahim, son of Nāzuk Shāh (p. 359, II) that the *yāk* is meant. The Kashmiris retaliated by pursuing the marauders, and exacting as compensation 500 horses, 1000 pieces of *pattu*, 200 sheep and 50 *kutās* cows. Later on, it is mentioned by Abul Fazl among the fauna of India and described as little differing from the common cow except in the tail which is a distinguishing peculiarity, and the origin of its name, *kutās*.

³ Rubia Munjista, Roxb. a native of Nepal and other mountainous countries N.-E. of Bengal. Its root yields a red dye.

⁴ Tieffenthaler asserts that it derives its name from Brahma who is supposed to have sacrificed here, but according to the I. G. there is a legend that in one of these tanks, Rāmā washed away his sin of having slain a Brāhman in the person of Ravana, who had carried off his wife Sita.

Lucknow is a large city on the banks of the Gunti, delightful in its surroundings. *Shaikh Mina* whom the people consider a saint, lies buried here.

*Surajkand** is a place of worship frequented by various classes of people from the most distant places.

Kheri is a town on the banks of the river *Sai* upon which the people go in boats to spear fish.

Bilgrām is a small town the air of which is healthy and its inhabitants are generally distinguished for their quick wit and their love of singing. There is a well here which adds to the intelligence and comeliness of whomsoever drinks of it for forty days.

This *Subah* is divided into five *Sarkārs* and thirty-eight *parganas*. The measured lands are 1 *kror*, 1 *lakh*, 71,180 *bighas*. Its revenue, 20 *krors*, 17 *lakhs*, 58,172 *dāms*, (Rs. 5,043,954-4), of which 85 *lakhs*, 21,658 *dāms* (Rs. 213,041-7). are *Suyurghāl*. The provincial force consists of 7,640 Cavalry, 168,250, Infantry and 59 Elephants.

Sarkār of Oudh.

Containing 21 *Mahals*, 2,796,206 *Bighas*, 19 *Biswahs*, Revenue, 40,956,347 *Dāms* in money. *Suyurghāl*, 1,680,248 *Dāms*. Castes various. Cavalry 1,340, Elephants 23, Infantry 31,700.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Infantry	Cavalry	Elephants	Castes
Oudh, with suburban district, 2 mahals ..	38,649-17	2,008,366	158,741	5	500	...	Brāhman Kumbi
Ambodha, has a brick fort ..	282,037	1,298,724	7,318	30	700	...	Bais
Ibrahimābād' ..	19,338-8	445,417	103,806	Ansāri

* Identified with Asokpur, between Ajodhya and Gonda [Elliot, ii, 549].

Sarkār of Oudh—(contd.).

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Infantry	Cavalry	Elephants	Castes
Anhonah, has a brick fort	74,090	1,268,470	...	100	2,000	...	Chauhān, . newly con- verted to Islām
Panchhamrāth ..	289,085	4,247,104	38,885	20	500	...	Rājput, Bāch- hāl, Ghelot
Bilehri, has a brick fort	15,859	815,831	...	50	2,000	...	Bachgoti
Basodhi	31,188	505,473	1,500	20	500	...	Do.
Thūnah Bhadāon ..	8,703.2	427,509	36,172	...	1,000	...	Do.
Bakthā	44,401	385,008	3,960	...	500	...	Do.
Daryābād, has a brick fort	487,014	5,369,521	226,871	100	2,000	...	Rājput Chau- hān, Raik- wār*
Rudauli, has a brick fort	351,533	3,248,680	269,083	50	2,000	...	Rājput, Chau- hān, Bais
Silak, do. ..	571,071	4,723,209	200,945	100	2,000	...	Rājput, Raik- wār
Sultānpur do. ..	75,903	3,832,530	98,967	200	7,000	8	Bachgoti
Sātānpur do. ..	80,154	1,600,741	109,788	300	4,000	...	Bais, newly converted to Islām, Bachgoti, Joshi
Subeha†	104,780	1,609,293	87,200	30	1,000	...	Rājput
Sarwapāli	58,170	1,210,335	47,107	...	1,000	...	Bachgoti
Satrikah (Satrikh) ..	37,041	1,126,295	92,695	20	1,000	...	Ansāri
Gawārchak	79,158	3,773,417	3,782	50	1,070	...	Raikwār
Kishni, has a brick fort	25,674	1,339,286	123,847	...	1,500	3	Rājput
Mangalsi	116,401	1,360,753	86,504	20	1,000	...	Sombānsi
Naipur	5,997	308,788	2,940	...	500	...	Various

* The origin of this tribe *Raikwār* is given in the I. G. (Bahraich) and their settlements in Sherring I, 219.

† Subeha is a well-known *parganah* in Bāra Banki District. In the I. G. its area is recorded as 88 square miles, or 56,467 acres of which 30,783 are cultivated. Govt. land revenue £6611. In Akbar's time according to the above figures Rs. 40,232-7, and the average taking the bigha $\frac{5}{8}$ of an acre, 65,487 $\frac{1}{2}$ acres nearly.

Sarkār of Gorakhpur.

Containing 24 Mahals, 244,283 Bighas, 13 Biswas.
 Revenue 11, 926,790. Dams in money. Suyurghal 51,235
 Dams. Castes various. Cavalry 1,010. Infantry 22,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Uranā, has a brick fort	82,082	1,897,887	6,935	50	1,500	...	Afghān-i- Miyānah
Unhanā	4,114-17	201,120	2,170	...	400	...	Bisen
Bisāikpur, has a brick fort	18,887-7	600,000	...	400	3,000	...	Rājput Sa- rajbansi
Rābhānpārāh (E. Ram- hān, p.)	6,688	414,194	2,000	...	Rājput
Rhawāpārāh	8,108-15	155,900	200	...	Bisen
Telpur, has a brick fort	9,005-17	400,000	...	100	2,000	...	Rājput Sa- rajbansi
Chilpārāh, do.	6,588-14	289,892	2,000	...	Rājput
Daryāpārāh (E. Dhuria, (p.)	81,887-19	1,517,078	5,087	60	400	...	Bisen
Dewāpārāh and Kotiāh 2 mahals	16,184-17	717,840	...	20	2,000	...	Do.
Rihli, (or Rudanli)	88,188-19	1,618,074	20,873	...	1,000	...	Rājput Bisen
Rasulpur and Ghosi, 2 mahals (E. Ghansi)	4,200	622,080	500	...	Sombansi
Rāmgarh and Gauri, 2 mahals	10,762	485,948	Do., troops entered under Bi- nāikpur
Gorakhpur with subur- ban district, has a brick fort on the Rapti, 2 mahals	12,656-8	567,888	8,919	40	200	...	Sarajbansi
Katiliā, has a brick fort	900-12	40,000	...	800	2,000	...	Ransi
Rahlpārāh, Do. (E. Rihli, p.)	16,012	425,845	...	20	800	...	Bisen
Mahanli, Do.	2,528	618,256	2,000	...	Bisen
Mandwah	1,908-19	452,821	...	20	500	...	Sombansi
Mandlah	1,252-6	51,100	
Maghar and Ratangar, 2 mahals, has a brick fort	26,062	1,882,588	16,771	...	2,000	...	Bisen, Rais

* Elliot, Dhewāpāra Kūhānā.

Sarkār of Bahraich.

Containing 11 *Mahals*, 1,823,435 *Bighas*, 8 *Biswas*.
Revenue 24,120,525 *Dāms* in money. *Suyurghal*, 466,482
Dāms. Castes various. Cavalry 1,170. Infantry 14,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bahraich with suburban district has a fort on the river Sarju	697,231	9,139,141	402,111	600	4,500	...	Rājput
Bahrah	926	37,185	500	...	Kalnah (Kher?)
Hushampur, has a brick fort	157,415	4,707,035	1,601	70	900	...	Raikwār, Bisen
Dangdun	84,436	440,562	2,000	...	Janwār*
Rajhat	4,064-11	166,780	1,000	...	Ditto
Sajhauli	124,810	877,007	Rājput, Jan- wār
Sultānpur	58,146	166,001	700	...	Janwār
Fakhrpur, has a brick fort	191,720	3,157,876	56,035	150	2,000	...	Raikwar
Pirozābād, ditto	108,601	1,933,079	4,107	200	7,000	...	Rājput or Tanwār
Fort of Nawagarh	417,601	2,140,858	...	50	1,000	...	Various
Kharansa, has a brick fort	28,489-17	1,315,051	2,628	100	1,000	...	Bais

* A tribe of Rajputs in Sihonda and Simauni of Bundelkhand : Rasulābād
and Bithur of Cawnpore, and in Kutiya Gunir of Fatehpur.

Sarkār of Khairābād.

Containing 22 *Mahals*, 1,987,700 *Bighas*, 6 *Biswas*.
Revenue, 43,644,381 *Dāms* in money. *Suyurghal*, 171,342
Dāms. Castes various. Cavalry 1,160. Infantry 27,800.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Baror Anjnah	79,670-9	4,325,437	107,079	50	2,000	...	Rājput,
Baswah, has a brick fort	135,119	3,545,643	107,916	30	1,000	...	Brāhman
Pāli	144,627	1,849,270	37,945	30	1,000	...	Rājput, Bāchhal Asnin?

Sarkār of Khairābād—(contd.)

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bāwan	56,156	1,161,235	26,488	20	1,000	...	Ditto.
Basrah	60,063	300	...	Various
Bhurwārah, has a brick fort	8,971-18	43,543	...	50	2,500	...	Alinin
Basārā	21,740	276,066	200	...	Bachhal
Pilā	981-14	48,202	200	...	Alinin
Chihatyāpur	64,706	1,765,641	41,094	50	700	...	Rājput Gaur
Khairābād with subur- ban District, 2 Mahals, has a brick fort	159,072	2 161,234	174,191	50	2,000	...	Brāhman
Sāndi, has a brick fort	211,804	3,055,339	195,106	20	2,000	...	Sombansi
Sarah	68,832	2,091,983	8,666	60	500	...	Chauhān
Sadrpur	120,698	831,175	15,581	20	500	...	Janwār
Gopāman, has a brick fort	107,368.5	5,620,466	562,037	100	3,000	...	Būchhal
Kheri, do. do.	260,168	3,250 522	50,522	60	1,500	...	Rājput Kuār
Khairigarh, one of the most important fort- resses in Hindustān. There are 6 forts of brick and mortar, at a short distance from it	43,052-7	1,829,328	...	300	1,500	...	Bais, Bisen, Bachhal, Kahnah
Kharkhelā	15,815-16	473,727	...	20	500	...	Asin ?
Khānkhat Mau	3,058-11	235,656	400	...	Various
Lāharpur	208,288	3,029,479	209,079	50	1,000	...	Brāhman
Machharhatta	71-069	2,112,176	2,430	30	2,000	...	Rājput,
Nimkhār, has a brick fort	58,775-18	3,566,055	66,055	100	1,500	...	Bachhal
Hargarāon	66,952	200,000	26,385	20	500	...	Ahir

Sarkār of Lucknow.

Containing 55 Mahals, 3,307,426 Bighas, 2 Biswas.
Revenue 80,716,160 Dāms in money. Suyurghāl, 4,572,526
Dāms. Castes various. Cavalry 2,680. Elephants 36.
Infantry 83,450.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Amethi, has a brick fort	117,381	3,076,480	300,217	300	2,000	20	Ansāri
Unām, has a brick fort	61,045	2,012,372	253 747	50	4,000	...	Sayyid
Isauli, has a brick fort on the Gumti	1,670,093	4,208,046	240,846	50	2,000	...	Rājput, Bachgoti

Sarkār of Lucknow—(contd.)

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Asiyan	57,726	830,625	63,421	10	500	...	Bais, Chan- del
Asoha	25,027	509,901	400	...	Ahmin
Unchahgāon	33,122	417,957	...	1000	2,000	...	Bais
Bilgrāon, has a brick fort	192,600	5,124,113	356,892	20	1,000	...	Sayyid, Bais
Bangarman Ditto	242,291	3,802,122	151,481	...	2,000	...	Rājput, Ghelot
Bijlaur (i. Bijnori)	80,581	2,505,047	193,961	30	1,000	...	Chauhān
Bāri	80,590	1,284,799	51,560	30	1,000	...	Bais
Bhariman	19,409.3	591,406	...	20	500	...	Bais
Pangwān	34,727	420,732	12,730	...	500	...	Bais
Betholi	8,736	340,191	8,194	...	200	...	Rājput, Jāt
Panhan	8,945	267,809	300	...	Bais
Parsandan	9,111	237,537	200	...	Rājput, Kumbhi
Pātan	5,621	214,256	400	...	Brāhman, Kunbi
Bārāshakor	9,357	169,594	300	...	Brāhman
Jahloter	61,774	1,123,176	21,441	20	2,000	...	Chandel
Dewi, has a brick fort	88,637	1,939,837	174,207	30	2,000	...	Rājput
Deorakh	13,340.9	689,586	...	100	1,500	...	Bais
Dadrah	10,796	73,737	...	50	Rājput
Ranbarpur, has a brick fort	75,490	2,425,885	79,225	100	2,000	...	Bais, Brāh- man
Rāmkot, Ditto	9,790	268,099	200	...	Rājput
Sandilali, Ditto	393,700	10,623,901	837,245	100	5,000	...	Ghelot, Bāchhal
Sāipur	39,083.15	2,625,388	28,836	40	1,000	...	Rājput, Chandel
Sarosi	2,571	1,239,767	1,567	20	1,000	...	Chandel, Rājput
Sātanpur	60,600	1,028,800	10,192	50	2,000	...	Bais, Brāh- man
Sahāli	13,065	694,707	130,216	10	500	...	Rājput
Sidhor	35,794	1,692,281	313,022	100	1,000	...	Afghān, Rāj- put
Sidhpur	9,371.4	505,018	...	150	1,500	...	Bais
Sandi	7,856.9	392,313	13,792	...	1,000	...	Rājput
Saron	5,876	210,316	2,858	...	100	...	Rājput, Shaikhzādah,
Fatehpur, has a brick fort	198,300	3,161,440	261,440	200	2,000	5	Kunbi Rājput
Fatehpur Chaurāsi	105,952	909,176	6,594	10	500	...	Rājput, Chandel
Garh Anblhatti (Amethi) has a brick fort	47,356	1,800,000	...	250	5,500	8	Rājput, Bah- man Goti
Kursi, has a brick fort	80,817	1,693,844	62,919	20	2,000	3	Rājput
Kākori, Ditto	31,584	1,134,432	14,430	30	500	...	Rājput, Bisen
Khanjrah	22,300	818,472	...	100	2,000	...	Bais

Sarkār of Lucknow—(contd.)

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Ghātampur	27,390	552,561	500	...	Brāhman
Kachhandan	22,066	430,596	4,460	...	500	...	Chandel
Gorandā	4,803	334,769	200	...	Brāhman
Konbhi	5,940	267,089	400	...	Rājput
Lucknow with subur- ban district	91,722	1,746,771	241,195	200	3,000	...	Shaikhzādah, Brāhman, Kāyath
Lashkar	16,894	168,529	4,000	...	Bais
Malihābād, has a brick fort	169,269	4,479,250	108,545	30	1,000	...	Bais
Mālūwah	83,022	3,598,713	222,038	30	2,000	...	Bais
Mohān has a brick fort	60,990	1,996,673	198,484	30	2,000	...	Rājput, Bais
Morāon has a brick fort	68,847	1,698,444	4,806	150	2,000	...	Rājput, Bais
Madiāon	49,422	1,136,213	32,900	30	500	...	Barkhalā*
Mahonāh	50,895	977,860	8,805	50	2,000	...	Rājput
Manawī, has a brick fort	29,455	771,372	13,767	...	2,000	...	Mussalmān, Rājput
Makrāed	17,959	576,200	5,247	...	1,000	...	Rājput, Bais
Harlia, has a brick fort	163,226	2,450,522	6,509	100	1,500	...	Bais
Hardoi	11,734	359,748	6,026	...	300	...	Brāhman
Hanhār	13,109	329,735	...	80*	500	...	Bais

* Here a word illegible, Barkalā is an inferior class of Rājputs found in Western and Central *parganahs* of Bulandshahr.

The Subah of Agra, the Royal Residence.

It is situated in the second climate. Its length from Ghātampur on the Allahabad side to *Pakwal* on that of Delhi is 175 *kos*. In breadth it extends from *Kanauj* to *Chanderi* in *Mālūwah*. On the east lies *Ghātampur*; to the north, the *Ganges*; to the south *Chanderi*, and to the west, *Pakwal*. It possesses many rivers, of which the principal are the *Jumna* and the *Chambal*. The former flows down from the northern mountains, the latter rises at *Hāsilpur* in *Mālūwah* and unites with the *Jumna* at *Kālpi*. Ranges of hills lie scattered to the south. The excellence of its climate is almost unrivalled. Agriculture is in perfection. Fruits and flowers of all kinds abound. Sweet-scented oil, and betel-leaf of the first quality are here obtained, and its melons and grapes rival those of Persia and Transoxiana. *Agra* is a large city and possesses a healthy climate. The river *Jumna* flows through it for five *kos*, and on either bank are delightful villas and pleasant stretches of meadow. It

is filled with people from all countries and is the emporium of the traffic of the world. His Majesty has built a fort of red stone, the like of which travellers have never recorded. It contains more than five hundred buildings of masonry after the beautiful designs of Bengal and Gujerat which masterly sculptors and cunning artists of form have fashioned as architectural models. At the eastern gate are two elephants of stone with their riders graven with exquisite skill. In former times Agra was a village dependent on *Biānah*. Sultan Sikandar Lodi made it his capital, but his present Majesty embellished it and thus a matchless city has arisen. On the opposite side of the river is the *Chār Bāgh*, a memorial of Bābar.* It was the birth-place of the writer of this work, and the last resting-place of his grandfather and his elder brother. Shaikh Ālāu'ddin Majzub, Rāfiu'ddin Safawē and many other saintly personages also repose there.

Near the city on the banks of the river Jumna is a village called *Rangtah*, a much frequented place of Hindu worship.

Fatchpur was a village formerly one of the dependencies of *Biānah*, and then called *Sikri*, situated twelve *kos* distant from Agra. After the accession of his Majesty, it rose to be a city of the first importance. A masonry fort was erected and two elephants carved in stone at its gate inspire astonishment. Several noble buildings also rose to completion and although the royal palace and the residences of many of the nobility are upon the summit of the hill, the plains likewise are studded with numerous mansions and gardens. By the command of his Majesty a mosque, a college and a religious house were also built upon the hill, the like of which few travellers can name. In the neighbourhood is a tank, twelve *kos* in circumference and on its embankment his Majesty constructed a spacious courtyard, a *minār*, and a place for the game of *Chaugān*; elephant fights were also exhibited. In the vicinity is a quarry of red stone whence columns and slabs of any dimensions can be excavated. In these two cities under his Majesty's patronage carpets and fine stuffs are woven and numerous handicraftsmen have full occupation. *Biānah* in former

* The old Agra of the Lodi dynasty lay on the left bank of the river where traces of its foundations still exist. The modern city is on the right bank and is the work of Akbar. The fort was built in A.D. 1566. Bahar's garden later called *Hasht Bihisht*, or *Nurafshān* Gardens, now called the *Rām Bāgh*.

times was a large city. It possesses a fort containing many buildings and cellars, and people at the present day still find therein weapons of war and copper utensils. There is also a lofty tower. Fine mangoes grow here, some of them more than two pounds in weight. Sugar of extreme whiteness is also manufactured. Here too is a well, with the water of which mixed with white sugar, they make cakes weighing two pounds more or less which they call *kandaurah* (with no other water will they solidify) and these are taken to the most distant parts as a rarity. Indigo of finest quality is here to be obtained, selling at ten to twelve rupees per *man* weight. Excellent *hinna* (*Lawsonia inermis*) is also to be found, and here are the tombs of many eminent personages.

Todah Bhim is a place at a distance of three *kos*, from which is a pit full of water, the depth of which none has sounded. Mines of copper and turquoise are said to exist, but the expense of working them exceeds their income.

Mathura (Muttra) is a city on the banks of the *Jumna* : it contains some fine temples, and is one of the most famous of Hindu shrines. *Kālpi* is a town on the banks of the *Jumna*. It is the resting-place of many saintly personages. Excellent sugarcandy is here manufactured. In the time of the *Sharqi* princes, it was tributary to Delhi. When Qādir Khān affecting the airs of sovereignty proclaimed his independence, Sultān Hoshang marched from Mālwah and having chastised him, reinstated him in the government. Sultān Muḥmud of the *Sharqi* dynasty, however, seized it in turn from Nasir Khān, the son of Qādir Khān.

Kanauj was in ancient times the capital of Hindustān.

Gwalior is a famous fortress and an elephant carved in stone at its gate fills the beholder with astonishment. It contains some stately edifices of its former rulers. Its climate is good. It has always been noted for its exquisite singers* and lovely women : here is an iron mine.

Alwar (Ulwar) produces glass and woollen carpets.

Bairāt possesses a copper mine, so profitable that from a *man* weight of ore, they obtain 35 *sers* of metal. A silver mine is also said to exist but it does not pay to work it. [A dependency of Narnol, but now in Jaipur.]

Near the hill of *Nārnol* is a well at which the Hindus worship and when the *tithi* of *Amāwas* falls on a Friday,

* According to the *S. ul M.* the famous Tānsen was one of these. See Vol. I, pp. 611 of the *Āin*.

it overflows at sunrise and water can be drawn without the aid of a rope.

At *Singhānah*, *Udaipur* and *Kotputli* are mines of copper. In the town of *Kānori* are many cold and hot springs.

The *Subah* contains thirteen *Sarkārs*, two hundred and three *Parganahs* (fiscal subdivisions). The measured lands are 2 *krors*, 78 *lakhs*, 62,189 *bighas*, 18 *biswas*. The revenue is 54 *krors*, 62 *lakhs*, 50,304 *dāms*. (Rs. 13,656,257-9-6). Of this, 1 *kror*, 21 *lakhs*, 5,703½ *dāms* (Rs. 302,642-9) are *Suyurghāl*. The provincial force consists of 50,681 cavalry, 577,570 Infantry and 221 elephants.

Sarkār of Agra.

Containing 33 *Mahals*, 91,007,324 *Bighas*. Revenue 191,819,265, *Dāms* in money. *Suyurghāl* 14,566,818 *Dāms*. Castes various. Cavalry 15,560. Infantry 100,800.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Agra with suburban district	891,990-5	44,956,458	8,824,454	3000	1,5000	...	Gaur,* Jat, Lodh, &c.
Etāwan, has brick fort on the Jamna	284,106	10,739,325	151,362	2000	1,5000	...	Chauhān, Bhadauriya, Brāhman
O'l [=Alo, near Dig.]	159,377-9	5,509,477	81,542	1000	1000	...	Rājput, Brāhman
Oudehi, (Elliot Odhi)	274,067	2,884,365	78,165	20	500	...	Rājput, Brāhman, &c.
Ud [Udai]	203,505	1,003,848	36,870	100	500	...	Shaikhzādah
Bijwārah has a stone fort	663,236	10,966,560	...	1500	5000
✓ Bānah with suburban dist. has a stone fort	235,442	7,110,104	562,205	50	100	...	Ahir, Jat
Bāri	276,964	5,064,158	57,414	300	7000	...	Rājput, Panwār
Bhosāwar	303,509	5,505,460	255,460	50	1500	...	Rājput of various castes
Banāwar [?Bhandor]	12,880	155,360	...	30	400	...	Bargujar

* A Surajbansi tribe of Rajputs. *Lodh*, a widely spread tribe, chiefly fishermen. *Bhadauriya* is a branch of the Chauhan Rājputs. For *Oudehi* I suggest *Uchen* and for *Bhaskar* either *Pahsar* or *Bisawar*. [J. S.]

Sarkār of Agra—(contd.)

		Bighas, Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Todah Bhim	264,103-11	3,737,075	13,361	100	1000	...	Rājput, Thattar ¹
Bhaskar	43,009	2,891,100	15,325	20	700	...	Rājput, Brāhman, Ahir
Jalesar, has a brick fort	904,733	6,835,400	412,080	400	5000	...	Ghelot, Suraj Bānkrah
Chandwar, has a brick fort on the Jamna	407,652	11,442,250	60,342	200	7000	...	Chauhān
Chausath [Chau- mulah]	974,34	4,182,048	674,315	50	1000	...	Rājput, Brāhman, Jat, Ahir
Khānwah	5,334	2 912,495	222,628	30	4000	...	Rājput, Jat
Pholpur, has a brick fort on the Cham- bal	284,087	9,729,311	255,747	200	4000	...	Sikarwār ²
Rāpri, has a brick fort	477,201-11	13,508,035	173,407	200	4000	...	Chauhān, descen- dants of Rāwat- Bāhan
Rajhohar [?Raja- khera]	318 285	1,694,208	48,023	20	300	...	Rājput
Songar Songri	90,599	985,700	7,822	70	500	...	Rājput, Chauhān
Fatchpur, has a stone fort	202,723-17	8,494,005	597,346	500	4000	...	Shāikhzādah, Chishti, Rājput, Sankarwāl
Kotumbar	96,760	745,951	...	50	300	...	Rājput, Jat
Mahāwan, has a brick fort	290,703	6,784,780	284,787	200	2000	...	Sayyid, Brāhman
Mathurā, do.	37,347	1,155,807	69,770
Maholi	66,690	1,501,246	...	30	500	...	Rājput, &c.
Mangotlah [Mang- tai]	74 974	1,148,075	79,355	20	400	...	Do.
Mandāwar	10 190	132 500	...	150	800	...	Chauhān
Wazirpur	71,328	2,009 255	9,255	20	300	...	Rājput
Hindaun	482,930	9,049,831	301,980	100	1000	...	Rājput, Brāhman, Jat
Hatkānt, has a brick fort	606,991-12	5,693,807	43,231	2000	20,000	...	Chauhān, Bhadauriya
Hilak	137,421	2,789,494	30,531	20	500	...	Rājput of various castes.

¹ Gujars converted to Islam. Elliot, I, 101.² Sikarwār, a branch of the Bargujar Rajputs.

Sarkār of Kālpi.

Containing 16 *Mahals*, 300,023 *Bighas*, 9 *Biswas*, Revenue, 49,356,732 *Dāms* in money. *Suyurghāl* 278,290½ *Dāms*. Castes various, Cavalry 1,540. Elephants 30. Infantry 34,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
U'lai [? Urai] ..	95 677-18	1 297,379	72 213	20	500	...	Rājput
Bilāspur ..	126 888-14	3,714,547	13 110	103	50 000	...	Kachhwāh
Bhudekh ..	72 930-14	1 260,199	3 414	50	2000	...	Shaikhzādah
Derāpur ..	103,085	1,760 750	4 221	50	2000	...	Brāhman
Deokali [?Churki] ..	103,652	1 466,985	1 700	200	2000	10	Brāhman
Rāth, has a brick fort	510,970-16	9,270,894	270,894	70	3000	9	Afghan, Tur- koman
Rāepnr	43,166-8	120,000	500	10	Rājput,
Suganpur [?Jagmanp]	...	1,507,877	58 664	60	1000	...	Rājput, Bais
Shāhpur	8,848,420	245,747	300	3000	6	Chauhān, Malikzādah
Kālpi, with suburban district	4,871,053	203,909	4000	5000	10	Various
Kanār [? Karmār]	4,943,096	6,085	100	2000	1	Sengar*
Chandaut	3,027,917	27,121	50	4000	...	Parihār
Khandelal, (Elliot Khurela) ..	86,053-11	871,733	15,008	20	1000	...	Rājput
Muhammadābād ..	184,080	1,617,257	4,260½	50	1000	...	Rājput Kumbi
Hamirpur ..	404,797-6	4,803,828	182,245	200	2000	...	Kumbi

Sarkār of Kanauj.

Containing 30 *Mahals*, 2,776,673 *Bighas*, 16 *Biswas*. Revenue 52,584,624 *Dāms*. *Suyurghāl*, 1,184,655 *Dāms*. Castes various. Cavalry 3,765. Infantry 78,350.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bhongāon, has a fort and near it a tank called Somnāt full of water extremely sweet	337,105	4,577,010	53 316	1000	10,000	...	Chauhān
Bhojpur ..	150,974-13	3,446 737	104 705	150	3000	...	Kharwār
Tālgrāon ..	74,100-10	3,387,076	128,558	20	1000	...	Rājput, Mussalmān

* Sengar, a branch of the Agnibansi Rājputs.

Sarkār of Kanauj—(Contd.)

			Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bithur	175,042-11	2,921,389	...	300	5000	...	Chandel
Bilhaur	63,773-14	2,828,347	216,741	20	1000	...	Rājput
Patīāli	158,634-14	1,877,600	45,656	100	2000	...	Rājput, Chauhān
Pati Alipur	38,418-11	1,153,682	8,060	20	500	...	Rājput
Pati Nakhat [?Agath]	49,261-18	566,997	2,497	50	500	...	Sengar
Barnah	34,736-14	450,000	...	10	200	...	Rājput of various castes
Bārā	8,739-14	400,000	...	10	300	...	Chauhān
Phapund	111,546	5,482,391	19,913	300	2000	...	Sengar
Chhabrāman	76,318-7	1,522,028	22,128	20	500	...	Rājput, Chauhān
Deolā	11,950-12	483,171	79,045	20	300	...	Chauhān Bais, Dhā- kar ¹
Saket	132,955-9	3,230,752	158,310	100	3000	...	Chauhān
Sonj [=Sonkh]	64,070-6	1,200,000	...	200	3000	...	Dhākar
Sahāwar	78,574-9	252,245	21,969	20	500	...	Gāurua ²
Sheoli	12,523	623,473	...	10	300	...	Rājput
Sakatpur	22,561	628,441	...	300	4000	...	Rājput, Bais
Sakrāon	19,817-10	549,050	2,253	10	500	...	Rājput
Sahār	25,195-8	846,553	1,640	30	500	...	Chauhān,
Saurikh	10,089-5	465,328	7,138	20	400	..	Chauhān, Dhākar
Sikandrapur Udhu	4,964-14	276,918½	22,624	10	200	...	Gauruah, Brāhman
Saror [Barour]	20,121-16	447,563	2,044½	10	800	...	Chauhān, Sengar
Sikandarpur Atreji	36,084-17	269,622	6,511	5	150	...	Rājput
Shamsābād, has a fort on the Ganges	718,577-7	7,138,452	19,603	400	2000	...	Rāthor
Kanauj, with suburb. dist. has a brick fort : one of the great capi- tals of Hindustān	126,255-12	2,470,743	222,036	200	10,000	...	Shaikhzādah, Farnuli, Afghān, Chauhān
Kampil	139,803-6	1,651,586	30,370	100	200	:	Rājput, Chauhān, Panwār
Kurāoli	40,445-6	1,409,988	...	20	1000	...	Rājput
Malkusali	30,229-14	1,500,000	...	300	15,000	...	Rājput, Ghe- lot
Nānūman ³	3,329-5	136,921	...	200	200	...	Rājput, Brāhman

¹ Dhākar, a Rajput tribe scattered over Agra, Mathura, Etāwa and Rohilkhand. Elliot, I. 78.

² Gauruah, an inferior clan of Rājputs often confounded with Gaurāhars but quite distinct. Elliot, I. 115.

Sarkār of Kol, (Koil).

Containing 21 Mahals, 2,461,730 Bighas. Revenue 54,992,940 Dāms in money, Suyurghāl 2,094,840 Dāms. Castes various. Cavalry 4,035. Infantry 78,950.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Atrauli	320,569	5,454,459	5400,459	500	9500	...	Rājput, Chauhān, Afghān
Akbarābād	118,389	3,003,409	23,060	500	5000	...	Rājput, Pun- dir ¹
Abār, has a brick fort on the Ganges	45,764	2,106,554	87,140	20	400	...	Musalmān, Brāhman
Pahāsu	55 060	2 502,562	...	100	2000	...	Bargujar
Bilrāon	111,878	2,131,765	56,561	50	1000	...	Afghān Chauhān
Pachlānā	39,128	624,825	...	200	5000	...	Rajput, Gaurāhar Chauhān
Tappal, has a brick fort Thānah Fāridā [=Pharihā]	163,046	1,802,571	2,571	100	8000	...	Rajput, Bāchhal
Jalālī	145,801	2,957,910	86,352	500	6000	...	Rājput, Pun- dir
Chandaus	42,469	1,749,238	36,662	100	2000	...	Chauhān
Khurjah	89,726	3,703,020	583,056	200	5000	...	Bargujar
Dibhāi, has a brick fort	48 539	2,169,939	72,869	50	1000	...	Do.
Sikandrah Rāo, has a brick fort	83,480	4,412,331	290,458	400	4000	...	Afghān, Pundir
Soron, has a brick fort	40,656	875,016	16,900	20	400	...	Sayyid, Rāj- put
Sidhupur	70,567	989,458	...	200	2500	...	Rājput Surki
Shikārpur	44,830	1,974,827	50,291	250	2000	...	Sayyid, Shaikh zādah, Bargujar
Kol, has a brick fort ..	548,655	10,412,305	445	450	29,050	...	Chauhān, Janghārāh ²
Gangeri	53,545	372,050	31,849	25	200	...	Afghān, Rājput
Marabrah	205 537	3 679 582	156 095	200	2000	...	Chauhān
Malakpur	30,845	1,446,132	2,288	50	400	...	Pundir, Chauhān
Nuh, has a brick fort, (Elliot, Noh)	139,299	1,311,955	29,160	100	3000	...	Rājput, Jat, Afghān

¹ Pundir is one of the numerous branches of the Gujar clan. Elliot, I. 19.

² A turbulent tribe of Rājputs of the Tuar clan in the S. E. Rohilkhand. Elliot, I. 141.

Sarkār of Gwālīor.

Containing 13 *Mahals*, 1,146,465 *Bighas*, 6 *Biswas*.
 Revenue 29,683,649 *Dāms* in money. *Suyurghāl* 240,350
Dāms. Castes various. Cavalry 2,490. Infantry 43,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Anhon, has a fort ..	106 899-14	2,277,947	...	200	4000	...	Tonwar
Badrhattah, Do. ..	63,914-18	696,800	...	300	5000	...	Do., Rāj- put
Chinaur Do. ..	140 140-16	1,051 341	35,930	100	4000	...	Brāhman
Jhalodā [Jakhoda] fort	32 677-15	219 306	...	100	2000	...	Gujar
Dandrolī ..	197,316-11	1,807,207	...	50	1000	...	Rājput Ton- war
Rāepur ..	87 797-17	1,017 721	...	40	700	...	Tonwar
Sirseni [Sirsi] ..	94 243	832 128	...	200	5000	...	Sikarwāl
Samauli [Silauli] ..	46,284-8	2,001,344	...	50	700	...	Bāgri
Sarbandah, has a brick fort ..	22,124-17	267,497	...	200	6000	...	Sikarwāl
Alāpur, has a fort; during Sultān Alā- uddin's time it was called Akhār ¹ ..	211,229	5,128,766	...	50	500	...	Brāhman
Gwālīor with suburban district ..	345,657	12,488,072	188,740	1000	2000	...	Rājput, Ton- war
Khatoli, has a fort ..	198,270	3,105,315	6,450	200	4000	...	Jat

Sarkār of Irij.

Containing 16 *Mahals*, 2,202,124 *Bighas*, 18 *Biswas*.
 Revenue 37,780,421 *Dāms* in money. *Suyurghāl* 456,493
Dāms. Castes various. Cavalry 6,160. Elephants 190.
 Infantry 68,500.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Irij ..	625,597	2,922,436 in money.	101,661	100	5000	10	Kāyath
Parhār, ² has a brick fort ..	752,791	5,237,096	172,380	940	20500	59	Rājput
Uhānder ..	257 042-18	2,533,449	100,638	50	2000	5	Afghān, Kāyath
Bijpur [Bijawar] ..	30,635	1,391,097	...	3000	5000	...	Tanwar
Pāndor [Pandwaha] ..	8,951	464 111	...	100	2000	5	Parihār

¹ Var. Akhar, Kahār, Sahār.

² Probably Panwāri.

Sarkār of Irij—(contd.)

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Jhatra, 4 mahals, has a brick fort	11,787,904	...	4000	15000	70	Rājput
Riābānah ¹ , has a fort ..	12,072	500,000	...	50	2000	...	Kachhwā- hah
Shāhzādapur	21,257	450,781
Khatolah &c. 3 mahals, has a fort	3,000,000	...	100	5000	20	Gond
Kajhodah [?Gahrauli]	...	750,200
Kidār	120,000
Kunch, has a fort ..	155,320	1,851,802	27,712	50	2000	...	Kumbi
Klinkes, ² has a fort ..	89,233	1,343,073	7,673	50	1000	...	Kachhwā- hah
Kānti	240,000	...	20	5000	10	Gond
Khāerah, [Khārela] has a brick fort ..	222,557	4,776,357	46,729	200	5000	10	Kachhwā- hah
Maholi	26,581	502,102	...	100	10000	10	Parihār

Sarkār of Bayānwān.

Containing 27 Mahals, 762,014 Bighas. Revenue 8,459,296 Dāms. Suyurghāl 82,662 Dāms. Castes various. Cavalry 1,105. Infantry 18,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Antri, yields excellent quality of betel leaf from which the reve- nue is chiefly derived	906,140	10	100	...	Various
Amwāri [Amola] ..	223,000	Entered under Ratanagarh.	200	...	Mārwar Gauruah
Atiwan [Araon] ..	35,958	165,165	54,114	15	200	...	Gond, Gauruah
Autelah	29,444	32,455	1,257	...	100	...	Brāhman
Bayānwān	86,241	801,275	20,169	320	3000	...	Pundir, Pan- wār
Banwūr	17,329	457,439	6,558	20	300	...	Brāhman, Khidma- tiyah
Parānchah [Paraich] ..	89,784	396,193	21,541	20	500	...	Bundela

¹ Riābānah = ? *Rebai* of map.² Kedpur.³ Khankes. Khakesh. Ganges. Khaksen.

Sarkār of Bayānwān—(contd.)

	Bighas Biswas	Revenue D.	Suynr- ghāl D.	Cavalry	Infantry	Elephants	Castes
Badnun [Bardūn]	275,000	...	10	200	...	Bundela
Bhāsandā	169,040	...	10	300	...	Panwar
Chinaur, has a fort ..	50,973	548,631	3,800	10	200	...	Ahir, Brāh- man
Jarhali ..	19,865	144,055	...	10	800	...	Panwār
Jagtān [?=Jignā]	128,680	150	...	Various
Dahāilah,* here a large lake, full of water- lilies ..	13,127	17,306	...	20	350	...	Brahmān, Gujar
Ruchādah [Ruchera] ..	94,223	472,839	15,702	10	200	...	Kāyath, Brāhman
Ratangarh, has a fort	70,523	855,995	...	200	4000	...	Jat
Roherah ..	2,309	1,017,682	...	50	500	...	Gujar
Sohandi, has a brick fort [? Suchendi] ..	81,655	896,959	...	800	5000	...	Panwār
Kanaulah [Karaia] ..	11,764	364,968	...	10	200	...	Gujar, Jat
Karharah	277,000	Mentioned under Ratan- garh
Kaheod,† has a fort in the mountains ..	27,290	196,804	200	...	Brāhman
Khandhā ..	17,403	162,661	3,036	...	200	...	Ahir, Jat
Khand Bajrah the greater ..	33,782	138,934	...	25	300	...	Bundela, Jat
Do. the lesser ..	1,602	68,470	...	10	200	...	Mīnā, Gujar
Kherihāt ..	24,318	112,079	800	...	Do.
Kajbūrah, has a stone fort on a hill ..	17,269	82,291	...	5	300	...	Gujar
Kadwāhah ..	7,169	43,296	...	50	300	...	Ahir
Mau, has a fort ..	59,070	850,429	5,189	50	1000	...	Ahir

* *Dahāilah* [Ind. Atlas. 51 S.E.], 16 m. due east of Narwar, on the way to Antri, has a very large lake. It was 2 miles to the west of this place, according to T. that Abul Fazl lost his life in the ambushade set for him by the Bundelā Chief Bir Sing. *Dabra* in the maps 13 miles south of Antri and 42 m. n. of Jhansi, has no lake, and cannot be this mahal.

† Prob. *Kāmōd* of map.

Sarkār of Narwar.

Containing 5 *Mahals*, 394,353 *Bighas*. Revenue 4,233,322 *Dāms*. *Suyurghāl* 95,994 *Dāms*. Castes, Rajput Tonwar. Cavalry, 500. Infantry, 20,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Baroi, has a fort; some of the villages near the Saklā are of great productive value	88,085	638,700
Bauli (? Paori), has a fort on the Saklā ..	242,456	141,915
Seopuri, has a stone fort	24,975	1,250,000
Kolāras has 2 forts, one near the village of Barwā. There is a small hill with a waterfall. It is a place of Hindu worship	133,10	764,880	14,882
Narwar with suburb. dist. has a stone fort. In certain parts of the fort are ancient Hindu temples of stone	25,522	438,025	81,312

Sarkār of Mandrāel.

Containing 14 *Mahals*. 65,642 *Bighas*. Revenue 3,738,084 *Dāms*. Castes Rājput, Jādon. Cavalry 4,000. Infantry 5,000.

	Bighas Biswas	Revenue D.		Bighas Biswas	Revenue D.
Untgar, has a stone fort on a hill and below it flows the river Chambal ..	7,674	498,978	Dungri	902	54,126
Bijapur	6,413	359,706	Ratanbalāhar	1,215	82,098
Balāoli	6,866	324,091	Samarthalah	9,160	526,380
Bakhar (=Manākhur) ..	4,382	261,746	Kamukherah	1,938	116,168*
Baground	Kharnun	820	54,074
Jhakwār (=Jakoda) ..	769	38,498	Kahtoni	1,925	51,944
Dāng Makhori	7,812	493,978	Mandrāel, has a fort on a hill and the river Chambal on the north	15,745	697,794

* Var. 1310 and 764,380 for the area and revenue.

Sarkār of Alwar.

Containing 43 *Mahals*, 16,62,012 *Bighas*. Revenue 39,832,204 *Dāms*. *Suyurghāl* 699,212 *Dāms*. Cavalry 6,504. Infantry 42,020.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Alwar, has a stone fort on a hill	85,084	2,679,820	350 056	10	1,500	...	Khānzādah of Mewāt, des- cendants of Bahādūr Khān
Anthlah Bhābru ..	24,956	850,731	...	20	500	...	Kachhwāhah
Umran	39,762	642,153	1,043	20	1,000	...	Baqqāl
Ismāilpur	28,988	503,840	2,266	40	500	...	Khānzādah of Mewāt
Bairāt, has a stone fort (Parāt, p. 103) ..	23,522	7,201,791	1,796	50	1,000	...	Baqqāl
Bihrozpur	119,015	2,621,958	9,317	350	2,000	...	Khānzādah of
Bahādūrpur	60,451	1,950,000	95,000	500	2,000	...	Mewāt
Bharkol	74,281	678,733	...	50	1,000	...	Do. Do.
Balhār (? Bairohar) ..	58,654	443,612	...	40	500	...	Do. Do.
Barodah Fateh Khān ..	16,074	201,059	1,059	30	300	...	Bargujar, Rājput
Panāin	28,726	195,680	...	5	50	...	Mewāt
Baroda [Bagar] Meo ..	13,062	158,045	619	50	300	...	Khānzādah o Khānzādah and Meo.
Bhudah Thal	80,606	146,000	...	5	50	...	Do.
Bhiwāi	14,918	122,088	...	5	50	...	Various
Basānah (= Baswa) ..	20,789	100,356	...	5	50	...	Do.
Bajherah	2,663	104,890	...	10	50	...	Khānzādah and Meo.
Balheri (Bālhatah) ..	6,565	188,507	...	30	500	...	Bargujar
Jalālpur	46,840	893,599	10,665	Khānzādah and Meo.
Hasanpur Badohar ..	20,353	947,871	3,020	100	300	...	Do.
Hasanpur Kori, (Gori) Hājipur, has a stone fort	47,740	1,259,659	...	120	300	...	Do.
Deoli Sājari	26,489	456,779	3,120	500	1,000	...	Chauhān
Dadekar	83,188	1,600,000	...	150	1,000	...	Bargujar
	27,051	695,262	7,312	150	1,000	...	Meo.

¹ Mentioned in Elliot as in ancient times a well-known lawless plundering race, driven out of the Etawah tract by the Senghers and Chauhāns. According to Sherring (III, 90) they are an indigenous tribe converted to Islām, but retaining a good many Hindu customs; now an agricultural people divided into 12 clans.

Sarkār of Akwar—(contd.)

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Caste:
Dharā	12,338	512,613	5,015	100	508	...	Khānzādah and Meo.
Rāth	6,030	229,741	3,744	10	100	...	Meo.
Sakhān	18,790	804,262	...	100	700	...	Chauhān
Khohari Rana ..	2,208	4,359,272	96,919	900	5,000	...	Khānzādah of Mewāt, A'mā and Duar (obscure text)
Khelohai	58,276	1,459,048	14,088	125	1,000	...	Meo
Kol [= Gol] Dhoār ..	33,956	627,100	...	30	500	...	Rājput
Kiyārah	307	600,000	...	100	1,000	...	Mīnā
Khīrali	26,746	465,640	23,150	100	500	...	Sayyid, Gu- jar
Ghāt Sudan (or Seon) has a fort	16,494	357,110	
Kohrānā [= Ghos-rana]	3,565	166,666	...	300	1,000	...	Māhat (?)
Mandāwar, has a brick fort	100,322	1,889,097	5,608	500	1,000	...	Chauhān
Manjpur	44,140	639,858	12,022	300	500	...	Abbāsi
Mubārakpur [Mārakpur]	18,636	514,193	...	50	300	...	Khānzādah
Mongonā [Mangwar] ..	38,112	475,260	...	100	700	...	Do.
Mandāwar	17,800	27,051	...	4	20	...	Chauhān
Naugāon (Nowgong) ..	23,771	2,056,512	34,296	70	500	...	Khānzādah
Nāhargarh	35,452	604,194	...	20	200	...	Do.
Harsoli	11,800	227,096	...	10	100	...	Meo
Harpur	16,944	686,605	3,255	20	4,000	...	Jat
Harsānā	4,025	208,281	...	40	500	...	Meo

Sarkār of Tijārah.

Containing 18 Mahals. 740,001 Bighahs. $5\frac{1}{2}$ Biswas.
 Revenue 17,700,460 Dāms. Suyurghāl 701,761 $\frac{1}{2}$. Cavalry
 1,227. Infantry 9,650.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Indri, has fort on a hill	134,150	1,995,216	26,096	400	3,000	...	Khānzādah of Mewat
Ujinali [Uchaira] ..	33,926	428,347	22,796	45	150	...	Khānzādah, Thathar

Sarkār of Tijārah—(contd.)

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Umri	8,107	307,037	...	10	100	...	Thathar, Meo
Bisru	35,703	215,800	5,354	10	200	...	Khānzādah, Meo
Par	2,476	540,645	1,559	10	200	...	Thathar
Pinangwān, has a stone fort	75,148	1,329,350	34,312	20	300	...	Meo
Bhasohrā, has stone fort	57,778	1,416,715	25,471	30	400	...	Do.
Tijārah, has a fort ..	131,960	3,603,596	204,419	500	2,000	...	Do.
Jhimrāwat, has a stone fort on a hill ..	22,632-11	496,202½	31,283½	50	300	...	Do.
Khānpur	9,893	195,620	...	20	150	...	Do.
Sākras	12,106	460,088	50,411	14	150	...	Do.
Sānthādāri	7,712-11	406,811	267,470	200	Do.
Firozpur, situated on the skirt of a hill in which there is an ever-flowing fountain with an image of Mahadeo set up; a Hindu Shrine ..	64,150	3,042,612	69,014	50	1,000	...	Do.
Fatehpur Mungartā ..	43,700	1,135,140	12,955	10	200	...	Do.
Kotlāh, has a brick fort on a hill on which there is a reservoir 4 kos in circumference	71,265	1,552,196	7,017	30	700	...	Khānzādah, Gujar
Karherah, (Ghāserah, Elliot)	9,785	330,076	...	10	200	...	Meo
Khora ka Thānah. So in MSS., but Elliot Khawā)	7,945	168,719	...	10	250	...	Do.
Naginān [Noganwa] ..	7,215-19	377,257	3,572	100	150	...	Do.

Sarkār of Nārhol.

Containing 16 Mahals. 2,080,046 Bighas. Revenue 50,046,703 Dāms. Suyurghāl 775,103 Dāms. Castes various. Cavalry 7,520. Infantry 37,220.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bārhi	146,754	2,060,662	...	100	1,000	...	Chauhān, Rājput, Musalmān, Khandār. (Var. Ke- dār).

Sarkār of Nārnol—(contd.)

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bābāi, has a stone fort and a coppermine; hills adjacent ..	78,426	920,170	...	400	3,000	...	Parihār.
Barodah [Bahora] Rāna	47,266	592,995	...	300	2,000	...	Chauhān.
Chālkaliānah	517,540	7,744,027	56,164	200	5,000	...	Jat of the Sangwān clan.
Jhojeun [Jhajlai], has a stone fort on the skirt of a hill ..	95,331	2,329,069	...	2000	3,000	...	Kiyām- Khāni.*
Singhānah Udaipur, has a coppermine and mint for copper coin- age	11,881,629 in money.	3,351	400	1,000	...	Tonwar, Parihār.
Kānodah, in the village of Zerpur in this Par- ganah, a large Hindu temple	10,723	4,356,189	91,577	1000	4,000	...	Rājput, Mu- salmān, Hālu. [Jat]
Kōtputli, has a stone fort and in the village of Bhandhārah is a copper mine in work- ing	170,674	4,266,837	29,425	700	4,000	...	Tonwār Rāj- put, Gond.
Kanori [?Kanti], has 3 forts in three villages	150,297	2,721,126	...	1000	5,000	...	Tonwār.
Khandelā	1,300,000 in money.	...	200	2,000	...	Rājput, Kachhwā- hah.
Khodāna [or Konodana] Lapoti [=Pataudi] ..	18,493 88,281	808,109 1,512,470	...	20 100	700 500	...	Jat. Chanhān.
Villages at the foot of the mountain where is a copper mine. In that of Rāepore is a copper mine and a mint and the stream there is polluted by it	176,650	274,350	...	100	2,000	...	Narbān.
Nārnol, has a stone fort	214,218	5,913,228	549,161	500	2,000	...	[Chauhan]
Narhar [?Narera] do. ..	356,293	4,262,837	29,405	500	2,000	...	Ahīr. Kiām Khāni, Afghan, Mākar. (?)

* Called Kāim Khāni by Elliot and Sherring. They are Chauhāns converted to Islam. Their ancestors fought against Bāber in 1528.

Sarkār of Sahār.

Containing 7 *Mahals*. 763,474 *Bighas*. Revenue 5,917,569 *Dāms*. *Suyurghāl* 109,447 *Dāms*. Castes various. Cavalry 265. Infantry 1,000.

	Bighas Biswas	Revenue D.	<i>Suyurghāl</i> D.	Cavalry	Infantry	Elephants	Castes
Pahāri	106,422	1,228,999	26,045	20	700	...	Meo, Thathar
Bandhanli	25,980	441,840	6,840	10	300	...	Jat &c.
Sahār, has a fort ..	385,895	2,489,816	21,678	200	7,000	...	Bāchhal, Gujar, Jat, Kachhwā- hah.
Kāmah	90,500	505,724	1,229	10	300	...	Meo, Jat Ahir
Koh Mujāhid [Q. Kho]	23,769	170,365	...	4	200	...	Meo, Jat,
Nunherah	50,816	618,115	17,515	Ahir, Jat, Meo
Hodal	78,500	462,710	33,140	10	200	...	Jat &c.

THE SUBAH OF MĀLWA.

It is situated in the second climate. Its length from the extreme point of *Garha* (*Māndla*) to *Bānswārah* is 245 *kos*. Its breadth from *Chanderi* to *Nandarbār* is 230 *kos*. To the east lies *Bāndhun* [*Rewa*]; to the north *Narwar*; to the south *Baglānah*; to the west *Gujarāt* and *Ajmer*. There are mountains to the south. Its principal rivers are the *Narbadah*, the *Siprā*, the *Kālī Sind*, the *Betrwa*, and the *Godī*.* At every two or three *kos* clear and limpid streams are met on whose banks the willow grows wild, and the hyacinth and fragrant flowers of many hues, amid the abundant shade of trees. Lakes and green meads are frequent and stately palaces and fair country homes breathe tales of fairyland. The climate is so temperate that in winter there is little need of warm clothing, nor in summer of the cooling properties of saltpetre. The elevation of this province is somewhat above that of other areas of the country and every part of it is cultivable. Both harvests

* The *Godī* is a tributary of the *Narmada*.

are excellent, and especially wheat, poppy, sugarcane, mangoes, melons and grapes. In *Hāsīlpur* the vine bears twice in the year, and betel leaves are of fine quality. Cloth of the best texture is here woven. High and low give opium to their children up to the age of three years. The peasants and even grain dealers are never without arms. *Ujjain* is a large city on the banks of the *Sipra*. It is regarded as a place of great sanctity and wonderful to relate, at times the river flows in waves of milk. The people prepare vessels and make use of it, and such an occurrence brings good fortune to the reigning monarch.

In the 43rd year of the Divine Era when the writer of this work was proceeding to the Deccan by command of his Majesty, a week before his arrival at *Ujjain*, on the 16th of the Divine month of *Farwardin* (March) four *gharis* of the night having elapsed, this flow occurred, and all conditions of people, Musalman and Hindu alike talked of it.*

In the neighbourhood are 360 places of religious worship for Brāhmans and other Hindus. Close to this city is a place called *Kāliyādah*, an extremely agreeable residence where there is a reservoir continually overflowing yet ever full. Around it are some graceful summer dwellings, the monuments of a past age.

Garha† is a separate State, abounding with forests in which are numerous wild elephants. The cultivators pay the revenue in mohurs and elephants. Its produce is sufficient to supply fully both *Gujarāt* and the Deccan.

Chanderi was one of the largest of ancient cities and possesses a stone fort. It contains 14,000 stone houses, 384 markets, 360 spacious caravanserais and 12,000 mosques.

Tumun is a village on the river *Betba* (*Betwā*) in which mermen are seen. There is also a large temple in which if a drum is beaten, no sound is heard without.

In the *Sarkār* of *Bijāgarh* there are herds of wild

* Another reading adopted by Gladwin is "partook of it." Gladwin while rejecting this fable, suggests a sudden impregnation of the river with chalk.

† It was the ancient capital of the Gond Dynasty of *Garha Mandla* and its ruined keep known as the *Madan Mahal* still crowns the granite range along the foot of which the town stretches for about 2 miles. I, G.

elephants. *Mandu* is a large city; the circumference of its fort is 12 *kos*, and in it there is an octagonal tower. For some period it was the seat of government and stately edifices still recall their ancient lords. Here are the tombs of the Khilji Sultāns. A remarkable fact is that in summer time water trickles from the domed roof of the mausoleum of Sultān Hoshang and the simpleminded have long regarded it as a prodigy, but the more acute of understanding can satisfactorily account for it. Here the tamarind grows as large as a cocoanut and its kernel is extremely white.

Learned Hindus assert that a stone is met with in this country which when touched by any malleable metal turns it into gold, and they call it *Pāras*. They relate that before the time of Bikramājī, there reigned a just prince named Rājā Jai Sing Deva who passed his life in deeds of beneficence. Such a stone was discovered in that age, and became the source of vast wealth. The sickle of a straw cutter by its action was changed into gold. The man, not understanding the cause, thought that some damage had occurred to it. He took it to a blacksmith by name Māndan to have it remedied, who divining its properties, took possession of it, and amassing immense wealth, garnered a store of delights. But his natural beneficence suggested to him that such a priceless treasure was more fitted for the reigning prince, and going to court he presented it. The Rājā made it the occasion of many good deeds, and by means of the riches he acquired, completed this fort in twelve years, and at the request of the blacksmith, the greater number of the stones with which it was built, were shaped like an anvil. One day he had a festival on the banks of the Narbadah, and promised to bestow a considerable fortune on his Brāhman priest. As he had somewhat withdrawn his heart from worldly goods, he presented him with this stone. The Brāhman from ignorance and meanness of soul, became indignant and threw the precious treasure into the river to his subsequent and eternal regret. Its depth there prevented his recovering it, and to this day that part of the river has never been fathomed.

Dhār is a town which was the capital of Rājā Bhoja and many ancient princes. The vine here bears twice in the year when the sun first enters Pisces (February) and Leo (July), but the former of these two vintages is the sweeter.

In the Sarkār of *Handiah* are numerous wild elephants.

In *Nandurbār* good grapes and melons are obtainable.

This *Subah* contains 12 *Sarkārs*, subdivided into 301 *Parganahs*. The measured land is 42 lakhs, 66,221 *Bighas*, 6 *Biswas*. The gross revenue is 24 krs, 6 lakhs, 95,052 *Dāms*. (Rs. 6,017,376,-4-15). Of this 11 lakhs, 50,433 *Dāms* (Rs. 28,760-13) are *Suyurghāl*. The Provincial force consists of 29,668 Cavalry, 470,361 Infantry and 90 Elephants.

Sarkār of Ujjain.

Containing 10 *Mahals*. 925,622 *Bighas*. Revenue 43,827,960 *Dāms* in money. *Suyurghāl*, 281,816 *Dāms*. Castes various. Cavalry 3,250. Infantry 11,170.

	Bighas Biswas	Revenue D.	<i>Suyurghāl</i> D.	Cavalry	Infantry	Elephants	Castes
Ujjain with suburban district, has fort of stone below and of brick above ..	269,660	1,868,035	55,323	760	2,000	...	Ujjainia, Rāthor
Unhel ..	56,841	2,801,972	20,935	130	500	...	Rājput, Ujjainia, Dhakarali
Badhnāwar has a stone fort ..	60,096	8,056 195	1,095	500	3,000	...	Rāthor, &c.
Pānbihār ..	36,567	1,837 596	29,400	100	500	...	Ujjainia
Dipālpur ..	95,706	6,000,000	...	500	1,000	...	Rājput, Ujjainia
Ratlām ..	94,466	4,421,540	21,548	500	1,000	...	Rājput Meh- tar, Soriali
Sānwer ..	46,694	2,418,375	133,156	150	300	...	Rājput, Magwar
Kampil has a fort partly stone, partly brick	59 802	2,907,817	2,344	150	400	...	Rājput
Khāchrod ..	66,626	2,651,044	...	60	1,200	...	Rājput, Deora [Chauhan], Dharar or Dhur (?)
Nolāi has a brick fort on the banks of the Chambal [? Naulāna]	120,264	3,851,886	18,015	400	1,200	...	Bais, Jādon, (Yadu)

Sarkār of Rāisin.

	Bighas Biswas	Revenue D.	Suyurgāl D.	Cavalry	Infantry	Elephants	Castes
Asapuri &c. 6 <i>Mahals</i> ..	3,238	...	173,064	170	945	...	Rājput
Bhilsah ..	40,816	6,094,970	...	480	1,000	...	
Bhori (? Bamari) ..	5,970	316,017	100	...	
Bhojpur ..	4,097	220,592	...	115	1,000	...	Rājput
Bālābahat	215 122	...	265	500	...	
Thānah Mir Khān	735,315	...	200	500	...	
Jājoi (Khajuri ?)	215,122	...	15	100	...	Rājput
Jhatānawi ..	3,404	184,750	...	10	150	...	
Jalodā ..	250	13 290	...	2	5	...	
Khiljipur ..	775	41,060	...	2	150	...	Rājput
Dhāmoni (=Dharoli) ..	13,007	788,389	...	5	400	...	
Digwār ..	4,932	292,313	...	75	520	...	
Dilod ..	1,974	144,000	...	35	100	...	Rājput, Solankhi
Diwātia [?or Dhānia]	...	21,502	...	20	170	...	
Raisin, with suburb, district has a stone fort on a hill, one of the famous fortresses of Hindustān ..	17,497	934,739	...	80	425	...	
Siwāni ..	10,975	580,828	...	80	945	...	Rājput
Sarsiah (? Bersia) ..	5,557	279,346	...	70	500	...	
Shāhpur ..	1,673	89 067	...	5	40	...	
Khimlāsah ..	11,720	645,665	...	40	100	...	Rājput
Kherā ..	10,534	560,037	...	30	320	...	
Kesorah ..	8,375	473 267	...	40	100	...	
Kham-Khera ..	7,102	378 460	...	50	100	...	Rājput
Kargarh ..	6,907	365,707	...	70	500	...	
Korai	145,566	...	50	100	...	
Laharpur	32,267	...	30	100	...	Rājput
Māhsamand (Dhamand) ..	814	48,024	...	50	140	...	

*Sarkār of Garha.**

Containing 57 *Mahals*. Revenue 10,077,080 *Dāms*.
Castes Gond. Cavalry 5,495. Infantry 254,500.

	Bighas Biswas	Revenue D.	Suyurgāl D.	Cavalry	Infantry	Elephants	Castes
Amodgarh has a brick fort on a hill	239,000	Gond
Bāri and Bangar, 2 mahals	485,000	...	5	200	...	Do.

* Clearly printed in the Persian text as *Garha*, but misread by Jarrett as *Kantuj*. [J. S.]

Sarkār of Garha—Contd.

	Bighas Biswas	Revenue D.	Suyrgāl D.	Cavalry	Infantry	Elephants	Castes
Bhutgōn	400,025	...	50	1,000	...	Gond
Bārī, Sīmā and Jhāmā- har, 3 mahals	395,000	...	200	4,000	...	Do.
Bāwar and Nejli, 2 mahals	300,000	Do.
Bakūrah	238,000	...	100	10,000	...	Do.
Banōkar, Amrel, 2 ma- hals, has a stone fort	140,000	...	150	10,000	...	Do.
Babai	82,000	...	100	10,000	...	Do.
Bairagarh has a strong fort	45,000	...	15	200	...	Do.
Chāndpur, Chanderi, 2 mahals	50,000	...	5	Do.
Jetgarh, Bhaldevi and suburb, district, 3 mahals	12,000	...	400	30,000	...	Do.
Jethā (v. Chetia)	12,000	...	100	1,000	...	Gond Brāh- man
Damodah	1,355,000	...	10	500	...	Gond
Dhāmēri (Dhamari) and Dhamerā, 2 mahals	49,000	...	10	200	...	Do.
Deogōn	25,000	...	20	1,000	...	Do.
Deohār, Harbhat, 2 mahals	18,000	...	20	1,000	...	Do.
Darkarah	18,000	...	10	200	...	Do.
Ratanpur and Pathar, 2 mahals	613,000	...	10	Do.
Rāngarh	400,000	...	200	10,000	...	Do.
Rāngarh and Sārangpur (? Singarpur) 2 mahals	1,055,000	...	10	200	...	Do.
Rasuliya	12,000	...	200	5,000	...	Do.
Sitalpur	75,000	Gond men- tioned un- der Garha
Shālipur, Chaurāgarh, 2 mahals, has a strong fort	350,000	...	100	1,000	...	Gond
Garha with suburb, dis- trict has a strong fort	1,857,000	...	500	8,000	...	Do.
Kedārpur &c. 12 mahals Khatolahi	121,000	...	500	50,000	...	Do.
Lānji, Karolahi, Dunga- rolahi, 3 mahals	1,626,000	...	500	10,000	...	Do.
Mandlā	1,000,000	...	200	20,000	...	Do.
Mandlā	352,000	...	100	1,000	...	Do.
Harariya(Deogarh, 2 mahals, has a wooden fort on a hill	900,000	...	1500	50,000	...	Do.

Sarkār of Chanderi.

Containing 61 *Mahals*. 554,277 *Bighas*. 17 *Biswas*.
 Revenue 31,037,783 *Dams*. *Suyurghāl* 26,931 *Dāms*.
 Castes various. Cavalry 5,970. Infantry 66,085.
 Elephants 90.

	Bighas Biswas	Revenue D.	Suyurghāl D.	Cavalry	Infantry	Elephants	Castes
Udaipur has a stone fort	35,995	832,086	...	2000	10,400	...	Bāgri, Bak- kāl
Aron	216,000	...	10	40	...	Khātī
Eran	1,759	1,759	...	10	100	...	Dāngī (Bundelas)
Itāwa	2,315	80,000	...	15	50	...	Ahir &c.
Bhorāsa has a stone fort on the Betwa ..	6,783	755,000	...	40	150	...	Brāhman
Bandarjhalā	2,750	720,000	...	25	600	...	Brāhman, Jat, Bāgri
Bāra &c. 5 mahals. Each of the 5 Par- ganahs has a fort of which 4 are stone and that of Māl (?) brick	12,074	635,500	...	500	5,000	...	Bundela, Kāyath
Badarwās and Ahak, 2 mahals	4,951	304,800	...	10	170	...	Ahir
Bajhār (? Pachar) has a brick fort and a large tank and small hill are adjacent ..	2,600	174,000	...	20	300	...	Brāhman
Beli [=Bijli]	1,253	70 000	...	10	170	...	Ahir
Tāl Baroda [Barwa Sa- gar]	18,619	1,090,000	...	60	3,000	...	Musalman
Tumun, on the Betwa : the residents there say that mermen in- habit the river. There is also a temple ..	6,704	312,504	...	15	120	...	Brāhman
Thatābariyār (? Manohar Thāna)	403-17	22,500	...	5	10	...	
Thanwāra, Lalatpur &c. 3 mahals, has a stone fort	10,977	619,997	...	80	2,000	...	Rājput Sāhtī

Sarkār of Chanderi—Contd.

	Bighas Biswas	Revenue D.	Suyarghāl D.	Cavalry	Infantry	Elephants	Castes
Chanderi* with suburban district, 2 mahals, has a stone fort	23,021	1,186,388	...	95	1,350	...	Ahir
Jhājhon, Deohari the smaller, 2 mahals ..	6,469	387,480	...	80	900	...	Chauhān &c.
Jorsingār &c. 5 mahals	9,568	448,000	...	30	100	...	Makhāti
Chirgāon has a fort ..	5,096	200,000	...	15	150	...	Khāti
Joāsah	2,550	144,000	...	15	40	...	Rājput, Khāti
Deohari, the greater, on the river Sindh ..	16,466	857,998	...	65	200	...	Do.
Dub Jākar has a stone fort	8,875	580,500	...	500	5,000	...	Khichi
Daurāhāl &c. 4 mahals	2,600	147,282	...	310	5,000	...	Various
Ranod has a stone fort and near it a large reservoir which is a Hindu shrine ..	5,833	364,000	...	15	60	...	Baqqāl
Rodahi &c. 5 mahals, has a stone fort above the bandar where there is also a large temple ..	3,652	206,000	...	20	700	...	Rājput, Gond
Rāgah (? Rāghogarah) has a stone fort ..	1,487	84,000	...	50	150	...	Rājput, Us Karor
Saronj, white muslin of the kind called Mahmudi is here manufactured	186,427	11,065,765	26,931	100	2,500	...	Rawāthansī karer (?)
Sahjan &c. 3 mahals ..	70,221	3,976,700	...	150	20,000	...	Dandar (?)
Shādhora near this town is a small hill ..	5,840	334,290	...	50	1,000	...	Makhāti
Gunā has a brick fort ..	18,615	1,092,062	...	15	250	...	Khichi &c.
Garanjiyab has a stone fort on the Betwa ..	8,837	468,000	...	30	200	...	Dingi
Koroi (=Korwai) on the Betwa	4,196	252,000	...	25	150	...	Brāhman
Kāngrah has a stone fort on the Sind ..	4,670	239,990	...	35	100	...	Musalman
Kādrohā has a stone fort	2,970	168,000	...	20	400	...	Dingi

* Emendations suggested by J. S.—Deohari (=Dehri), Kangra (=Kanjit), Kadrāla (=Kadwāna), Kojan (=Kanjia), Bandarjhalā (=Bandrāilā), Bārah (=Barāgāon), Thanwara (=Tahrauli), Jhājhon (=Jakhon), Joāsa (=Churāra), Kalakot (=Kūlapāhar), Laroah (=Ladhaura), Rāgah (may also be Raksa)—all found in the Survey of India maps.

Sarkār of Chanderi—Contd.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Kolakot, has a stone fort on a hill ..	2 771	156 459	...	150	1,500	...	Gujar.
Kojān, on the Betwa ..	1,224	69,152	...	10	20	...	Bakkāl.
Laroālāh, on the Betwa	3,140	168,000	...	10	20	...	Bakkāl.
Mungāoli, has a brick fort ..	29,756	1,440,000	...	70	700	...	Kāyath.
Mīānah, 3 kos from it is a high hill ..	12,196	668,600	...	60	3,000	...	Rājput Khātri.
Mahadpur ..	561	144,000	140	...	Khātri.

Sarkār of Sārangpur.

Containing 24 *Mahals*. 706,202 *Bighas*. Revenue 32,994,880 *Dāms*. *Suyurghāl* 324,461 *Dāms*. Castes various. Cavalry 3,125. Infantry 21,710.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Ashtah ..	48,502	800,790	790	230	1,500	...	Chauhān, Dodhi, (Dodhia).
Akbarpur ..	30,094	170 610	...	45	150	...	Various.
Āgra ..	7,852	472,362	...	100	2,000	...	Chauhān.
Bajilpur produces the finest quality of betel leaf ..	11,590	647,544	...	140	560	...	Khichi.
Paplun ..	11,180	610,544	...	160	700	...	Rathor.
Bhorāsah ..	4,147	259,777	...	30	100	...	Various.
Bajor (? Pachor) ..	1,100	65,820	...	10	200	...	Do.
Bāniān ..	721	40 841	...	25	100	...	Do.
Beāwar ..	2,505	156,740	...	60	700	...	Kāyath.
Talain ..	48,056	1,800,700	27,826	150	500	...	Chauhān.
Khiljipur ..	113	6,027	...	100	200	...	Various.
Zirapur ..	6,047	377,352	...	40	300	...	Various.
Sārangpur, with suburb. district 2 mahals, has a brick fort ..	21,800	1,294,321	47,559	120	2,000	...	Khichi. Chauhān.
Sahār Bābā Hāji ..	20,263	1,093,049	...	150	1,000	...	Dhandel.

Sarkār of Sārangpur—Contd.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Sandarsi	9,443	434,389	...	105	2,000	...	Chauhān.
Sosner	121	54,876	...	25	300	...	Various.
Shujāapur	133,433	8,017,124	238,212	500	3 000	...	Chauhān.
Karhali (Karapli) ..	17,179	7,447,906	80,506	500	2,000	...	Do.
Kāyath (=Kāoti) ..	33,938	1,193 396	10,368	110	700	...	Do.
Kānhar (Khātar) ..	26,045	1,097,047	15,318
Karhari	288	17,252	...	25	200	...	Various.
Muhammadpur	47,704	1,981,182	...	170	1,000	...	Aljiyah, Dharar, Rāthor, Dudmā. (?)
Nangām	69,472	2,755,438	4,882	200	1,500	...	Chauhān.

Sarkār of Bijāgarh.†

Containing 29 Mahals. 283,278 Bighas, 13 Biswas.
Revenue 12,249,121 Dāms. Castes various. Cavalry 1,773.
Infantry 19480.

	Bighas Bighas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Anjari (=Amjad), situ- ated near the Nar- bada	13,713	1,707,093	Bhil, includ- ed in seo- rānah.
Un, Sanāwads, here a temple to Mahadeo	5,321	290,348	...	300	1,000	...	Sohar, Raj- put.
Amlāta, here a lake called by the Hindus Saman (? Biman) ..	4,919	226,677	Rājput, So har, includ- ed in Balak- warah.
Bāmangāon	15,679	781,014	...	5	100	...	Bersiya Brāhman.
Balakwāra, famous for fine sweet musk me- lons	9,268	407,014	...	500	1,000	...	Sohar, Rājput.
Barodara	5,452	369,898	...	5	50	...	Brāhman.

† South of the Narmada and south of Mandaleshwar.

Sarkār of Bijāgarh—Contd.

	Bighas Biawas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Bikhangāon, has a stone fort; here good horses are procurable	12,580	223,810	...	50	215	...	Rājput, Sohar.
Balkhar, near the Narbada; adjacent are small hills ..	5,584	223,615	...	included in Balakwārah	Rājput.
Bāsniyāh	8,870-13	85,000	50	...	As above mentioned.
Badriya (? Berin) ..	8,839	84,293	50	...	Rājput, Sohar.
Bangelah, forest adjacent where elephants are hunted	2,185	52,939	...	5	500	...	Bhil.
Biror (=Barur) ..	7,477	391,333	...	5	500	...	Do.
Tikri, on the Kodi; here a large temple to Mahādeo, and a small hill	14,771	645,245	...	included in Seorānah	Rājput, Bhil, &c.
Jalālābād, with suburb. district has a stone fort	9,285	414,268	...	34	1,470	...	Bhil, Bāhal.
Chamāri, has a stone fort	17,916	543,994	...	100	500	...	Rājput, Sohar.
Deolā Khatīā (Dival) ..	6,430	392,080	Rājput, Sohar, included in Balakwārah.
Deolā Narhar (?Dhaoda) Seorānah, near the Narbada, and a large temple there ..	3,286	98,569	...	5	500	...	Bhil.
Sindhawā, good hunting ground for elephants	13,074	627,207	...	300	2,025	...	Bhil, &c.
Silwārah, has a brick fort	9,974	353,819	...	24	550	...	Koli.
Sāngori (=Sangvi) ..	9,628	325,544	...	350	9,000	...	Bhil.
	4,607	170,210	...	5	250	...	Nahal, Karhah.
Kasrūd, on the Narbada, has a large tank and a small hill	20,490	1,150,569	...	under Balakwārah.			Sohar.

Sarkār of Bijāgarh—Contd.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Khargon, has a fort, stone below, brick above	14,526	753,194	...	50	500	...	Rājput, So- har, Kanā- rah (Khatri?)
Kānapur	5,358	126,846	...	under Balak- wālah.			Do. do.
Khudegāon	2,738	85,082	...	5	20	...	Rājput, Kanāri.
Lahrpur, commonly Muhammadpur ..	6,792	205,743	...	5	400	...	Rājput, Kahiri.
Lowārikoh	2,476	50,000	...	5	300	...	Bhil.
Mandawara, here a large temple ..	15,948	777,881	4,187	under Seoranañ			Do.
Mahoi (Mohipur), near the Narbada ..	8,318	395,206	...	5	50	...	Bhil, &c.
Morāna (Mardāna) has a stone fort ..	9,211	355,902	...	5	70	...	Rājput, So- har.
Nāwari (Newali), has a stone fort ..	9,779	408,164	Bhil.
Nangalkādi	9,057	370,208	...	5	500	...	Bāhal.

Sarkār of Mando.

Containing 16 Mahals. 229,969 Bighas, 15 Biswas.
Revenue 13,788,994 Dāms. Suyurghāl 127,732 Dāms.
Castes various. Cavalry 1,180. Infantry 2,526.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Amjhara	395,400	3,806	60	
Barodah	27,370-19	1,307,760	3,936	80	150	...	
Betmān	7,780-12	656,556	8,750	60	100	...	
Choli Mahesar ..	18,183	969,370	10,500	70	200	...	
Hāsulpur, the vine here bears twice a year, and fine cloth of the kind Amān and Khā- sah are manufactured	4,805-13	210,000	...	40	85	...	
Dhār, anciently a large city	38,660	2,079,306	36,364	120	150	...	

Sarkār of Mando —Contd.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Dikhtān	17,643	958,986	...	70	200	...	
Dharmagāon	3,018-11	916,442	
Sāgor	12,807-14	683,084	...	50	150	...	
Sanāsi	70,670	3,097,190	29,696	800	600	...	
Kotra	2,393,871	385	165	300	...	
Mando, with suburb. district, 2 mahals ..	540-17	48,398	...	10	50	...	
Manāwara	2,048-10	102,164	...	20	50	...	
Nalchah	9,949-7	545,952	34,105	70	200	...	
Nawāli	224,608	...	45	100	...	

Sarkār of Handiah.

Containing 23 *Mahals*. Land under special crops 20 *Mahals*. 89,573-18 *Bighas*, 18 *Biswas*. Amount of revenue in cash from crops charged at special rates and from land paying the general *bigah* rate. 11,610,969 *Dāms*. *Suyur-ghāl* 157,054 *Dāms*. Castes various. Cavalry 1,296. Infantry 5,921.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Unchod	59,495	2,037,877	10,825	200	500	...	
Angalgāon	414	422,947	...	150	200	...	
Amondah	392	21,834	...	7	20	...	
Bijnolā	606	44,418	...	25	100	...	
Punāsa	873	25,251	...	10	100	...	
Balahri (? Bhilakheri)	...	825	15	...	
Chakhodā	2,319	158,876	13,324	20	80	...	
Champāner	317	20,350	...	20	100	...	
Dewās	188,249	6,718,000	42,837	875	2,000	...	
Rājorā	383	25,641	...	7	20	...	
Satwās	971	89,080	7,504	45	150	...	
Samarni [? Timurni] ..	775	52,115	...	5	40	...	
Siyāngarh	160	20,494	...	111	550	...	
Seoni	2,250	...	50	500	...	
Khandohā Islāmpur ..	22,632	1,298,581	6,400	120	500	...	
Mundi	367	19,443	...	7	20	...	
Mardānpur	450	...	50	500	...	
Nimāwar	18,207	946,467	...	25	100	...	
Naugāon	1,187	79,264	...	30	120	...	
Niman (=Nimanpur) ..	1,160	75,152	...	14	56	...	
Handah (=Harda) ..	2,954	146,044	...	30	100	...	
Handia, with suburb. district, has a stone fort on the Narbada on a level plain ..	5,154-15	350,051	76,160	40	150	...	

Sarkār of Nandurbār.

Containing 7 Mahals, 2,059,601 Bighas. Revenue 50,162,250 Dāms. Suyurgāl 198,478 Dāms. Castes various. Cavalry 500. Infantry 6,000.

Bighas Bighas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
------------------	---------------	-------------------	---------	----------	-----------	--------

Sarkār of Mandesor.

Containing 17 Mahals. Revenue 6,861,396 Dāms. Suyurgāl 23,387 Dāms. Castes various. Cavalry 1,194. Infantry 4,280.

Bighas Bighas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Rāmpur	...	716,355	...	80	250	Sisodhiā.
Pjenvā	...	170,953	...	60	200	Ahir, Gond.
Bānd	...	515,400	...	80	250	Sisodhiā.
Bodhiā	...	255,062	...	65	300	Rājput, Dodia, (Bodhiā.)
Tharod	...	109,220	...	74	250	Ahir.
Bāndish	...	103,703	...	50	200	Ahir, Gond.
Bāndish	...	90,970	727	30	100	Chauhān.
Bhāthpur (Bhāthpur)	...	63,104	...	16	250	Rājput, Dodia.
Tāl	...	1,600,000	...	160	250	Do. do.
Tātel	...	500,000	...	80	220	Do. do.
Jamkewā	...	619,759	...	80	200	Sisodhiā.
Sukhera	...	46,090	...	50	300	...
Ghivāpur	...	138,690	...	60	800	Gond, Ahir.
Qiyāmpur	...	175,350	...	110	300	Deorā.
Ketri	...	803	...	50	500	...
Mandesor, with suburb, district, 2 mahals	...	1,651,920	28,660	100	400	Rājput.

Sarkār of Gāgron.

Containing 12 *Mahals*. 63,529 *Bighas*. Revenue 4,535,794 *Dāms*.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Urmāl	502,774 in money.	
Akbarpur	62,500	
Panch Pahār	21,399	1,573,560	
Chechat	222,640	
Khairābād	17,136	646,000	
Rāepur	9,716	28,730	
Sonel	9,638	281,909	
Sendar (=Sandhara) ..	695	81,929	
Ghāti	600,046	
Gāgron, with suburb. district, has a stone fort	19,781 in money.	
Nimthor	4,945	608,834	

Sarkār of Kotri Parāwa.

Containing 10 *Mahals*. 190,039 *Bighas*. Revenue 8,031,920 *Dāms*. Castes various. Cavalry 2,245. Infantry 6,500.

	Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Alot (<i>missp.</i> Āsop) ..	42 220	1,733 927	250	700
Ājigarh	4,553	855 612	350	200	Rajut, Deora.
Āwar	9 204	532,056	...	80	300
Barod	20,224	923,667	...	160	400	...	Rajput, Sondhia.
Dāgdudhālia	13,881	458,144	...	125	400	...	Do. do.
Soyat	13 381	693,585	...	240	500	...	Do. Deora.
Kotri Parāwa, 2 mahals with suburb. dist. ..	46,046	1,856,566	...	770	1,800	...	Kayath.
Gangrār	200,615	1,066,683	...	200	700	...	Rajput, Sondhia.
Ghosi (? Gadguchi) ..	2,597	116,380	...	60	200	...	Sondhia.

Princes of Mālwa.

I.

Five Rājahs of this dynasty reigned in succession,
387 years, 7 months, 3 days.
(Dates from Prinsep.)

			Ys.	Ms.	Ds.
B. C. 840.	Dhanji, (Dhananjaya, a name of Arjun, about 785 before Vikramaditya),	100	0	0
„ 760.	Jit Chandra,	86	7	3
„ 670.	Sālivāhana,	1	0	0
„ 680.	Nirvāhana,	100	0	0
„ 580.	Putrāj, (Putra Rājas of Vansāvalis without issue),	100	2	0

II.

Eighteen princes of the Ponwār caste reigned
1,062 years, 11 months, 17 days.

B. C. 400.	Aditya Panwār, (elected by nobles. [Co-temp. Sapor, A. D. 191. Wilford.	86	7	3
„ 390.	Brahmarāj, (reigned in Vidarbhanagar),	30	7	3
„ 360.	Atibrahma, (at Ujain, defeated in the north),	90	0	0
„ 271.	Sadhroshana, (Sadāsva Sena. Vāsudeva of Wilford, Basdeo of Ferishta, A. D. 390, father-in-law of Bahrām Gor. revived Kanauj dynasty),	80	0	0
„ 191.	Hemarth, (Heymert, Harsha Megha, killed in battle),	100	0	0
„ 31.	Gandharb,* (Gardabharupa, Bahrāmgor of Wilford),	35	0	0
B. C. 56.	Bikramjit, (Vikramaditya. Tuār caste, 3rd of Wilford),	100	2	3

* Under power of a curse, in consequences of a crime, he was changed into an ass resuming his human form only at night. Hemar I, notwithstanding, gave him his daughter in marriage and she gave birth to Vikramaditya.

			Ys.	Ms.	Ds.
A. D.	44.	Chandrasen of the same race (possessed himself of all Hindustān),	86	3	2
,,	135.	Kharagsen, (Surya Sena, w. 676),	85	0	0
,,	215.	Chitarkot,	1	0	0
,,	216.	Kanaksen, (conquered Saurashtra [Surāt and Gujerāt] founder of the Mewār family, ancestry traced by Jain Chronicles consulted by Tod, to Sumitra, 56th from Rāma),	86	0	0
,,	302.	Chandrapāl of the same race, ...	100	0	0
,,	402.	Mahendrapāl,	7	0	0
,,	409.	Karamchand of the same race, ...	1	0	1
,,	410.	Bijainand, (Vijyananda), ...	60	0	0
,,	470.	Munja, (killed in the Deccan, reigned A. D. 993, according to Tod).			
,,	483.	Bhoja, (by Tod 567 A. D. The other two Rājās Bhoja, Tod fixes in 665 [from Jain MSS.] and 1035, the father Udāyati. Kālidās flourished), ...	100	0	0
,,	583.	Jayachand, (put aside in favour of the following),	10	0	2

III.

Eleven princes of the Tonwar, (Tuar) caste reigned 142 years, 3 days.

A. D.	593.	Jitpāp,	5	0	0
,,	598.	Rānā Rāju,	5	0	0
,,	603.	Rānā Bāju,	1	0	3
,,	604.	Rānā Jaj Jalu, <i>var</i> , and U. T.),	20	0	0
A. D.	620.	Rāna Chandra,	30	0	0
,,	654.	Rāna Bahadur,	5	0	0
,,	659.	Rāe Bakhmal, (Bakhtmal), ...	5	0	0
,,	664.	Rāe Sukanpāl,	5	0	0
,,	669.	Rāe Kiratpāl,	5	0	0
,,	674.	Rāe Anangpāl, (rebuilt and peopled Delhi 791, Tod.), ...	60	0	0
,,	734.	Kunwarpāl,	1	0	0

IV.

Eleven princes of the Chauhān caste reigned
140 years.

			Ys.	Ms.	Ds.
A. D. 735.	Rājā Jagdeva,	...	10	0	0
„ 745.	Jagannāth, his nephew,	...	10	0	0
„ 755.	Hardeva,	...	15	0	0
„ 770.	Bāsdeva,	...	16	0	0
„ 786.	Srideva,	...	15	0	0
„ 801.	Dharmdeva,	...	14	0	0
„ 815.	Baldeva,	...	10	0	0
„ 825.	Nānakdeva,	...	9	0	0
„ 834.	Kiratdeva,	...	11	0	0
„ 845.	Pithurā,	...	21	0	0
„ 866.	Māldeva, (conquered by Shaikh Shāh father of Ala u'd din),	...	9	0	0

V.

Ten princes reigned 77 years.

A. D. 1037.	Shaikh Shāh, (from Ghazni),	...	70	0	0
„ 1037.	Dharmrāja Sud, (Vizier during minority of,	...	20	0	0
„ 1057.	Ālā u'd din, son of Shaikh Shāh, put the Vizier to death,	...	20	0	0
„ „	Kamāl u'd din, (murdered by,	...	12	0	0
„ 1069.	Jitpal Chauhān, (Jaya Sing of Delhi and Lahore? 977, a descendant of Mānikya Rai?)	...	20	0	0
„ 1089.	Harchand,	...	20	0	0
„ 1109.	Kiratchand,	...	2	0	0
„ 1111.	Ugarsen,	...	13	0	0
„ 1124.	Surajchand,	...	12	0	0
A. D. 1136.	Birsen, (dispossessed by the following),	...	10	0	0

VI.

Eight princes reigned 205 years.

A. D. 1146.	Jalāl u'd din, (an Afghan),	...	22	0	0
„ 1168.	Ā'alam Shah, (killed in battle by,	...	24	0	0

Ys. Ms. Ds.

A.D. 1192.	Kharagsen, son of Birsen (Birsen, emigrated to Kām- rup, married the king's daughter, succeeded to the kingdom and regained Mal- wah),	...	8	0	0
„ 1200.	Narbāhan.	{ Ūdayādityadeva, Naravarmadeva, Yasovarmadeva, Jayavarmadeva, Lakhan,*	20	0	0
„ 1220.	Birsāl,	...	16	0	0
„ 1236.	Puranmal,	...	39	0	0
„ 1268.	Haranand,	...	62	0	0
„ 1330.	Sakat Sing, (killed at the inva- sion of the following),	...	60	0	0

VII.

Eleven princes reigned 142 years, 2 months
4 days.†

A. D. 1390.	Bahādur Shāh, (king of Deccān, killed at Delhi),	...	some ms.		
„ 1390.	Dilāwar Khān Ghori, (viceroy of Mālwa h assumed sove- reignty),	...	20	0	0
„ 1405.	Hoshang Shāh,	...	30	0	0
„ 1432.	Muhammad Shāh, (Ghizni Khān, poisoned),	...	some ms.		
„ 1435.	Sultān Mahmud, uncle of Hoshang, (Rānā of Chitor Kumbho, presents <i>tankas</i> coined in his own name, 1450),	...	34	0	0

* These five reigned A.D. 1137—1143 according to the Ujjain inscription.

† Correct list of Malwa Sultans—

Dilawar Kh. Ghuri	A.H. 794/1932	A.D.
Hushang Sh.	808/1405	
Muhammad Sh. (Ghazni Kh.)	838/1435	
Ma'sud	839/1436	
Māhmud I.	839/1436	
Ghiyās-ud-din	873/1469	
Nāsir-ud-din	905/1500	
Mahmud II.	916-937/1510-31	

among the celestials in the form of a *Gandharb*¹ and then clothed in human shape. Thus he became universally known by this name and prospered the world by his justice and munificence. A son was born to him named Bikramājī who kept aflame the lamp of his ancestors and made extensive conquests. The Hindus to this day keep the beginning of his reign as an era and relate wonderful accounts of him. Indeed he possessed a knowledge of talismans and incantations and gained the credulity of the simple. Chandrapāl obtained in turn the supreme power and conquered all Hindustān. Bijainand was a prince devoted to the chase. Near a plant of the Munja² he suddenly came upon a newborn infant. He brought him up as his own son and called him by the name of Munja. When his own inevitable time approached, his son Bhoja was of tender age. He therefore appointed Munja his successor, who ended his life in the wars of the Deccan.

Bhoja succeeded to the throne in the 541st year of the era of Bikramājī and added largely to his dominions, administering the empire with justice and liberality. He held wisdom in honour, the learned were treated with distinction, and seekers after knowledge were encouraged by his support. Five hundred [*correctly* nine] sages, the most erudite of the age, shone as the gathered wisdom of his court and were entertained in a manner becoming their dignity and merit. The foremost of these was Barruj [Vararuchi], a second was Dhanpāl [Dhanwantari] who have composed works of great interest and left them to intelligent seekers of truth, as a precious possession. At the birth of Bhoja, either through a grave miscalculation of the astrologers or some inadvertence on the part of those who cast his horos-

¹ A class of demigods who inhabit the heaven of Indra and form the celestial choir at the banquets of the deities. He appears in the lists as *Gandhapāla*, fostered by an ass, *Gandharuṣa* or *Harshamegha*, epithets of the same animal. According to Wilford the Pandits who assisted Abul Fazl disfigured the chronology of the supplement to the *Agni-purana*. Of Salivahana and Naravahana they made two distinct persons as well as of Bahrām with the title of Gor in Persian and Himār, or the Ass in Arabic. Thus they introduced Himār or Hemarth and Gor or Gandharb.

² *Saccharum munja*, a rush or grass from the fibres of which a string is prepared of which the Brahmanical girdle is properly formed. Munja wrote a geographical description of the world or of India which still exists under the name of *Munja-prati-desa-vyavasthā* or state of various countries. It was afterwards corrected and improved by Rājā Bhoja, and still exists in Gujerāt. Munja transferred the capital from Ujjain to Sonitpura in the Deccan called after him *Munja-pattana* on the Godaveri.

When Kunwarpāl died, the royal authority passed into the hands of the Chauhāns. During the reign of Maldeva, Shaikh Shāh came from Ghazni and acquired possession of Mālwah and lived to an advanced age. At his death his son Alā u'd din was a minor, and his chief minister Dharm Rāj Sud occupied the throne. As soon as Alā u'd din came of age, he rose in arms to assert his rights and put to death the disloyal usurper. Jitpal Chauhān, a descendant of Mānik Deva Chauhān, who was in the service of Kamāl-u'd-din, under the impulse of malice and in pride of wealth compassed the destruction of his master and in the hope of gain, acquired for himself eternal perdition. Under the rule of Tippiarsen, an intriguing Afghān, getting together some desperate characters as his abettors, laying an ambush for the Rājā, slew him while hunting, and assumed the sovereignty with the title of Jalāl u'd din. Tippiarsen had married his son Kharagsen into the family of the Rājā of Kāmrup. The Rājā, for his eminent services, appointed this adopted son his heir, and when the Rājā died, Kharagsen ascended the throne and to avenge his wrongs marched an army against Mālwah and Aālam Shāh was killed in battle.

In the reign of Sakat Singh a prince named Bahādur Shāh advanced from the Deccan and having put the Rājā to death, marched against Delhi and was taken prisoner while fighting against Sultān Shahāb u'd din.

From the time of Sultān Ghiyās u'd din Balban (A.D. 1265) to that of Sultān Muhammad son of Firoz Shāh (A.D. 1387) no serious weakness in the imperial authority betrayed itself, but on his death the empire of Delhi became a prey to distractions. Dilāwar Khān Ghori who had been appointed by him to the government of Mālwah, assumed independence. The Sultān bestowed the government of four provinces upon four individuals who had been faithful to him in his adversity. To Zafar Khān¹ he gave Gujerāt; Khizr Khān was appointed to Multān; Khwājah Sarwar to Jaunpur and Dilāwar Khān to Mālwa. After his death, the time being favourable, each of the four assumed independence. [Persian text confused.]

Alp Khān the son of Dilāwar Khān was elected to the succession under the title of Hoshang. It is said that his father was poisoned by his order whereby he has gained

¹ Zafar Khān took the title of Muzaffar Shāh.

everlasting abhorrence. Sultān Muzaffar of Gujerāt marched against him and took him prisoner and left his own brother Naṣir Khān in command of the province. But as he was tyrannous in conduct and ignored the interests of his subjects, Muṣa, cousin of Hoshang, was raised to the throne. Sultān Muzaffar released Hoshang from confinement and despatched him to Mālwa in company with his own son Ahmad Khān, and in a short time he was restored to power. On the death of Muzaffar, he perfidiously marched against Gujerāt, but meeting with no success, returned. On several

title of Muhammad Shāh. Mahmud Khān, cousin of Sultān Hoshang, basely bribed his cup bearer and that venal wretch poisoned the Sultān's wine. The generals of the army kept his death secret hoping to place his son Masaud Khān upon the throne and they sent to confer with Mahmud Khān. He replied that worldly affairs had no longer any interest for him but that if his presence in council were necessary, they must come to him. They foolishly went to his house and were placed in confinement, and by the aid of some disloyal mercenary partisans, he seized upon the sovereignty of Mālwa and was proclaimed under the title of Sultān Mahmud (Khilji). Upon such a wretch,¹ in its wondrous vicissitudes thus did Fortune smile and the awe he inspired secured him the tranquil possession of power. He waged wars with Sultān Muhammad son of Mubārak Shāh, king of Delhi, with Sultān Ahmad, king of Gujerāt, with Sultān Hussain Sharqi of Jāunpur, and with Rānā Kumbha of Mewār.

Khwājah Jamāl u'd din Astarābādī² was sent to him as ambassador by Abu Said Mirza with costly gifts which greatly redounded to his glory. Mahmud II (1512 A.D.) through his ungenerous treatment of his adopted followers' fell into misfortune but was again reinstated in power by the aid of Sultān Muzaffar Shāh (II) of Gujerāt (A.D. 1511-26). Through his reckless bravery in battle he was taken prisoner by the Rānā (Sanga)³ who treated him with generosity and restored him to his kingdom. He was again captured in action against Sultān Bahādur of Gujerāt and conveyed to the fortress of Chāmpāner. He was killed (A.D. 1526) on his way thither and Mālwa was incorporated with Gujerāt until it was conquered by Humayun. When this monarch returned to Agra, one of the relations of Sultān Mahmud, by name Mallu, seized on the government of Mālwa under the title of Qādir Khān.

¹ He proved notwithstanding, the ablest and most chivalrous of all the Mālwa princes.

² This ambassador arrived with presents from Mirza Sultān Said 3rd in descent from Tamerlane who reigned over Transoxiana and held his court at Bokhārā—grandfather of Bāber. He returned with presents of elephants, singing and dancing girls, Arab horses and an ode in the vernacular composed by Mahmud himself which Abu Said valued above all the other gifts. Ferishta II, 254.

³ The reference is to his dismissal of his Hindu minister Medni Rāe and the Rājput troops to whom he owed his kingdom when deserted by his nobles at the beginning of his reign.

⁴ Rana Sanga (A.D. 1508—1529) under whom Mewār reached its highest prosperity, fought Babar in 1526.

During the supremacy of the usurper Sher Khān the control of the province was invested in Shujāat Khan, who rebelled under the reign of Salim Khān and assumed independence under Mubāriz Khān.

On his death, his eldest son Bāyizid succeeded under the title of Bāz Bahādur until the star of his Majesty's fortune arose in the ascendant and this fertile province was added to the imperial dominions.

May the robe of this daily-widening empire be bordered with perpetuity, and its inhabitants enjoy to their hearts' fill a prosperity that shall never decay.

SUBAH OF DĀNDES.

This flourishing country was called *Khāndes*, but after the capture the fortress of *Asir* (1600 A.D.) and when this province fell under the government of prince Dānyāl, it was known as *Dāndes*.¹ It is situated in the second climate. Its length from *Borgāon* which adjoins *Handiah* to *Lalang* which is on the borders of the territory of *Ahmadnagar* is 75 *kos*. Its breadth from *Jāmod* adjoining *Berār* to *Pāl* which borders *Mālwa* is 50; and in some parts only 25 *kos*. On its east is *Berār*; to the north, *Mālwa*; to the south, *Gālnah* (*Jālna*)*: to the west, the southern chain of the mountains of *Mālwa*. The rivers are numerous, the principal being the *Tāpti* which rises between *Berār* and *Gondwāna*, the *Tabi* which has its source from the same quarter and which is also called the *Purna*, and the *Girna* near *Chāpra*. The climate is pleasant and the winter temperate.

Jowāri is chiefly cultivated, of which, in some places, there are three crops in a year, and its stalk is so delicate and pleasant to the taste that it is regarded in the light of a fruit. The rice is of fine quality, fruits grow plentifully and betel leaves are in abundance. Good cloth stuffs are woven here: those called *Siri Sāf* and *Bhiraun* come from *Dharangāon*.

Asir is the residence of the governor. It is a fortress on a lofty hill. Three other forts encompass it which for strength and loftiness are scarcely to be equalled. A large and flourishing city is at its foot. *Burhānpur* is a large city three *kos* distant from the *Tapti*. It lies in latitude 21° 40', and is embellished with many gardens and the sandalwood also grows here. It is inhabited by people of all countries and handicraftsmen ply a thriving trade. In the summer, clouds of dust fly which in the rains turns to mud.

Aādilābād is a fine town. Near it is a lake, a noted place of worship, and the crime of *Rājā Jasrat* (*Dasarath*)¹

* *Galna* is 20 m. S.W. of *Dhulia* in W. *Khandesh*, while *Jalna* is far to the south of E. *Khandesh*, beyond the *Ajanta* range.

¹ *Dasarath's* crime was committed in his youth when he unwittingly killed the hermit's son in the forests by the banks of the river *Sarayu* in *Oudh*. The story is told in *Rāmāyan*, Bk. II, Sec. 63 (see Griffith's translation, Vol. II, p. 243). He was cursed by the bereaved father and fated to be similarly agonised for the loss of his son in after years.

was expiated at this shrine. It is full all the year round and it irrigates a large area of cultivation.

Chāngdeo is a village near which the *Tapti* and the *Purnā* unite, and the confluence is accounted a place of great sanctity. It is called *Chakra Tirth*. Adjacent to it is an image of *Mahādeo*. They relate that a blind man carried about him an image of *Mahādeo* which he worshipped daily. He lost the image at this spot. For a time he was sore distressed, but forming a similar image of sand, he placed it on a little eminence and adored it in a like spirit. By a miracle of divine will, it became stone and exists to this day. Near it a spring rises which is held to be the *Ganges*. An ascetic by the power of the Almighty was in the habit of going to the *Ganges* daily from this spot. One night the river appeared to him in a dream, and said, "Undertake these fatigues no longer; I myself will rise up in thy cell." Accordingly in the morning it began to well forth and is flowing at the present time.

Jāmod is a rich *parganah*. In its neighbourhood is a fort on a high hill called *Pipaldol*. *Dhāmarni* is a prosperous town. Near it is a tank in which a hot spring perpetually rises and which is an object of worship.

Choprah is a large flourishing town, near which is a shrine called *Rāmesar* at the confluence of the *Girna* and the *Tapti*. Pilgrims from the most distant parts frequent it. Adjacent to it is the fort of *Malkāmad* [= *Malkheda*].

Thālner was for a time the capital of the *Fāruqi* princes. The fort though situated on the plain is nevertheless of great strength.

This *Subah* contains 32 *parganahs*. Scarce any land is out of cultivation and many of the villages more resemble towns. The peasantry are docile and industrious. The provincial force is formed of *Kolis*, *Bhils* and *Gonds*. Some of these can tame lions, so that they will obey their commands, and strange tales are told of them.

Its revenue is 12,647,062, *Bcrāri tankahs* as will appear in the statement. After the conquest of *Asir*, this revenue was increased by 50 per cent. The *tanka* is reckoned at 24 *dāms*. The total is therefore, 455,294,232 *Akbari dāms*. (Rs. 11,382, 355-12-9).

Sarkār of Dāndes.

Containing 32 *mahals*. Revenue in money 12,647,062 Tankas.

	Tankas		Tankas
Asir, north of Burhanpur ...	1,060,221	Chāndsir, south ...	198,900
Atrāl, south ...	284,249	Jalod, south [Jalam?] ...	317,205
Brandwel, east, by south ...	543,828	Chopra, west ...	730,965
Amalnēr ...	2,406,180	Dāngri, south ...	315,325
Warungson, east by south ...	215,504	Dāmri, west ...	325,300
Pūcharah, west ...	206,728	Rāver, west ...	883,655
Farmāl, west ...	162,830	Ranpur, east [? Ranapur] ...	820,971
Ridwad, south-west ...	183,540	Sāvdā, south ...	430,008
Names omitted in all MSS ...	{ 58,511	Shendurni, between E. and W. ...	104,754
Rihāl, south ...	290,311	Asdīlābād, east by south ...	527,223
Bhadgām, south ...	256,331	Lāling, south ...	352,644
Betāwad, south ...	320,782	Lohārā, south ...	247,965
Rāer [Rāmer], west by south ...	595,988	Mānjrud, east [Mānjāl] ...	104,965
Thālner, west by south ...	594,230	Nasirābād, south ...	824,925
Jūmod, east ...	175,844	Name omitted in all MSS. ...	316,336
Rāmer, midway between E. and W. ...	470,042		

In ancient times this country was a waste and but few people lived about the fortress of Asir. The locality was traditionally connected with *Ashwatthāmā** and established as a shrine. It is related that *Malik Rājī* from whom *Bahādūr*† is the ninth in descent, under stress of misfortune came from *Bīdar* to these parts and established himself in the village of *Karondā*‡ a dependency of *Thālner*, but being molested by the natives, he repaired to Delhi and took service under *Šultān Fīroz*. The king admired his skill as a huntsman, and his reward being left to his own choice, he received a grant of that village and by judicious policy acquired possession of other estates and reclaimed much waste land. In the year 784 A.H. (A.D. 1382), he made *Thālner* his seat of government, assumed the title of *Aādil Shāh* and reigned for 17 years. He was succeeded by his son *Ghizvi Khān* under the title of *Nasir Shāh*, after which this province became known as *Khāndes*. He reigned 40 years, 6 months, and 26 days. On his death his son *Mirān Shāh* administered the State. By some he is called *Aādil Shāh*. He occupied the throne 3 years, 8

* Son of *Prona*, a hero of the *Mahābhārata*.

† *Bahādūr Khān Fīrūzī*, 1396 A.D. last of the dynasty.

‡ According to P., his father was *Khān Jahān* one of the ministers in the court of *Alā-ud-dīn Khiljī* and of *Mahammad Tughlaq*. He claimed descent from the *Caliph Umar* called by *Mahammad* "al *Fīrūz*" or the discriminator, on the day that he publicly professed his conversion, because on that day "Islam was made manifest and truth distinguished from falsehood." See as *Sayyid's Hist. of the Caliphs*, Jarrret's translation, p. 118. *Karondā* = *Harmand*, 12 m. n. of *Thālner*.

months and 23 days. He was followed by his son Mubārik Shāh Chāukandi Sultān during 17 years, 6 months and 29 days. His son Aādil Shāh Aynā whose name was Ahsan Khān, had a prosperous reign of 46 years, 8 months and 2 days. He removed to *Burhānpur* and made himself master of Asir. Sultān Ahmad of Gujerāt, the founder of Ahmedābād, gave him his daughter in marriage. At his death, his brother Dāud Shāh reigned for 7 years, 1 month and 17 days. Aādil Shāh (II) son of Hasan took refuge in Gujerāt. Sultān Māhmud Bigarah Rāji gave him in marriage *Ruqayya* the daughter of Sultān Muzaffar, (his son) and accompanying him to *Khāndes*, restored him to his kingdom and returned to his own. He reigned 13 years. He left two sons, Mirān Muhammad Shāh and Mubārik Shāh. Sultān Bahādur of Gujarāt being on terms of friendly alliance with the first-named¹ made him his heir, and guardian to his nephew Mahmud and his own brother Mubārik. Mirān Shāh from a sense of their deserts, and with political sagacity did them no injury and contenting himself with the kingdom of Khāndes, restored Mahmud to the sovereignty of Gujerāt. He reigned 16 years, 2 months and 3 days. When the measure of his days was full, the nobles raised his son Rāji to the throne. Mirān Mubārik wrested it from him and reigned in succession to his brother, administering the government for 31 years, 6 months and 5 days. He was succeeded by his son Mirān Muhammad who reigned 9 years, 9 months and 15 days. When he died, his younger brother Rāja Ali Khān² was elected and assumed the title of Aādil Shāh. His administration was conducted with ability and he was killed in the

¹ His sister being mother of Mirān Shāh.

² He married a sister of Abul Fazl.

Khandesh Muslim rulers—

Malik Rājā, Rājā Ahmad	A.H. 784/1382 A.D.
Nasir Khan	801/1399
Adil Kh. I.	840/1437
Mubārak Kh. I, Chāukanda	844/1441
'Adil Kh. II, Ainā	861/1457
Dāud Kh.	907/1501
Ghazni Kh.	914/1508
Hasan Kh.	914/1508
'Alam Kh. (usurper)	914/1508
'Adil Kh. III. ('Alam Kh.)	914/1509
Mirān Muhammad Sh. I.	926/1520
Ahmad Sh.	943/1537
Mubārak Sh. II.	943/1537
Muhammad Sh. II.	974/1566
Hasan Sh.	984/1576
'Adil Sh. IV. (Rājā 'Ali Kh.)	985/1577
Bahādur Sh. (Qadr Kh.)	1006-1009/1597-1601

wars of the Deccan fighting on the side of his Majesty's victorious troops. He was buried at Burhānpur, after a successful reign of 21 years, 3 months and 20 days. At his death the succession devolved on Khizr Khān, his son, who took the name of Bahādur Shāh. But the star of his destiny was obscure and in the 45th year of the Divine era, he was deprived of his kingdom as has been recorded in its proper place.

SUBAH OF BERĀR.

Its original name was *Wārdātāt*, from *Wārdā*, the river of that name and *tāt*, a bank. It is situated in the second climate. Its length from *Baithakwādi* to *Biragarh* is 200 *kos*, its breadth from *Bidar* to *Handia* 180 *kos*. On the east lies *Biragarh* adjoining *Bastar*; to the north is *Handia*; to the south *Telingāna*;¹ on the west *Mahkarābād*. It is a tract—situated between two hill-ranges having a southerly direction. One of these is called *Bandah* upon which are the forts of *Gāwilgarh*, *Narnāla* and *Melgarh*. The other is *Sahia*, where rise the forts of *Mahur* and *Rāmgarh*.

The climate and cultivation of this province are remarkably good. There are many rivers, the principal of which is called *Ganga Gautami* called also the *Godavari*. As the Ganges of Hindustān is chiefly connected with the worship of Mahādeo, so is this river with (the *Rishi*) *Gautama*. Wonderful tales are related regarding it and it is held in great sanctity. It rises near *Trimbak*² in the *Sahia* range and passing through the country of *Ahmadnagar*, enters *Berār* and flows into *Telingāna*. When Jupiter enters the sign *Leo*, pilgrims flock from all parts to worship.³ The *Tāli* and *Tapti* are also venerated. Another river the *Purnā* rises near *Dewalgāon*, and again the *Wārdā*

¹ As this province corresponds geographically with the ancient *Tri-Kalinga*, Gen. Cunningham thinks *Telingana* to be probably, a slight contraction of *Tri-Kalinga*. See *Anc. Geo. Ind.*, p. 519.

² In the *Nāsik District*, about 50 miles from the Indian Ocean. At this spot is an artificial reservoir, reached by a flight of 90 steps, into which the water trickles drop by drop from the lips of an earthen image shrouded by a canopy of stone.

³ Once in every 12 years, a great bathing festival called *Pushkaram*, is held on the banks of *Godavari*, alternately with the other eleven sacred rivers of India. The most frequented spots are the source at *Trimbak*, *Bhadrāchalam* on the left bank about 100 miles above *Rājamahendri*, the latter itself, and the village of *Kotipāli*. I. G. *Tāli*, variants *Pāli*, *Pāli*.

issues forth ten *kos* higher up than the source of the *Tāli*. The *Napta** also rises near *Dewalgāon*.

In this country the term for a *Chaudhri* [village head-man] is *Desmukh*, for a *Qānūngo*, *Des Pāndia*; the *Muqaddam* is called *Patil* and the *Patwāri*, *Kulkarni*.

Elichpur is a large city and the capital. A flower violet in colour is found here and is very fragrant. It is called *Bhui champah*¹ and grows close to the ground.

At the distance of 7 *kos* is *Gāwil*, a fortress of almost matchless strength. In it is a spring at which they water weapons of steel.

Panār is a strong fort on an eminence which two streams surround on three sides.

Kherla is a strong fort on a plain. In the middle of it is a small hill which is a place of worship. Four *kos* from this is a well, into which if the bone of any animals be thrown it petrifies, like a *couric-shell* only smaller. To the east of this resides a *Zamindār* named *Chātawāi* (= *Jātibā*) who is master of 2,000 cavalry, 50,000 foot and more than 100 elephants. Another such *Zamindār* is named *Dādhi Rāo* who possesses 200 cavalry, and 5,000 foot. To the north is *Nāhar Rāo* a chief whose force consists of 200 horse and 5,000 foot. Formerly in this neighbourhood, was a *Zamindār* named *Hatiā*, but now his possessions are under other subjection and the whole race are *Gonds*. Wild elephants are found in this country. The chiefs were always tributary to the kings of *Mālwa*; the first, to the governor of *Garha*, and the others to the government of *Handia*. *Narnālah* is a strong fortress on a hill, containing many buildings. *Bija Rāo* is a *Zamindār* in the neighbourhood who has a force of 200 cavalry and 5,000 foot. Another is *Dungar Khān* with 50 horse and 3,000 foot: both of the *Gond* tribe. Near *Bālāpur* are two streams, about the borders of which are found various kinds of pretty stones, which are cut and kept as curiosities. Six *kos* distant was the head-quarters of Prince Sultān Murād which grew into a fine city under the name *Shahpur*.

Near *Melgarh* is a spring which petrifies wood and other substances that are thrown into it.

* *Napta*—doubtfully written in Persian. The great *Penganga* is evidently meant, but only one small feeder of it rises here; *NPTA*=*PNNA*.

¹ The *S. ul M.* calls it *Bhuin Champa* and adds "it grows also in Bengal; it shoots from the ground with leaves like the ginger-plant and till the rainy season it continues in growth and is green. In the winter it withers away and disappears altogether." The word is properly *Bhum Champak*, "The ground Champak", and is the *Kœmpferia Rotunda*.

Kallam (Kalamb), is an ancient city of considerable importance; it is noted for its buffaloes. In the vicinity is a *Zamindār* named *Babjeo* of the *Gond* tribe, more generally known as *Chāndā*: a force of 1,000 horse and 40,000 foot is under his command. *Birāgarh* which has a diamond mine and where figured cloths and other stuffs are woven, is under his authority. It is but a short time since that, he wrested it from another chief. Wild elephants abound.

About *Bāsim* is an indigenous race for the most part proud and refractory called *Hatkars*: their force consists of 1,000 cavalry and 5,000 infantry. *Banjāra* is another *Zamindārī*, with 100 horse and 1,000 foot. At the present time it is under the authority of a woman. Both tribes are *Rājputs*.

Māhur is a fort of considerable strength situated on a hill. Adjacent is a temple dedicated to *Durgā*, known in this country as *Jagadathā* [=Jagatdhātri]. Here the buffaloes are of a fine breed and yield half a *man* and more of milk. The *Zamindār* is a *Rājput* named *Indradco* and is entitled *Rānā*. He commands 100 horse and 1,000 foot.

Mānikdrug is a remarkable fort on a hill surrounded by extensive forests. It is near *Chandā*, but up to the present is independent territory.

Jitanpur is a village in the *Sarkār* of *Pāthri*, where there is a thriving trade in jewels and other articles of value.

Telingānah was subject to *Qutb ul Mulk*¹ but for some time past has been under the authority of the ruler of *Berār*.

In *Indur* and *Nirmal* there exist mines of steel and other metals. Shapely stone utensils are also carved here. The breed of buffaloes is fine and, strangely enough, the domestic cocks are observed to have bones and blood of a black colour.* A *Zamindār* called *Chanāneri*,² is *Desmukh*, a man of the most distinguished character, who has a force of 300 horse. *Rāngir* is a strong fort on a hill, enclosed by forests. Wild elephants are numerous. It has not as yet been annexed to the empire.

¹ *Warangal* was the ancient capital of this kingdom founded by the *Narapati Andhras* which was also considered to include the coast territory from the mouth of the *Ganges* to that of the *Kistnā* known as *Kalinga*. After the invasion of *Alā u'd dīn* in 1303, it continued with some interruptions under *Hindu* rule till its remains were incorporated in the dominions of *Quli Qutb Shāh* the founder of the *Qutb Shāhi* dynasty, in 1512 with *Golconda* as its capital.

* See Constable's ed. of *Bernier*, p. 251, note.

² *Var. Jayaberi*.

Lonār is a division of *Mehkar*, and a place of great sanctity. The Brahmans call it *Bishan Gayā*. There are three *Gayās*, where the performance of good works can be applied as a means of deliverance to the souls of deceased ancestors; namely, *Gayā* in *Behār* which is dedicated to *Brahma*, *Gayā* near *Bijāpur* dedicated to *Rudra*, and this one. Here is also a reservoir, having a spring in it of great depth, and measuring a *kos* in length and in breadth, and surrounded by lofty hills. The water is brackish, but when taken from the centre or at its sides, it is sweet. It contains the essential materials for the manufacture of glass and soap, and saltpetre is here produced and yields a considerable revenue.

On the summit of a hill is a spring at the mouth of which is carved the figure of a bull. The water never flows from this spring to the other, but when the 30th lunar day (conjunction) falls on a Monday, its stream flows into the large reservoir. In the neighbourhood is a *Zamindār* called *Wāilah* of the Rājput tribe, commanding 200 horse and 2,000 foot. Another is called *Sarkath*, also a Rājput, and possesses 100 horse and 1,000 foot.

Batialah is a fort of considerable strength on a hill, of which *Pātāl Nagari* is a dependency. In the sides of the hill twenty-four temples have been cut, each containing remarkable idols. The *zamindar* is *Medni Rāo*, a Rajput, with 200 horse and 1,000 foot. Another is *Kāmdeo*, a Rājput having under him 100 horse and 1,000 foot.

This *Subah* contains 16* *sarkārs* and 142 (should be 242) *parganahs*. From an early period the revenues were taken by a valuation of crops, and since the *tankah* of this country is equal to 8 of Delhi, the gross revenue was $3\frac{1}{2}$ *krors* of *tankahs* or 56 *krors* of *dāms*¹ (Rs. 14,000,000). Some of the Deccani princes increased the revenue to 37,525,350 *tankahs*. In the time of Sultān Murād a further

* But only 13 Sarkars are named in the detailed statement given in the following pages.

¹ This makes 16 *dāms* to the *tankah*. In the revenue statement of Khandesh, the *tankah* is reckoned at 40 *dāms*. That of Gujerāt = two-fifths of a *dām* or 100 to the rupee of 40 *dāms*. Bayley *Hist. of Gujerāt*, p. 6. If Prince Murād's increase be added to that of the Deccani princes, the total gives 40,162,804 *tankahs*. This sum multiplied by 16 results in 642,604,864 *dāms*. As 40 Akbari *dāms* are equivalent to a rupee, the above total represents 16,065,121 rupees. Under Akbar, according to the I. G. the land tax of Berār was Rs. 17,376,117. Under Shāh Jahan, Rs. 13,750,000, and under Aurangzeb, 15,350,625, but the latter amount, taken by Mr. E. Thomas from Manucci, is given by Tieffenthaler from the same authority as 10,587,500. See his dissertation on the apparent inaccuracies of calculation in the registers of the empire and their cause. Vol. I, p. 65.

addition of 2,637,454 Berāri *tankahs* was made. The total amounted to 40,162,704 Berāri *tankahs*. The original amount and the additional increase were thus tabulated, the whole reaching the amount of 642,603,272 Delhi *dāms*.

Eight *parganahs* of the *Sārkar* of Kallam (Kalamb) were annexed to *Chāndā*, the revenue of which is not included, nor those of 22 *parganahs* of the *Sarkār* of Kherla, held by Chātwā (Jātibā) and some few other *Zamindārs*.

Sarkār of Gāwil.

Containing 46 *parganahs*. Revenue 134,666,140 *dāms*.
Suyurghāl 12,874,048 *dāms*.

	Revenue D	Suyur- ghāl D		Revenue D	Suyur- ghāl D
Sub. dis. of Ellichpur, has a fort of stone and brick on the plain ..	14,000 000	2,800,000	Thugāon ..	5,600,000	...
Āshṭi ..	4,800,000	...	Chakhli, (Banjārās) and Gonds, 400 Cav. 2,500 Inf.) ..	2,400,000	...
Aron ..	3 200 000	...	Daryāpur ..	6,400 000	...
Ānji ..	1,600 000	...	Dhāmori ..	2,718,540	1,118,540
Anjangāon ..	3,200,000	...	Ridhpur ..	6,400,000	...
Karyāt Bāhil ..	604,000	...	Sarasgāon ..	5,296,000	496,000
Bāri ..	114 368	82,368	Qasbah Serālā ..	1,835 390	1,015,390
Bhādkali ..	3 200,000	...	Sarson ..	4,800,000	...
Basrauli ..	1,280 000	...	Sālor ..	340,000	...
Beāwadā ..	700,000	60,000	Karyāt Sherpur ..	48,000	...
Palaskher ..	960,000	...	Karhāṭha Kuram ..	2,400,000	...
Karyāt Pālā, (100 Cav., 2,000 Inf. Gonds) ..	800,000	...	Kholāpur ..	4,870,114	70,114
Baror ..	1,280,000	...	Kāranja, Badhonā, 2 mahals ..	4,800,000	...
Qasbah Baligāon ..	817,350	177,350	Karanjgāon, Qasbāh Kherah, 2 mahals ..	523,200	...
Postah ..	814 416	594,460	Kumargāon ..	640 000	...
Radharāmani ..	4,825,300	1,625,300	Kāranja Bibi ..	4 200 000	1,400,000
Tivsā ..	800,000	...	Kurha ..	4,800 000	...
Maner ..	800,000	...	Mane ..	4,800,000	...
Mānjarkher ..	6,400,000	...	Nandgāon Pith
Mālkhher ..	480,000	...	Nandgāon ..	6,633,826	233,826
Manglor, (Mangrol) ..	2,800,000	...	Parganah Nir ..	3,220,000	...
Murjhī [Mojhri] ..	4,800,000	...	Hātgāon ..	3,200,000	1,600,000
				1,600,000	...

Sarkār of Panār.

Containing 5 *Parganas*. Revenue 13,440,000 *Dāms*.

	Revenue D.		Revenue D.
Sub. dist. of Panār, has a lofty stone fort, surrounded on 3 sides by water ...	4,000,000	Kheljhari, 100 horsemen, 400 foot, Rājput ...	2,400,000
Sewanbārhā, Kānt Barhā ...	640,000	Māndgāon Karar, 25 horse, 400 foot, Rājput [=Nandgaon Qazi of map] ...	4,800,000
Shelu, 10 horsemen, 400 foot	1,600,000		

Sarkār of Kherla.

Containing 35 Parganahs. Revenue 17,600,000 Dāms.

	Revenue D.		Revenue D.
Atner, has a stone fort on the plain. Rājput, 100 horse, 2,000 foot ...	3,200,000	Suburb. dist. of Kherla, Rājput, Lohāri, Gond, 50 horse, 2,000 foot ...	3,200,000
Ashla	160,000	Sātner, Atner, 2 mahals, Gond, 100 horse, 2,000 foot ...	1,600,000
Patan	1,200,000	Sāinkherah	2,000,000
Bhesdahi, Rājput, 100 horse, 2,000 foot	1,600,000	Qasbah Jaror	480,000
Baror, Chandji Māli (?) 20 horse, 500 foot	2,800,000	Mundavi, Brahman, Gond, 10 horse, 100 foot ...	480,000
Bāsad, (Māsod), Brahman, Gond, 10 horse, 100 foot ...	480,000	Multāi
Pauni, Rājput, 40 horse, 500 foot	400,000	Durgah
		Nārangwari [?Maramjhiri]	...
		Mālābil
Māloi	Bāri
Mangah	Wāigāon
Sewah	Deo thānah
Jāmkher	Bāri
Belwāli	Saloi
Sirāi	Rāmjok
Chakhli	Janābak [? Halbatak]	...
Khāwar [? Kenaar]	...	Jonār [? Chopar]	...
Wāldah	Habiyāpur

*Sarkār of Narnāla.*Containing 34 Parganas. Revenue 130,954,476 Dāms.
Suyurghāl 11,038,422 Dāms.

	Revenue D.	Suyur- ghāl D.		Revenue D.	Suyur- ghāl D.
Ankot	6,470,066	70,066	Dhārōr	1,200,000	...
Adgāon, Dogar, Gond, 50 horse, 2,000 foot ...	8,000,000	...	Dhendā	5,600,000	...
Amner and Jalpi, 2 mahals	4,800,000	...	Rohankher	2,000,000	...
Angolāh	11,200,000	...	Rājōr	1,000,000	520,000
Bālapur	22,000,000	3,300,000	Sheolā	640,000	...
Panjar	2,000,000	...	Sherpur	48,000	...
Bārsi Tānkli	2,864,000	...	Karankher	2,400,000	800,040
Pigalgāon	2,400,000	...	Kothāl	1,409,000	209,000
Pātar Shaikh Bābu	3,700,000	500,000	Kothil	640,000	...
Qasbah Bārigāon ..	1,600,300	640,000	Mangāon	4,800,000	...
Pātarra	3,342,500	1,262,500	Mahen	600,000	280,000
Bānbahar	1,568,000	668,000	Malkāpur	11,200,000	...
Badner Bhuli	2,764,450	364,452	Melgarh, (from pro-		
Badner Kānka	4,813,700	13,800	ceeds of road tolls		
Jalgāon	10,000,000	2,000,000	or safe-conduct		
Jaipur	400,000	...	passports)	94,360	...
Chāndor	4,687,000	87,000	Karyāt Rājōr	400,000	170,356
			Nādura, (Nandura)	1,200,000	...
			Qasbah Hatgāon ..	1,500,000	300,000

Sarkār of Kallam (Kalāmb).

Containing 31 *Parganahs*. Revenue 32,828,000 *Dāms*
in money.

	Revenue D.		Revenue D.
Indori [Undri] ...	1,200,000	Qasba Kallam ...	500,000
Amrāoti ...	1,200,000	Kelāpur ...	1,200,000
I'ni [Anjni] ...	1,600,000	Lādkher ...	1,600,000
Punah [? Pusda] ...	3,600,000	Nāigāon ...	960,000
Bori ...	1,200,000	Nachangāon ...	640,000
Belur ...	2,800,000	Yunt Lohārā [? Noni L.]	128,000
Tālegāon ...	100,000	Barkhonda or Tark Chanda	
Talegaon, Waigāon ...	4,800,000	(in the possession of a	
Dungar ...	1,600,000	Zamīndār) ...	
Rālegāon ...	200,000	Malbori ...	
Sālod ...	3,200,000	Chandur ...	
Kurha ...	960,000	Lahubāti [? Lohagarh] ...	

Sarkār of Bāsim.

Containing 8 *Parganahs*. Revenue 32,625,250 *Dāms*
in money. *Suyurghāl* 1,825,250.

	Revenue D	Suyur- ghāl D		Revenue D	Suyur- ghāl D
Aunda ..	4,864,000	64,000	Chār Thāna ..	4,800,000	1,600,000
Suburb. dist. of Bā- sim, Rājput, 100			Kalambuh Nūri ..	3,200,000	
horse, 1,000 foot ..	8,161,250	161,250	Karari and Bāmni ..	1,200,000	
Bāthi [Pathri] ..	2,400,000	...	Manglur ..	3,200,000	
			Narsi ..	4,800,000	

Sarkār of Māhur.

Containing 20 *Parganahs*. Revenue 42,885,444 *Dāms*
in money. *Suyurghāl* 97,844 *Dāms*.

	Revenue D.		Revenue D.
Ansing ...	960,000	Pūsād ...	4,000,000
Amar Kher ...	6,400,000	Tāmsā ...	2,177,844
Chikni ...	3,200,000	Seoli ...	64,000
Chincholi ...	2,400,000	Giroli ...	3,200,000
Suburb. dist. of Māhur, with		Khenot ...	1,300,000
Qasbah, of Surah, <i>Suyur-</i>		Korath [Korandh] ...	480,000
<i>ghāl</i> 97,844 ...	3,680,000	Meṭh [Mantha] ...	2,400,000
Dhārwalh ...	2,400,000	Mahāgāon ...	1,600,000
Dhānki [Dhamni] ...	320,000	Nāndāpur ...	2,000,000
Shevālā ...	2,400,000	Hald Bādhonā

Sarkār of Manikdrug.

Containing 8 *Parganahs*. Revenue 14,400,000 *Dāms* in money.

	Revenue D.		Revenue D.
Papal	3,400,000	Rājor	2,400,000
Bhān	2,000,000	Karath	2,000,000
Chāndor	2,400,000	Nair	1,600,000
Jāir [? Jaora] ...	1,600,000		

Sarkār of Pāthri.

Containing 18 *Parganahs*. Revenue 80,805,954 *Dāms* in money. *Suyurghāl* 11,580,954 *Dāms*.

	Revenue D	Suyur- ghāl D		Revenue D	Suyur- ghāl D
Ardhāpur	1,600,000	...	Jahri [Jherree] ..	1,600 000	400,000
Suburban district of			Shevli	3 600,000	1,200,000
Pathri	25,114,740	5,014,740	Kosri	3,200 000	...
Parbani	8,000 000	...	Lohgāon	4,800,000	1,600,000
Pānchalgāon	2 000 000	...	Makat Mādhkher ..	2,400 000	...
Ralhor [Valur] ..	2,400 000	...	Mātargāon [? Māne- gaon]	480,000	160,000
Basmat	11,200 000	...	Nander	6,871 203	471,209
Bārad	160,000	...	Wasā	400,000	...
Tākli	640,000	...	Hātā	1,200,000	240,000
Jintor	3,600,000	1,200,000			

Sarkār of Telingāna.

Containing 19 *Parganahs*. Revenue 71,904,000 *Dāms* in money. *Suyurghāl* 6,600,000 *Dāms*.

	Revenue D.		Revenue D.
Indur	4,800,000	Qaryāt Khudāwand Khān ...	640,000
Ullah	800,000	Dhakhwār [? Deglur] ...	96
Bodhan, <i>Suyurghāl</i> 4,400,000	8,000,000	Rājor, <i>Suyurghāl</i> 800,000	1,600,000
Bāsar, <i>Suyurghāl</i> 400,000	1,600,000	Kotgir, <i>Suyurghāl</i> 1,000,000	2,200,000
Bhaisa	6,400,000	Kharki	6,400,000
Bālkondā	6,400,000	Kosambet	664,000
Bimgal [Potangal] ..	2,400,000	Luhgāon	11,200,000
Bānorā [Banauli] ...	3,200,000	Mudhol	6,400,000
Blukar	1,600,000	Nirmal	6,400,000
Tamburni	1,600,000		

Sarkār of Ramgarh [= Rāmgir]

Containing 5 *Parganahs*. Revenue 9,600,000 *Dāms* in money.

	Revenue D.		Revenue D.
Bal Arab	800,000	Khandwah [? Khandar] ...	2,240,000
Subab. dist. of Rāmgir	2,560,000	Mul Marg	800,000
Chinur	3,200,000		

SUBAH OF GUJARAT.

It is situated in the second climate. Its length from *Burhānpur* to *Jagat* [i.e., *Dwārkā* in *Kathiawar*] is 302 *kos*; its breadth from *Jālor* to the port of *Daman* 260 *kos*, and from *Idar* to *Kambhāyat* (*Cambay*) 70 *kos*. On the east lies *Khāndes*; to the north *Jālor* and *Idar*; to the south, the ports of *Daman* and *Kambhāyat*, and on the west, *Jagat* which is on the seashore. Mountains rise towards the south. It is watered by noble rivers. Besides the ocean, there are the *Sābarmatti* (*Savarnamati*), the *Bātrāk*, the *Mahendri*, the *Narbadah*, the *Tapti*, the *Saraswati*, and two springs called *Ganga* and *Jamna*. The climate is temperate and the sandy character of the soil prevents it from turning into mud in the rainy season. The staple crops are *Jowāri*, and *Bājra*, which form the principal food of the people. The spring harvest is inconsiderable. Wheat and some food grains are imported from *Mālwa* and *Ajmer*, and rice from the *Deccan*. Assessment is chiefly by valuation of crops, survey being seldom resorted to. The prickly pear is planted round fields and about gardens and makes a goodly fence, for this reason the country is difficult to traverse. From the numerous groves of mango and other trees it may be said to resemble a garden. From *Pattan*¹ to *Baroda* which is a distance of a 100 *kos*, groves of mango yield ripe and sweet fruit. Some kinds are sweet even when unripe. Fine figs grow here and musk-melons are delicious in flavour both in summer and winter, and are abundant during two months in both seasons. The grapes are only moderate in quantity: flowers and fruit in great plenty. From the thick growth of forest sport is not satisfactory. Leopards² abound in the wilds.

The roofs of houses are usually of tiles and the walls of burnt brick and lime. Some prudently prepare the foundations of stone, and of considerable breadth, while the walls have hollow spaces between, to which they have secret access. The usual vehicles are two-wheeled drawn by two oxen. Painters, seal-engravers and other handicraftsmen

¹ I. G. Anhilwāra *Pattan*, lat. 23° 51' 30" N., long. 72° 10' 30" E. on the *Saraswati*, one of the oldest and most renowned towns of *Gujarāt*.

² The term *yuz* is employed in *Āin* 27 and 28 Vol. I, (Book II) for leopards generally including the hunting leopard, (*F. Jubata*), being used indifferently with the common name for the latter, *chilū*.

are countless. They inlay mother-o'-pearl with great skill and make beautiful boxes and inkstands. Stuffs worked with gold thread and of the kinds *Chirah*, *Fotah*,¹ *Jāmahwār*, *Khārā*, and velvets and brocades are here skilfully manufactured. Imitations of stuffs from Turkey, Europe, and Persia are also produced. They make likewise excellent swords and daggers of the kinds *Jamdhār*² and *Khaphwāh*, and bows and arrows. There is a brisk trade in jewelry and silver is imported from Turkey and Irāq.

At first *Pattan*³ was the capital of the province, next *Champāner* and at the present day, *Ahmadābād*. The latter is a noble city in a high state of prosperity, situated on the banks of the *Sābarmattī*. It lies in latitude 25°. For the pleasantness of its climate and its display of the choicest productions of the whole globe it is almost unrivalled. It has two forts, outside of which are 360 quarters of a special kind which they call *Pura*,⁵ in each of which all the requisites of a city are to be found. At the present time only 84 of these are flourishing. The city contains 1,000 stone mosques, each having two minarets and rare inscriptions. In the *Rasulābād Pura* is the tomb of *Shāh Aālam Bokhārī*. *Batwāh*⁶ is a village 3 kos from

¹ See p. 52, (note II) Vol. II, Book III, and pp. 93—95 of Vol. I, B. I. *Chirah* is a parti-coloured cloth used for turbans. *Jāmahwār*, is a kind of flowered woollen stuff, well known, *Khārā* an undulated silk cloth.

² See p. 110, Vol. I, Book I.

³ Of successive dynasties of Rājput kings from 746 to 1194 A.D. *Champāner* was taken by Mahmud (Bigārah) of Ahmadābād after a siege, it is said, of 12 years and was made his capital and continued to be that of the Gujarāt kings till about 1560 A.D. I. G.

⁴ Lat. 23° 1' 45" N., long. 72° 38' 30" E. The Emperor Aurangzeb had a different opinion of its climate and called it among other abusive epithets, *Jahannumābād* or the Abode of Hell. See Bayley, p. 91.

⁵ A quarter or ward of a town, having its own gateway. The I. G. has *pol* and describes it as a block of houses varying in size from small courts of 5 or 10, to large quarters of the city containing as many as 10,000 inhabitants. The larger blocks are generally crossed by one main street with a gate at each end and subdivided into smaller blocks each with its separate gate branching off from the chief thoroughfare.

⁶ The text has *Patwāh*, the variant *Batwāh* being relegated to the notes, but the best authorities concur in the latter reading. For Qutb-i-Aālam, see Bayley, p. 128, and Briggs' *Cities of Gujarashtra*, p. 292. Regarding the lithoxyle over the tomb, Briggs writes that one of the legends given him concerning it is that Qutb-i-Aālam on a journey to his masjid tripped against a stone and picking it up, said, "Can this be stone, wood or iron?" and the combination ensued. A visitor who had preceded Briggs on a visit to this place wrote to him as follows: "The size mentioned by Abul Fazl is correct. The stone is not now on the sepulchre but deposited in the chief Said's house. Great reverence is paid to it and on such occasions as visitors desire to see it, it is produced under a covering of brocade. It appears to be petrified wood, the barky part gives it the appearance of iron oxydised; that portion where it has been chipped by the hand of Akbar when he visited Batwa (according

Ahmadābād where are the tombs of *Qutb-i-Aālam* father of *Shāh Aālam*, and of other eminent personages. In the vicinity are fine gardens. Over the tomb is suspended a covering of about the measure of a cubit, partly of wood, partly of stone and a part also of iron, regarding which they relate wonderful stories. At a distance of three *kos* is the village of *Sarkhech* (*Sarkhej*) where repose *Shaikh Ahmad Khattu*,¹ *Sultān Ahmad* after whom *Ahmadābād* is named, and many other princes. Indigo of good quality is here grown and exported to Turkey and other countries.

Twelve *kos* from *Ahmadābād* is *Mahmudābād* a city founded by *Sultan Mahmud*, in which are beautiful buildings extending to an area of 4 *kos* square. The whole is surrounded by a wall and at every half *kos* is a pleasure house and a preserve in which deer and other kinds of game are at large.

The chief of *Idar* is a *Zamindār* named *Narāin Dās*, and of such austere life that he first feeds his cattlẽ with corn and then picks up the grains from their dung and makes this his food, a sustenance held in much esteem by the *Brāhmans*. He is regarded as the head of the *Rāthor* tribe and has a following of 500 horse and 10,000 foot.

The ports of *Ghoga* and *Kambhāyat* (*Cambay*) are included in this (*Gogo*) *Sarkār*. The latter is a large city where merchants of divers kinds reside and wherein are fine buildings and much merchandise. Vessels sail from and trade to *Ghogah*. The cargoes are put into small ships called *Tawari* which transport them to *Kambhāyat*.

In *Kari* are fine oxen, a pair being worth 300 rupees, and according to their shapeliness, strength and speed fetching even a larger price.

Jhālāwār was formerly a separate principality containing 1,200 villages. Its length is 70 *kos* and its breadth 40. It furnished 10,000 horse and the same number of infantry. Now it possesses but 2,000 horse and 3,000 foot. Its ruler was subject to the king of *Gujarāt*. It formed four divisions, the inhabitants mostly of the *Jhāla* tribe of *Rājputs*.

to the Abbot of the community) shews the fibre or vein of the wood; and upon the opposite side, where it seems to have been ground crosswise, it bears the appearance of stone."

¹ See Bayley's *Hist. of Gujarāt*, pp. 90 and 130. A description of these mausoleums will be found in Messrs. Hope and Fergusson's "*Architecture of Ahmedābād*." London Murray, 1866. *Khattu* is one of the towns in the *Sarkār* of *Nāgor*. Cf. Briggs' *Cities of Gujarashtra*, p. 275.

At the present day it is accounted a *Pargana* of Ahmadābād, and its villages and districts are summarized in the following table.

Great Jhālāwār contains *Birāmgāon* residence of the chief, *Halod*, *Wadhvān*, *Koha*, *Daran Gadra*, *Bijānā*, *Pātri* which has a salt-pit, *Sahālā*, *Baroda*, *Jhinjhuwārā*, *Sanjān*, (? *Sanand*), *Dhulhar*, *Mandal*.

Parganahs of *Machhukhantā* contain *Morbi*, *Rāmpur*, *Tankārā*, *Khanjariā*, *Malia*, *Kazor*, in the vicinity of which pearls are found, *Dhansar*, *Amrol* (*Amreli*).

Parganahs of *Jāmbuji* contain *Jāmbu*, *Limri*, *Siāni*.

Parganahs of *Chaubisi*, chief seat of the *Parmār* tribe contain *Morbi*, with 36 villages and *Chotilā* with 55 villages. Now *Morbi* with 7 districts is included in *Sorath*.

Pattan has two forts, one of stone and one of brick. It lies in long. $117^{\circ} 10'$, lat. $23^{\circ} 30'$. It produces fine oxen that will travel 50 *kos* in half a day. Good cotton cloths are here woven and are taken to distant parts as gifts of value.

Sidhpur is a town on the *Sarsuti* and a great place of pilgrimage.

Barnagar [*Vadnagar*] is a large and ancient city and containing 3,000 pagodas, near each of which is a tank; it is chiefly inhabited by *Brāhmans*.

Chāmpāner is a finely situated fort on a crag of great height¹; the approach to it for two *kos* and a half is extremely difficult. Gates have been posted at intervals. At one place a cutting about 60 yards long has been made across which planks are laid which can be removed when necessity arises. Fine fruits abound.

Surat is a celebrated port. The river *Tapti* runs by it and at a distance of 7 *kos* thence, falls into the sea.

Rānder on the opposite side of the *Tapti* is a port dependent on *Surat*; it was formerly a large city. The ports of *Khandewi* and *Balsār* also are a part of the *Surat* division. Numerous fruits abound especially the pine apple, and oils of all kinds and rare perfumes are obtainable. The followers of Zoroaster coming from Persia, settled here. They follow the teaching of the *Zend* and the *Pāzend*, and erect funeral structures. Thus through the wide tolerance of His Majesty, every sect enjoys freedom. Through the negligence of the ministers of state and the commanders of the frontier pro-

¹ Tieffenthaler states that the fortress on the summit of the hill is called *Panagarh* and the town at its foot *Chāmpāner*.

vinces, many of these *Sarkārs* are in the possession of European nations, such as *Daman*, *Sanjān*,¹ *Tārāpur*, *Māhim* and *Base* (Bassein) that are both cities and ports.

Bharoj (Broach) has a fine fort. The *Narbada* flows past it in its course to the ocean. It is accounted a maritime town of first rate importance, and the ports of *Kāwi*, *Ghandhār*, *Bhābhut* and *Bhankorā* [Bhakora] are its dependencies.

Near the town of *Hānsot* is a game preserve 8 *kos* in length by 4 in breadth, full of deer and other animals. The cover is rich and fresh with verdure, being situated on the banks of the *Narbada* and is perfectly level.

The *Sarkār* of *Sorath*² was an independent territory, having a force of 50,000 cavalry and 100,000 infantry, the ruling tribe being *Ghelot*. Its length from the port of *Ghogo* (Gogo) to that of *Arāmdāc*³ is 125 *kos*; its breadth from *Sardhar* (? *Sadra*, n. of Ahmadabad) to the seaport of *Diu*, 72 *kos*. On the east it is bounded by *Ahmadābād*; on the north by the State of *Kachh* (Cutch); on the south and west by the (Indian) Ocean. Its climate is healthy, its fruits and flowers numerous and grapes and melons grow here. This territory is divided into 9 districts each inhabited by a different tribe, as follows:—

Parganahs of new Sorath.

Junahgarh with suburban district, *Sultānpur*, *Barwa* [Bantva], *Hānsāwar*, *Chaura Rāmpur*, *Kandolnā*, *Hast Jati*, *Und*, *Bagsarā*, *Mahandrā* [Mandurda], *Bhāntror* [Ghantwar], and others.

Parganahs of old Sorath, called Nāghar.

Pattan Somnāth, *Aunah*, *Delwārah*, *Manglor*, *Korinār*, *Mul Mahādeo*, *Chorwār*, *Diu*, &c.

Parganahs of Gohelwārah.

Lāthi, *Luliyānah*, *Bhimpur*, *Jasdhom*, *Māndwi*, *Birāi*, *Sehor*.

¹ A small village in Thānā (Tanna) Dist., where the Parsis first landed in India, known to the Portuguese and long after their time as St. John. I. G.

² The old name for Kāthiawār, or Saurāshtra and Prakritised in that of Sorath which is to this day the name of a large district 100 miles in length in the south-west.

³ *Aramda*, near port Okha, n. of Jagat Dwarka,

*Parganahs of Wālā.**Mahwah, Talājā, Pālītānah, &c.**Parganahs of Bādhelāh.**Jagat* (called *Dwārkā*), *Arāmdāc*, *Dhārhi* (? *Sanku-dhār*).*Parganahs of Barrā. (Berda ?)**Barrā, Gumli, &c.**Parganahs of the Bāghelā¹ tribe.**Sordhār, Gondāl, Rāyet, Dhānak, &c.**Parganahs of the Wājī in the uncultivated tracts.*
*Jhānjhmer.**Parganahs of the Timbel tribe.*

Not assigned in any of the MSS.

The first district known as New *Sorath* had remained unexplored on account of the impenetrable nature of the forests and the intricate windings of the mountains. A recluse by chance found his way into it and through him a knowledge of it was gained. Here is the celebrated stone fortress of *Junahgarh* which Sultān Māhmud,² I, captured by force of arms and at the foot of it built another fort of stone. At a distance of 8 *kos* is the fort of *Osam* on the summit of a hill; it has now fallen into decay, but is worthy of restoration. There is also another stronghold on the summit of the hill of *Girnār* in which are many springs, a place of worship of the *Jains*. Adjacent is the port of *Kondi Kolidyā*,³ which derives its name from two villages at a distance of one *kos* from it. In the rear of *Junahgarh* is an island called *Siālkokah* 4 *kos* in length by 4 in breadth,

¹ The I. G. (I. 550) calls this clan Wāghelā tribe of Rājputs, a remnant of the Solanki race who fled from Anhilwārah when that kingdom was destroyed by Alā u'd din in A.D. 1297.

² Bigarāh of Gujārāt. One derivation of this name is its supposed meaning of two forts (*garh*) because Mahmud's army conquered on one day Chāmpāner and Junahgarh, Vol. I, p. 506, n. According to T. Junahgarh signifies the ancient fort, because it was long concealed in the dense forest and discovered by a wood cutter. The legend runs that 1500 years elapsed from its discovery to the time of Māndalik from whom Mahmud wrested the fortress. See Bayley's Hist. of Gujārāt, pp. 161—182, for the derivation of the name.

³ Far. and G. Kondi or Gondilakiyāt. [Can it be *Kodinar*?]

adjacent to which is a forest, 3 *kos* square, where wild fruits grow and where there is a settlement of *Kolis*. This tract is called *Gir*. Near the village of *Tunkagosha*,¹ the river *Bhādar* falls into the ocean. Its fish are so delicate that they melt when exposed to the sun. Good camels are here obtainable and a breed of horses somewhat larger than the *Gunth*.

In the second district is *Pattan*, a city on the seashore possessing a stone fort. This they call *Pattan Somnāth*. It is both a capacious harbour and a town having nine² stone towers on the plain, within an area of three *kos* on the seashore. Good swords are made here, there being a well in the vicinity the water of which gives them a keen edge.

The ports of *Manglor*,³ *Diu*, *Purbandar*, *Korinār*, *Ahmadpur* and *Muzaffarābād* are about this coast. A spring of the *Sarsuti* (*Saraswati*)⁴ rises near *Somnāth*. The Brahmanical shrines are numerous, but among these *Somnāth*, *Parānchi*, and *Korinār* are accounted among the most sacred. Between the rivers *Haran* and *Sarsuti* about 4,000 years ago, 560,000,000 of the *Yadu* race while engaged in sport and merriment, fell to fighting and all of them perished in that field of death, and wonderful are the legends that they relate. Two and a half *kos* from *Pattan Somnāth* is *Bhāl ka Tirth*⁵ (or the shrine of the Arrow). In this place an arrow struck *Sri Kishn* and buried itself under

¹ A note says *Tunkragosā*, in the maps. There are two rivers of the name of *Bhādar*; one rises in the *Māndav* hills and flowing S. W. falls into the sea at *Nawi-Bandar* after a course of 115 miles. Another from the same hills, flowing E. falls into the Gulf of Cambay. The *Kolis* are a predatory tribe and their distribution is not confined to a single province. They were spread over the country between Cambay and *Ahmadābād* and the well-wooded country afforded them a refuge from attack.

² Gladwin has turned these words into a name which mistranslation I notice as it has been adopted by Count von Noer in his monograph on Akbar, p. 98. (Mrs. Beveridge's Trans.). The *Diwān* of Junagarh, *Haridās Viharidās*, has courteously given me the benefit of his local knowledge. The new temple and the ruins of the old are within the fort which was inhabited chiefly by the attendants of the shrine, the population living in the environs forming the town. *Pattan* is said to have had three walls and hence named *Trigadhi*. The length of the present walls covers nearly two miles. The fort had or has 10 towers or bastions of which 8 are existing and two are in ruins.

³ The I. G. gives *Mangrol*. The text unites *Diu* and *Purbandar* (elsewhere *Porbandar*) in one name, as *Somnāth* is called *Deo Pattan*, but it is probable that the port of *Diu* was intended by *Abul Fazl*.

⁴ The river rises in Mount Abu and enters the *Runn* of Cutch, though a part of its course near *Siddhpur* and *Patan* towns, is said to be subterranean.

⁵ Apparently the *Bhāl Kund* of the I. G. *Yudhisthira* after the slaughter of the 56 tribes of the *Yadu* race on the field of *Kurukshetra* and the death of *Duryodhana*, in grief at the loss of so many kinsmen, placed *Parikshita* on the throne of *Indraprastha*, and retired with *Krishna* and *Baldeo* to *Dwarka*. They were attacked by the *Bhils* and *Krishna* was slain. *Baldeo* founded the city of *Patalibotra* or *Patna*.

a *pipal* tree on the banks of the *Sarṣuti*. This they call *Pipal sir*, and both these spots are held in great veneration. An extraordinary event occurs at the town of *Mul Mahādeo* where there is a temple dedicated to Siva. Every year on a certain day before the rainy season, a bird called *Mukh*¹ appears. It is somewhat smaller than a pigeon, with a coarser beak and pied in colour. It alights on the temple, disports itself for a while, and then rolls over and dies. On this day, the people of the city assemble and burn various kinds of perfume and from the proportions of black and white in the plumage of the bird, they calculate the extent of the coming rainfall, the black portending rain, the white, drought. In this tract, there are three crops of *jowar* annually. At *Unah* there are two reservoirs, one of which is called *Jamna*, the other *Ganga*. The water bubbles up and forms a stream and the fish of these two springs have three eyes, the third eye being in the forehead.

Between *Manglor* and *Chārāwār* is a tract into which the sea enters. On a certain day of the year the water is sweet. It is related that in ancient times a certain person was in need of Ganges water. A recluse made a sign to the expanse and sweet water came forth. Ever since, upon that day this wonder is repeated to the astonishment of all.

In both of these districts the *Ghelot* tribe of Rājputs prevail and the ruling power in this country is in their hands. At the present time the force (of the first district) consists of 1,000 horse and 2,000 foot. There is also a settlement of Ahirs called *Bābriyas*.² The force (of the second district) is 2,000 horse and 3,000 foot.

In the third district at the foot of the *Satrunjah* (Satrunjaya) hill,³ is a large fort and on its summit, the fort of *Pālithānah*. Though in ruins, it deserves restoration. It is in great veneration with the *Jains*. The port of *Ghoga* (Gogo) is a dependency of this district. The island of *Biram* (Perim) was formerly the residence of the governor; it is 9 *kos* square and is a low rocky island in

¹ Or *Makh*. In a work called *Haqiqat-i-Hindustān*, the word is *Sakh* or *Sukh*. See Bayley, p. 197, who records this event and places it in the village of Madhopur.

² The name of one of the old territorial *prants* or districts into which Kāthiawār was divided, was called Bābriawār, a hilly tract on the S.E.

³ The hill is sacred to Adināth the deified priest of the *Jains*. The description of Pālithāna in the I. G. taken from Mr. Burgess' "Notes of a visit to Satrunjaya Hill," gives an interesting sketch of this temple hill. Perim (the Baiones of the *Periplus*) is in the Gulf of Cambay, 8 miles S. of Gogo.

the midst of the sea. The *Zamindār* is of the *Gohel*¹ tribe. This district possesses 2,000 horse and 4,000 foot.

In the fourth district, are the ports of *Mohwah* and *Talājā*, inhabited by the *Wali* clan. The local force consists of 300 men and 500 foot.

In the fifth district is *Jagat*, called also *Dwārka*. *Sri Krishna* came hither from Mathura (Muttra) and here died. It is a great Brahmanical place of worship. The island of *Sankudhār* [Bait] 4 *kos* square is reckoned within this district. Near *Arāmdāe* is an island 70 *kos* in length and breadth. An area of half a *kos* of this land is for the most part stony and if an excavation is made salt-water pours in on all sides. *Malik Ayās*² *Khās Khel*, of Sultān Mahmud I of Gujerāt, had, one-fourth of it dug up. The port of *Arāmdāe* is superior to most of its class. The inhabitants are of the *Bādhel* tribe. It musters 1,000 horse and 2,000 foot.

In the sixth district *Barra*,³ the country is so hilly, the forests so impenetrable and the defiles so extensive that it is impassable for troops. The *Jaitwah* clan inhabit it. It furnishes 1,000 horse and 2,000 foot.

In the seventh district are the *Baghelahs*. It furnishes 200 horse and the same number of foot. The *Kāthis*⁴ are numerous in this tract; they are of the *Ahir* caste and are skilful in the management of horses. The military force is 6,000 cavalry and 6,000 infantry. They are said by some to be of Arabian origin. Cunning but hospitable, they will eat of the food of people of every caste, and are a handsome race. When any *Jagirdar* comes amongst them they make it a condition that there shall be no account

¹ The *Gohels* came from the north in the 13th century, and retreating before the tide of Muhammadan conquest conquered for themselves new seats in the decadence of Anhilwāra. They are now in B. Kāthiawār.

² See Bayley's Hist. of Gujerāt, p. 233 et seq. *Khās Khel* represents the position of a royal equerry combined with high command. Ferishta calls him the *ghulām-i-khās* or confidential attendant of Mahmud. He was premier noble (Amir u'l Umarā) and commander in chief of the army, fought and defeated the Portuguese fleet at Chaul and sank the admiral's flagship valued at a *kror* of rupees. (A.H. 913—A.D. 1507).

³ I have no doubt that this is Bardā (or Jaitwār) of the I. G.; a division of Kāthiawār lying between 21° 11' and 21° 57' N. lat., and 69° 30' and 70° 7' E. long., bounded N. and N.-E. by Hallār; E. by Sorath, and S.-W. by the Arabian Sea. The Barda hills are from 12 to 18 miles distant from the coast and formed a favourite refuge for outlaws.

⁴ The name of Kāthiawār, was formerly given to a tract to the B. of the centre of the peninsula; from having been overrun by the Kāthis who entered from Cutch in the 13th and 14th centuries, it was extended to the whole country by the Mahrattas who had come into contact with them in their forays.

taken of the incontinence of any of their people. In the vicinity of the *Kāthīs* on the banks of the river *Dondī*, there is a sept of *Ahirs* called *Porechas*. Their force is 3,000 horse and the same number of foot. They are perpetually at feud with the *Jāms*.¹

In the eighth district *Jhānjhmer* is a maritime port. The *Wāji* tribe prevail. There are 200 horse and 2,000 foot.

In the ninth district is the *Chāran* tribe. Mahadeva formed a man from the sweat of his brow and gave him the charge of his own bull. He spoke in rhythmic sentences and sang the divine praises and revealed the past and the future. His descendants are known by his name. They chiefly recite panegyrics and genealogies and in battle chant deeds of valour and animate the warriors and some of them reveal future events. There are few of the nobles of *Hindustān* who have not some of these in their retinue. This district furnishes 500 horse and 4,000 foot. The tribe called *Bhāt* resemble this caste in their panegyrics, their powers, their battle-chants, and genealogical recitations, and although in some of these respects they surpass them yet the *Chārāns* are better swordsmen. Some pretend that the *Chārāns* were called into life by the mere volition of the divinity, and the *Bhāts* from *Mahādeva*.

Between *Jhālwāra* in the *Sarkār* of *Ahmadābād*, and *Pattan* and *Sorath* is a low-lying tract, 90 *kos* in length by 7 to 30 in breadth, called the *Ran*² (the Runn). Before the rainy season, the sea rises and covers this area and falls as the rains cease. A considerable part dries up and is covered with salt, the duties of which are collected in the *pargana* of *Jhālwāra*. *Ahmadābād* lies to the east of this tract. On the west is a large separate territory called *Kachchh* (Cutch) 250 *kos* in length by 100 *koṣ* in breadth. *Sind* lies to the

¹ The *Jāreja* : *ijputs*, to which branch the Rao of Cutch belongs, are descended from the *Summa* (*Sama*!) tribe and came originally from the north. They are said to have emigrated from *Sind* about the 15th century under the leadership of *Jā Lākha*, son of *Jāra* from whom the tribe derive their name. Till 1540 the *Jāms* ruled over Cutch in three branches. About that year *Khengār* succeeded in making himself head of the tribe and master of the province. His uncle *Jām Rāwal* fled to *Kāthiawār* and founded the present reigning house of *Nawanagar*, the rulers of which are still called *Jāms*. See *Jām* under the account of *Sind*.

² The word in Hindi signifies a waste or wilderness. There are two, the northern or larger Runn, 150 by 80 miles has an area of about 7,000 square miles. The eastern or smaller Runn, 70 miles from E. to W., covers an area of 2,000 square miles. Except a stray bird, a herd of wild asses, or an occasional caravan, no sign of life breaks the desert loneliness. *I. G.*

west of Cutch. The physical aspect of the country is barren and sandy. There is an excellent breed of horses believed to be of Arabian race, and there are good camels and goats. The chief of this country is of the *Yadu*¹ race and his tribe is now known as *Jārejas*. The military force of this clan is 10,000 cavalry and 50,000 infantry. The men are handsome, tall in stature and wear long beards. The residence of the chief is *Bluj*, which has two strong forts *Jhārah* and *Kantkot*. On the Gujarāt side towards the south is a *Zamindār* of note whom they call *Jām*, a relative of the ruler of the above-mentioned state. Sixty years ago, *Jām Rāwal*, after a war of two months, was driven out of the country, and settled in *Sorath* between the territories of the *Jaitwah*, *Bādel*, *Chāran*, and *Tumbel* tribes. He possessed himself of other parts and founded the city of *Nawanagar* and his country received the name of *Little Cutch*. *Sattarsāl* the present *Rājah*, is his grandson. There are many towns and the agricultural area is extensive. The residence of the chief is at *Nawanagar* and his force consists of 7,000 cavalry and 8,000 infantry. The camels and goats are of good breeds. For a considerable period the prime ministers of these two states have been of the Muhammadan religion.

In the vicinity of *Morā* and *Mangrej* is a state called *Pāl*² through which runs the river *Mahendri* towards the Gujarāt side. It has a separate ruler who resides at *Dungarpur*. On the Mālwa side is *Bānswāra* and that too has a separate chief. Each of them has a force of 5,000 horse

¹ The lunar race established by the Scythian Budh, expanded into fifty-six branches and filled nearly the whole of northern India. *Yadu* 4th in descent from Budh gave his name to the royal line which closed in Krishna and Balrāma. While the solar race was confined to a narrow strip of land between the mountains and the Ganges, the *Yadus* had spread over the whole country. *Yadu*, says Elliot, (*Races of the N.-W. P.*, Vol. I, 128) is the patronymic of all the descendants of Buddha, the ancestor of the Lunar race, of which the Bhatti and the Jāreja are now the most conspicuous, but the title of *Jādon* is now exclusively applied to that tribe which appears never to have strayed far from the limits of the ancient Suraseni, and we consequently find them in large numbers in that neighbourhood. The tract south of the Chambal called after them *Yaduvati* is in the possession of the Gwalior Mahrattas and the state of Kirauli on the Chambal is now their chief independent possession.

² *Pāk* in the text, with the emendation *Pāl* by the Editor. There are two of the name, one within Māhi Kānta on its N. E. frontier. The other one of the petty states in Hallār, Kathiawār. The former must here be meant, as *Dungarpur* lies in lat. 23° 52' N., long. 73° 49' E. It is now a separate native state. The early history of the ruling family is not known with certainty; they paid tribute to the Mughal Empire and did military service, and on the fall of the Empire became tributary to the Mahrattas. I. G. The name *Pāl* says Bayley, seems to have been given to a congeries of petty hill states of which the rulers were Hindus. They appear to have included *Dungarpur*, *Bijanagar* and others.

and 10,000 foot, and both are of the *Sisodia* clan. The rulers were of the Rānā's family, but for some time past it has been otherwise.

Adjoining the *Sarkār* of Pattan is a state, the chief town of which is *Sirohi* and which possesses a force of 2,000 horse and 5,000 foot. On the summit of a hill is the strong fortress of *Abugarh* (Mount *Ābu*) about which are 12 flourishing villages. Pasturage is plentiful.

There is also a territory having *Nandurbār* on the east, *Mandu* on the north, *Nandod* on the south and *Chāmpāner* on the west. Its length is 60 *kos*, and its breadth 40. The chief is a *Chauhān* and his residence is the town of *Āli Mohān*. Wild elephants are numerous. The force consists of 600 horse and 15,000 foot.

Between *Surat* and *Nandurbār* is a mountainous but flourishing tract called *Baglāna*, the chief of which is a *Rathor*, commanding 3,000 cavalry and 10,000 infantry. Fine peaches, apples, grapes, pineapples, pomegranates, and oranges grow here. It possesses seven remarkable forts, among which are *Mulher*¹ and *Salher*.

Between the *Sarkārs* of *Nandod* and *Nandurbār* is a hilly district 60 *kos* in length by 40 in breadth, which the *Gohel* tribe of *Rājputs* inhabit. At the present day a *Brāhman* named *Tewāri* has the management of affairs, the titular *Rajah* being of no account. He resides at *Rājpipla* or *Khulu*, and has a force of 3,000 horse and 7,000 foot. The water of this tract is very unwholesome. Rice and honey of the finest quality are here produced.

This *Subah* embraces 9 *Sarkārs* and 198 *Parganahs*, of which 13 are ports. The revenue is 43 *krors*, 68 *lakhs*, 22,301 *dāms* (Rs. 10,920,557-8-0) and one *lakh*, 62,028 $\frac{3}{4}$ *Mahmudis*² as port dues.

The measured land (except *Sorath* which is paid in money by estimate) is 1 *kror*, 60 *lakhs*, 36,377 *bighas*, 3 *biswas*, out of which 4 *lakhs*, 20,274 *dāms* are *Suyurghāl*. The local force is 12,440 cavalry, and 61,100 infantry.

¹ Both these lie in the Navasari (Nosari) district of the Baroda territory, the latter in the S. E. corner. Songarh and Rupgarh are two other forts. The former 43 miles E. of Surat, and Rupgarh 10 miles S. of Songarh. The hills must refer to the Rājpipla range, there being no other in the whole territory.

² Mr. E. Thomas (*Numismatic Chronicle*, Vol. III, 3rd series) quotes Sir T. Herbert as saying about 1676 A.D. "A mahmudi is twelve pence, a rupee two shillings and three pence." See Bayley's *History of Gujarāt*, p. 16. The relative value of coin varied according to time and locality. The Changezi Mahmudi is variously valued at half and two-thirds of a rupee and at half a crown, French money. *Ibid*, pp. 12 and 16,

Sarkār of Ahmadābād.

Containing 28 *Mahals*. 8,024,153 *Bighas*. Revenue 208,306,994 *Dāms*. *Suyurghāl* 6,511,441 *Dāms*. Castes various. Cavalry 4,120. Infantry 20,500.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
City of Ahmadābād	15,000,073	144,680	100	300	
Suburb. dist. of Ahmadābād	370,087	23,999,371	4201,783	
Rurdhu Matar (<i>mis.</i> Arhar M.) on the river Baroli	145,384	9,662,753	160,938	100	200	Chauhān.
Ahmadnagar has a stone fort faced with <i>chunam</i>	54,370	1,770,912	50,774	500	5,000	Solanki.
Adar, [revenue by estimate of crops]	1,616,000	...	1000	5,000	Garāsiah ¹
Bahiel ...	375,675	6,988,920	...	100	200	Rājput.
Bārah Sewah [Bāla Sinor]	84,960	2,814,124	5,608	50	100	Bhodia
Birpur [? Pithapur] has a stone fort on the Mahen- dri ...	173,385	1,778,300	...	300	600	Rājput, Lodiali. Rājput, Kharbā and Bonah.
Paplod [Palod] ...	39,930	1,493,249	...	50	100	Rājput.
Parāntij ...	159,273	2,076,574	...	100	200	Ol.
Bandar Solah [? Bhadarwa] (revenue in money)	600,000	
Petlād	771,960	128,990	
Thāmanah [? Thāwad] (rev. in money)	600,000	
Chhala-Babra, has a brick fort, somewhat dilapi- dated, saltpetre obtain- ed here ...	43,283 579,877	34,903,220 4,825,392	232,860 5,627	200 50	10,000 200	Koli. Jhālāwār.
Dholga, the Sābarinātī flows adjacent ...	834,606	1,650,000	188,160	50	100	Ponwār.
Dhandhok, has a masonry fort of <i>chunam</i> ...	403,523	113077044*	...	500	4,000	Do.
Sirūāl ...	80,646	2,528,632	...	100	300	Garāsiah, Melhtar.
Kari ...	936,837	30,125,778*	394,963	300	1,000	Ol. etc.
Kambhāyat ...	336,813	22,147,986	160,405	100	200	Rājput, Bārah.
Kapadibhanj, a masonry fort of <i>chunam</i>	50,125,778	27,309	100	500	Koli.
Mandwa	22,147,978	301,320	50	500	Do.
Molān, has a brick fort	507,370	423,510	16,062	100	200	Do.
Mahmūdābād, has a tem- ple to Mahādeva ...	45,590	1,748,080	160,088	Chauhān.
Mahmūdābād, has a brick fort ...	213,855	1,400,000	Ol (Koli)
Manerej, has a masonry fort of <i>chunam</i> ...	76,629	121,762	...	100	300	Chauhān.
Narāl ...	202,062	8,103,098	49,478	entered under Sirūāl		Garāsiah.
Hind ...	200,020	752,202	...	20	100	Koli.

* The Rājputs are here divided into two classes. (i) Garāsiahs or land-owners. See Eryley's *History of Gujarat*, p. 93, for the derivation of this term), and (ii) Cultivators. The former live a life of idleness on their lands and are

Sarkār of Pattan, north.

Containing 16 Mahals. 38,500,015 Bighas. Revenue 600,325,099 Dāms. *Suyurghāl*, 210,627 Dāms. Castes various. Cavalry 715. Infantry 6,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Pattan, has two forts	957,462	143,862	150	3,000	Rājput, Koli, Kumbi.
Bijāpur ...	290,554	6,001,832	2,832	200	500	Koli.
Pāthanpur	528,611	3,600,000*	50	500	Do.
Badnagar, has a stone fort	37,600-13	1,844,324	1,749	under Bijapur		Do.
Visalunagar ...	13,281	674,348	...	20	100	Rājput, Jādun.
Therād, has a brick fort ...	240,052-11	4,000,000	...	50	200	Rājput, Bārhaḥ.
Tervāda do. ...	294,516-17	2,130,000	...	50	1,000	Koli.
Suburb. dist. of Pattan ...	14,787-50	20,054,045	862,104	under Pattan		
Rādhan [-pur], has a brick fort ...	257,709-6	4,000,000	...	100	200	Koli.
Sami, has a shrine much venerated in Hindustan	107,298*	1,266,498	...	20	100	Do.
Santalpur ...	34,267	287,340	
Kherālu ...	101,946-17	4,000,000	
Kākrej ...	112 338	1,312,590	...	under Tehrār		
Munjpur ...	51,814-11	909,630	...	25	100	Do.
Morvāda ...	47,777	320,020	200	Do.
Disah, has a brick fort ...	288,270	1,600,000	...	50	200	Do.

* So the MSS, but I apprehend these figures should be reversed, the larger coming under revenue, as G. has it.

Sarkār of Nandod—north.

Containing 12 Mahals. 541,817 Bighas, 16 Biswas. Revenue 8,797,596 Dāms. *Suyurghāl* 11,328 Dāms.

	Biswas Bighas	Revenue D.		Bighas Biswas	Revenue D.
Amreli ...	15,548-16	148,620	Jamungāon ...	21,444	412,093
Avidhā ...	4,290	17,076	Kahāar ...	14,903	80,307
Barsāi, (<i>Suyurghāl</i> 11,328) ...	158,696	2,061,368	Marghadrah ...	15,028	62,328
Badāl [?Bhadli] ...	40,663	272,645	Māndun ...	5,402	16,000
Tilakwāda ...	55,859	1,595,525	Nāndod with suburb dist. ...	128,021	3,929,330
Tahwā [Tankhala]	73,263	165,500	Natrang ...	15,188	40,798

Sarkār of Baroda, south.

Containing 4 *Mahals*. 922,212 *Bighas*. Revenue 41,145,895 *Dāms*. *Suyurghal* 388,358 *Dāms*. Castes various. Cavalry 900. Infantry 5,800.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Baroda with sub. dist. has a brick fort	500,920	20,403,485	...	200	400	Ponwār, &c Rājput.
Bahādurpur, has a brick fort	1,680,920	6,243,280	...	500	5,000	Rājput.
Dabhoi, has a stone fort ...	167,090	9,252,550	4,562	500	500	Rājput, Bahrāh.
Sinor, the Narbada, in its course from the north, passes under the town ...	148,150	5,746,580	...	500	5,000	Rājput, fol- lowing name ille- gible).

Sarkār of Broach, south.

Containing 14 *Mahals*. 349,771 *Bighas*. Revenue 21,845,663 *Dāms*. *Suyurghal* 141,820 *Dāms*. Castes various. Cavalry 990. Infantry 8,600.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Olpād	186,420	1,659,877	Gwālīā.
Anklesar	138,376	558,010	
Atlesar [Amalsari] ...	90,333	307,737	...	50	230	
Broach, has a brick fort, on the Narbada; here is a Hindu shrine	64,660	456,230	...	500	5,000	Rājput,
Tarkesar	8,752	5,651	Rājput, Barhāh. Rājput, Garāsiah.
Chharmandvi	44,821	122,795	
Suburban dist. of Broach	52,975	7,022,690	64,516	
Dehej Bārḥā [Vagra] ...	42,664	1,174,540	
Kāri [Kareli]	177,939	4,275,000	12,650	20	300	
Kala [Ghalha]	15,181	353,670	300	Rājput, Garāsiah.
Gandhār, a port frequen- ted by vessels	240,000	

Sarkār of Broach, South—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Lorakh [?Luhara], on the seashore ...	31,760	1,287,250	
Maqbulābād, on the sea- shore. Salt here obtained	81,750	1,912,040	...	20	100	Rājput. Musalmān.
Hānsot, one of the ports of this district ...	77,560	2,439,158	...	400	3,000	Rājput Bāghelāh.

Sarkār of Chāmpāner.

Containing 9 Mahals. 80,337 Bighas. 11 Biswas.
Revenue 15,009,884 Dāms. Suyurghāl 173,730 Dāms.
Castes various. Cavalry 550. Infantry 1,600.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Arwārah ...	19,129	48,209	
Chāmpāner, with sub. dist. has two stone forts, one on a hill called Pāwah, and the second at its foot ...	159,590	1,429,649	173,730	500	1,000	
Chandāwārah ...	27,328-8	21,530	
Chaurāsi ...	107,713	2,215,275	
Dohad, has a stone fort ...	68,249	1,283,300	
Dhol [Derol] ...	32,014	172,992	
Dilāwārah ...	18,129	48,628	
Sonkherah ...	240,313	2,995,696	
Sānwes, has a strong stone fort ...	120,391-1	2 300,000	...	50	100	Rājput.

Sarkār of Surat.

Containing 31 Mahals. 1,312,815 Bighas. 16 Biswas.
Revenue 19,035,180 Dams. Suyurghāl 182,370 Dāms.
Castes various. Cavalry 2,000. Infantry 5500.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Ambhel, has a stone fort	6,581	424,355	
Pārchol [=Parujan] ...	55,920	1,508,000	

Sarkār of Surat—Contd.

	Bighas	Revenue D.	Suyur ghāl D.	Cavalry	Infantry	Castes
Balsūr, on the sea ...	74,702	1,281,420	59,785	100	500	Rājput.
Balesar ...	86,400	1,013,045	15,035	
Beāwarāh, has a stone fort near Tapti ...	58,659	554,320	...	2000	5,000	
Balwārah, has a stone fort, and a shrine with a hot spring [?Palsana] ...	41,650	478,620	
Bhesrot [Bhestan] ...	21,170	425,055	
Pārnera ...	54,460	277,475	
Bhutsar ...	12,075	146,230	
Bālor [?Kadod] ...	21,435	592,180	
Tilāri [Taori] ...	85,095	917,890	90,835	
Timbā ...	51,029-19	263,390	2,040	
Chikhli, on the sea, has an iron mine ...	337,613	389,320	
Dhamori, on the river Timi? (Kim?) ...	40,994-19	767,520	
Rander ...	5,529	63,692	13,092	
Surat with suburb. dist. has a stone fort ...	50,733	5,530,145	
Supā ...	37,594	73,151	8,720	
Sarbhun ...	64,127	601,257	
Khoblori [?Kumbharia] ...	4,024	026,760	
Ghandevi ...	4,524	835,330	7,810	
Kharka [Kharsawa], on the Timi ...	42,019	629,310	
Karodah [Kathodra] ...	000,704	383,240	24,550	
Kāmrej ...	68,044	328,205	
Kos [-amba], has a stone fort ...	9,771	228,390	
Lohari ...	5,928	85,280	
Maroli, on the sea ...	17,044	370,410	
Mahwah (Moha?) on the sea ...	15,016	100,290	
Nāroli ...	1,620	65,220	
Nosari, with a manufac- tory of perfumed oil, found nowhere else ...	17,353	297,720	
Nariād, on the sea ...	7,290	130,700	

Sarkār of Godhrā.

Containing 12 *Mahals*. 535,255 *Bighas*. Revenue 3,418,624 *Dāms*. Castes various. Cavalry 1,000. Infantry 5,000.

	Bigha	D.		Bigha	D.
Audhā [Aradrā] ...	17,877	184,935	Bera [Bariya] ...	37,318	257,202
Atlawara [?Aṭar Sunba] ...	46,704	63,460	Jadnagar* ...	46,690	120,660

* *Jadnagar*—either Jambughoda or Chandpur.

Sarkār of Godhrā—Contd.

	Bigha	D.		Bigha	D.
Jhālod [Halol] ...	92,409	794,654	Kohāna [Kadana]	20,858	785,360
Dhānbod [Dhanpur] ...	17,082		Marāl [Marwa]	46,755	525,975
Shehara ...	35,702	146,322	Mahadwārah ...	19,285	10,826
Godhra with sub. dist. ...	150,250	785,660			

Sarkār of Sorath (Kathiawad).

Containing 12 Mahals, of which 13 are ports. Revenue 63,437,366 Dāms. Cavalry 17,000. Infantry 365,000.

	Revenue D.		Revenue D.
Una ...	7,620,388	Dharwār [Dholarwa] ...	59,792
Aivej ...	780,500	Dhāntror ...	252,048
Amreli ...	1,784,160	Dhāri ...	644,270
Apletah ...	1,214,592	Rānpur ...	16,127
Pattan Deo [Somnath] ...	4,453,912	Rālgan ...	113,280
Bānwāra [?Wadhwan] ...	2,049,340	Rāmōt ...	28,320
Belkhā ...	140,000	Siyor ...	42,480
Bālsar ...	509,760	Sarii ...	4,936
Beri [? Baori] ...	145,600	Sultānpur ...	424,800
Barwa [? Baroda] ...	50,664	Gariadhar ...	623,040
Bandah ...	84,960	Korinār ...	4,538,560
Bāndor [Wanod] ...	14,060	Ghogah (Gogo), exclusive of port ...	
Bhimrād ...	28,320	Kianābanāerā ...	42,480
Pālitana ...	240,592	Kathar ...	127,480
Bagsra [? Digsar] ...	56,340	Garidhari ...	598,704
Barar ...	734,790	Gondal ...	56,640
Barwārā [? Wasawad] ...	74,792	Kotiānā (Katiana) ...	1,797,256
Bādli ...	14,160	Kandolnā ...	198,432
Tālāja ...	2,435,520	Lulīānā ...	1,423,080
Chokh [Charkha] ...	453,120	Lemorā Batwā ...	487,576
Jaitpur ...		Lāthi ...	296,152
Jagat [Dwarka] ...	803,200	Malikpur ...	995,048
Chorwād (Charadwa) ...	936,960	Mohwah, (Mowa) ...	2,051,136
Chaurā ...	97,288	Mandwi ...	127,440
Jetwad ...	1,071,660	Manglor ...	16,689,472
Jasdhon [Jasdān] ...	98,560	Medarah ...	2,208,160
Suburban dist. of Sorath	932,000	Morbi ...	2,603,326
Daulatābād ...	357,424	Miānah ...	14,106
Dāng ...	4,410	Nāgsari ...	755,376
Dungar ...	760,400	Hatasni (?) ...	1,012,592

Port duties.

	Revenue Mahmudis		Revenue Mahmudis
Port of Manglor ...	27,000	Port of Mohwah (Mowa)	1,000
„ Pattan Deo ...	25,000	„ Meykor ? ...	3,000
„ Korinār ...	1,000	„ Dungar ...	1,000
„ Nāgsari ...	10,000	„ Talājā, 4 Mahals	7,000
„ Porbandar ...	27,228	„ Una ...	15,000

Princes of Gujārāt.

Seven princes reigned in succession 196 years.

	Years.
Bana-rāj Chauhan ¹ ...	60
Jog Rāj ...	35
Bhimrāj ...	52
Bhor ...	29
Bahr Singh ...	25
Ratnādat (<i>var.</i> Rashādat) ...	15
Sāmant ...	7

* *Sorath* corresponds to mod. Junagad. The following emendations are suggested from Hamilton's *E. I. Gazetteer* and the Survey of India *Atlas*: Dhantror (=Dhamnagar), Dhari (=Darwa), Rālgāon (=Ranigaon), Siyor (=Sihor), Sarii (=Sarya), Korinar (=Kauri Nagar, 10 m. N. of Diu point), Kathar (=Kantharia), Kandolna (=Kadorna), Luliana (=Lilaola), Una =Unadelwara).—*J. Sarkar*.

¹ The following table is from the *U. T.* taken from the *Ain-i-Akbari*, and collated with the *Agni Purāna* of Wilford.

A.D.

696. Saila Deva, living in retirement at Ujjain found and educated.

745. (S. 802) Banarāja, son of Samanta Sinh (Chohān) who founded Anhalpur, called after Anala Cohān.

806. Jagarāja.

841. Bhira Rājā, (Bhunda Deva. Wilford).

866. Bhenr.

895. Behersinh.

920. Reshadat, (Raja Adity W.). •

935. Samanta, (dau. married son of Delhi Raja). The total of years of reigns in the A. A. makes 223 instead of 196. G. and T. give Bhimrāj 25 instead of 42, and thus correct the error.

Ten princes of the Solanki race reigned 224 years.¹

				Yrs.	Ms.
Mulrāj Solanki	56	0
Chāmand	13	0
Balabha	0	6
Durlabha, his nephew	11	6
Bhim, his nephew	42	0
Karan	31	0
Jai Singh, called also Sudhrāj	50	0
Kumārpāl, grandson of his uncle	23	0
Ajaipal, his nephew	8	0
Lakṣmul	8	0

Six princes of the Bāghelāh tribe reigned 126 years.²

				Yrs.	Ms.	Ds.
Hardmul Bāghelāh	12	5	0
Baldeva	34	6	10
Bhim, his nephew	42	0	0
Arjun Deva	10	0	0
Sārang Deva	21	0	0
Karan	6	10	15

¹ The totals give only 238 years. The *U. T.* runs as follows :—

A.D.

910. Mula Rāja, usurped the throne.

1025. Chāmund, invaded by Sultan Mahmud (Samanta. W.).

1038. Vallabha (ancient line restored).

1039. Durlabha (Dabisalima Ferishta) usurped the throne.

1050. Bhima Rāja.

Kaladeva (Karan. A. A.) Carna Rajendra or Visaladeva, (W.) who became paramount sovereign of Delhi.

1094. Siddha or Jayasinha, an usurper. Kumārapal, poisoned (by Ajaya-pala, son of Jayasinha).

² The *U. T.* give the following :—

The Bhāghela tribe.

Mula (Lakṣmul. A. A. Lakhan Raya. W.) without issue.

Birdmul } Baluca—Mula, W. of Bhāghela tribe.
Beildeva }

A.D.

1209. W. Bhima Deva, or Bala Bhima Deva, same as last W.

1250. Arjun Deva,

1260. Saranga Deva, } A. A.

1281. Karan

Karna the Gohila fled to the Deccan when in the year 1309 Gujarāt was annexed to Delhi by Alā ud din.

Fourteen (Muhammadan) princes* reigned about 160 years.

A.D.		Yrs.	Ms.	Ds.
1391.	Sultān Muzaffar Shāh, ...	3	8	16
1411.	Sultān Ahmad, I, his grandson (builds Ahmadābād and Ahmadnagar), ...	32	6	20
1443.	Mahammad Shāh, his son, ...	7	9	4
1451.	Qutb ud din Ahmad Shāh (opposes Malwa King and Chitor Raja Kombha), ...	7	0	13
1459.	Dānd Shāh, his uncle, (deposed in favour of) ...	0	0	7
1459.	Mahmud Shāh I, son of Muhammad Shāh (Begarrā : two expeditions to Deccan), ...	55	1	4
1511.	Sultān Muzaffar, his son, (war with Rājā Sangrām), ...	14	9	0
1526.	Sultan Sikandar, his son, (assassinated), ...	0	10	16
1526.	Sultan Nasir Khān, his brother, (Mahmud Shāh II, displaced by), ...	0	4	0
1526.	Sultan Bahādur, son of Sultān Muzaffar, (invades Mālwa : murdered by Portuguese), ...	11	9	0
1536.	Muhammad Shāh, sister's son, (Fāruqi of Mālwa), ...	0	9	0
1536.	Sultān Mahmud, grandson of Muzaffar, ...	18	2	
		some days.		
1553.	Sultān Ahmad (II) a descendant of Sultān Ahmad, (spurious heir set up by ministers), ...	8	0	0

* List of Gujrat Muslim rulers :

Muzaffar I	A.H. 798/1396	A.D.
Ahmad I	814/1411	
Md. I. Karim	846/1442	
Qutbuddin	855/1451	
Dānd	862/1458	
Mahmud I	862/1458	
Muzaffar II	917/1511	
Sikandar	932/1526	
Mahmud II	932/1526	
Bahādur	932/1526	
Muhammad II	943/1537	
Muhammad III	943/1537	
Ahmad II	961/1554	
Muzaffar III	969-980/1562-1572	

A.D.

Yrs. Ms. Ds.

1561. Sultān Muzaffar III, (Habbu, a suppo-
sitious son of Mahmud), ... 12 & odd.
1583. Gujarāt becomes a province of Akbar's Empire.

The Hindu chronicles record that in the year 802 of Bikramājī, corresponding with A.H. 154 *Sarāj* kindled the torch of independence and Gujarāt became a separate state. Rājā Sri Bhor Deva ruler of Kanauj put to death one of his dependants, named Sāmant Singh for his evil disposition, disloyalty and disorderly conduct, and seized his possessions. His wife was pregnant at the time, and urged by distress, she fled to Gujarāt and in an uninhabited waste gave birth to an infant. It happened that a Jain devotee named Saila Deva passing that way took compassion on the child and committed it to the charge of one of his disciples who took it to Rādhanpur, and brought it up with tender solicitude. When he grew to manhood, associating with wicked reprobates, he fell to outrage and highway robbery and a gang of free-booters was formed. He plundered the Gujarāt treasure on its way to Kanauj, and through the good fortune that attended him, he was joined by a grain merchant¹ called Chāmpā. Wisdom guided his sword and from works of evil he inclined to deeds of goodness till in the fiftieth year of his age, he acquired the sovereignty of the state, and founded Pattan. It is said that he long deliberated regarding the site of his capital and was diligent in search of a suitable place. A cowherd called Anhil informed him that he knew an excellent site which he would show on condition that the king would call the city after his name. His offer being accepted, he directed them to a wooded spot where a hare, he narrated, had grappled with a dog and by sheer strength of limb had got away. The Rājā founded the city there and named it Anhilpur. Astrologers have predicted that after the lapse of 2,500 years, 7 months, 9 days, and 44 *gharis*, it shall be in ruins. Through the corruption of language and syllabic change it came to be called Nahrwālah, but as in the tongue of that country 'chosen' is rendered 'Pattan,' it became universally distinguished by that name.

Rājā Sāmant Singh gave his daughter in marriage to Sri Dandak Solanki, a descendant of the Delhi princes.

¹ A trade in favour, apparently, with Gujarāt kings. One was the intimate friend and counsellor of Sultān Muhammad. See Bayley, pp. 132 and 188.

She died when on the point of giving birth, but a son was by a surgical operation taken from her womb. The moon at the time was in the sixteenth¹ mansion termed by the Hindus *Mul*, and hence he was named *Mulrāj*. Rājā Sāmant Singh adopted him as his own son and watched over his education. When he grew up, he entered into a conspiracy with some evil-disposed persons. The Rājā in a fit of drunkenness abdicated in his favour, but on becoming sober recalled his promise which so infuriated this miscreant that he slew his benefactor and assumed the sovereignty. During the reign of Rājā Chāmand A.H. 416 or 1064 of the era of Bikramājī,² Sultān Mahmud of Ghazni conquered this country, but on leaving, he found no fitter person on whom he might confer the government than a descendant of the royal line, and having arranged for the annual payment of a tribute, he returned by way of Sind. What is remarkable is that at the desire of this prince he carried with him captive another scion of the same family. After a time, either through fear or foresight, the captive's restoration was solicited by the same prince who went out to meet him as he approached his territory in order that intriguers might not secure his favour. On the day that they were to meet, the Rājā fell asleep for a short space under a tree, when an animal of prey tore out an eye. At that time a blind man being incapacitated from reigning, the ungrateful soldiers substituted the captive prince in his place and placed the Rājā in confinement.³

Kumārpāl Solanki through fear of his life lived in retirement, but when the measure of Jai Singh's days became full, he came forth from the wastes of disappointed ambition and seated himself on the throne and considerably enlarged his dominions. Ajaipāl wickedly poisoned his sovereign and for a fleeting gratification has acquired eternal abhorrence.

Lakmul having no issue, the worthiest representative of the Baghelah tribe was chosen as sovereign.

¹ Various taken as the 17th, 19th and 24th lunar asterism, containing 11 stars, apparently those in the tail of Scorpio and said to be unlucky. In the dissertation on Astronomy that follows in a subsequent book, *Mul* is counted as the 19th mansion.

² 1064 A.B. is equivalent to A.D. 1007 and A.H. 416 to A.D. 1025. It was in Sept. 1024 A.D. that Mahmud set out from Ghazni in his expedition against Somnāth.

³ The story is related at greater length from the *Mirat i Ahmadi* in Bayley's *Hist of Gujarāt*, pp. 29-34 and its probability defended in a discursive note.

During the reign of Karan, the troops of Sultān Alā u'd din overran Gujarāt. Karan, defeated in the field, fled to the Deccan. Although previous to this time Muizz u'd din Sām¹ and Qutb u'd din Iḥḥab had made expeditions into the country, it was not until the reign of Alā u'd din that it was formally annexed to Delhi.

In the reign of Muhammad, son of Firuz Shāh, Nizām Mustakhrāj, called also Rāsti Khān,² was appointed to the government of Gujarāt, but his injustice becoming oppressive, he was removed and the viceroyalty was conferred on Zafar Khān son of Wajih u'l Mulk Tānk. The former governor disloyally rebelling, was killed in the field. The events of this time may be gathered from the history of the Delhi sovereigns. His son Tātār Khān was a man of base character and in whom wickedness was ingrained. At this period after the death of Sultān Muhammad when the throne of Delhi devolved on Sultān Mahmud, considerable anarchy prevailed. Zafar Khān withdrew from affairs and Tātār Khān assumed the royal state and marched against Delhi, but was poisoned at the instigation of his father³ who coming forth from his retirement had the *Khutbah* read and the coin struck in his own name, and was proclaimed under the title of Sultān Muzaffar. (1407.) Gujarāt thus became an independent kingdom and the government of the province was established in the Tānk family. The father of Zafar, Wajih u'l Mulk had been a Brahman and was converted to Islām. Ahmad the son of Tātār Khān conspired against the life of his grandfather and took possession of the throne thus garnering eternal perdition. Ahmadābād was founded by him. With deep design and meditated hypocrisy he withdrew himself from all worldly pageantries till at a festival when all suspicion was laid asleep in the midst of universal enjoyment, he put to death twelve of his uncles. Subsequently he applied himself with earnestness to the

¹ Otherwise Shāhāb ud din Ghori.

² Malik Mufarrāh Sultānī, who afterwards obtained the title of Farhat ul Mulk Rāsti Khān. Zafar Khān was appointed to succeed him on the 2nd Rabiā I, 793 A.H. (21st Feb. 1931) (Bayley *Hist. of Guj.*), p. 58. Wajih ul Mulk was a Hindu called Sadhāran, converted to Islam and belonged, says the *Mirat i Sikandari*, to the Tānk caste, an outcast branch of the Khātris. One of them was expelled for his use of strong drinks and the name is said in Hindi to signify an outcast. The derivation is asserted to rest on some form of the Sanskrit *tyāga*, meaning separation, divorce. See Bayley's note. *Ibid.* p. 67. Baber calls the race *Tang*. *Memoirs*, Erskine, p. 311.

³ It is commonly believed, says the *Mirat i Sikandari* that Tātār Khān placed his father in confinement and seated himself on the throne under title of Mhd. Shāh, whence the reprisal. *Ibid.*, p. 81-82.

duties of his government and was filled with continual remorse, and to his last breath set himself to a just and capable administration of the state.

When Dāud Khān was deposed on account of his incapacity, Fath Khān son of Muhammad Shāh was raised to the throne and was proclaimed as Sultān Mahmud (I). He distinguished himself by his recognition of merit¹ and by his justice, and girt himself with the fence of munificence and liberality. Malik Shabān who held the title of Imād u'l Mulk was of the utmost service to him.² In the beginning of his reign some of the wealthy favourites conspired against the life of their lord and in the first instance plotted the overthrow of this judicious and sincere counsellor. Like intriguers as they were, they conveyed false allegations to the king, and as the worldly-minded are suspicious of each other, he imprisoned this peerless denizen of the world of faith and purposed putting him to death. He was on the point of being condemned when Malik Abdu'llah the superintendent of the elephants who had the royal ear, revealed the innocence of his faithful minister and the designs of the conspirators. The king skilfully contrived his escape and, the veil of their pretence being rent asunder, the miscreants took to arms. The royal guard and the slaves together with the officers in charge of the elephants made a stand against them, and the elephants themselves proved of service in chastising the rebels. Disgracefully routed, these disloyal subjects met with just retribution.. At Mahmud's death, his son Muzaffar Shāh, with the assistance of the nobles, ascended the throne and assumed the title of Sultān Muzaffar (II). His reign was beneficent. Shāh Ismail of the Sufi dynasty of Persia sent him as presents the choicest goods of Irāq³ and he in turn courteously reciprocated his acknowledgments. On his decease, his son succeeded him under the title of Sultān Sikandar. In a short time he was wickedly done to death by Imād u'l Mulk who raised his brother Nasir Khān to the throne. The nobles plotted to

¹ And likewise by his enormous appetite. His daily allowance of food was one *man Gujarāt* weight (equal to 15 Bahloli *seers*). He put aside 5 *seers* of boiled rice and before going to sleep, placed half on one side of his couch and half on the other, so that on whichever side he awoke, he might find something to eat. This was followed in the morning by a cup of honey, a cup of butter and 100 to 150 plaintains. After this, Abul Fazl's appetite sinks into insignificance. His allowance was 22 *seers* daily.

² The whole account will be found in Bayley under this monarch's reign. The reader is referred to that work for details of this historical synopsis.

³ A turquoise cup of great value, a chest full of jewels, many valuable tissues and 30 Persian horses. Bayley, p. 244.

displace him. The king appealed for succour to His Majesty Bāber and engaged to surrender to him the port of *Dih* (Diu) with its dependencies and several *krors* of *tankahs*, if he would advance in aid with his victorious troops. On account of his former ungrateful conduct, his offer was refused.¹ At this juncture, Bāhadur the son of Sultān Muzaffar came from Delhi at the invitation of the Bābriyas² and the nobles joined his standard. During his father's reign he was unable to remain at court through the envy borne towards him by his brother (Sikandar). He, therefore, betook himself to Sultān Ibrahim Lodi at Delhi and was received with favour. The nobles of Jaunpur invited him to be their king, and his intentions were inclined that way, when at this time his partisans wrote to him from Gujarāt and entreated his acceptance of the throne. He willingly set out for the capital and being successful, he made his administration prosperous by his justice and liberality. Carried away by the intoxication of worldly success, he imprudently engaged in a war with Humayun, and being defeated, sullenly withdrew in discomfiture.³

At his death, Mirān Muhammad ruler of Khāndesh, his nephew, whom during his lifetime he had constituted his heir, was in his absence proclaimed in the *khutbah* by the nobles, but died shortly before reaching Gujarāt. Mahmud, grandson of Sultān Muzaffar, who was then in confinement, succeeded him. A miscreant called Burhān with some of his adherents put him to death⁴ and under pretence of

¹ Ferishta says (Bayley, p. 319) that this letter never reached Bāber, the Rajah of Dundeigar having intercepted it.

² See Bayley, p. 35, n., and for his adventures after leaving Gujarāt, p. 321 *et seq.*

³ Bāber says of him that he acted rightly in enforcing the law of retaliation by putting to death Imād Mulk who had strangled his brother Sikandar, but besides this, he slew a number of his father's Amirs and gave proof of a bloodthirsty and unmerciful nature.

⁴ Bayley, p. 445, *et seq.* Burhān who had been a low favourite of the king, poisoned and stabbed his master and sallied forth from the palace in the pomp of royalty when he was met and slain by Shirwān Khān Bhatti, adopted son of Afzal one of the murdered nobles. Ferishta's account is that on the death of the king he came known, Imād Khān with Changiz Khan, Ulug Khan, Halahī and others, came out to oppose him. Burhān was thrown at the first charge and killed by Shirwān Khān. His feet were tied to a rope and he was dragged throughout the city. The *Mirāt-i-Sikandari* gives the name of Razi ul Mulk to one of the nobles who was sent to bring the new king, Ahmad, to the capital, but Ferishta expressly states that this descendant of Ahmad Shāh was named Razi ul Mulk and was raised to the throne as Ahmad Shāh II. He continues, that disgusted with his nominal sovereignty, after a 5 years' tutelage he took refuge with Mirān Mubārak Shāh one of the principal nobles on whose death in the field, an accommodation was again effected with Imād Khān, but having expressed himself too openly as desirous of death of that minister, he himself was found dead the next day,

establishing a rightful succession, massacred twelve of the nobles. Itimād Khān prudently absented himself on the occasion, and next morning collecting his followers, attacked him and put him to the death he deserved. He then set up one Razi u'l Mulk by name a descendant of Sultān Ahmad, I, under the title of Sultān Ahmad (II) as a nominal sovereign and took the government into his own hands. But when the boy grew to manhood, he altered his purpose and carrying him to the house of one of his adherents, he slew him and then leading some unknown minor by the hand, swore upon oath that he was the son of the last Sultān Mahmūd (II). By fraudulent allegations, he bestowed on him the sovereign authority and giving him the title of Sultān Muzaffar, he himself assumed the reins of power, until his present Majesty threw the shadow of justice over the province and annexed this prosperous country to the imperial dominions.

May it ever be adorned with perpetuity and high and low enjoy unfading blessings.

near the river opposite the house of Wajih ul Mulk and it was given out that, caught in a love intrigue in that nobleman's house, he had been unwittingly slain. The *Mirat-i-Sikandari* tells the story more in detail. On his death, Itimād Khān produced a boy (not named in Ferishta nor, I think, in the *Mirat*) whom he swore to be the son of Mahmud Shāh II, his mother's pregnancy not having been discovered till the 5th month when too late to check it. For Mahmud had unnaturally interdicted the fertility of his wives to avoid a disputed throne. The nobles accepted or feared to oppose the pretension, and the boy was placed under the control of Itimad Khān. The subsequent history may be read in Ferishta, or in Brigg's free but generally faithful rendering, but the events of his worthless life—it cannot be called a reign—are lost in the contests of the nobles for their share of short-lived power till the incorporation of the kingdom with the empire on the 24th Rajab A.H. 890 (Nov. 20th, 1572). Bayley's translation concludes with the death of Mahmud Shāh IV, but his original continues the history of Gujarāt to 1001 A.H. (1592-3) and the death by his own hand of the last of its sovereigns,

SUBAH OF AJMER

It is situated in the second climate. Its length from the village of Pokhar (*Bhakar*—Pushkar) and dependencies of *Amber* to *Bikaner* and *Jaisalmer* is 168 *kos*. Its breadth from the extreme limits of the *Sarkār* of *Ajmer* to *Bānswārah* is 150 *kos*. To the east lies *Agra*: to the north the dependencies of *Delhi*: to the south *Gujarāt*: to the west *Dipālpur* and *Multān*. The soil is sandy, and water obtainable only at great depth, whence the crops are dependent on rain. The winter is temperate, but the summer intensely hot. The spring harvest is inconsiderable. *Jowāri*, *Lahdara* and *Moth* are the most abundant crops. A seventh or an eighth of the produce is paid as revenue, and very little in money. The people dwell in tent-shaped bamboo huts. To the south are the (*Aravalli*) mountains of which the passes are difficult to traverse.

This Subah is formed of *Mewār*, *Marwār* and *Hadauti*.¹ The former possesses 10,000 (troops) and the whole of the *Sarkār* of *Chitor* is dependent on it. Its length is 40 *kos* by 30 in breadth. It has three famous fortresses, *Chitor* the residence of the governor, *Kumbhalmer*² and *Māndal*. In the village of *Jāwar*,³ one of the dependencies of *Chainpur* is a zinc mine. In *Chainpur* and other dependencies of *Māndal* are copper mines, which are extremely profitable.

The chief of the state was formerly called *Rāwal*, but for a long time past has been known as *Rānā*.⁴ He is of the *Ghelot* clan and pretends a descent from *Noshirwān* the Just.⁵ An ancestor of this family through the vicissitudes of fortune came to *Berār* and was distinguished as the chief of *Narnālah*. About eight hundred years previous to the present time, *Narnālah* was taken by an enemy and many were slain. One *Bāpā*, a child, was carried by his mother

¹ Harowtee or *Hārāoti*, a tract formed of the territory of *Kotah* and *Bundi*, and named after a dominant tribe of *Rājputs*.

² *Komulmir* is a pass that runs through a series of rugged ravines in the *Aravalli* ranges and is defended by a fortress. In art. *Udaipur*, it is spelt *Kumalmer*.

³ *Jāwar*, 24 miles S. of *Udaipur*, is said to have possessed zinc mines now unworked.

⁴ The foundation of the *Ghelot* dynasty in *Rājputāna* was effected by *Bappa Raval* who is said to have established himself in *Chitor* and *Mewār* in 728 A.D. I. G.

⁵ It is asserted that a daughter of *Noshirwān*, whose queen was a daughter of *Maurice* of *Constantinople* married into the *Udaipur* royal family.

from this scene of desolation to *Mewār*, and found refuge with *Rājāh Mandalik*,¹ a *Bhil*. When he grew up to man's estate he followed the pursuit of a shepherd and was devoted to hunting in which his daring was so conspicuous that he became in favour with the *Rājā* and a trusted minister of state. On the death of the *Rājā*, his four nephews disputed the succession, but they eventually decided to resign their pretensions in favour of *Bāpā* and to acknowledge his authority. *Bāpā*, however, declined their offer. It happened one day that the finger of one of these four brothers began to bleed, and he drew with the blood the ceremonial mark of installation on the forehead of *Bāpā*, and the others concurred in accepting his elevation. He then assumed the sovereignty. To this day the custom continues of making with human blood this sign of investiture on any *Rāna* who succeeds to the throne. The ungrateful monarch put the four brothers to death. On a former occasion while passing through the wilds, mistaking one *Marich* [*Rishi*], a hermit, for a wild animal, he fitted an arrow to his bow. The hermit intuitively prescient of this action through his purity of heart, made himself known, and the *Rājā* repentantly excused himself and humbly visited him with assiduity. The hermit one day predicted his elevation, and marvellous tales are told regarding him. Having made his head quarters at *Sisodā*, the tribe is called *Sisodia* and as a *Brāhman*, at the beginning of their history nurtured their house, they are accounted as belonging to this caste.

When *Rāwal Rattan Si* died, a relative named *Arsi* was raised to the throne and entitled *Rānā* from whom the present *Rāna Umrā* is tenth in descent, thus; *Hamir*, *Kaitā*, *Lākha*, *Mokul*, *Kombhā*, *Rāemal*, *Sangā*, *Udai Singh*, *Partāb*, *Umrā*.

Ancient chronicles record that Sultān Alā ud din Khilji king of Delhi had heard that *Rāwal Rattan Si* prince of *Mewār* possessed a most beautiful wife. He sent to demand her and was refused, upon which he led an army to enforce compliance and laid siege to *Chitor*. After a long persistence in beleaguering the place in vain, he had recourse to artifice and proposed terms of peace and friendship. The *Rājā* readily acquiesced and invited him to an entertainment. The Sultān entered the fort with his chosen followers and the meeting took place amid festivity and mirth, and finding

¹ Rao Mandalik says Bayley (*Hist. of Gujārāt*) is the title assumed by all the chiefs of *Gīrnār*.

his opportunity he seized the Rājā and carried him off. It is said that the Sultān's retinue consisted of a hundred men and 300 picked soldiers dressed as attendants. Before the Rājā's troops could assemble he was hurried away to the camp amidst the wailing of his people. The king kept the Rājā in close confinement with a view to extort compliance with his desire. The faithful ministers of the Rājā implored the king not to injure him and promised to deliver up to him not only the object of his love but other suitable partners of his harem. They also sent a forged letter purporting to come from the virtuous queen and lulled his suspicions to sleep. The king was delighted and not only refrained from personal violence but treated the Rājā with cordiality. It is related that 700 of the choicest troops dressed as women were placed in litters and set out for the king's camp and it was given out that the Rāni with a large number of her attendants was on the way to the royal pavilion. When they approached the camp, word was sent that the Rāni wished to have an interview with the Rājā previous to entering the king's quarters. Lapped in his illusive dream of security the king granted the interview, during which the soldiers seizing the opportunity, threw off their disguise and bore off their prince. Time after time the Rājputs stood to face their pursuers fighting manfully and many were slain before the Rājā had gone far. At length the Chauhāns, *Gaurā* and *Bādal* made a stand fighting to the death enabling the Rāwal to reach Chitor in safety amidst universal acclamation. The king having endured great hardships during the siege and finding it to no purpose, returned to Delhi. After an interval, he set his heart again on the same project but returned discomfited. The Rāwal wearied with these assaults, conceived that an interview with the king might result in an alliance and that he would thus escape this state of continual strife. Guided by a traitor he met the king at a place 7 kos from Chitor where he was basely slain. His relative *Arsi*, after this fatal event, was raised to the throne. The Sultān returned to the siege of Chitor and captured it. The Rājā was slain fighting and all the women voluntarily perished by fire.

Hamir his son betook himself to the adjacent mountains. Sultān Muhammad Khunī¹ made over the govern-

¹ "The murderer," the special title of fame of Muhammad Tuglak, but this monopoly of the epithet is scarcely fair to many other members of the royal houses of Delhi.

ment of Chitor to Māldeva Chauhān ruler of Jālor. As this prince was unable to bring the province into order, he summoned *Hamir*, made him his son-in-law, and through his means restored its prosperity. At his death, Hamir made away with his sons and raised the standard of independence.

The present local militia consists of 16,000 cavalry and 40,000 infantry, but Mewār formerly controlled much more extensive territories, so much so that Rājah Sanka (Sanga) possessed a force of 180,000 cavalry and a numerous infantry.

Mārwār is 100 *kos* in length by 60 in breadth, and it comprises the *Sarkārs* of *Ajmer*, *Jodhpur*, *Sirohi*, *Nāgor*, and *Bikaner*. It has long been the head quarters of the Rāthor tribe. When Muizz ud din Sām had terminated his campaign against *Pithurā* (Prithwi Rājā, A.D. 1191-93), he resolved to turn his arms against *Jaichand* king of *Kanauj*. The Rājah in his flight was drowned in the Ganges.¹ His brother's son Siha, who resided in *Shamsābād* was slain with a large number of troops. His three sons *Sutik*, *Ashwatthama* and *Aj* set out for Gujarāt, and on their way rested at *Pāli* near *Sojhat*. In this city dwelt a number of Brāhmans who were much molested by the *Minah* tribe, some of whom at this period made a raid on the town. The exiles came out, attacked them valorously, and put them to flight. The Brāhmans gave them great honour and treated them with every consideration and thus alleviated in some degree their distress of heart. As they acquired the means of worldly success they grew bolder and seized *Kher* [Kumbher] from the *Gohel* tribe and thus advanced their condition. *Sutik* independently wrested *Edar* from the *Minahs*, and *Aj* setting out for *Baglānah*, took that district by force from the *Kolis*. From that time their descendants have inhabited the country. The descendants of *Ashwatthamā* who remained in *Mārwār* gradually gained credit till eventually *Maldeva* his sixteenth descendant waxed so powerful, that Sher Khān nearly lost his life in his campaign against him.²

¹ Other accounts assert that he was slain by an arrow from the bow of Qutb-uddin the favorite general of the Muhammad Ghori, and the founder of the Dynasty of the Slave Kings. It is historical that his body was found and recognised by his false teeth, "a circumstance," says Elphinstone in the solitary instance of humour in his solemn history, "which throws grave light on the state of manners." One result of this defeat was the retreat of the greater part of the Rahtor clan from Kanauj to Mārwar.

² Sher invaded Mārwar in A.D. 1544 and his camp was surprised by an attack of 12,000 Rājputs who so nearly put an end to his campaigning that he declared he had nearly lost the empire of India for a handful of millet, alluding to the poverty of the country and the low quality of its produce.

This territory contains many forts, but the most important are *Ajmer*, *Jodhpur*, *Bikāner*, *Jaisalmir*, *Amar-keot*, *Abugarh* and *Jālor*.

Hādāoti is called also the *Sarkār* of *Nāgor*. It is inhabited by the *Hādā* (Hara) tribe.

This *Subah* comprises 7 *Sarkārs* and 197 *pargānahs*. The measured land is 2 *Krors*, 14 *lakhs*, 35,941 *bighas*, 7 *Biscas*. The revenue in money is 28 *krors* 84 *lakhs*, 1,557 *dāms*, (Rs. 7,210,308-14-9) of which 23 *lakhs*, 26,336 *dāms* (Rs. 51,158-6-5) are *Suyurghal*. The local force is 86,500 cavalry, 347,000 infantry.

Sarkār of Ajmer.

Containing 28 *Parganahs*, 5,605,487 *Bighas*. Revenue in money, 62,183,390 *Dāms*. *Suyurghāl* 1,475,714 *Dāms*. Tribes, *Kachhwāhah*, *Afghān*, *Chauhān*.

	Bighas	Revenue D	Suyurghāl D.
Ajmer with dist. its fort on a hill, one of the most important in India ...	795,335	6,214,731	D.
Amber, has stone fort on a hill ...	1,135,095	12,256,297	802,440
Arāin ...	179,573	1,755,960	...
Parbat [-sar] ...	279,295	2,200,000	...
Phāgi ...	90,488	486,161	...
Bhināi ...	349,774	1,400,000	...
Bharāna [Baghera] ...	68,712	271,256	...
Bawāl [? Borach] ...	168,712	749,733	...
Bāhal [Barl] ...	81,914-11	600,000	...
Bāndar Sindri ...	15,522	435,664	15,674
Bharondā ...	24,220	270,000	...
Tusinā [? Tilonia] ...	351,779-12	3,300,090	...
Jobner ...	138,718	241,442	...
Jhāk ...	27,092-18	501,844	...
Deogūon [Baghera] ...	49,065	1,200,000	...
Koshanpur [? Kishanpur] ...	76,548	692,512	...
Sāmbhar, has a stone fort ...	194,064	9,649,947	277,537
Sarwār, has a brick fort ...	245,136	1,616,825	...
Sithlā [Setholao] ...	72,098	1,270,000	16,027
Kekri ...	147,923	1,860,016	...
Kherwah ...	50,640	1,808,000	...
Mārot ...	71,356	7,020,347	...
Muzābād ...	252,871	5,756,402	...
Masandābād [Masuda] ...	251,973	1,459,577	...
Narāina ...	14,361	1,587,990	...
Harsuli, has a brisk fort ...	266,614	2,660,159	260,100
	163,273	1,200,926	926

Sarkār of Chitor.

Containing 26 *Parganahs*, 1,678,800 *Bighas*, 17 *Biswas*. Revenue, 30,047,649 *Dāms*. *Suyurghāl*, 360,737 *Dāms*. Tribes, Rājput Sesodia, Cavalry, 22,000. Infantry, 82,000.

	Bighas	Revenue D	Suyurghāl D.
Islāmpur, known as Rāmpura ...	101,526	7,000,000	...
Udaipur, here a large lake about 16 <i>Kos</i> in circumference; by its means wheat crops are grown	1,120,000 in money	...

Sarkār of Chitor—contd.

	Bighas	Revenue	Suyurghāl D.
Upamāl	27,805	280,000	...
Armed	44,720	200,000	...
Champur, known as Mohan	126,600	...
		in money	
✓ Badner, has a stone fort	113,265	4,311,551	59,815
Phulā do,	257,481	2,843,470	43,470
✓ Banerā	58,038	3,206,200	244,000
✓ Pur	199,209	2,601,041	13,452
✓ Bhainator, has a stone fort	1,200,000	...
✓ Bārer (Bāroli)	1,744-17	39,550	...
✓ Barun	234,804	1,175,729	...
✓ Barā [? Patil] Hajipur, has a stone fort	35,098	1,375,000	...
✓ Chitor, with rub. det. 2 mahals, has a stone fort, and is a frontier of Hindu- tan proper	451,118	800,000	...
✓ Jan	39,218	1,985,250	...
✓ Sawārahāt	470,291	...
✓ Sadri, has a stone fort	5,991	400,020	...
✓ Samāl [? Sanwad] with the cultivated tracts	100,000	...
		in money	
✓ Ro Būch [? Gounda]	52,713	263,812	...
✓ Mandavāh, has a stone fort on a hill	3,384,750	...
		in money	
✓ Māndā has a brick fort	18,818	447,090	...
✓ Māndāriyā [Madri]	160,000	...
		in money	
✓ Nīmāch &c. 3 mahals	21,416	719,202	...

Sarkār of Rantambhor.

Containing 73 Mahals. 6,024,196 Bighas, 11 Biswas.
Revenue, 89,824,576 Dāms. Suyurghāl, 181,134 Dāms.
Rājput Hādā (Hara). Cavalry, 9,000. Infantry, 25,000.

	Bighas	Revenue D.	Suyurghāl D.
Alampur	18,481	1,562,239	20,209
✓ Unārā	57,308	1,237,169	...
✓ Atādā [? Etawa]	45,349	770,525	...
✓ Aton	14,584	600,000	...

Sarkār of Rantambhor—contd.

			Bighas	Revenue D.	Suyurgāl D.
Islampur [=Aligarh]	5,191	77,500	...
Amkhorah	160,000	...
Antardah	166,173	in money	...
Awān Bosamir	25,747	1,500,000	...
Bundi, has a stone fort on a hill	33,161	1,200,000	...
Baonli, has a stone fort	151,430	2,622,747	22,747
Baroda	267,326	4,571,000	...
Jarwāra	163,226	1,969,776	...
Pātan [Kesorai]	139,280	2,800,000	...
Bhadlāon	96,895	2,686,389	...
Baklānt	149,087	1,200,000	...
Palāita	29,302	1,400,000	...
Bhosor	40,677	600,000	...
Banahā	21,257	524,356	...
B'lona	31,615	456,479	...
Bijari	15,594	334,800	...
Bālākhatri	33,930	300,000	...
Bhori Bhāri (Bari Pahar)	16,845	110,000	...
Bārān	242,107	880,000	...
Tonk	502,402	7,500,000	...
Toda	443,028	5,859,006	...
Todri	400,768	5,456,840	...
Talād	32,509	423,288	...
Jetpur	23,014	928,500	...
Chātsu	516,525	7,536,829	...
Jhalāwa (Jhalāi)	13,180	500,000	...
Jhāin	37,753	475,000	...
Khilchipur	30,813	1,209,886	...
Dhari (? Darah)	97,861	1,800,000	...
			54,668	409,260	
Dablāna	733,400	9,260
				in money	
Rantambhor with sub. dist	371-19	156,795	
Rawanjna (Dungar)	49,745	430,354	1,505
Sheopur	494,070	5,041,306	6,292
Sārsop	36,636	1,058,876	...
Sahansāri	28,575	300,000	...
Kotā, has a stone fort on a hill, near which the Chambal flows	360,378	3,000,000	...
Khāndar, has a stone fort on a hill	90,246	400,000	...
Khankra	220,350	1,511,994	...
Kheri	35,443	528,178	11,994
Khātoli	2,389	200,000	26,744
Gendawar	6,930-12	188,095	...
Karor, has a stone fort on a hill	6,377	200,000	...
Lākheri do.	3,523	800,000	...
Londa	17,400	250,000	...
Loharwāra	20,334	250,000	...
Luāwad	3,678	125,000	...
Mau-maidana, 16 Mahals		4,100,000	...
Malārna	172,693	3,299,241	...
Mangrol	140,799	1,004,348	...
Nawai	33,927	930,000	...
Nāgar (Nāgor)	33,900	1,000,000	...

Sarkār of Jodhpur.

Containing 22 *Mahals*. Revenue 14,528,750 *Dāms*.
Tribe, Rāthor, Cavalry 15,000. Infantry, 50,000.

	Revenue D.		Revenue D.
Asop has a brick fort ...	8,000,000	Jetāran, has a small fort on a hill ...	3,000,000
Indrāoti ...	8,000	Dunārā, has a stone fort	100,000
Phalodi, has a stone fort	640,000	Sojat, has a stone fort on a hill ...	2,812,750
Palpārāh [Pipar] ...	1,463,000	Sāalmer do. ...	560,000
Bilāra ...	314,000	Siwānā do. one of the most important strongholds in India ...	1,200,000
Pāli &c., 3 <i>Mahals</i> , has a small stone fort ...	250,000	Kherwā ...	220,000
Bahila ...	180,000	Khimwasar, has a stone fort ...	172,000
Podhah has a stone fort	46,003	Gundoj do. ...	90,000
Bhadrārjun, has a stone fort on a plain ...	800,000	Mahewah ...	960,000
Jodhpur with sub, dist. has a stone fort on a hill	280,000		

Sarkār of Sirohi.

Containing 6 *Mahals*. Revenue 4,2,077,437 *Dāms*.
Tribes, Rājput, Ghelot, Afghān. Cavalry, 8000. Infantry, 3,800.

	Revenue D.	Cavalry	Infantry	Tribe
Abugarh and Sirohi, 2 <i>Mahals</i> ; the latter has a strong stone fort ...	12,000,000	3,000	15,000	Rājput.
Bānswārāh, a delightful country; has a stone fort ...	8,000,000	1,500	20,000	Do.
Jālōr, Sānchor, 2 <i>Mahals</i> ; has a very strong stone fort ...	14,077,437	2,000	5,000	Afghān.
Dungarpur ...	8,000,000	1,000	2,000	Rājput Ghelot.

Sarkār of Nāgor.

Containing 31 *Mahals*. 8,037,450 *Bighas*, 14 *Biswas*.
Revenue, 40,389,830 *Dāms*. *Suyurghāl*, 30,805 *Dāms*.
Castes various. Cavalry, 4,500. Infantry, 22,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Amarsar	849,809	7,029,370	...	4000	20,000	Kachhwā- hah.
Indāna	262,302	1,313,006	479	

Sarkār of Nāgor—contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Bhadāna	544,340	2,271,960	70460
Baldu	87,947	570,000
Patoda	141,370	322,816
Baroda	2,620	220,363
Bārāh Kāin	230,379	58,000
Jāel	293,069	955,273	3200
Jārodah	141,592	874,284	2147
Jakhara, surrounded by a waste of sand	137,757
Khārij Khattu, has a stone fort, and a quarry of white marble*	77,577	348,814
Didwāna, has a brick fort	36,581	4,586,828	15215
Dronpur	219,698	780,085
Rewāsā	801,117	1,995,824
Run	615,212	913,251
Rasulpur	114,985	704,306
Rahot	45,269	188,137
Sādela	153,032	1,262,930
Fatehpur Jhunjhunu, has a stone fort	152,200	1,233,222	...	500	2000	Qiyām Khāni.
Kāslī	28,740	1,587,157
Khāela	114,955	558,560
Kuchera	270,490	466,890
Kolewa [Kolia]	12,748	352,805
Kumārī	469,881	435,604	8220
Kheran	26,033	57,160
Lādnu	149,760	780,842	4937
Merta, has a stone fort ..	2,114,773	7,701,522	45,433
Manoharnagar	129,895	2,903,386
Nokhā	83,096	380,756
Nāgor with sub. dist. has a brick fort	57,755-14	813,581	114,440

* *Khatu* is 38 miles s.e. of Nāgor.

Sarkār of Bikaner.

Containing 11 *Mahals*. Revenue 4,750,000 *Dāms*.
Tribe, Bhāti. Cavalry, 12,000. Infantry, 50,000.

	Tribe		Tribe
Bikampur	Bikaner	Rāthor.
Barsalpur	Jaisalmir	Bhāti.
Bāharnel (Barmer)	Chhotan
Pungal	Kotrā
Barkal	Dewādawar
Pokharan

SUBAH OF DELHI.

It is in the third climate. Its length from *Palwal*¹ to *Ludhiānah* on the bank of the *Satlej* is 165 *kos*. Its breadth from the *Sarkār* of *Rewāri* to the *Kumāon* hills is 140 *kos*, and again from *Hisār* to *Khizrābād* is 130 *kos*. On the east lies² the capital, *Agra*; on the north-east it marches with *Khairābād* in the *Subah* of *Oudh*; to the north are mountains; on the south the *Subahs* of *Agra* and *Ajmer*; on the west is *Ludhiānah*. The chief rivers are the *Ganges* and the *Jumna*, and both these take their rise in this *Subah*. There are besides numerous other streams, amongst them the *Ghaghar*. The mountains principally to the north. The climate is nearly temperate. Much of the land is subject to inundation and in some places there are three harvests. The fruits of *Irān*, *Turān* and *Hindustān* are here grown and abundant flowers of various kinds. City buildings of stone and brick delight the eye and gladden the heart, and it is scarce equalled for the choice produce.

Humāyun where a new and splendid monument has been erected. Sultān *Alā ud din* (1295-1316) founded another city and fort called *Siri*. *Tughlaqābād* is a memorial of *Tughlaq Shāh* (1321-24). His son *Muhammad* (1324-51) founded another city and raised a lofty pile with a thousand columns of marble and constructed other noble edifices. Sultān *Firoz* (1351-88) gave his own name to a large town¹ which he founded and by a cutting from the *Jumna* brought its waters to flow by. He likewise built another palace at a distance of 3 *kos* from *Firozābād*, named *Jahānumā* (the world-view). Three subterranean passages were made wide enough to admit of his passing along in mounted procession with the ladies of his harem; that towards the river, 5 *jaribs* in length; the second towards the *Jahānumā*, 2 *kos*, and the third to old Delhi, 3 *kos*. *Humāyun* restored the citadel of *Indrapat* and named it *Dinpanāh* (asylum of the faith). Sher Khān destroyed the Delhi of *Alā ud din* and built a separate town. Although the monuments of these cities are themselves eloquent and teach us the highest moral lessons, yet even is this latest Delhi now for the most part in ruins. The cemeteries are, however, populous. *Khawājah Qutb ud din Ushi* lies here and *Shaikh Nizām ud din Aulia*, and *Shaikh Nasir ud din Mahmud*, the Lamp of Delhi, and *Malik Yār-i-Pirān*, and *Shaikh Salāh*, and *Mālik Kabir-i-Aulia*, and *Maulanā Muhammad*, and *Hāji Abdul Wahhāb* and *Shaikh Abdullah Quraishi*, and *Shaikh Shams Tark-i-Biyābāni*, and *Shaikh Shams-i-Autād* and *Amir Khusrau*² with many other servants of God instructed in Divine knowledge who in this spot repose in their last sleep. Here too lie Sultān *Shahāb ud din Ghorī*, and Sultān *Shams ud din*, and *Nāsir ud din Ghāzi*, and *Ghiyās ud din*, and *Alā ud din* and *Qutb ud din*, and *Tughluq*, and *Muhammad Aādil*, and *Firoz* and *Bahlol*, and *Sikandar Lodi*. Many now living, likewise, have laid out pleasant spots and groves for their final resting-place—to the introspective a source of blissful ecstasy, to the wise an incentive to watchfulness.

In the hill of *Islāmābād* is a very deep spring called *Prabhās Kund* from which warm water continually bubbles up, and which is a great place of worship.

¹ It is supposed to have occupied the ground between *Humāyun's* tomb and the Ridge. I. G.

² Of these personages the last is sufficiently famous. The second and third and last on the list will be found in *Ferishta's* lives of the saints at the close of his History. Also *Ency. Isl.*

Biswamitra Rikhesar [Rishishwar] made a deep excavation of three *bighas* of this hill and devoted it to purposes of worship, and to this day it testifies to the antiquity of this construction.

Badāon is conspicuous amongst ancient cities and a great many holy religious are there buried.

A part of the northern mountains of this *Subah* is called *Kumāon*. Here are mines of gold, silver, lead, iron, copper, orpiment and borax. Here also are found the musk-deer and the *Qutās* cow,¹ as well as silk-worms, hawks, falcons and game of various kinds, and honey in abundance and the species of horse called *Gut* (Gunt).

There is game in plenty in the *Sarkār* of Sambal (*Sambhal*), where the rhinoceros is found.¹ It is an animal like a small elephant, without a trunk, and having a horn on its snout with which it attacks animals. From its skin shields are made, and from the horn, finger-guards for bow-strings and the like. In the city of Sambal is a temple called *Hari Mandal* (the temple of Vishnu) belonging to a Brāhman, from among whose descendants the tenth avatār will appear in this spot. *Hānsi* is an ancient city, the resting-place of *Jamal* the successor of Shaikh Farid-i-Shakar-ganj.

Near the town of *Sahnah** is a hot spring on the summit of a hill, the peculiarity of which is undoubtedly due to a sulphur mine.

Hisār (Hissār) was founded by Sultan *Firoz* who brought the waters of the *Jumna* to it by means of a cutting. A holy devotee predicted his accession to the throne and at his request the canal was made. Strange to say, it enters a pool named *Bhadrā* near the town of *Sirsā*, and there loses itself. Wonderful stories are related regarding it. There are few rivers in this district, and wells have to be dug to a considerable depth.

¹ Viswamitra is the name of a celebrated Kshatriya deriving his lineage from an ancestor Kusik of the lunar race: he was king of Kanyā-Kubjā or Kanauj. His famous quarrel with the rival sage Vasishtha to perform the great tribal sacrifice, runs through the Rig Veda and he succeeded in raising himself to the rank of a Brāhman by long and painful austerities. According to the Rāmāyan he became the companion and counsellor of the young Ramachandra. He was the father of Sakuntalā by the nymph Menakā whom the gods, jealous of his increasing power, sent to seduce him from his passionless life

* *Sohna*, 15 miles S. of Gurgaon City.

Sahrind (Sirhind) is a city of note. Here are the gardens of *Hāfiz Rakhnah*, the delight of all beholders.

Thanesar is accounted one of the most sacred places of pilgrimage. The *Saraswati* flows near it for which the Hindus have great veneration. Near it is a lake called *Kurukshetra*,² which pilgrims from distant parts come to visit and where they bathe, and bestow charitable offerings. This was the scene of the war of the *Mahābhārat* which took place in the latter end of the *Dwāpar Yug*.

In the city of *Hastinapur* reigned *Rājā Bharat* who by his justice and consideration for his people gathered a fitting reward of happiness, and his virtues and good deeds confirmed for a long period the succession in his family, and fortune favoured son after son. The eighth in lineal descent from him was *Rājā Kuru* from whom *Kuru-Kshetra* received its appellation. After six intermediate progenitors, an heir was born named *Vichitravirya*,³ who had two sons, one of whom was *Dhritarāshtra*. He was the father of 101 children, the eldest of whom was *Rājā Duryodhana*, and they are called the *Kauravas*. The other was *Pandu*. Although the first mentioned was the elder son yet on account of his blindness, the succession fell to his brother who obtained the sovereignty. His sons are called the *Pāndavas*. They were five, namely, *Yudishtir*, *Bhimsen*, *Arjuna*, *Nakul* and *Sahadev*. On *Pāndu's* death the kingdom reverted to *Dhritarashtra*, but although the nominal sovereignty was his, the real power was possessed by *Duryodhana*. Since to crush their enemies is the way of the princes of the earth, *Duryodhana* was ever in fear of the *Pāndavas* and sought their destruction. When *Dhritarashtra* observed the growing feud, he resolved to establish his nephews in the city of *Vārāṇāvatra*, and sent skilled artisans with instructions to build their residences. The

¹ Genl. Cunningham says (p. 145) that the name of Sarhind or 'frontier of Hind' was popularly given to the city at an early period when it was the boundary town between the Hindus and the later Muhammadan kingdom of Ghazni and Lahore, but the name is probably much older as the astronomer Varāha Mihira mentions the *Sairindhas* immediately after the *Kulutas* or people of *Kullu* and just before *Brahmapura* which was the capital of the hill country N. of *Hardwar*.

² It is an oblong sheet of water, 3,546 feet in length by 1,900. During eclipses of the moon, the waters of all other tanks are believed to visit this, so that the bather is blessed by the concentrated virtues of all other ablutions. The right ankle of *Durga* is said to have fallen here on her being cut to pieces and her limbs scattered over the earth by *Vishnu*.

³ He died childless, but at the request of his mother *Satya-vati*, the *Rishi* *Dwaipāyana* raised up three children to him, viz., *Dhritarashtra*, *Pāndu* and *Vidura*. *Vishnu Purāna*.

workmen at the instigation of *Duryodhana* constructed a secret chamber of lac and pitch, in order that at a fitting opportunity the *Pāndavas* might be destroyed in a flaming conflagration. But whom the Lord defends by his protection, what avails against him the striving of the impotent? When the *Pāndavas* accepting their exile, settled in this spot, they became aware of the design. By chance a woman with five sons dwelt hard by. The *Pāndavas* set the house on fire and set out for the wilds with their mother, while their neighbours were consumed in the flames.

Duryodhana believing that the *Pāndavas* were destroyed, held a festival of rejoicing. The *Pāndavas* after many adventures came forth from the wilds to the inhabited country and settled in the city of *Kampilā* [Panchāl]. In a short time, the fame of their valour, skill and open-handed munificence filled the world, but none knew their name or lineage, till *Duryodhana* himself awaking from his dream of security suspected that the burning of the *Pāndavas* was a fable. After prosecuting inquiries, his suspicions were confirmed, upon which he had recourse to entreaty, and recalled them with protestations of friendship, hoping thus to secure his aim. He bestowed *Delhi* (Indraprastha) upon them with half his kingdom and retained *Hastinapur* with the other half. *Yudhishtira* by his prudence and good fortune aided by the divine favour rose to greatness and his administration advanced his power. The *Kauravas* flocked to his service, and in a short space he acquired universal sway. The other brothers likewise reduced many princes to their obedience. *Duryodhana* was beside himself at the sight of their sovereign splendour, and the pangs of envy drove him more distraught. With deceptive intent, he held a restival and invited the *Pāndavas* and proposed a game of *chaupar*, playing himself, with cogged dice. By this means he won all they possessed. The last stake was made on the condition that if the *Pāndavas* won, they should recover all that they had lost, but if otherwise, they were to quit the royal dominions and wander in the wilds for twelve years in the garb of mendicants after which they might return to civilised life for a year, and so conduct themselves that none should know them. If this last particular were infringed, they would have to pass a similar period of twelve years in the forests. Unsuspecting foul play, their uprightness brought them to ruin. Elated by the success of his device, *Duryodhana* was lulled into the slumber of a false

security while the *Pāṇḍavas* under the divine direction accomplished their part of the agreement. *Duryodhan* now began to treat them with severity. Much altercation followed till the *Pāṇḍavas* consented to accept five villages if peacefully 'surrendered to them. *Duryodhana* in his pride refused and rose in arms. The scene of the conflict was in the vicinity of *Kuru-kshetra*. But as the end of the fraudulent is disaster, *Duryodhana*, and his companions were totally destroyed and *Yudhishtira* was victorious after eighteen days of successive engagements.

Towards the close of the *Dwāpar Yug*, 135 years before the beginning of the *Kali Yug*, and 4,831 years anterior to this the 40th of the Divine Era,* this event rose into fame and was left to posterity as a record of portentous warning.

It is said that in this mighty war, the army of the *Kauravas* consisted of 11 *achhauhini*, and that of the *Pandavas* of 7. An *achhauhini* consists of 21,870 men mounted on elephants, the same number in chariots, and 65,610 cavalry; and 109,350 infantry. Marvellous to relate but 12 individuals of both armies survived this war. Four of the army of *Duryodhana*, escaping with their lives took refuge with *Yudhishtira*, viz., *Kṛipāchārya* Brahman who had been preceptor to both families and was renowned for wisdom and valour; *Ashwatthāmān* who was celebrated for the same qualities; *Kritvarmān* Yadu, a brave champion; and *Sanjaya* who, together with his reputation for wisdom, acquired renown as the charioteer of *Dhritarāshtra*. On the side of the *Pandavas*, eight survived,¹ viz., the 5 brothers; *Satyaki* Yadu famous for his bravery and sagacity; *Yuyutsa* brother of *Duryodhana* by another mother, and *Krishna*. After this *Yudhishtira* reigned supreme for 36 years, and his happy destiny and virtuous disposition discovering to him the vanity of mundane things, he sought retirement and resolutely forsook a world that oppresses the weak. Together with his brethren he chose the path of renunciation and played the last stake of his life.

This great war has been related in the *Mahābhārata* with numerous episodes in a hundred thousand couplets, and has been translated into Persian by command of His Majesty under the title of *Razmnāma* (History of the War).

* See p. 15 where it is stated that from the era of Rāja *Yudhishtira* to the 40th of Akbar's reign (A.H. 1003, commencing 5th Dec. 1594 and ending 25th November, 1595 A.D.) there had elapsed 4,696 years, making the commencement of the *Kali Yuga* 3,101 B.C. To this period an addition of 135 brings the figure to 4,831.

It is set forth in eighteen *Parba* or books. The *first* part is an account of the *Kauravas* and *Pandavas* and a list of contents. The *second*; *Yudhishtira* sends his brethren to conquest—his supreme monarchy—the gambling feast held by the *Kauravas*, &c. *Third*, the departure of the *Pandavas* into the solitude of their exile and other events. *Fourth*, the coming of the *Pandavas* from the wilds to the city of *Virāta* and remaining unknown. *Fifth*, the *Pandavas* discover themselves; the mediation of *Krishna* and his rejection; the gathering at *Kura-kshetra* and disposition of the armies. *Sixth*, the opening of the combat, the wounding of *Bhishma*, the slaughter of many of the sons of *Dhritarāstra*, and the events of the ten days' engagement. *Seventh*, the council of war held by *Duryodhana*; the appointment of *Drona* to the general command, his death and other events during five days. *Eighth*, description of the two days' battle; *Duryodhana* names *Karna* to the command, his exploits—the flight of *Yudhishtira* before him—the death of *Karna* at the hand of *Arjuna* on the second day. *Ninth*, *Shalya* is appointed general on account of his heroism—his death—*Duryodhana* conceals himself in a tank—his end and that of many champions. *Tenth*, the conclusion of the war, the coming of *Kritvarmān*, *Ashwatthāmān*, and *Kripāchārya* to *Duryodhana* on the field of battle while still breathing and his advice of a night attack &c. *Eleventh*, the lamentations of the women on both sides—*Gāndhāri* mother of *Duryodhana* curses *Krishna*. *Twelfth*, account of *Yudhishtira* after the victory—his desire to resign his kingdom. *Byās* and *Krishna* comfort him by their counsel. *Bhishma* delivers many admirable and instructive maxims setting forth the duties of sovereign administration. *Thirteenth*, the advice tendered by *Bhishma*. In my judgment, the 12th and 13th books should be comprised in one as they both contain the counsels of *Bhishma*, and the 9th divided into two, the one dealing with the episode of *Shalya* and the other with the death of *Duryodhana*. *Fourteenth*, the great horse-sacrifice (*ashwa-medh*). *Fifteenth*, the retirement to a hermitage of *Dhritarāstra*, *Gāndhāri*, and *Kunti* mother of *Yudhishtira*. *Sixteenth*, the destruction of the *Yadu* tribe. *Seventeenth*, *Rāja Yudhishtira* retires with his brethren who all perish in a snow-drift. *Eighteenth*, *Yudhishtira* in his own body mounts to the upper world; the dissolution of the mortal remains of his brethren. The conclusion called *Haribans*, contains the history of the *Yadus*,

In this work, although there are numerous extravagant tales and fictions of the imagination, yet it affords many instructive moral observations, and is an ample record of felicitous experience.

This *Subah* contains 8 *Sarkārs* subdivided into 232 *parganahs**—the measured land consists of 2 *krors*, 5 *lakhs* and 46,816 *Bighas* 16 *Biswas*. The revenue is 60 *krors*, 16 *lakhs* 15,555 *Dāms* (Rs. 15,040,388-14) of which 3 *krors*, 30 *lakhs*, 75,79 are *Suyurghāl* (Rs. 8,26,893-7-7). The local force is 31,490 Cavalry, 242,310 Infantry.

*The eight *Sarkārs* comprise 232 *mahals*, if we omit the five unsettled *mahals* of Kumaon. The *Suyurghāl* total is incorrect, because by adding together the *Suyurghāl* for 7 *Sarkārs* only (that of Kumaon not being given), we get a total of 3,31,75,437 *dāms*. [J. S.]

Sarkār of Delhi.

Contains 48 *Mahals*, 7,126,107 *Bighas*, 17 *Biswas*,
 Revenue 123,012,590 *Dāms*. *Suyurghāl* 10,990,260 *Dāms*.
 Castes various. Cavalry, 4,000. Infantry 23,980.

	Bighas Biswas	Revenue D.	Suyur- ghāl	Cavalry	Infantry	Castes.
Islāmābād Pākāl, has a stone fort on a hill ..	970,67-19	1,779,407	31,462	50	1000	Rājput Sānd
Adhahī [?Odhan] ..	14,912-8	513,081	45,420	20	200	Ahir
Pānipat, has a brick fort	568, 444	10,756,647	3,540,632	100	2000	Afghān, Gu- jar, Rang- har
Pālam ..	245,240	5,726,787	1,231,880	70	1000	Jat
Baran, has a brick fort on the Kālī Nādī ..	171,160	3,907,928	153,190	20	300	...
Bāghpat, on the Jumna, between two streams	200,515	3,582,868	180,159	20	200	[Brāhman Chauhān
Palwal, ¹ has a brick fort and it stands on a mound ..	234,783	1,769,493	218,225	25	500	Rājput, Gu- jar
Barnāwah ..	145,000	1,879,125	50,759	25	200	Shaikhzā- dah
Pāth, has a brick fort	48,191	621,749	7,243	60	600	Tonwar (Tuar)
Beri Dobaldhan ..	119,002-19	1,404,225	...	40	800	Jat
Tilpat, has a brick fort	119,578	3,077,913	92,583	40	400	Brāhman, Rājput, Gujar
Tāndah Phugānah on the Jumna ..	51,669	1,289,308	11,366	25	200	Afghān
Tilbegampur ..	14,237-7	370,374	15,754	10	100	Jat.
Jhajhar ..	128,417	1,422,451	306,461	60	1000	
Harsia, has a stone fort in the village of Dhānah (cor. Dhaulī) built by Sultān Firoz on the banks of the Hindan ..	87,923	3,605,228	376,079	60	600	Badgujar
Jewar ..	133,746	1,878,378	85,439	40	400	Rājput, Chhokar
Jhinhānah ..	57,923-16	1,700,250	100,250	20	300	Jat
Chaprauli, stands be- tween two streams ..	32,701-12	1,138,759	5,719	20	300	Do.
Jalālābād, stands be- tween two stream amid much forest ..	96,189	1,333,711	9,099	50	600	Do.
Jalālpur Barawat, much forest ..	42,061-17	1,001,875	1,775	20	400	Do.

¹ *Palwal*.—This mound stands to this day considerably above the surrounding level and consists entirely of ancient remains crumbling to decay. It is a town of undoubted antiquity and supposed to figure in the earliest Aryan traditions under the name of Apelava, part of the Pandava Kingdom of Indra-prastha. *Baran* is the mod. Bulandshahar.

Sarkār of Delhi—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
The old suburban district	128,417	1,422,451	306,460	10	40	Jat, Chauhan.
The new do. do. ..	36,447	3,635,315	595,984	25	300	Gujar, Jat, Ahir.
The metropolis of Delhi	971	736,406	18,783	135	1,500	...
Dasna between Ganges and Jumna	282,777	4,933,310	162,535	60	900	Ghelot (here some illegible words).
Dādri Tāhā	179,789	4,326,059	118,577	20	400	Afghān, Jat.
Dankaur, on the Jumna	128,523	1 016,682	4,840	20	200	Gujar.
Rohtak, has a brick fort	636,835	8,599,270	428,000	100	2,000	Jat.
Sonipat (Sonpat) has a brick fort	283,299	7,727,323	775,105	70	1,000	Afghān, Jat.
Safidun, has a brick fort	81,730	1,975,596	99,647	60	600	Rājput Ranghar, Jat.
Sikandarābād	66,907-15	1,259,190	17,844	50	400	Bhātī, Gujar etc.
Sarāwa, has a brick fort	42,387-12	1,583,899	31,914	40	300	
Santha	39,147-9	854,191	48,207	30	300	Chauhān.
Siyāna, between two streams	166,407-17	849,090	4,959	50	400	Taga.*
Shikarpur	52,139	2,111,996	780,305	70	200	Chauhān.
Karnāl, the stream Sānjauli flows below the town	540,444	5,678,242	207,999	50	800	Ranghar Chauhan.
Ganaur, has a brick fort	40,990-16	1,718,792	33,390	20	400	Tagā.
Garh Muktesar, has a brick fort on the Jumna, a Hindu place of pilgrimage	101,340-10	1,591,492	41,490	40	400	Rājput, Musalmān, Hindu.
Kutāna	91,706-13	1,423,779	892	20	150	Jat.
Kāndhla	68,934-5	1,374,430	37,930	20	30	Gujar.
Kāsna, on the Jumna	104,021-19	1,522 315	149,250	40	400	Do.
Kharkhanda	51,895-15	1,105,856	4,958	50	600	Afghān, Jat.
Gangeru Kherah, has a brick fort between two streams	11,062-15	316,405	13,830	40	300	Sayyid.
Lonī, has a brick fort between two streams	75,363	3,278,878	148,445	20	200	

* Sir H. Elliot has an interesting discussion on the Gaur *Tagas*, an important tribe of Brahmanical descent in the N.-W. of India extending over a great part of upper Rohilkhand, the upper Doāb and the Delhi territory. Sherring's *Hindu Tribes and Castes* should be consulted in elucidation of the doubtful readings of the text.

Sarkār of Delhi—Contd.

	Bighas Biswas	Revenue D.	Suyur- Suyur- D.	Cavalry	Infantry	Castes
Mirath (Meerut) has a brick fort between two streams	610,422	4,391,996	331,096	100	300	Tagā, Ranghar, Chandrāl.
Māndāuthi, the autumn harvest abundant : near the town a tank which is never dry throughout the year	90,464	2,858,223	2,994	30	500	Jat.
Masandābād, has an old brick fort ..	89,478	2,809,156	269,315	30	30	Do.
Hastināpur, on the Ganges : an ancient Hindu settlement ..	176,340	4,466,904	36,291	20	300	Tagā.
Hāpur, on the Kālī Nadi between two streams	239,845	2,103,589	5,229	4	300	Do.

Sarkār of Badāon.

Containing 13 Mahals. 8,093,850 Bighas, 10 Biswas. Revenue 34,817,063 Dāms. Suyurghāl 457,181 Dāms. Castes various. Cavalry, 2,850. Infantry, 26,700.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Ajāon [Rajwan]	82,467-17	1,362,867	...	500	3000	Chauhān.
Aonla	14,701	690,620	...	50	400	Kānwar [?Tnar]
Badāon with suburban district	658,320-5	7,357,571	287,986	50	5000	Shaikhzā- dah, Kāy- ath.
Bareli	661,227	12,507,434	91,320	1000	10,000	Rājput.
Barsar [? Paraur]	196,700	2,147,824	6,754	50	500	Kāyath.
Paund [Elliot Punar]	5,749	260,840	...	50	300	Kahor
Talhi (Ballhati)	25,982	1,077,811	1,505	50	1000	Tagā, Brāh- man.
Sahiawan	253,120	2,493,898	15,444	100	2000	Tagā, Brāh- man.
Sanās Mandah (R. Satāsi Mundiya)	58,110	795,815	3,471	50	500	

Sarkār of Badāon—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Suneyā	29,753	1,815,725	...	50	500	Ulus ?
Kānit [=Kānt]	55,584	2,439,369	48,444	300	2000	Bāchhal.
Kot Sālbāhan has a fort	227,500-8	1,219,165	...	50	500	Kanwār.
Golah	24,540	1,136,931	4,257	100	1000	Dewak, Bāchhal.

Sarkār of Kumāon.

Containing 21 *Mahals*. The revenue of 5 *Mahals* undetermined. 16 *Mahals*, in money. 40,437,700 *Dāms*. Castes various. Cavalry, 3,000. Infantry, 50,000.

	Revenue D.		Revenue D.
Audan [?Adon] ...	400,000	Jakrām ...	5,000,000
Bhuksi and Bhāksū, 2	...	Jariyah ...	3,000,000
Mahals ...	400,000	Jāwan ...	2,500,000
Bastwah ...	200,000	Chauli, Sahajgar, Guzar-	
Pachotar ...	400,000	pur, Dwārakhot [Kot	
Bhikan Diwār ...	200,000	Dwara]* ...	
Bhakti ...	11,000,000	Malwārah ...	
Bhuri, undetermined	...	Malāchor, Sitachor, Ke-	
Ratilā [? Balila] ...	10,025,000	mus, 3 Mahals	
Chanki [Chanki-ghal3	400,000		

* Sahajgar is now *Jaspar*, Guzarpur is *Gadarapura*; Malwara may be *Talwara*.

Sarkār of Sambhal.

Containing 47 *Mahals*. 4,047,193 *Bighas*, 2 *Biswas*. Revenue 66,941,431 *Dāms*. *Suyurghāl* 2,892,394 *Dāms*. Castes various. Cavalry, 4,375. Infantry, 31,550. Elephants, 50.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Amrohah	820,654	6,342,000	993 358	1000	5000	50	Sayyid.
Āzampur	55,467	2,889,478	137,544	30	300	...	Tagā.
Islāmpur Bharu ..	66,096	1,370,640	12,133	100	200	...	Baishnavi.

Sarkār of Sambhal—Contd.

		Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Ujhāri	125,221	697,609	2,788	20	300	...	Jat.
Akbarābād	53,790-14	640,264	27,860	50	200	...	
Islāmpur Dargu	11,217-10	429,675	675	20	200	...	
Islāmābād	25,261-10	346,348	6,394	50	500	...	Jat.
Bijnaur	60,362	3,855,465	18,154	60	500	...	Tagā, Brāh- man.
Bachharāon	115,226-12	828,322	8,632	50	200	...	Tagā.
Biroi	15,027-12	150,000	...	25	100	...	Kohi
Bisārā	8,008-7	200,000	...	25	100	...	Khasia.
Chāndpur	87,278	431,071	259,959	50	200	...	Tagā, Jat, &c.
Jalālābād	49,398	1,470,072	12,263	25	100	..	Jat.
Chānpalāh	1,016,199	1,840,812	...	100	500	...	Gaur.
Jhālā	26,795	237,809	84,916	50	400	...	Jat.
Jadwār	76,757-19	828,846	...	50	200	...	Badgujar.
Suburban district of Sambhal	206,450	3,822,448	148,739	100	500	...	Tagā, Brāh- man &c.
Deorah	96,965	1,924,887	...	25	200	...	
Dhaka	130,158-16	670,364	6,487	25	200	...	Rahes.
Dabhūrsi	82,692-11	280,306	..	25	200	...	
Dudilāh	80,180-15	210,000	...	20	100	...	Kohi
Rājpur	189,390	700,000	...	50	400	...	Rājput.
Rājābpur	40,346-9	612,977	2,288	25	100	...	Kokar, Shaikhzādah
Sambhal, has a brick fort	42,400	850,958	63,404	50	400	...	Khokhar.
Seohārāh	27,945	1,833,782	1,418	50	800	...	Tagā.
Sirsi	52,400-11	958,769	152,814	20	200	...	Sayyid, &c.
Sahanspur	54,844-10	944,804	1,088	50	400	...	Tagā.
Sursāwah	37,502	808,065	...	15	400	...	Kaurawah.
Sherkot	19,870	4,921,051	218,157	100	1000	...	
Shāhi	80,417	500,496	478	20	200	..	Gaur.
Kundarki	86,164	674,986	74,936	50	400	...	Kāyath.
Kīratpur	80,978	2,410,609	166,218	100	500	...	Tagā, Jat.
Kachh	99,868	1,248,995	5,765	20	200	...	
Gandāur	18,576-17	751,520	34,270	30	200	...	Tagā.
Kābar	83,282-7	566,839	16,019	50	400	...	Chauhān.
Ganaur	51,005-1	267,919	17,719	10	100	...	Musalman.
Khānkari	31,546-7	200,000	...	10	100	...	
Lakhnor	246,440	2,499,208	32,983	1000	5000	...	Gaur.
Liswah	1,871	100,000	...	10	100	...	
Mughalpur	168,374	3,580,800	80,900	100	500	...	Tagā.
Majhāulāh	142,461	1,737,556	6,970	400	8000	...	Badgujar.
Mandāwar	65,710	1,256,995	20,455	25	300	...	Bais.
Nagina	99,238	2,647,242	284,368	50	500	...	Ahir.

Sarkār of Sambhal—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Nahaur, in this <i>par- ganah</i> , the mulberry grows in great per- fection of size and sweetness—a span in length*	85,974-12	1,788,160	4,675	50	300	...	Tagā.
Neodhanah	209,620-10	904,675	...	100	500	...	Gaur.
Naroli	181,621	1,408,093	48,212	50	400	...	Badgujar.
Hatamnah	5,706-14	250,000	...	50	400	...	Kodar.

*Probably, according to Dr. King, the *Morus lacvigata*, a long thin berry with a mawkish, sweet taste.

Sarkār of Sahāranpur.

Containing 36 *Mahals*. 3,530,370 *Bighas*, 3 *Biswas*.
Revenue, 87,839,659 *Dāms*. *Suyurghāl* 4,991,485 *Dāms*.
Castes, various. Cavalry, 3,955. Infantry, 22,270.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Indri, has a brick fort near the Jumna	143,900-28	7,078,326	691,903	50	1000	...	Ranghar, Tagā.
Ambilhta	17,764	324,560	...	20	300	...	Gujar, Aawān?
Budhāna	155,633	3,698,041	131,780	40	300	...	Tagā, Jat.
Bidauli	111,226	3,115,125	1,400,255	Sayyid
Bhatkanjāwar	173,471	2,676,407	146,749	50	500	...	Tagā, Bārhal.
Bhogpur, has a brick fort on the Ganges, a Hindu place of worship	94,428	2,338,120	6,941	100	1000	...	Rājput
Purchapār	86,949	2,191,460	120,438	20	200	...	Sarir.
Bhumah	67,451	2,135,496	28,453	2000	7000	...	Sayyid.
Baghrā	50,390	1,918,196	74,840	20	200	...	Jat.
Bhanāth	49,288	1,321,440	8,650	20	200	...	Tagā.
Thānah Bhim	281,377	3,578,540	317,260	20	500	...	Rājput, Sadbār.

Sarkār of Sahāranpur—Contd.

		Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Elephants	Castes
Tughlaqpur	81,856	222,277	128,853	20	30	...	Jat.
Jaurāsi	211,751	2,471,277	71,297	20	200	...	Bidar.
Jauli	45,653	1,310,057	152,396	Sayyid (Cavalry entered under Sarot).
Charthāwal	35,916	1,668,882	68,872	20	200	...	Tagā.
Suburban district of Sahāranpur, has a brick fort, cloths of the kinds <i>Khasa</i> and <i>Chaulār</i> (Vol. I, p. 94) are here made in perfection								
Deoband, has a brick fort	212 335-16	6,951,545	706,448	100	800	...	Afghān.
Rāmpur	335 861	6,477,977	641,946	60	800	...	Kulāl Tagā.
Rurki	79,419	1,777,908	78,597	50	400	...	Gujar, Tagā. Sadbār, Tagā.
Rāepur Tātār	2,768	1,628,860	8,361	25	200	...	Rājput, Sadbār, Tagā, Brāhman.
Sikri Bhukarheri	4,688-8	369,080	...	10	200	...	Tagā.
Sarsāwah, has a brick fort	189,211	3,008,611	110,611	40	200	...	Jat.
Sarot	106,800	2,516,125	16,165	90	200	...	Tagā.
Sardhana	90 617	2,207,779	51,571	50	1000	...	Do.
Sambalherā	113,780	1,590,606	43,842	30	800	...	Tagā, Ahir
Soranpalri	31,963	1,011,078	11,078	Sayyid (Cav. entered under Bhona).
Khatauli	10 648	574,320	22 628	40	250	...	Jat.
Khodi	104,747	8,624 588	190,919	40	800	...	Tagā, Kulāl
Kairāna	85,618	2,514,673	58,906	50	400	...	Jat, Tagā.
Gango	71,245	2,025,238	223,579	20	200	...	Gujar.
Lakhnauti	52,137	2,029,032	322,515	800	2000	...	Turkomān.
Muzaffarābād	79,694	1,796,058	76,602	300	2000	...	Do.
Manglaur, has a brick fort	81,305-15	4,074,064	71 899	20	200	...	Ranghar, Sander (?Pundir).
Malhaipur	60,987	2,850,311	197 216	40	800	...	Brāhman, Badgujar.
Nakor	81,010	2,244,070	23,077	100	500	...	Afghān, Tagā, Brāhman.
Nānauta	65,612-10	1,987,070	26,104	40	800	..	Afghān, Brāhman.
	..	29,224	724,150	18,684	40	800		Afghān.

Sarkār of Rewāri.

Containing 12 *Mahals*. 1,155,011 *Bighas*, 10 *Biswas*.
Suyurghāl, 739,268 *Dāms*. Revenue† * * *. Cavalry,
 2,175. Infantry, 14,600.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Bāwal	110,375	4,114,753	16,274	100	2001	Rājput, Ahir, Jat.
Pātaudhi	61,970	2,270,080	5,260	50	500	Do. Do.
Bhoharah (E. Bhorah) ..	38,547	755,543	345	100	1000	Ahir.
Tāoru, has a brick fort ..	35,858	986,228	11,573	50	500	Musalmān. Khaildār(?)
Rewāri with sub. dist., has a brick fort	405,108	11,906,847	404,100	400	2000	Thathar, Ahir, Jat.
Ratāi Jatāi	52,120	289,603	523	...	400	
Kot Qāsim Ali	80,410	3,357,830	110,330	25	400	Rājput, Ahir.
Ghelot	27,270-10	656,688	...	700	2000	Rājput, Thatar.
Kohāna	15,264	421,440	...	50	500	Do. Do.
Suhna, has a stone fort on a hill; here a hot spring and Hindu shrine	251,738	3,928,364	150,563	200	2000	Do. Do.
Nimrāna, has a stone fort on a hill	85,047	682,259	...	500	4000	Various.

† By deducting the revenues of the other 7 *Sarkārs* from the total revenue of the *Subah* (given on p. 290), we get 35,222,658 *dāms* as the revenue of *Rewāri*. [J. S.]

*Sarkār of Hisār Firozah.**

Containing 27 *Mahals*. 3,114,497 *Bighas*. Revenue,
 52,554,905 *Dāms*. *Suyurghāl*, 1,406,519 *Dāms*. Castes,
 various. Cavalry, 6,875. Infantry, 60,800.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Agrowa (var. Agrohah). Game of all kinds abounds. Sport chiefly hawking	45,717	1,748,970	6,654	200	2000	Jātu, Jat.
Ahroni	19,537	857,357	160,038	100	1000	Gujar. Jat.

* Called after the Emperor Firoz Shāh Tughlaq who founded the town of that name about 1354 A.D.

Sarkār of Hisār Fīrozah—Contd

Sarkār of Hisār Firozāh—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Fathābād, has a brick fort	83,661	1,184,392	81,867	200	3000	Rājput, Rāthor, Gujar, Jat.
Gohāna	68,951	2,876,115	16,146	300	8000	Jat, Dād- balāsa Duhna ?
Khānda, here a large tank in which the Hindus think it auspicious and holy to bathe	19,438	1,119,364	47,978	100	2000	Jat, Gadi (var. Kari).
Muhim, has a brick fort ..	188,080	4,958,613	84,202	700	2000	Rājput, Tonwar, Jat.
Hānsi, has a brick fort ..	886,115	5,434,438	180,056	500	7000	Rājput, Multāni, Jātu, Jat.

Sarkār of Sirhind.

Containing 33 *Mahals*. 7,729,466 *Bighas*, 7 *Biswas*.
 Revenue, 160,790,549 *Dāms*. *Suyurghāl*, 11,698,330.
 Castes, various. Cavalry, 9,225. Infantry, 55,700.

	Bighas Biswas	Revenue D.	ghāl D.	Cavalry	Infantry	Castes
Ambāla	154,769	4,198,094	321,488	100	1000	...
Banor	420,337	12,549,953	1,087,209	700	8000	Ranghar, Afgān.
Pāel, has a brick fort ..	525,932	7,322,260	162,267	200	2000	Ranghar, Jat.
Bhader	86,877	3,103,269	1,406,106	50	700	Jat, <i>Dāh- surati</i> ?
Bhatinda	3,125,000	...	400	2000	Bhatti.
Pāndri	34,190	686,870	47,152	20	300	Ranghar.
Thāra, has a brick fort on the Sutlej	273,866	7,850,809	2,869,841	1500	1,000	Munj (or Shaikh). Jat.

Sarkār of Sirhind—Contd.

	Bighas Biswas	Revenue D.	Sayur- ghāl D.	Cavalry	Infantry	Castes
Thānesar, has a brick fort	228,988.17	7,850,808	2,069,841	50	1500	Ranghar, Jat.
Chahat on the Ghaggar ..	158,739	750,994	49,860	650	1100	Afghān, Rājput.
Chark	68,689	1,598,090	21,619	20	800	Jat.
Khizrābād, has a brick fort	332,489	12,059,918	528,170	200	3000	Bhatti, Jat.
Dorāla	65,768	2,188,443	86,710	50	300	Ranghar.
Dhota	71,357	1,601,846	1,346	800	1500	Rājput.
Deorāna	12,389	580,985	17,385	20	200	Jat.
Rupar, has a brick fort ..	66,144	5,005,549	26,084	200	1000	Rājput &c.
Sirhind with sub. dist. has a brick fort	828,458	12,082,680	608,536	1700	2000	Rājput, Barāh, Khauri, Dādah (Dādū ?), Jat.
Samāna	904,261	12,822,270	782,000	700	2000	Barāh, Jat.
Sunām, has a brick fort ..	988,562	7,007,696	7,696	500	2000	Ranghar.
Sadhuna, has a brick fort	34,861	4,298,064	278,265	400	5000	Chauhān, Ranghar.
Sultānpur Bārha	18,736	427,085	82,759	20	100	Do. Rājput.
Shāhābād	184,146	6,751,468	761,587	200	1500	Chauhān, Rājput, Brāhman.
Pathpur	50,931	684,370	15,440	25	400	Rājput, Pundir.
Karyāt Rāe Samu	28,099	1,220,090	5,874	40	900	Ranghar, Jat, Barāh, (var. Bārah).
Kaithal, has a brick fort : here Hindu shrines	918,025	10,688,630	309,146	200	8000	Rājput.
Gulhrām, Do.	188,574	6,188,630	1,058,982	50	100	Ranghar, Jat, Khauri.
Ludhiāna, has a brick fort on the Sutlej	43,469	2,294,688	44,683	100	700	Awān,* Khauri, Ranghar.
Mustafābād	271,899	7,496,691	570,976	200	1000	Chauhān, Ranghar.
Masengan	204,877	7,058,259	626,690	200	1000	Jat.
Mansurpur	116,242	1,830,025	326,690	200	1000	Ranghar.
Māler	103,444	260,583	26,176	100	500	Munj.
Māchhiwāra, has a brick fort	17,272	250,556	250,552	100	500	Khauri, Wāh (var. Wārah)
Hāpari	93,756	1,145,118	...	80	300	Ranghar, Jat.

* See—Elliot, I, 113. Extract from Cunningham who gives the possession of Taxila to this people before Alexander's invasion.

III.

Eleven princes of the Ghori dynasty reigned 96 years 6 months and 20 days.

A.H.	A.D.							
588	1192	Sultān	Muizzu'ddin	Muham-				
			mad	Sām Ghori	...	14	0	0
602	1206	..	Qutbuddin	Ibāq	...	4	0	0
607	1210	..	Arām	Sāh, his son	...	1	0	0
607	1210	..	Shamsuddin	Altmish	...	26	0	0
633	1235	..	Ruknu'ddin	Fīroz Shāh,				
			his son	0	6	28
634	1236	..	Raziah,	his sister	...	3	6	6
637	1239	..	Muizzu'ddin	Bahrām				
			Shāh,	his brother	...	2	1	15
640	1242	..	Alāu'ddin	Masaud Shāh,				
			his nephew	4	1	1
643	1245	..	Nāsiru'ddin	Mahmud				
			Shāh,	his uncle	...	19	3	0
664	1265	..	Ghiyāsu'ddin	Balban	...	20	and some months	
685	1286	..	Muizzu'ddin	Kaikubād,				
			his grandson	3	Do.	

IV.

Thirteen princes of the Khilji dynasty reigned 129 years 10 months and 10 days.

A.H.	A.D.					Ys.	Md.	D.
688	1289	Sultan	Jalālu'ddin	Khilji	...	7	some months	
695	1295	..	Alāu'ddin	Khilji,	his			
			nephew	20	some months	
716	1316	..	Shahabu'ddin	Omar,	his			
			son	0	3	some days
717	1317	..	Qutbu'ddin	Mubārak				
			Shāh	his elder brother	...	14	4	0*

* All the MSS. concur in this glaring error, an evident slip of a copyist of 14 for 4. He was raised to the throne on the 7th Muharram A.H. 717 (22nd March 1317) and was killed 5th Rabī' I, A.H. 721 (5th April 1321).

721	1321	„	Nāsiru'ddin Khūsrau Khān ...	0	6	0
721	1321	„	Ghiyāsu'ddin Tughlaq Shāh ...	4	some months	
725	1324	„	Muhammad, his son ...	27	0	0
752	1351	„	Fīroz Shāh, son of his paternal uncle ...	38	some months	
790	1388	„	Tughlaq Shāh, his grandson ...	0	5	3
791	1389	„	Abu Bakr Shāh, son of his paternal uncle ...	1	6	0
793	1391	„	Muhammad Shāh, his paternal uncle ...	6	7	0†
796	1393	„	Ala'uddin Sikandar, his son ...	0	1	11
796	1393	„	Mahmud, his brother ...	20	2	0

V.

817	1414	Khizr Khān of the Sayyid Dynasty ...	7	2	2
824	1421	Mubārak Shāh ...	13	3	16
837	1433	Muhammad Shāh ...	10	some months	
850	1446	Sultān Alā'uddin Aālam Shāh ...	7	do.	
854	1450	„ Behlol Lodi ...	38	8	8
894	1488	„ Sikandar, his son ...	28	5	0
923	1517	„ Ibrahim, his son ...	7	some months	
		„ Bābar ...	5	0	0
		„ Humayun ...	9	8	1
947	1540	„ Sher Khān Sur ...	5	0	0
952	1545	„ Salim Khān, his son ...	8	and odd	
960	1552	„ Mubārīz Khān Adali.			
961	1553	„ Ibrahim ...		some months	
962	1554	„ Śikandar ...		do.	
		„ Humāyun ...	1	3	0

† Thus in all MSS., but Ferishta discovers the method of computation by dating this reign from the abdication of his father Fīroz Shāh in his favour on the 6th Shabān 789 A.H. (21st August 1387) to his death on the 17th Rabī' I 796 (20th January 1393) disregarding the two intermediate reigns.

In the year 429 of the era of Bikramājī (A.D. 372) Anangpāl¹ of the Tonwar tribe reigned with justice and founded Delhi. In the year 848 of the same luni-solar era (A.D. 791) in the vicinity of that renowned city, a hotly contested battle was fought between Prithirāj Tonwar and Bildeva Chauhān, and the sovereignty was transferred to this latter tribe. During the reign of Rājā Pithaura (Prithwi Rājā) Sultān Muizzu'ddīn Sām made several incursions into Hindustān without any material success. The Hindu chronicles narrate that the Rājā engaged and defeated the Sultān in seven pitched battles. In the year 588 A.H. (A.D. 1192), an eighth engagement took place near Thānesar and the Rājā was taken prisoner. One hundred renowned champions (it is related) were among his special retainers. They were severally called *Sāmant*² and their extraordinary exploits cannot be expressed in language nor reconciled to experience or reason. It is said that at this battle none of these champions was present, and that the Rājā kept to his palace in selfish indulgence, passing his time in unseemly pleasure, heedless of the administration of the state and of the welfare of his troops.

The story runs that Rājā Jaichand Rathor, who held the supremacy of Hindustān was at this time ruling at Kanauj, and the other Rājās to some extent acknowledged his authority and he himself was so liberal-minded that many natives of Irān and Turān were engaged in his service. He announced his intention of celebrating the great sacrifice symbolic of paramount supremacy and set about its preparations. One of its conditions is that all menial service should be performed by princes alone, and that even the duties of the royal scullery and the kindling of fires are directly a part of their office. He likewise promised to bestow his beautiful daughter on the bravest of the assembled chivalry. Rājā Pithaura had resolved to attend the festival, but a chance speech of some courtier that while the Chauhān sovereignty existed, the great sacrifice could

¹ Another name for Raya-Sena. Wilford says that he was called Anangpāla or befriended by love probably for his success in his amours, which he displayed by carrying off his brother's wife. Tieffenthaler calls him Rasena and credits him with the building of Delhi, which is confirmed by the *Agnipurāna*.

² I learn from Professor Cowell that the primary meaning attached to this term in the St. Petersburg Dict. is 'neighbour', and the second signification, 'vassal', in which sense it often occurs in Sanskrit poetry. Monier Williams defines it as "a neighbouring king—a feudatory or tributary prince" and adds a third meaning 'a leader, general, champion' which applies to the text.

not legitimately be performed by the Rathor chief, inflamed his ancestral pride and he held back. Rājā Jaichand proposed to lead an army against him, but his counsellors representing the duration of the war and the approach of the appointed assembly, dissuaded him from the enterprise. To carry out the integrity of the festival, a statue of Rājā Pithaura was made in gold and placed in the office of porter at the royal gates. Roused to indignation at this news, Rājā Pithaura set out in disguise accompanied by 500 picked warriors and suddenly appeared at the gathering and carrying off the image, he put a great number to the sword and hastily returned. The daughter of Jaichand, who was betrothed to another prince, hearing of this adventurous deed, fell in love with Pithaura and refused her suitor. Her father, wroth at her conduct, expelled her from her chamber in the palace and assigned her a separate dwelling. Pithaura, distracted at the news, returned with a determination to espouse her, and it was arranged that Chāndā a bard, a rival in skill of Babylonian* minstrelsy, should proceed to the court of Jaichand on the pretence of chanting his praises, while the Rājā himself with a body of chosen followers should accompany him as attendants. Love transformed the intention into act, and by this ingenious device and the spell of valour, he carried off his heart's desire, and after prodigies of bravery and heroism reached his own kingdom. The hundred *Sāmants* (above mentioned) accompanied him under various disguises. One after the other they covered his retreat and defeated their pursuers. Gobind Rāe Gehlot made the first stand and bravely fighting, fell. Seven thousand of the enemy sank engulfed in death before him. Next Narsingh Deva, Chāndā, Pundir, and Sārdul Solanki, and Pālhan Deva Kachhwāha with his two brothers, during the first day's action, after performing feats of astonishing heroism sold their lives dearly, and all these heroes perished in the retreat.

The Rājā, with the bard Chāndā and two of his brothers, brought his bride to Delhi amid the admiration of a wondering world.

Unfortunately the prince was all engrossed by his affection for his beautiful wife and neglected all other affairs.

* The text here is corrupt, and the variants printed give no help. Jarrett made the above translation with the warning that he was not satisfied with it. I suggest the emendation—"Chand the bard, who was a clever confidant [of Prithvi Rāj]," *āz dāmsāzān-i-māhtr-ash ast.* [J. Sarkar.]

After a year had thus passed, Sultān Shahābu'ddin by reason of the above events, formed an alliance with Rājā Jaichand, and assembling an army, invaded the country and captured many places. But no one dared even to represent, not to say, remedy this state of affairs. At last, the principal nobles meeting together, introduced Chāndā through the seven gates of the palace, who entering the women's apartments, by his representations somewhat disturbed the Rājā's mind. But in the pride of his former victories, he marched to battle with but a small army. As his brave champions were now no more, his kingdom fallen from its ancient renown, and Jaichand his former ally, reversing his past policy, in league with the enemy, the Rājā in this contest was taken prisoner and carried by the Sultān to Ghazni, Chāndā in his fidelity and loyalty hastened to Ghazni, entered the Sultān's service and gained his favour. By his address, he discovered the Rājā and comforted him in his prison. He proposed that he should praise his dexterity with the bow to the Sultān who would desire to witness it, and that then he might use his opportunity. The proposal was carried out and the Rājā pierced the Sultān with an arrow. His retainers fell upon the Rājā and Chāndā and cut them to pieces.

The Persian historians give a different account and state that the Rājā was killed in battle.

Fate discloses many such events from its treasure-house of wonders. But where—and blessed is he—who will take warning thereby and act on the lesson?

When the Chauhān dynasty fell, the choicest portion of Hindustān passed into the hands of Sultān Muizzu'ddin Ghori. Leaving Malik Qutbu'ddin (Eibak) who was one of his slaves, at the village Guhrām, [Ghulam in Patiala] he himself returned to Ghazni, laying waste the hilly country on his northern march. Qutbuddin in the same year possessed himself of Delhi and many other places and followed up his successes with remarkable ability. On the death of Muizzu'ddin, Ghiyāsu'ddin Mahmud son of Ghiyasu'ddin Muhammad sent from Firozkoh (his capital) the umbrella and insignia of royalty to Malik Qutbu'ddin. Qutbu'ddin was enthroned at Lahore and exalted his reputation by his justice, munificence and valour. He lost his life while playing at *chaugan* [polo.]

The nobles raised his son Arām Shāh to the throne, but a strong faction set up Malik Altmish, who had been a

purchased slave, and was the son-in-law and adopted heir of Qutbu'ddin. Arām Shāh was defeated and retired into obscurity, and Altmish assumed the title of Shamsu'ddin. It is said that his father was chief of some of the Turkish tribes. His brethren and cousins distracted by envy, sold, like Joseph, this nursling of intelligence, into slavery. Through the vicissitudes of fortune, he had various changes of masters until a merchant brought him to Ghazni. Sultān Muizzu'ddin Sām proposed to purchase him, but his owner chaffered for his value and placed an exorbitant price on him. The Sultān enraged, forbade any one to purchase him. Qutbu'ddin on his return to Ghazni after the conquest of Gujrāt, having obtained permission, bought him for a large sum and adopted him as a son. Khwājah Qutbu'ddin Ushi* was his contemporary and edified the world by his outward demeanour and the sanctity of his interior life. When Altmish died, his son (Ruknu'ddin Firoz Shāh) succeeded him who regarded wealth as a means of self-indulgence and thought little of winning the affections of his people. He made over the control of affairs to his mother Shāh Turkān. The nobles withdrawing their allegiance raised Raziah the daughter of Sultān Shamsu'ddin to the throne. The Sultān himself had previously made her his heir. Some of his courtiers asked him the reason of his doing so while he had sons still living. He replied that his sons, addicted to drinking were unfitted for the dignity. During the reign of Muizzu'ddin Bahrām Shāh, the Mughal troops devastated Lahore. A disloyal faction imprisoned the king and put him to death. In the reign of Sultān Alāu'ddin Masud Shāh occurred an irruption of the Mughals into Bengal, entering by way of China or Tibet, but his troops defeated them. Another body advanced from Turkistān to Uch. The Sultān set out to engage them, but on reaching the banks of the Biāh, intelligence reached him that the enemy had retreated. He returned to Delhi and there affected the company of low and base flatterers and ended his days in prison.

Nāsiṛu'ddin Mahmud ruled with capacity and munificence. In his time also, the Mughals entered the Panjāb but retreated on hearing of his approach.

* Ush is in Transoxiana and his birthplace. He is also known as Kāki from the miraculous production of bread cakes of the kind called in the vernacular *kāk* applied by the prophet Khizr for the needs of his family whose sustenance his meditations gave him no leisure or occasion to provide.

The *Tabaqāt i Nāsiri* takes its name from him. He had many excellent qualities. Ghiyāsu'ddin Balban who had been the slave and son-in-law of his father, he raised to the rank of chief minister and gave him the title of Ulugh¹ Khān. This minister filled his high office worthily and sought the divine favour in watchfulness over his people.

Nāsiru'ddin dying without children, the faithful minister was raised to the sovereignty. Clemency and solid gravity of character added fresh lustre to his dignity, and far from spending his precious hours in unworthy pursuits, he gladdened his kingdom by his appreciation of merit, his knowledge of men and his devotion to God. Those of ill repute and the wicked were banished into obscurity, and the good happily prospered under his encouragement. He conferred the government of the Panjāb on his eldest son Muhammad, commonly known as *Khān i Shahid*² through whose valour and vigilance the province rested in security. Mir Khusrau and Mir Hasan were in his suite. He was returning from a visit to his father unprepared for hostilities, when he encountered some Mughal troops between Dipālpur and Lahor and lost his life in the action. Mir Khusrau was taken prisoner but contrived to escape. The province of Bengal had been bestowed by Ghiyāsu'ddin on his youngest son Bughra Khān.

On the death of Ghiyāsu'ddin, the nobles despatched Kai-Khusrau the son of Khān i Shahid, who had been nominated heir, to (his father's government of) Multān, and bestowed the title of Sultān Muizzu'ddin Kaikubād on the son of Bughra Khān who thus acquired the sovereignty of Delhi. His father in Bengal, assuming the title of Nāsiruddin marched to Delhi whence Kaikubād advanced with a force to encounter him. The armies met on the banks of the Sarju (Gogra) near the town of Ajodhya, and through the conspiracy of disloyal and evil counsellors, the father after the interview returned to Bengal and the supreme sovereignty rested with the son. It is strange that Amir Khusrau should have chosen such a subject as this interview for encomium in his poem the *Qirān us Sa'dain*.

¹ *Ulugh* is a Tartar word and signifies 'great', and used often as a proper name as in the case of Ulugh Beg grandson of Timur.

² Or the martyred prince. Abul Fazl's assertion of the prince's unpreparedness is not confirmed. It was in the pursuit of the flying Mughals that he was surprised by an ambush while he halted by the banks of a stream to drink and to return thanks to God for his victory. Amir Khusrau alludes to his escape in his well-known poem, the *Khizr Khāni*.

The fortunes of this thankless unfilial son through his insobriety fell into decay. A faction set up his son, under the title of Shamsu'ddin to remedy the disorder, and the body of the wretched Kaikubād was flung into the waters of the Jumna. Shamsuddin was set aside and the sovereignty, by assent of the ministers, conferred on the Khiljis.

Jalālu'ddin who was paymaster of the Imperial forces, ascended the throne and by his simplicity of character lent no favour to the designs of the factious. His nephew Malik Alāu'ddin who had been brought up under his care, went from Karrah to the Deccan and having amassed great booty was inflated by its possession and proved rebellious. The Sultān by the persuasion of intriguers advanced from Delhi to Karrah, where the traitor slew him and assumed the title of Sultān Alāu'ddin. Thus by a marvel of Fate did the empire devolve on this miscreant, yet he accomplished some excellent reforms. On several occasions he encountered and defeated the Mughals. Mir Khusrau dedicated to him his *Khamsah*¹ and the story of Dewal² Rāni to his son Khizr Khān. Unfortunately he abandoned his usual prudence and fell under the influence of a eunuch (Kāfur) on whom he conferred the conduct of the administration. Through the suggestions of that wretch, his three sons Khizr Khān, Shādi Khān and Mubārak Khān were imprisoned, and on his own death, by the same instrumentality the youngest son was raised to the throne under the title of Shahābuddin. He destroyed the sight of two of his brothers, but Mubārak Khān providentially escaped. A few days later the wretch (Kāfur) was himself assassinated and Mubārak Khān who was in prison became chief minister.

¹ Or *five* poems, viz., the Hasht Bihisht, Sikandar Nāmah, Panj Ganj, Laila wa Majnum, and Shirin wa Khusrau.

² The story will be found in Briggs, Vol. I, pp. 327-366. Kaunla Devi her mother, the wife of Karan Rāe of Nahrwāla had been taken captive in the war against that prince (1297) and placed in the royal harem. In 1306 an expedition proceeding to the Deccan under Kāfur, Kaunla Devi represented to the king that she had borne two daughters to her former husband, that one had died, but the other Dewal Devi was still alive and she desired to recover her. Passing through Mālwal, Kāfur demanded her of Karan Rāe without success. Shankar Deva Rāe, prince of Deogarh had long sought to obtain her hand, but the proud Rajput had hitherto refused his daughter to the upstart Mahratta. The desire to gain his aid in the war against the king's troops secured his consent and he despatched her under an escort which fell in accidentally with a body of Muhammadan troops near the caves of Ellora. An engagement resulted in the capture of the princess and her despatch to her mother at Delhi. Her beauty won the heart of Khizr Khān the king's son and the rough course of their love with its hapless termination is celebrated in the Khizr Khāni. When they first met these prococious lovers were respectively ten and eight years of age.

Subsequently he deposed his younger brother, and assumed the title of Sultān Qutbuddin. He reduced Gujarāt and the Deccan. Through his incapacity and licentious disposition he chose a favourite of the lower orders named Hasan for the comeliness of his person, and bestowed on him the title of Khusrau Khān. Although the faithful ministers of the Crown represented the man's unworthiness and infamy, the king regarded their honest advice as the suggestions of envy, till Khusrau Khān, plotting secretly, dared to assassinate his master and assumed the sovereignty under the title of Nāsiru'ddin. He put to death the surviving members of the family of Alāu'ddin and perpetrated the greatest cruelties. Malik Ghāzi who was one of Alāu'ddin's chief nobles, defeated and slew him and with the concurrence of the nobles, ascended the throne with the title of Sultān Ghiyāsu'ddin Tughlaq Shāh. After settling the affairs of Bengal, he returned to Delhi. His son Muhammad Khān erected a pavilion at the distance of 3 *kos* from Delhi, in the space of three days and with much entreaty invited the king to enter it. The roof of the building fell in and the king perished in the ruins. Although (Ziāuddin) *Barni*¹ endeavours to substantiate the innocence of Muhammad Khān, the haste with which the pavilion was erected, and the eagerness to entertain the king therein, have all the appearance of guilty design.

When^o Sultān Muhammad died, Firoz the son of (Sālār) Rajab his paternal uncle was, according to the will of Muhammad, raised to the throne. He ruled with capacity and prudence and left many useful works as memorials of his reign. At his death anarchy to some extent prevailed in the empire. A faction set up his grandson (Ghiyāsuddin) Tughlaq Shāh (II) but in a short space he was sent to his last sleep by the hands of traitors and Abu Bakr¹ another grandson succeeded him.

In the reign of Sultān Mahmud, the direction of affairs devolved on Mallu Khān who received the title of Iqbāl Khān, but his incapacity and ill-fortune were unequal to the burden of state guidance. Internal disorders arose. A grandson of Firoz Shāh was acknowledged by some, under the title of Nasrat Shāh and increased the anarchy. Constant struggles took place in the vicinity of Delhi till in the

¹ The well-known author of the *Tarikh i Firoz Shāhi*.

¹ Son of Zafar Khān, son of Firuz Shāh.

year 801 A.H. (A.D. 1398) Timur invaded the country. Sultān Mahmud fled to Gujarāt and every competitor for power was crushed.

When Timur was on his return march, he left Khizr Khān, whom he had met during his invasion, in the government of Multān and Dipālpur. For two months Delhi was a waste. Nasrat Shāh who had fled into the Doāb, took possession of the throne. Iqbāl Khān then marched on Delhi and seized it and the other fled to Mewāt. Mahmud Khān now came from Gujarāt and Iqbāl Khān feigned acceptance of his service. One night the Sultān, in desperation of his affairs departed alone to the court of Sultān Ibrahim of the Sharqi dynasty (of Jaunpur) but met with no encouragement nor assistance. He was compelled therefore to return and Iqbāl Khān now opposed him but without success, and subsequently was taken prisoner in an action against Khizr Khān and was slain. Sultān Mahmud now took possession of Delhi, and was for some time occupied in hostilities, till he was carried off by an illness, and the Khilji dynasty terminated with him.

For a short period allegiance was paid to Daulat Khān (Lodi) *Khāsah Khail*, till Khizr Khān marched from Multān and took possession of Delhi. Malik Mardān Khān, one of the nobles of the Court of Sultān Firoz, had adopted Sulaimān the father of Khizr Khān as his son who subsequently, in default of recognised heirs, succeeded to his government.¹ Khizr Khān in gratitude (to Timur) did not² assume the regal title but styled his Court "The Sublime Standards," and adorned the *Khutbah* with the name of that illustrious monarch and afterwards with that of Mirzā Shāh Rukh, but it concluded with a prayer for himself. His son Mubārak Shāh succeeded him in accordance with his will. Sultān Ibrahim Sharqi and Hoshang (of Mālwah) being engaged in hostilities, Mubārak intended an attack

¹ The obscurity of this sentence in the original lies in the elliptical style of Abul Fazl. The sense I have given is in accordance with the facts of Ferishta who says that Malik Mardān Daulāt had adopted Sulaimān, and being him self appointed to the government of Multān, was succeeded at his death by his own son Malik Shaikh. The latter dying, made way for Sulaimān who was in turn succeeded by his son Khizr Khān. Ferishta makes the name Mardān and not Mardān.

² The MSS. omit the negative, but the text supplies it. Ferishta is clear on the point. "He did not take the name of king nor assume any regal epithet." The title in the text is not mentioned by him, which, however, is somewhat analogous to the Ottoman style of the 'Babi Aālī' or Sublime Porte, though in the latter it is absolute, and in the former vicarious.

on Kālpi and the adjacent territories, but he was perfidiously set upon by a band of traitors and slain.¹ Muhammad Shāh, who according to some was the son of Farid the son of Khizr Khān, while another account makes him the son of Mubārak, was raised to the throne. Sultān Alāu'ddin (his son and successor) possessed no share of rectitude and abandoned himself to licentious gratifications.

Bahlol (Lodi) now aspired to greatness. He was the nephew of Sultān Shāh Lodi of the Shāhu Khel tribe (of Afghāns). His father Bahrām in the time of Sultān Mahmūd, came with five sons from the borders of Balot to Multān and subsisted with some difficulty by traffic. Sultān Shāh² obtained service under Khizr Khān. He received the title of Islām Khān, and the revenues of Sirhind were assigned to him. Bahlol, the son of his nephew on his brother's side was prospering ill in Sirhind, but was received into favour by him and adopted as a son. Bahlol was born in Multān and during the month in which his birth was expected, a beam of the house fell and killed his mother. He was extracted by the Caesarean operation and his destiny proved fortunate. Although he allowed his sovereign (Alāu'ddin) who lived in retirement (at Badāon) to retain nominal power, he boldly assumed the supreme authority.³ His reign showed some capacity and his conduct was marked by intelligence and recognition of merit. He was carried off by an illness in his 80th year. It is said that he once happened to meet with a darvesh, having at the time with him but a trifling sum of money. The spiritually enlightened recluse called out, "Who will buy the kingdom of Delhi for such a sum of money?" His companions laughed in mockery at the man, but Bahlol frankly gave him all he had, and paid him reverence and eventually fulfilled the prediction. He carried on wars with the Sharqi kings which continued with varying successes, until he took Jaunpur and this dynasty was overthrown. He left his son, Bārbak at Jaunpur and returned to Delhi. As he was returning to Delhi from an

¹ He had laid the foundations of the city of Mubārakābād on the Jumna and was in the habit of visiting it to inspect the progress of the buildings. It was in one of these that he was assassinated at the instigation of the Wazir Sarwar ul Mulk on the 9th Rajab 837 (A.D. 1433). Ferishta.

² His eldest son, the others were Malik Kālā, Malik Firoz, Malik Muhammad and Malik Khwājah. Ferishta.

³ Removing the name of Alāu'ddin from the *Khutbah*, and assuming the insignia of royalty. Ferishta.

expedition against Gwalior he died near the town of Saketh.¹ His son Nizām Khān with the concurrence of the nobles, assumed the sovereignty and was styled Sultān Sikandar. He ruled with sagacity and appreciation of character and transferred the capital to Agra. In the year A.H. 911 (A.D. 1505), a great earthquake occurred and many lofty buildings were levelled. Sikandar was of comely person and mild disposition and popular from his liberality and open-handedness.

On his death, his son Sultān Ibrahim ascended the throne of Delhi and his authority was recognised as far as the confines of Jaunpur, the nobles conferring upon Jalāl Khān, another son of Sikandar's, the sovereignty of Jaunpur. Dissensions followed between the brothers, and Jalāl Khān abandoned his government and took refuge with the governor of Gwalior, but meeting with no success, fled to the court of Sultān Mahmud of Mālwa and succeeding as little there, he set out for Gondwāna. There the royal partisans seized him and carried him to the king by whom he was put to death. During his reign various chiefs revolted, such as Daryā Khān Lohāni viceroy of Behār, and his son Bahādur Khān had the *Khutba* read and the coin minted in his own name. Daulat Khān Lodi fled at Kabul and sought protection at the court of Babar, whom he led to the conquest of Hindustān while affairs resulted in a prosperous issue.

¹ Saketa or Saketa according to the *I. G.* is one of the classical names borne by Ajodhya, the ancient capital of Oudh. Abul Fazl places *Saketh* in the Sirkār of Kanauj.

SUBAH OF LAHOR.

It is situated in the third climate. Its length from the river *Satlaj* (Sutlej) to the *Sind* river is 180 *kos*. Its breadth from *Bhimbar* to *Chaukhandi* one of the depen-


had throughout the whole year. They come first in season when the sun is in Taurus and Gemini, (April, May, June), and a later crop when he is in Cancer and Leo (June, July, August). When the season is over, they are imported from Kashmir and from Kābul, Badakhshān and Turkestan. Snow is brought down every year from the northern mountains. The horses resemble the Irāq breed and are of excellent mettle. In some parts of the country, they employ themselves in washing the soil whence gold, silver, copper, *rui*,¹ zinc, brass and lead are obtained. There are skilful handicraftsmen of various kinds.

Lāhor is a large city in the *Bari Doāb*. In size and population it is among the first. In ancient astronomical tables it is recorded as *Lohāwar*. Its longitude is $109^{\circ} 22'$, lat. $31^{\circ} 50'$. During the present reign the fortifications and citadel have been strengthened with brick masonry and as it was on several occasions the seat of government, many splendid buildings have been erected and delightful gardens have lent it additional beauty. It is the resort of people of all countries whose manufactures present an astonishing display and it is beyond measure remarkable in populousness and extent.

Nagarkot is a city situated on a hill : its fort is called *Kāngrah*. Near the town is the shrine of *Mahāmāyā*² which is considered as a manifestation of the divinity. Pilgrims from distant parts visit it and obtain their desires. Strange it is that in order that their prayers may be favourably heard, they cut out their tongues : with some it grows again on the spot, with others after one or two days. Although the medical faculty allow the possibility of growth in the tongue, yet in so short a space of time it is sufficiently amazing. In the Hindu mythology, *Mahāmāyā* is said to be the wife of Mahādeva, and the learned of this creed represent by this name the energizing power of the deity. It is said that on beholding the disrespect (shown to her husband, Siva) she cut herself in pieces and her body fell in

¹ This metal is defined at p. 41 Vol. I. as being composed of 4 *scr*s of copper to $\frac{1}{2}$ of lead, and in India called *Bhangār*.

² The Great Illusion, or the illusory nature of worldly objects divinely personified, an epithet of the goddess Durgā. The earlier name Hardwār, *Māyāpur*, represents the ancient worship of this supreme energy and 'by her, whose name is Maya', says the *Bhagavata* "the Lord made the universe." His temple still exists in Hardwar, and is described in Cunningham's *Anc. Geog.*



Sarkār of the Bet Jālandhār Doāb.

Containing 60 *Mahals*, 3,279,302 *Bighas*, 17 *Biswas*.
 Revenue 124,965,212 *Dāms* in money. *Suyurghāl*
 2,51,788 *Dāms*. Castes, various. Cavalry, 4,155. In-
 fantry 79,436.

Sarkār of Bet Jālandhar Doāb—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Rājpurpatan, has a stone fort	1,800,000
Sultānpur, has a brick fort	101,865	4,020,232	405,830	200	1000	Bhatti.
Sinkarbanot	59,952	2,533,225	16,485	50	500	Khori Wāhah.
Salet Mandi, has copper and iron mines	42,150	1,680,000	...	100	8000	Sombansi.
Sagar	24,583	1,000,000	2000	Sa. shwāl.
Saba, has a stone fort ...	8,114-18	800,000	...	200	2000	Do.
Soran	213,333
Shaikhpur	97,173	4,722,604	52,639	150	2000	Bhatti.
Sherzath	3,610	194,294
Sūpur	346,667
Kothi	116,286	5,546,661	30,670	30	400	Jat.
Gash Diwāla	58,083	2,670,087	4,530	20	200	Jat.
Kotla	42,152	1,680,000	...	300	4000	Jasrotiah.
Kot Dehar, has a stone fort	32,932-16	1,310,847	...	200	3000	Kotlahariah.
Kharokdhār	42,043-12	48,000
Kheukhera, has a stone fort	6,021-16	240,000	...	under
Gangot, has a stone fort ...	6,021-16	240,000	...	Nakroh	...	Jaswāl.
Khera	6,021-16	240,000	Do.
Ghawāran (var. and G. Ghawle)	14,742-14	586,905	...	20	4000	Surajbansi.
Lādheri	15,959-8	536,414	17,810
Lāhauri	5,937	236,850
Māni Nuria	68,229	21,061,565	6,156	20	400	Bhatti.
Mehi	54,653-17	1,823,559	1,217	20	3000	Ranghar, Jat.
Muhammadpur	38,231	1,802,558	10,553	100	1000	Ranghar, Main.
Mānawāl	6,668	286,667
Malot	6,412	4,603,620
Mandhotā (Mandot)	13,280	426,367
Nakolar	78,731	3,710,756	9,757	20	1000	Man.
Nangal	4,808	267,270
Nakroti	32,642	1,300,061	...	500	5000	...
Nannuāl	46,180	2,315,368	...	30	300	...
Nandon	133,439	5,300,000	...	100	1500	...
Harhana (Hariana) with Akbarābād, 2 Mahals ...	626,889	6,032,032	49,650	40	408	Nakr.
Hadiābād	17,126	519,467	2,067

Sarkār of Bāri Doāb—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Kāngra, has a stone fort	...	2,400,000	...	2400	29,000	Sombansi.
Kotla	182,518
Karkārāon	16,000
Malik Shāh	28,684-9	1,475,562	52,283	10	100	Bhandāl, (var. Bhadāl).
Man and Nabā [=Omba], 2 Mahals	2,400,000	...	300	...	Rājput.
Mahrar	24,000
Hoshiār Karnāla ...	22,225	489,372	...	20	400	Jat.
Pālam,	9,600
Patiyār, } These four par- Bhatti, } ganahs, are now Jarjiya } abandoned.

Sarkār of the Rechnāu Doāb.

Containing 57 Mahals. 4,253,148 Bighas, 3 Biswas.
Revenue, 172,047,691 Dāms. Suyurghāl, 2,684,134 Dāms.
Castes, various. Cavalry, 6,795. Infantry, 99,652.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Amrāki Bhatti	70,752-8	1,942,606	8,673	50	1000	Bhatti.
Lands of Bāgh Rae Bocha	2,683	52,837
Eminābād, has a brick fort	515,675-4	24,853,006	498,480	500	5000	Khokhar, Chimah &c.
Panchnagar	31,741	1,181,266	27,879	50	500	Jat.
Parsaror	509,858-4	27,978,583	486,551	200	4000	Jat, Bājoh Telah &c.
Badubhandāl	23,752-18	1,611,882	46,979
Pati Zafarwāl, has a fort	6,108,148	3,697,338	150,865	50	2000	Jat, Bholron.
Pati Tarmali	29,056	525,953	...	20	400	Kolrā.
Bhalot	20,312-10	818,182	...	100	2000	Manhās.
Bhadran, situate on a hill	...	240,000	...	50	4000	Do.
Balāwarah	6,021-6	240,000	...	50	3000	Balāwariah.
Bhutiāl	2,407,18	96,000	...	30	1000	Bhutiālāh.
Ban	1,346-19	48,000	...	100	4000	Manhās.
Tāral	38,669-8	2,144,945	8,400	150	2000	Jat, Tāral.
Talwandi	95,698-17	1,578,207	3,792	30	300	Jat.
Chima Chata	95,698	5,878,691	26,439	100	1000	Chimah Chatah.
Chandanwarak, (var. darak)	81,426-6	4,128,313	30,571	...	150	Jat, Warak.
Chhotādhar	22,858-5	1,391,692
Jabudhadi	12,474	815,587	31,135
Chiniwot, has a brick fort	154,154	2,806,369	190,052	500	5000	Jat Jabuhar.

Sarkār of Rechnāu Dāab—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Jammu, situate at the foot of a hill, and a stone fort above it* ...	19,329-11	3,956,000	...	1000	20,000	Manhās.
Jasrotā (in one MS.) ...	150,430	400	5000	Malanhās.
in another ...	430-19	1,150,000
Chari Champā [Chamba] ...	6,021-6	240,000	...	100	1000	Gwāleri.
Hāfizābād ...	169,499	4,548,000	48,000	150	150	Jat Balhan (Bhalar).
The lands of Khānpur ...	402	27,028
Daulatpur ...	4,779-10	115,050
Dāud Bhandāl Barhi ...	23,142	1,725,089	237,082
Daulatābād ...	14,368	241,740	...	10	100	Jat Salah, (var. Sad).
Rupnagar ...	6,705	410,513
Rinhā ...	58,850-8	275,550	5,461	Brāhman, Bāghbān.
Rechnā ...	130,207	8,680,742	442,082	700	7000	...
Sāhumali ...	152,391	5,574,764	18,353	40	1200	...
Sidhpur ...	108,923	3,127,212	79,972	100	2000	Jat, Marāli.
Siālkot, is situate on the edge of a ridge on the banks of the Aik torrent, has a brick fort ...	102,035	22,090,792	184,305	500	7000	Jat, Ghaman and Chimah.
Sahajrāo ...	5,627-7	362,326	4,803	100	1000	Chimah.
Sohdra, on the Chenāb, has a high brick minaret ...	121,721-1	7,096,710	99,731	100	1000	Do.
Shānzdah Hīnjrāo ...	64,140	1,536,480	...	50	1000	Jat, Hīnjrāo.
Shou [-kot?] ...	107,347	2,278,940	5,061	1000	5000	Jat, Langāh, Sanāwal (Sahāwal).
Fattu Bhandāl Barhi ...	7,826-7	613,917	5,842
Fazlābād ...	2,115-7	136,528
Gobindwāl ...	55,069	1,253,957	194,622	50	300	Orak and Jat.
Kāthohā ...	126,598-12	5,888,254	...	20	10,000	Kāmwal (var. Kāhwāl).
Gujrān Barhi ...	2,631-14	670,936	11,787
Kālāpind ...	2,801-19	203,964	21,702
Kārnari, commonly called Sāniā ...	27,665-4	1,500,000	...	100	300	...
Kharli Tarli	768,000
Lakhnor ...	17,169-1	681,818
Mangtanwāla ...	131,583	3,819,690	57,788	50	300	Jat.
Muhammad Bari Dukrāo ...	16,561-6	1,127,903	3,367	Jat.
Mahrar ...	102,586-4	3,005,602	6,602	5	500	Brāhman.
Mengri ...	62,293	1,475,225	5,748	20	1000	Silhariyā and Gujar.
Mankot, includes 4 towns each with a stone fort ...	1,312	85,119	...	30	1200	Manhās.
Wan ...	140,234	371,553	20,278	50	1000	Jārak Silhar.
Haminagar ...	141,063	8,391,082	59,541	30	1000	Jat.
Hantiyāl (var. Hatiyāl) ...	6,201-6	240,000	...	30	200	Hatiyālāh.

* The town and palace stand on the south bank of the river Tāvi a tributary of the Chenab; the fort overhangs the left or east shore at an elevation of 150 feet above the stream, I. G.

Chenhāt (Jech) Doāb.

Containing 21 *Mahals*, 2,633,210 *Bighas*, 5 *Biswas* Revenue 64,502, 394 *Dāms*. *Suyurghāl* 511,070 *Dāms* Castes, various. Cavalry, 3,730. Infantry, 44,200.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Andarhāl	31,070	485,418	...	—	...	Gakkhar (see Vol. I. 546). Manhās.
Akhāndor Ambūran ...	9,866-5	352,000	...	300	3000	
Bhera, on the banks of the Bhimbar ¹	912,107-7	19,910,000	53,560	700	10,000	
Bahlolpur, on the banks of the river Chenab ...	170,607*	3,830,575	10,583	100	500	Jat.
Bolet	8,748	400,080	...	50	300	
Bhimbar, situated on the banks of the stream ...	28,668	1,200,000	Jat, Bhandwāl. Mangharwāl. Khokhar.
Bhadu	4,717	192,000	...	30	1200	
Buhati	2,874	57,222	...	10	100	
Sāilā and Dudiyaī, 2 <i>Mahals</i>	27,421	735,741	...	200	800	Jat, Khokar, Jander.
Shorpur	169,874	3,121,546	8,497	100	1000	
Shakarpur	7,684	1,050,819	Khokhar. Do.
Gujrāt	285,094	8,266,150	...	120	1000	
Kariyāli	57,818	2,643,270	6,633	100	2000	
Khokhar, has a brick fort	92,826	2,320,594	58,410	100	1000	Khokhar. Do.
Ghari, on the river Bihat	20,176	1,505,241	...	20	2000	
Lolor, separated from Khushāb	192,253	3,746,166	11,290	200	2000	Khokhar and Mikan. Manhās.
Mangli	2,839	432,000	...	400	2000	
Malot Rāe Kedāri, situ- ate on a hill	17,007	370,549	...	40	400	Mangharwāl. Tat, Barwānji ? Jat, Khokar Bāranij ?
Hareo	247,878	9,150,828	76,321	300	3000	
Hazāra, has a brick fort	270,392	4,689,136	219,536	700	3000	

¹ Bherah is on the left bank of the Jhelum. The Bhimbar torrent rising in the second Himalayan range, flows within 4 miles N. W. of Gujrāt and eventually joins the Jalālīa nālā a branch of the Chenab. I. G.

Sindh Sāgar Doāb.

Containing 42 *Mahals*, 1,409,929 *Bighas*. Revenue, 51,912,201 *Dāms*. *Suyurghāl*, 4,680 *Dāms*. Castes, various. Cavalry, 8,553. Infantry, 69,700.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Akbarābād Tarkheri ...	204,381	5,491,738	...	2000	15,000	Gakkhar.
Atak Benares (Attock) ...	5,418	3,202,216	...	1000	5000	Khatar, called also Salāsah.
Awān, here are horses of good breed ...	10,096	415,970	...	50	500	Awān. (See Vol. I, 456, n. and I.G. under Hazāra).
Paharhāla, has a stone fort, below the fort runs the river Sowāri (=Sohān) ...	192,247	5,158,109	
Bel Ghāzi Khān ...	17,426	320,000	...	100	1500	Jānohah (Janjuah).
Bālā Khattar ...	5,825	1,000,040	...	20	100	Khattar.
Parn Khattar ...	1,195	48,000	
Balokidhan ...	7,679	1,316,801	...	100	500	Gakkhar.
Tharchak Dāmi ...	6,082	250,575	...	100	1000	Do.
Suburban dist. of Rohtas,* has a stone fort, be- neath which flows the Kuhān stream ...	120,884	60,403,140	67,052	500	3000	Gakkhar. Bagiyāl.
Khushāb, situate near the river Bihat (Jhelum) the greater part is jungle ...	73,086	2,702,509	...	500	7000	Afghān Niyazi and Isā Khel.
Dān Gari [D. Gali] ...	147,647	3,301,201	...	1500	10,000	Gakkhar,
Dhānkot [Dinkot], on the banks of the river Mih- ran, viz., Indus, has a salt mine ...	8,927	488,000	...	150	4000	Awān.

* The fort built by Sher Shāh as a check on the Gakkhar tribes, now in picturesque ruin. It is situated in the Salt Range on a gorge overlooking the Kuhān Nadi 11 miles north-west of Jhelum town. The walls extend for three miles and encircle the rocks which command the entrance of the pass. Some parts have a thickness of from 30 to 40 feet. One gateway still remains in excellent preservation. I. G.

Sindh Sāgar Doāb—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Darband, (here two un- intelligible words)	3,100,000	...	20	500	Janohāh (Janjuah).
Dhrāb ...	2,330	96,000	...	20	150	Do.
Dudwat ...	2,830	96,000	...	20	300	Do.
Reshān ...	1,195	92,496	...	10	200	Awān.
Shamsābād ...	24,664	7,034,503	...	50	500	Gakkhar (var. Khokhar).
Patālā ...	11,146	624,000	...	100	1500	Jānohah.
Fatchpur Kālauri (var. Ka- nauri and T.) ...	157,042	4,261,831	...	500	10,000	Gakkhar.
Kalbhalak ...	40,913	2,883,253	18,176	30	200	Baloch.
Gheb (var. Khet, Khes, Khep) ...	16,961	934,161	...	300	1200	Khattar (sic).
Khār Darwāzah ...	4,316	24,541	...	50	300	Jānohah.
Girjhāk ¹ ...	21,491	961,755	...	100	1500	Do.
Kachākot, one kos distant from this parganah is the spring of Hasan Abdāl ² ...	5,825	340,000	...	50	2000	Rāwalah, Tarin, Afghan.
Kāhwān, has a stone fort	4,660	192,000	...	10	200	Jānohah.
Kambat ...	2,330	96,000
Langahtiyār (var. G. Siyār)	2,330	96,000	...	10	100	...
Mākhiāl, has a stone fort on a hill—there is scar- city of water—has a salt mine and a shrine ...	9,320	834,000	...	100	1500	Jānohah.

¹ Said by Cunningham, (*Ancl. Geog.*, p. 163 and pronounced *Girjhak*) to be the Hindu name for Jalālpur, the probable site of the famous city of Bukephala built in memory of Alexander's horse.

² This well-known village lies on the road between Rawal Pindi and Peshawar which with its ruins, says the I. G., forms part of a group of ancient cities lying round the site of the ancient Taxila. Hwen Tshang the Chinese Buddhist pilgrim of the 7th Century A.D. visited the tank of the Serpent King, Elapatra, identified with the spring of Bābā Wali (Kandahārī) or Panja Sāhib. The fountain is hallowed by legends of Buddhist, Brahman, Moslem and Sikh. The shrine of Panja Sāhib crowns a precipitous hill about one mile east of the town, and at its foot is the holy tank, a small square reservoir, full of fish. Delapidated brick temples surround the edge and on the west side the water gushes out from beneath a rock made with the representation of a hand, ascribed by the Sikhs to their founder Bābā Nānak. The scenery is extremely picturesque; the river Haroh hard by affords excellent fishing, and on its near shore two ancient cypresses are the only epitaph above the tomb of one of Akbar's wives. For *Kachakot*, see Cunningham, *Ancl. Geog.*, p. 116.

Sindh Sāgar Doāb—Contd.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Marāli, at the foot of a mountain	5,825	240,000	..	15	500	-
Malot, has a stone fort on a hill	3,236	133,233	...	10	200	Janohah.
Nandanpur, has a brick fort on a hill	40,997	24,110	4,110	20	150	Do.
Nilāb, (Indus) land included under (Attock) Benares	8,787	481,305	
Nārwi, on the Sind	997	38,091	...	under Akbarā-bād		Gakkhar.
Nokosiral Khattar	926	38,096	...	10	50	Khattar.
Hazāra Qarlug	214,982	1,805,342	5,342	100	500	Dālāzāk
Haliyār Lang	7,281	300,000	Afghān.
						Bhakar bar-khatri (with illegible variants).
Hazāra Gujrān	6,575	280,896	...	under Akbarā-bād		
Himmat Khān Karmun	165	48,000	...	Do.		Gakkhar.

*Beyond the Five rivers (Birun i Panjnad).**

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Belot	322,740	...	100	10,000	Baloch.
Sahlor	1,700,000	...	40	700	Chandel and others.
Kahlor, (Punjab Hill State)	...	1,800,000	...	50	1000	Do.

* The valley of the Jhelum takes the name of *Trimāb* (Three rivers) after its junction with the Chenāb and the Rāvi and that of *Panjnad* (Five rivers) after receiving the united waters of the Beās and Sutlej. I. G. This restricted signification cannot here apply. Certain outlying portions beyond the limits of the Punjab Proper were evidently attached to the *Subahs* of Lahor and Multān and to the *sarkar* of Dipalpur and were denominated—*Birun i Panjnad*.

SUBAH OF MULTĀN

It is situated in the first, second and third climates simultaneously. Before *Tattah* was comprised in this province, its length from *Firozpur* and *Sewistān*, was 403 *kos* and its breadth from *Khatpur*¹ to *Jaisalmir*, 108 *kos*, but since its inclusion, it measures to *Kach* (*Gandāvā*) and *Mekrān*, 660 *kos*. On the east, it marches with the *Sarkār* of *Sirhind*; on the north with *Shor*; on the south, with the *Subah* of *Ajmer*, and on the west, with *Khach* and *Mekrān*. 660 *kos*. On the east, it marches with the *Sarkār* of *Sirhind*; on the north with *Shor*; on the south, with the *Subah* of *Ajmer*, and on the west, with *Khach* and *Mekrān*. For facility of reference, the two territories are separately described. Its principal rivers are the six already mentioned. The *Bihat* (*Jhelum*) joins the *Chenāb* near the *pargana*h of *Shor* and after a course of 27 *kos*, they unite with the *Ravi* at *Zafarpur* and the three flowing collectively in one stream for 60 *kos*, enter the *Indus* near *U'ch*. Within 12 *kos* of *Firozpur*, the *Biāh* joins the *Sutlej* which then bears several names, *viz.*, *Har*, *Hāri*, *Dand*, *Nugni*,² and in the neigh-

¹ *Khatpur* is placed by *Abul Fazl* in the *Rachna Doāb* and by *Tieffen-thaler* as the first stage in a journey from *Lahor* to *Multān*.

² The text diffidently forms two names of these four, *viz.*, *Harhāri*, *Dand-nurni*, but the authority of the two best MSS. (relegated to the notes) divides them. One at least of these names, *Dand*, still lives in the local designation of a former bank of the *Sutlej*, whose shifting course has modified the aspect of the country. One ancient bed, forming the base of the segment where the *Sutlej* after its junction with the *Beās* curves round to the south-west is called the *Sukhar Nai* (*I. G.*) which crosses the district east to west and joins the modern channel near the borders of *Sirsa*. The *Danda* bank points to a still more ancient course crossing the south-west corner 35 miles east of the present stream, traceable as far as *Moodkee* and thence at intervals to the *Sutlej* 15 miles farther north. The old beds of the *Rāvi* and *Beās* which formerly united their waters much lower down, at present may be traced through a great part of the *Bāri Doāb*. (*I. G.*) See the ancient courses of these rivers in *Cunningham's Ancient Geography of India*, p. 220, *et seq.* General *Cunningham* bases his discussion on *Gladwin's* translation, *viz.*, 'For the distance of 17 *kos* from *Feerozpoor*, the rivers *Beyah* and *Seteluj* unite: and then again as they pass along, divide into 4 streams, *viz.*, the *Hur*, *Haray*, *Dund* and the *Noorny*: and near the city of *Multān* these 4 branches join again,' and says that these beds still exist but their names are lost. Now *Abul Fazl* does not say that the *Sutlej* divides into 4 streams, but that it bears several names. *Abul Fazl* is describing the rivers watering the *Multān Subah*. He says they are the six previously mentioned, *viz.*, under *Lahor*. He first speaks of the *Jhelum* and the *Chenāb* and follows them to their junction with the *Rāvi* and then to their meeting with the *Indus*. Here are four. He now turns to the *Beās* and *Sutlej* which join near *Firozpur* and the stream after bearing several names becomes confluent with "those four" near *Multān*, not, I consider,

bourhood of *Multān*, confluent with the former four, their accumulated waters unite. Every river that discharges itself into the Indus takes its name of *Sindh*. In *Tattah*, they call it *Mihhrān*.¹

To the north are the mountains. Its climate is similar to that of *Lahor* which it resembles in many aspects, but in *Multān*, the rainfall is less and the heat excessive.

Multān is one of the oldest cities of India: Long. 107° 35'; Lat. 29° 52'. It has a brick fort and a lofty minaret adds to its beauty. *Shaikh Bahā-u'ddīn Zakariyā* and many other saints here repose.

Bhakkar (Bhukkur) is a notable fortress; in ancient chronicles it is called *Mansura*.² The six rivers united roll beneath it, one channel passing the southern face of the fort, the other the northern. The rainfall is inconsiderable, the fruits excellent.

Between *Siwī*³ and *Bhakkar* is a vast desert, over which for three months of the hot season the simoom blows.

names, even were they separate beds, but with the four that complete the six. The doubt arises why he should place the junction near *Multān* instead of *Uch*, but this is not surprising to any one accustomed to his obscure and vague style of narrative. Moreover the passage in the text resembles a notice of these six rivers in *Baber's Memoirs* to which *Abul Fazl* was much indebted in the preparation of this third book of the *Ain*. The passage is as follows: I use the translation of *Erskine*. "To the north of *Sehrend*, six rivers, the *Sind*, the *Behat*, the *Chenāb*, the *Rāvi*, the *Biāh*, and the *Setlej*, take their rise in these mountains, and all uniting with the *Sind* in the territory of *Multān*, take the common name of *Sind*, which flowing down to the west, passes through the country of *Tatta*, and disembogues into the sea of *Oman*." Further the division of the *Sutlej* into the four local streams does not alter its point of junction with the *Chenāb* for at p. 222, *Cunningham* says that *Abul Fazl's* measurements of distances from the confluence of the *Chenāb* and *Jhelum* to that of the *Chenāb* and *Rāvi* and the *Chenāb* and *Indus* agree with the *later* state of these rivers.

¹ The main stream of the Indus. See its course and the names of its channels in *Cunningham's Ancient Geography of India*, pp. 252, 272, 286, 293, &c.

² After the decline of the Arab power in *Sind* about A.D. 871, two native kingdoms raised themselves at *Multān* and *Mansura*. The former comprised the upper valley of the Indus as far as *Alor*; the latter extended from that town to the sea and nearly coincided with the modern province of *Sind*. *Alor*, or *Aror*, the capital, almost rivalled *Multān* and had an extensive commerce. *I. G. Genl. Cunningham (Ancient Geog.)* gives the name of *Mansura* to the town founded, according to *Masaudi*, by *Jamhur*, the Moslem governor of *Sindh*, and named after his own father *Mansur*, so close to *Brahmanābād* as to be regarded as the same place. His learned discussion depends too much on analogies of sound in names, to be quite convincing. See, also *Mansura* in *Elliot's Arabs in Sind*, p. 50, *et seq.*

³ *Siwī*, *Sewistān*, and *Schwān* are constantly confounded or mistaken as *Elliot* remarks without, however, himself determining the position of the first which is a town or the geographical limits of the second which is a province. *Siwī* is somewhat south of the direct line between *Dera Ghazī Khān* and *Quetta*, now well known as *Sibi*. Vol. I, p. 362, *Sewe*.

The river *Sind* (Indus) inclines every few years alternately to its southern and northern banks and the village cultivation follows its course. For this reason the houses are constructed of wood and grass.

This *Subah* comprises three *Sarkārs* of 88 *parganahs*, all under assessment for crops paying special rates. The measured land is 3,273,932 *bighas*, 4 *biswas*. The gross revenue is 15 *krors*, 14 *lakhs*, 3,619 *dāms*. (Rs. 37,85,090-8-0), of which 30 *lakhs*, 59,948 *dāms* (Rs. 76,498-11-2), are *Suyurghāl*. The local militia consists of 18,785 Cavalry and 165,650 Infantry.

Sarkār of Multān. Four Doābs.

Containing 47 *Mahals*, 558,649 *Bighas*, 4 *Biswas*. Revenue, 53,916,318 *Dāms*. *Suyurghāl*, 5,494,236 *Dāms*. Cavalry, 8,965. Infantry, 90,650.

Bet Jālandhar Doāb.

Containing 9 *Mahals*, 52,090 *Bighas*. Revenue, 17,240,147 *Dāms*. Cavalry, 1,410. Infantry, 17,100.

			Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Adamwāhan	5,386	369,445	...	30	700	Hasar.
Jalālābād	5,000	299,798	...	10	200	Bhim.
Dunyapur	27,889	1,876,862	11,998	50	400	Uki, Rānu.
Rājpur	1,368	90,397	...	20	300	Junah.
Shergarh	75,000	5,741,200	...	400	4000	Kachhi, Junah, Bikānah, Malāh.
Fathpur	61,797	4,008,661	24,596	500	5000	Junah.
Kahrōr	47,695	305,856	40,931	100	2000	Junah.
Khāibuldi	80,411	594,233	...	200	...	Jat and an- other name illegible.
Ghalu Khārah	19,820	1,201,086	...	100	2000	Kalu, Jat.

Bāri Doāb.

Containing 11 *Mahals*, 137,629 *Bighas*, 13 *Biswas*.
 Revenue, 9,863,341 *Dāms*: *Suyurghāl*, 207,382 *Dāms*.
 Cavalry 775. Infantry, 14,550.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Islāmpur, has a brick fort	23,085	1,550,896	60,394	1000	3000	Bhim, Maral.
Ismailpur ...	900	49,932	...	5	50	Maral.
Multān town, has a brick fort ...	2,324	1,719,168	88,980	50	1000	Bhim, Shaikh- zādah. Sohu.
Tulamba ...	19,310	1,200,778	15,766	300	5000	
Villages of the <i>pargānah</i> of Chaukhandi ...	2,927	191,054	
Suburban dist. of Multān	35,925	2,288,354	37,463	Bhim.
Villages of <i>pargānah</i> of Khatpur ...	2,487	149,578	
Do. Do. Deg.* Rāvi	897-14	50,146	
Shāh Aīlampur ...	24,121	1,555,563	1,180	200	4000	
Villages of <i>pargānah</i> of Khāibuldi ...	7,584-19	460,654	
Matila ...	2,068	608,418	3,598	20	500	Jat.

* The Degh (*I. G.*) is the chief tributary of the Rāvi, which it receives after entering Montgomery District on its north-west bank and then passes into Multān District.

Rechnāu Doāb.

Containing 6 *Mahals*, 83,229 *Bighas*, 18 *Biswas*. Re-
 venue, 5,113,883 *Dāms*. Cavalry, 770. Infantry, 9,500.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Irajpur and Deg Rāvi ...	37,230	2,377,300	...	100	2000	Kharal.
Chaukhandi ...	7,620	215,830	...	100	2000	Do.
Khatpur ...	8,387	505,398	...	500	3000	Jat, Sindh.
Dalibhati ...	3,768-18	256,569	...	20	500	Kharal.
Kalbah ...	16,208	958,786	...	50	2000	Jat, Sohu.

Sind Sāgar Doāb.

Containing 4 Mahals, 34,812 Bighas. Revenue, 2,178,192 Dāms. *Suyurghāl*, 13,399 Dāms. Cavalry, 220. Infantry, 2,000.

	Bighas Biswas	Revenue D.	<i>Suyur- ghāl</i> D.	Cavalry	Infantry	Castes
Villages of Islāmpur ...	5,775	378,357	Jat. Bhim.
Rangpur ...	22,907	1,410,737	10,737	200	2000	
Raepur Kanki ...	5,550	376,068	2,662	20	500	
Miscellaneous villages, 1 Mahal ...	600	38,030	

Beyond the Five Rivers. (Birun i Panjnad.)

Containing 17 Mahals, 205,893 Bighās, 13 Biswas. Revenue, 18,820,255 Dāms. *Suyurghāl*, 38,688 Dāms. Cavalry, 5,800. Infantry, 57,600.

	Bighas Biswas	Revenue D.	<i>Suyur- ghāl</i> D.	Cavalry	Infantry	Castes
Ubaura ...	11,320	915,256	4,684	30	500	Dhar. Shahibzadah, Bakhari, Sayyid.
Uch ...	29,056	1,910,140	...	100	400	
Bhurtiwāhan, (var. and G. Dāman) ...	16,696	1,336,029	13,564	200	2000	Rājput, Lodhi.
Jamsher ...	4,334	348,037	...	150	2000	Baloch, Bholdi and Nardi.
Dudāi, has a brick fort ...	40,520-11	2,400,000	...	4000	30,000	Dudāi.
Diwār i Awwal, (Cunning- ham. Dirāwal) ...	2,718	140,000	...	50	500	Rājput, Kot- wāl.
Dud Khān ...	17,690	1,440,000	Afghān. Dhar.
Villages of Rājpur ...	452	29,854	
Rupari ...	12,075	1,080,000	
Sitpur ...	44,538-8	4,608,000	...	1000	20,000	
Scorāhi ...	5,124	28,600	...	20	100	Kuraishi. Bhatti.
Villages of Fatehpur ...	5,224	330,779	
" " Kaharor ...	1,384	87,289	
Majlōl Ghāzipur ...	40,521	2,400,000	
Mauh, has a brick fort. (Cunningham Moj.) ...	9,083	707,069	20,440	50	1000	Bhatti.
Marot, do. ...	5,456	204,000	...	200	1000	
Mahand ...	9,336-12	8,014,000	...	200	1000	

¹ Of these Cunningham can identify but Uch, Dirāwal, Moj and Marot, which he places, east of the Sutlej. The limits of the province of Multān in the time of Hwen Tshang included the north half of the Bhawalpur territory in addition to the tract lying between the rivers, the north frontier extending from Deraḥ Din Panāh on the Indus to Pāk Pattan, a distance of 150 miles; on the west, the frontier line of the Indus to Ekānpur, 160 miles; on the east from Pāk Pattan to the old bed of the Ghager, 80 miles; on the south from Khānpur to the Ghager, 220 miles, p. 220.

Sarkār of Dipālpur.

Containing 29 *Mahals*, 1,433,767 *Bighas*, 8 *Biswas*.
 Revenue, 129,334,153 *Dāms*. *Suyurghāl*, 2,079,170 *Dāms*.
 Cavalry, 5,210. Infantry, 53,300.

Bet Jālandhar Doāb.

Containing 10 *Mahals*, 710,946 *Bighas*, 10 *Biswas*.
 Revenue, 88,808,855 *Dāms*. *Suyurghāl*, 1,481,564 *Dāms*.
 Castes, various. Cavalry, 2,400. Infantry, 20,400.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Pattan, (Pāk Pattan) has a brick fort	49,014	2,628,928	599,989	100	2000	Bhil, Dhokar.
Dipālpur Lakhi, has a brick fort	242,344-11	13,514,059	499,535	502	7000	Jat, Kho- khar, Kasu, Bhatti.
Dhanakshāh, has a brick fort	60,676-1	3,484,375	87,152	...	400	
Deotir	40,730	2,489,850	23,400	50	1000	Jat.
Rahmatābād	38,285	1,825,009	...	100	2000	Baloch, Khokhar.
Qabula, has a brick fort	86,615-12	4,808,817	...	1000	2000	Jusah Rumi.
Qiyāmpur Lakhi, has a brick fort	54,678-19	2,008,274	88,855	300	2000	Bhatti, Jat.
Kalnāki Lakhi	55,243-3	2,385,969	93,809	50	1000	Do. do.
Khokarāin Lakhi	21,130	1,011,715	35,383	150	1000	Khokhar.
Lakhi Losqāni	61,519-16	3,156,759	5,940	100	2000	Bhatti, Khilji.

Bāri Doāb.

Containing 6 *Mahals*, 193,495 *Bighas*, 9 *Biswas*. Re-
 venue, 1,175,393 *Dāms*. Castes, various. Cavalry, 1,100.
 Infantry, 14,000.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Bahrapāl	18,717-9	1,175,393	...	50	500	Bhatti.
Bābā Bhoj, has a fort ...	39,385	2,020,256	20,256	150	2000	Sayyid, Jat.
Chahni	25,993	1,200,600	600	50	2000	Sayyid, &c.
Rahimābād	24,829	1,182,714	...	50	500	Kharal, Baloch.
Sadkharah [?Satgarh] ...	59,447	3,551,680	20,976	300	4000	Do.
Mandhāli	25,624	2,708,429	...	500	5000	Bhim.

Containing 7 Mahals, 142,856 Bighas, 2 Biswas. Revenue, 8,534,915 Dāms. Suyurghāl, 5,808 Dāms. Castes, various. Cavalry, 710. Infantry, 6,300.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Khānpur ...	19,534.18	1,285,740	50,380	30	500	Kharal.
Dalchī Chandhar ...	9,153.12	605,557	1,620	50	1000	Chandhar.
Shahzādah Baloch ...	12,749.12	789,741	...	100	1000	Baloch.
Aābidi Ābād ...	5,975	343,932	...	10	300	Jat.
Faryādābād ...	18,708	1,098,694	...	20	1000	Jat.
Kharal ...	53,782	1,507,069	2,800	300	2000	Khari.
Mahes ...	42,844	2,509,182	...	200	500	

Beyond the Five Rivers (Birun i Panjnad).

Containing 6 Mahals, 386,470 Bighas, 7 Biswas. Revenue, 20,580,771 Dāms. Suyurghāl, 549,972 Dāms. Cavalry, 1,000. Infantry, 12,300.

Sarkar of Bhakkar (Bukkur).

Containing 12 *Mahals*, 282,013 *Bighas*. Revenue, 18,424,947 *Dāms*. *Suyurghāl*, 600,419 *Dāms*. Cavalry, 4,600. Infantry, 11,100.

	Bighas Biswas	Revenue D.	Suyur- ghāl D.	Cavalry	Infantry	Castes
Alor, has a fort ...	143,700	1,132,150	20,550	200	500	Dharejah.
Bhakkar, has a strong fort	74,362	...	200	1000	Mehar and Rahār.
Jāndola ...	57,847	8,102,709	85,064	400	800	Jahna.
Jatoi ...	179,821-14	2,346,878	156,841	400	800	
Darbela ...	121,146	1,262,761	68,872	200	500	Bhatti.
Sankar ...	100,818	1,808,628	32,332	500	1000	Sahejah.
Siwi	1,381,930	...	500	1500	
Fathpur ...	8,050-10	477,859	...	200	1000	Saheja, Dharejah.
Khajāna ...	10,063	645,205	...	200	1000	Jāman.
Khāra Kākan ...	154,151	2,732,331	138,608	500	1000	Dharejah.
Kākhari, (var. Kākri) ...	178,338-16	2,106,431	63,208	500	1000	Mankrerah.
Mānhalah ...	128,078	1,353,718	28,944	500	1000	Dharejah (var. Hāre- jah).

*Kings of Multān.**

	Years.
Shaikh Yusuf, reigned ...	2
Sultān Mahmud† (var. Muhammad Shāh) ...	17
„ Qutbu'ddin, his son ...	16
„ Husain, his son ...	30

* This province, says the *U. T.*, was first conquered by Mahomed Kāsim at the end of the first century Hejira. It was recovered by the Hindus on the decline of the Ghazni power. After Mahomed Ghori's subjugation it remained tributary to Delhi until

A.H.	A.D.	
817.	1443.	Shaikh Yusuf established an independent monarchy.
819	1445.	Rav Sehra, or Kutbu'ddin Hosen Langa I expelled the Shaikh.
908.	1502.	Mahmud Khān Langa; his minister Jam Bayezid.
931.	1524.	Hosen Langa II, overcome by Shāh Hosen Arghun. Under Humayun, becomes a province of the empire.

† This name is altogether omitted by Ferishta who describes Qutbu'ddin's intrigue and succession, in his history of Multān. The name of Qutbu'ddin was Rāe Sehra and he was governor of Sewi and the adjacent territory and the head of the Afghān clan of Langāh. He died in A.H. 874 (A.D. 1469), Husain Shāh in 904 or 908 (1493 or 1502) and Mahmud in 931 (1524).

Sultān Fīroz, his son	1
„ Husain, a second time.			
„ Mahmud, son of Sultān Fīroz	...		27
„ Husain II, son of Sultān Mahmud	...		1
Shāh Husain, (Arghun), ruler of Sind.			
Mirzā Kāmran.			
Sher Khan.			
Salim Khān.			
Sikandar Khān.			

At one period the province was subject to the sovereigns of Delhi: at another it was under the control of the rulers of Sind, and for a time was held by the princes of Ghazni. After its conquest by Muizzu'ddīn Sām (Ghori), it continued to pay tribute to Delhi. In the year A. H. 847 (A. D. 1443) when Sultān Alāu'ddīn reigned at Delhi, and constituted authority fell into contempt, every chief in possession of power, set up a pretension to independence. A noisy faction raised Shaikh Yusuf Quraishi, a disciple of Shaikh Bahāu'ddīn Zakariya, to supremacy. He was subsequently deposed and proceeded with haste to the court of Sultān Bahlol at Delhi. The sovereignty now devolved upon one of the Langāh family, who assumed the title of Sultān Mahmud Shāh. It is related that this chief had given his daughter in marriage to Shaikh Yusuf, and on the strength of this connection, used frequently to visit her alone, till one night by a successful intrigue he accomplished his design on the throne. During the reign of Sultān Qutbuddin, Sultān Mahmud Khilji advanced from Mālwah against Multān but returned without effecting anything. Some maintain that the first of the Langāh family who was raised to the throne was Qutbu'ddīn. In the reign of Sultān Husain, Bahlol sent (his son) Barbak Shāh with a force to reinstate Shaikh Yusuf, but they returned unsuccessful. Sultān Husain becoming old and doting, placed his eldest son upon the throne under the title of Fīroz Shāh, and withdrew into retirement. His Wazir Imadu'l Mulk, poisoned him in revenge for the murder of his own son and Sultān Husain a second time resumed the sceptre and appointed Mahmud Khān, son of Sultān Fīroz, his heir. On the death of Sultān Husain, after a reign of 30 or 34 years [908 A.H.], Sultān Mahmud ascended the throne. During his reign several incursions were made by the Mughals who, however, retired discomfited. Some malicious intriguers through jealousy created a misunderstanding-

ing between the Sultān and Jām Bayazid who had long held the office of prime minister, and misrepresentations cunningly made in a roundabout way, brought them into open conflict. The minister withdrew from Multān to Shor and read the *khutbah* in the name of Sultān Sikandar Lōdi. On the death of Sultān Mahmud, his infant son was raised to the throne as Sultān Husain (II). Mirzā Shāh Husain (Arghun) marched from Tattah and took Multān and entrusted its charge to Langar Khān. Mirzā Kāmran dispossessed him of it and after him Sher Khān, Sālim Khān and Sikandar successively held it till the splendour of Humayun's equal administration filled Hindustān with its brightness and secured its peace. At the present day under the just sway of His Majesty his subjects find there an undisturbed repose.

Sarkār of Tattah.

During a long period this was an independent territory but now forms part of the imperial dominions. Its length from Bhakkar to *Kach* and *Mekrān* is 257 *kos*, its breadth from the town of *Budin* to *Bandar Lāhari*,¹ 100 *kos*, and again from the town of *Chāndo* one of the dependencies of *Bhakkar*, to *Bikaner* is 60 *kos*. On the east lies *Gujarāt*: to the north *Bhakkar* and *Sewi*;² to the south, the ocean, and to the west *Kach* and *Mekrān*. It is situated in the second climate and lies in Longitude 102° 30' Lat. 24° 10'.

The ancient capital was *Brāhmanābād*,³ a large city. Its citadel had 1,400 towers, at an interval of a *tanāb*, and to this day there are many traces of its fortifications. *Alor*³ next became the metropolis and at the present day it is *Tattah*, also called *Debal*. The mountains to the north

¹ "Lahari Bandar" in Cunningham's account of Sindh. (*Ancient Geography*).

² Identified by Cunningham with Harmatelia, (a softer pronunciation of Brāhmatala, or Brahmanasthala) of Diodorus and placed on the east branch of the Mīlran or Indus, 47 miles north-east of Haiderābad 28 miles east of Hāla and 20 miles west of the eastern channel of the Indus known as Nāra. He gives the number of bastions as 140 on the authority of the MSS. but both Gladwin and Blochmann concur in 1,400, and there is no variant reading. His conclusion is, that the place known now as *Bambhira ka thul* represents the ruined city of Mansura and the neighbouring mound now called *Dihura*, Brahmanabād.

³ The ruins of *Alor*, or more correctly *Aror*, are situated to the south of a gap in the low range of limestone hills stretching from Bhakar to the south for about 20 miles until it is lost in the broad belt of sand hills bounding the Nāra or old bed of the Indus. On the west, Cunningham regards it as the capital of the Musicanī of Curtius. He disputes the assertion of Abul Fazl that Debal and Tattah are the same. Sir H. Elliot places Debal at Karāchi. General Cunningham prefers a site between Karāchi and Tattah.

form several branches. One of them trends towards *Qandahār*, and another rising from the sea coast extends to the town of *Kobhār*, called *Rāmgar*, and terminates in *Sewistān* and is there known as *Lakkhi*.¹ This tract is inhabited by an important Baloch tribe called *Kalmāni*, [*? Kirmāni*] consisting of twenty thousand cavalry. A fine breed of camels is here indigenous. A third range runs from *Sehwān* to *Sewi* and is called *Khattar* [*Kirthar*], where dwells a tribe named *Nohmardi* that can raise a force of 300 horse and 7,000 foot. Below this tribe, there is another clan of the *Baloch* known as *Nazhari* with a force of a thousand men. A good breed of horses comes from this tract. A fourth mountain chain touches *Kach* (*Gandāvā*) on one side, and on the other the *Kalmāni* territory, and is called *Kārah* inhabited by 4,000 *Balochis*.

In the winter season there is no need of *poshtins* (fur-lined coats) and the summer heats are moderate except in *Sewistān*. Fruits are of various kinds and mangoes are especially fine. In the desert tracts, a small kind of melon grows wild. Flowers are plentiful and camels are numerous and of a good breed. The means of locomotion is by boats of which there are many kinds, large and small, to the number of 40,000. The wild ass is hunted, and game, such as, hares, the *kotah pāchah*² and wild boars; fishing likewise is much pursued.

The assessment of the country is made on the system of division of crops, a third being taken from the husbandman. Here are salt-pits and iron mines. *Shāli* rice is abundant and of good quality. Six *kos* from *Tattah* is a mine of yellow stone, large and small slabs of which are quarried and used for building. The staple food consists of rice and fish. The latter is smoked and loaded in boats, and exported to the ports and other cities, affording a considerable profit. Fish-oil is also extracted and used in boat building. There is a kind of fish called *palwah* which comes up into the *Indus* from the sea, unrivalled for its fine and exquisite flavour. Milk-curds of excellent quality are made and keep for four months. [*Palo*, Bengali *hilsā*.]

¹ The *Lakhi* range is an offshoot from the *Kirthar* which separates *Sind* from *Beluchistān*. I. G.

² Literally 'short legged'. It is thus described in *Babar's Memoirs*, "Its size may be equal to that of the white deer. Its two fore-legs as well as its thighs are short, whence its name. Its horns are branching like those of the *gawezin* but less. Every year too it casts its horns like the stag. It is a bad runner and therefore never leaves the jungle." These characteristics seem to point to the hog-deer, (*Cervus porcinus*).

Near *Sehwān* is a large lake, two days' journey in length called *Manchur*, in which artificial islands have been made by fishermen who dwell on them.

But the greatest of all wonders is the *Liver-eater* (*Jigar Khwār*), an individual who by glances and incantations can abstract a man's liver. Some aver that under certain conditions and at certain times, he renders the person senseless upon whom he looks, and then takes from him what resembles the seed of a pomegranate, which he conceals for a time in the calf of his leg. During this interval the person whose liver is stolen remains unconscious, and when thus helpless, the other throws the seed on the fire which spreads out like a plate. Of this he partakes with his fellows and the unconscious victim dies. He can convey a knowledge of his art to whomsoever he wills, by giving him a portion of this food to eat and teaching him the incantation. If he is caught in the act and his calf be cut open and the seed extracted and given to his victim, the latter will recover. The followers of this art are mostly women.

They can convey intelligence from long distances in a brief space of time and if they be thrown into the river with a stone tied to them, they will not sink. When it is desired to deprive one of these of this power, they brand both sides of his head and his joints, fill his eyes with salt, suspend him for forty days in a subterraneous chamber, and give him food without salt, and some of them recite incantations over him. During this period he is called *Dhachrah*. Although his power then no longer exists, he is still able to recognize a Liver-eater, and these pests are captured through his detection. He can also restore people to health by incantation or administering a certain drug. Extraordinary tales are told of these people that are beyond measure astonishing.

This country is the fourth *Sarkār* of the *Subah* of *Multān*. From the confines of *Uch* to *Tattah* towards the north are rocky mountain ranges inhabited by various Baloch tribes, and on the south from *Uch* to *Gūjarāt* are sandhills in which region are the *Ahshām Bhatti*¹ and other

¹ According to Cunningham, the early Arab geographers place a strong fort called *Bhātia* between *Multān* and *Alor*, which, from its position has a claim to be identified with the city built by Alexander among the Sogdi, but he mentions no tribe of the name, neither have any of the Bhatti Rajputs mentioned by Elliot any such prefix as *Ahshām* [=warriors]. The Sodahs have been identified by Tod with the Sogdoi. *Ancient Geography*, pp. 253-254.

numerous clans. From *Bhakkar* to *Nasirpur* and *Umarkot* are the *Sodah*, *Jārejāh* and other tribes. This *Subah* contains 5 *Sarkārs* subdivided into 53 *parganahs*. The revenue is 6,615,393 *dāms*.* (Rs. 165,384-13-2.)

Sarkār of Tattah.

Containing 18 *Mahals*. Revenue, 25,999,891 *Dāms*.

	Revenue D.		Revenue D.
Lāhari Bandar	5,521,419	Sankurah ¹	2,108,097
Batorā	4,932,286	Sirsi Jām	142,641
Bahrāmpur	1,311,612	Karhar, (var. and K. Kar- kar)	3,328,476
Bori	434,305	Lekin Kherah	535,795
Jakār [Jarāk] ²	348,462	Maljah	1,105,606
Jārā	82,390	Mānjar	1,221,752
Darak, (var. Durg)	2,970 441	Nizāmpur	352 724
Dankari, (var. Dekri)	315,921		
Ratnah	842,144		

* This is incorrect. Adding together the revenues of the five sarkārs, we get a total revenue of 6 62,51,393 *dāms* (Rs. 16,56,284-13-2).

¹ Var. Patora, Batwār, Banwār.

² *Jarak*, midway between Haidarābad and Tatta.

³ See Elliot, *Arabs in Sind*, p. 230.

Sarkār Hājkan.

Containing 11 *Mahals*. Revenue 11,784,586 *Dāms*.

	Revenue D.		Revenue D.
Bāgh Fath	340,173	Karori	529,937
Belah	656,317	Laundā	1 119,973
Hājkan	555,699	Mandni, (var. and G. Mandri)	694,269
Jaun	3,165,418	Madui	2,352,605
Rahbān	742,973	Nubiyar, (var. and G. Napiyār)	1,280,439
Detached villages ¹	436,783		

¹ *Qariyāt-i-mazkuri*, the term *mazkuri*, being applied in old revenue accounts to small and scattered estates not included in the accounts of the districts in which they were situated and of which the assessments were paid direct to Government.

Princes of Tattah.¹

1. The family of Tamim Ansāri during the ascendancy of the House of Umayyah.

2. The Sumra (Rājput) line of 36 princes, reigned 500 years, (according to Ferishta—100—their names unrecorded).

3. Of the Samma dynasty,

	Years	Months	D.
Jām Unar, reigned 3	6	0
„ Junā, his brother 4	0	0
„ Banhatiyah 15	0	0
„ Tamāchi, his brother 13 and some months.		
„ Salāhuddin 11 and	do.	
„ Nizāmuddin, his son 2 and a fraction.		
„ Ali Sher Tamāchi 6 and some months.		
„ Karān, son of Tamāchi 0	0	1½
Fateh Khān, son of Sikandar 11 and some months.		
Tughlaq, his brother 28	0	0
Mubarāk, the chamberlain 0	0	3

¹ The following list is from the *U. T.*

A.H. A.D.

87. 705. Belochistān invaded by Hijaj, governor of Bassora, and Md. Qāsim.

The *Ansaries*, the *Sameras*, and the *Samanas* or *Jams*, successively gain the ascendancy, then a Delhi governor (1205?) Nasir ud dīn Qabbacha, becomes independent, drowned.

The *Jami* Dynasty of Sumana, originally Rājputs.

A.H. A.D.

737. 1336. Jām Afra; tributary to Toghlak Shāh.

740. 1339. „ Choban.

754. 1383. „ Bang; asserted his independence.

782. 1367. „ Timaji, his brother.

782. 1380. „ Salāhu'ddin, convert to Islām.

793. 1391. „ Nizamu'ddin.

796. 1393. „ Aly Sher.

812. 1409. „ Giran, son of Timaji.

812. 1409. „ Fattah Khān.

827. 1423. „ Toghlak, invaded Gujerat.

854. 1450. „ Sikandar.

856. 1452. „ Sangar, elected.

864. 1460. „ Nandā or Nizām-u'ddin, cot. of Hasan Langa.

894. 1492. „ Feroz; the Turkhan family became powerful, 1520.

927. 1520. Shāh Beg Arghun, occupies Sind.

930. 1523. Shāh Hosein Arghun.

962. 1554. Mahmud of Bhakar.

982. 1572. Akbar annexes Sind. (Ferishta, 1001=1592).

The title of Jām, Ferishta pronounces, is a boast of their supposed descent from Jamshid, but commonly given to their head or chief to preserve the tradition of this fabulous lineage. The lineage of the Sumra and Samma dynasties is discussed in Appendix P. of Elliot's *Arabs in Sind*. The latter name may be traced in the *Sambaste* and *Sambus* of Alexander's historians. *Sambus* occurs as *Sabbas* in Plutarch, *Saboutas* in Strabo, *Ambigarus* in Justin and *Ambiras* in Orosius.

	Years	Months	D.
Sikandar, b. Fath Khān ...	1	6	0
Sanjar, commonly called Rādhan (var. and G. Rādmān ...	8	and some months.	
Jām Nizāmuddin, known as Jām Nandā, (see Vol. I, p. 362) ...	60	and some months.	
Jām Fīroz, his son.			
„ Salāhuddin, a relation of Fīroz.			
„ Fīroz, a second time.			

In former times, there lived a Rājā named *Siharas*¹ whose capital was Alor. His sway extended eastwards, as far as Kashmir and towards the west to Mēkrān, while the sea confined it on the south and the mountains on the north. An invading army entered the country from Persia, in opposing which the Rājā lost his life. The invaders contenting themselves with devastating part of the territory, returned. Rāi Sāhi, the Rājā's son, succeeded his father, by whose enlightened wisdom and the aid of his intelligent minister *Rām*, justice was universally administered and the repose of the country secured. A Brāhman named *Jach* [Chach] of an obscure station in life, attached himself to the minister's service and by flattery and address made himself of much consequence and was advanced to a post of dignity, and on the death of the minister, was chosen to succeed him. He basely and dishonourably carried on an intrigue with the Rājā's wife, which the Rājā, notwithstanding its disclosure to him by the ministers of State, refused to credit. During the Rājā's illness, the wicked wretch, in collusion with this shameless paramour, sent for the generals of the army separately, on pretence of consulting them and set them apart, and by seductive promises won over the several enemies of each to accomplish their death. When they were put out of the way and the Rājā too had breathed his last, he assumed the sovereignty.

The pursuers of worldly interests attached themselves to his cause and he took the *Rāni* to wife, thus garnering eternal perdition, but he laboured for the prosperity and increase of his dominions and seized upon *Kach* (Gandāvā), and *Mēkrān*.

¹ Of the Rai dynasty whose capital was Alor. The *Tuhfatul Kīrām* makes *Siharas* the son and successor of *Rāi Dhūwāj*, followed by *Rāi Sāhasi*, the first, second and third of that name. It was under the latter that Chach rose to power.

During the Caliphate of Omar (b. u'l) Khattab, Mughirah Abu'l Aās advanced by way of *Bahrain* to *Debal*, but the troops there opposed him and he was killed in the engagement. In the Caliphate of Othmān an intelligent explorer¹ was sent to ascertain the condition of Sind, and an army of invasion was under orders. The messenger, however, reported that if a large force were sent, supplies would fail, and a small one would effect nothing and he added many dissuasive representations. The Prince of the Faithful, Āli, despatched troops that occupied the borders of *Debal* but on hearing of the death of the Caliph they withdrew in haste to *Mekrān*. Muāwiyah twice despatched an army to Sind and on both occasions many of the troops perished.

Chach died after a prosperous reign of 40 years, and his youngest son *Dāhir* succeeded him on the throne. In the Caliphate of Walid b. Abdul Malik, when Hajjāj was governor of Irāq, he despatched on his own authority Muhammad Qāsim his cousin and son-in-law to Sind who fought *Dāhir* in several engagements.² On Thursday, the 10th of Ramazān A.H. 99, (17th April 717) the Rājā was killed in action and the territory of *Tattah* became subject to the invaders. The two daughters of Rājā *Dāhir*, who had been made captive were sent with some valuable presents to the Caliph. In a spirit of revenge, they deceitfully represented to the Caliph that Muhammad Qasim had dishonoured them. He therefore abstained from visiting them, and in a fit of fury gave orders that Qāsim should be stuffed into a raw hide and despatched to his presence. The commands of the Caliph reached him when he was about to march against *Hari Chand*, king of *Kanauj*, and he obediently submitted to them. When he was thus

¹ Hākim, b. Jabala al Abdi was sent to explore *Sejistān* and *Mekrān* and the countries bordering on the Indus valley by Abdu'llah Amar, a cousin of the Caliph, who succeeded Abu Musa Ashari in the government of Basra. His report was as follows: "Water in that country is of a dark colour, flowing only drop by drop, the fruits are sour and unwholesome, rocks abound and the soil is brackish. The thieves are intrepid warriors, and the bulk of the population dishonest and treacherous. If the troops sent there are few in number, they will be exterminated, if they are numerous, they will perish of hunger." Elliot. The expeditions of Ali and Muāwiyah and the progress of the Arab conquests in Sind may be read in the succeeding pages. Elliot's conclusion that *Debal* was taken in A.H. 93 is confirmed by As Suyuti in his biography of Al Walid, b. Abdu'l Malik, in which year *Kirah*, or *Kiraj* as Ibn ul Athir calls it, was also captured. (See translation of As Suyuti's *History of the Caliphs*, p. 229). Elliot thinks this probably situated in, if not named from *Kachh*.

² Described in Elphinstone, p. 308, and in Briggs' *Ferishta*, IV, p. 417.

carried to the court, the Caliph exhibited the spectacle to the two princesses who expressed their gratification in viewing the slayer of their father in this condition. This decision of the Caliph excites astonishment inasmuch as it was pronounced without deliberate investigation. It is the duty of just princes not to be swayed by the representation of any one individual, but to be circumspect in their inquiries, since truth is rare and falsehood prevalent, and more especially in regard to the recipients of their favour, towards whom the world burns with envy without just cause of resentment. Against the outwardly plausible and inwardly vicious they should be particularly on their guard, for many are the wicked and factious who speciously impose by their affected merit and by their misrepresentations bring ruin on the innocent.

After Muhammad Qāsim's death, the sovereignty of this country devolved on the descendants of the Banu Tamim Ansāri.* They were succeeded by the *Sumrah* race who established their rule and were followed by the *Sammas* who asserted their descent from *Jamshid*, and each of them assumed the name of *Jām*. In the reign of *Jām Bānhariyah*¹ Sultān Fīroz Shāh on three occasions led an army from Delhi against that prince, and obtained some conspicuous successes. On the third occasion, he took him prisoner and carried him to Delhi, leaving Sind under charge of his own officials. Subsequently being satisfied with his good will and capacity he reinstated him in his government. On the death of *Jām Tughlaq*, the chamberlain *Mubārak* succeeded him through the efforts of a vain and seditious faction, and was followed by Sikandar the son of *Jām Fath Khān*.

During the reign of *Jām Nandā*, *Shāh Beg Arghān* made a descent from Qandahār and took *Sewi* and leaving the command of it to his brother Sultān Muhammad, returned to Qandahār. The *Jām* marched a force against

* Several of this tribe were at various periods sent to Sind. Under the Caliphate of Yazid b. Abd u'l Malik, Halāl a't Tamimi was sent in pursuit of the Banu Muhallab. About 107 A.H. Tamim b. Zaid al Utbi succeeded Junaid in the government of that province and died near Debal. Under the Abbassides Musa b. Kab a't Tamimi, drove out Mansur b. Jamhur the Umayyad governor. Abdu'r Razzāk the first Ghaznevide governor of Sind, about A.H. 417, (1026) found the descendants of old Arab settlers of the tribes of Thakifi, Tamimi, Asad etc.

¹ Māni according to Ferishta who says that the expedition of Fīroz Tughlaq took place in 763 A.H. (A.D. 1320).

Muhammad who was killed in action. Shah Beg made a second incursion and took possession of *Sehwān* and a considerable part of Sind and leaving his conquests in charge of his own people, withdrew.

In the reign of Jām Firoz, a relative of his named Salāhu'ddin rose in rebellion and failing in his attempt, took refuge with Sultān Mahmud of Gujarāt who received him graciously and assisted him with an army; Daryā Khān the prime minister of Jām Firoz espoused his cause and the kingdom of Sind fell under his power without a blow. Subsequently the said Daryā Khān determined to restore Jām Firoz who had withdrawn into private life, but who thus recovered his kingdom. Salāhu'ddin a second time advanced from Gujarāt with a force furnished by the Sultān and occupied Sind. Firoz retired to Qandahār and Shāh Beg supplied him with troops, and an engagement took place near *Sehwān* in which Salāhu'ddin and his son were slain. Thus Firoz was again established in his kingdom. In the year A.H. 929 (A.D. 1522-3) Shāh Beg took possession of Sind and Jām Firoz retired to Gujarāt, gave his daughter in marriage to Sultān Bahādur and was attached to the Court in the ranks of its nobles. Sind was now subject to Shāh Beg. This prince was the son of Mir Zu'n Nun Beg, the commander-in-chief of Sultān Husain Mirzā, who received the government of Qandahār. He fell fighting bravely against Shaibak Khān Uzbek who was engaged in hostilities with the sons of Sultān Husain Mirzā. His eldest son succeeded to the government of Qandahār, a prince of distinguished valour and versed in the learning of his age. At his death, his son Shāh Husain ascended the throne and wrested Multān from Sultān Mahmud. After him Mirzā Isā son of Abdu'l Ali Tarkhān¹ succeeded, followed by Muhammad Payandah² but his prince being subject to fits of mental estrangement, did not

¹ *Tarkhān* was originally a rank among the Mughals and Turks, but in the time of Baber it had come to belong to a particular family. The ancient Tarkhān was exempt from all duties and could enter the royal presence without asking leave and was to be pardoned nine times be the fault what it would. He had perfect liberty of speech and might say what he pleased before royalty. The name constantly occurs in the early portion of Baber's *Memoirs*.

² He has omitted the succession of Muhammad Bāqi son of Isā Tarkhān to whom Ferishta gives a prosperous reign of 18 years. The genealogical tree of Mirzā Jāni Beg and the subsequent history of this family will be found at pp. 361-2, Vol. I of this work. Ferishta altogether omits Muhammad Payandah and gives the succession to Jāni Beg immediately after Muhammad Bāqi.

Gazetteer, Rose's *Glossary of Punjab Tribes and Castes* (3 vols., 1914), and the *Travels of Vigne and Moorcroft*.

Abul Fazl devoted more space to the description of the places of note in Kashmir than in any other subah, because he looked upon it as a holy land full of sacred places, hermits' retreats and quiet natural scenes,—“appropriate to be the retired abode of the recluse”, as he himself says. This Sufi's paradise is said to contain a temple of liberal broad-minded worshippers of God, for which he wrote a charming inscription printed by Blochmann at the end of his life of Abul Fazl in the first volume of his translation (pp. xxxii-xxxiii).

But when Abul Fazl compiled his *Ain-i-Akbari*, Mughal rule was not yet firmly in the saddle in this recently conquered province, and full and correct reports on Kashmir had not begun to reach the imperial chancellory at Delhi. Hence its statistics are less accurate than those of the longer-settled subahs of Akbar's empire, which formed the basis of his *Imperial Gazetteer*. The Persian text of the chapter on Kashmir is vitiated by too many errors in proper names and topographical data, which may have been due to Abul

Fazl's clerks as well as to later transcribers of his book. The hopeless confusion thus created was first removed by the publication of Stein's two works cited above.

In the present edition, copious extracts have been made from these scholarly sources by Prof. N. B. Roy and the obsolete or useless notes of Jarrett have been deleted. *The new topographical notes are given in one place at the end of Abul Fazl's account and not at the foot of each page.*—*Jadunath Sarkar.*

Stein's remark on A. F.'s account of Kashmir.

“Abul Fazl's detailed description of Kashmir, is in many respects valuable to the historical student, but it is particularly in connection with topographical search that we must feel grateful to the author for having, like his great master, caught some of the enthusiasm of the valley.

The account of Abul Fāzl presents for us an authentic survey of all the Kashmirian *tirthas* that were well known and popular at the end of the 16th century. . . Abul Fazl's notes have enabled me to trace in more than one instance the position of ancient *tirthas* or particular features regarding them which have since his time been wholly forgotten.”
Stein, *Chron.* II, 382-83.

A NOTE ON THE LANGUAGE OF KASHMIR.

Kashmiri or Koshiru.

The Kashmiri language is the language of the Valley of Kashmir. In a dialectic form it has spread south-west into the Valley of Kashtawar (Kishtwar), and to the south it has flowed over the Pir Pantsal Range into the lower hills lying north of the River Chinab, where it reappears in a number of mixed dialects.

The word ‘Kashmiri’ is Persian or Hindi, and is derived from the Sanskrit Kasmirika. It is not the name used by the people of Kashmir itself. There the country is called Kashiru, and the language Koshiru.

Kashmiri has one true dialect,—Kashtawari, spoken in the Valley Kashtawar (commonly known as Kishtwar), lying to the south-east of the Valley of Kashmir. Kashmiri has also overflowed the Pir Pantsal Range into the Jammu Province of the State, and in the valleys between the southern

In the standard Kashmiri of the Valley, there are minor differences of language, which, however, are not sufficient to entitle us to divide it out into further separate dialects. For instance, the Kashmiri spoken by Musalmans, differs from that spoken by Hindus. Not only is the vocabulary of the former more filled with words borrowed from Persian, but also there are slight differences of pronunciation.

nearest and it has several routes of which three are good, viz., (1) *Hasti Bhanj*¹ which was the former route for the march of troops; (2) *Pir Panjāl*, which His Majesty has thrice traversed on his way to the rose garden of Kashmir. If on these hills an ox or a horse be killed, storm clouds and wind arise with a fall of snow and rain²; (3) *Tangtala*.

The country is enchanting, and might be fittingly called a garden of perpetual spring surrounding a citadel terraced to the skies, and deservedly appropriate to be either the delight of the worldling or the retired abode of the recluse. Its streams are sweet to the taste, its waterfalls music to the ear, and its climate is invigorating. The rain and snow-fall are similar to that of Turkestan and Persia and its periodical rains occur at the same season as in Hindustan. The lands are artificially watered³ or dependent on rain for irrigation. The flowers are enchanting and fill the heart with delight. Violets, the red rose and wild narcissus cover the plains. To enumerate its flora would be impossible. Its spring and autumn are extremely beautiful. The houses are all of wood and are of four stories and some of more, but it is not the custom to enclose them. Tulips⁴ are grown on the roofs which present a lovely sight in the spring time. Cattle and sundry stores are kept in the lower storey, the second contains the family apartments, and in the third and fourth are the household chattels. On account of the

¹ The three different routes into Kashmir are thus described. The first runs almost in a straight line passing through Nowshera, Rajori, the Pir Panjāl pass and Shupiyon. The second deviating from Rajori runs to the Punch river and on to Punch and crossing the Hāji Pir, joins the Murree road near Uri. The third, parting from Samani Sarai, passes through Kotli and Sera to Punch and unites with the second. The route by Shupiyon is the Pir Panjāl. The second is Tangtala which name, however, is no longer known and is probably a miscript. The third is believed to be the Hasti Bhanj, for it is the only one by which elephants can travel. Cf. Vigne's *Kashmir and Ladāk*, I. 147 in which 20 passes into Kashmir are mentioned and described.

² The superstition regarding the tempest of wind and snow and rain, appears to be connected with that of the *Yedch* or rain-stone frequently alluded to by Baber, the history of which is given by D'Herbelot. It is of Tartar origin and the virtues of the stone are celebrated in Yarkand and attested by authorities who have never witnessed them. It is said to be found in the head of a horse or a cow, and if steeped in the blood of an animal with certain ceremonies, a wind arises followed by snow and rain.

³ The terms are *Abi*, *Lalmi*. The first signifies in the N.-W. P., land watered from ponds, tanks, lakes and watercourses, in distinction to that watered from wells, and as being liable to fail in the hot season, is assessed at a lower rate. The second is a Pushtu word (*Raverty*) and means growing spontaneously and applied to crops wholly dependent on rain for irrigation or spring crops. The next term *Chalkhai* in the text has a variant *Jalkhaya* signifying parched land that has absorbed its moisture.

⁴ Dr. King takes this to be probably the *Fritillaria Imperialis*, though there is nothing against the plant being a real tulip. The *T. stellata* is common in many parts of the N. W. Himalayas.

abundance of wood and the constant earthquakes, houses of stone and brick are not built, but the ancient temples inspire astonishment. At the present day many of them are in ruins. Woollen fabrics are made in high perfection, especially shawls which are sent as valuable gifts to every clime. But the bane of this country is its people, yet strange to say, notwithstanding its numerous population and the scantiness of the means of subsistence, thieving and begging are rare. Besides plums and mulberries, the fruits are numerous. Melons, apples, peaches, apricots are excellent. Although grapes are in plenty, the finer qualities are rare and the vines bear on mulberry trees. The mulberry is little eaten, its leaves being reserved for the silk-worm. The eggs are brought from *Gilgit* and *Little Tibet*, in the former of which they are procured in greater abundance and are more choice. The food of the people is chiefly rice, wine, fish and various vegetables, and the last mentioned they dry and preserve. Rice is cooked and kept overnight to be eaten. Though *shālī* rice is plentiful, the finest quality is not obtainable. Wheat is small in grain and black in colour, and there is little of it, and little consumed. Gram (chick-pea) and barley are nowhere found. They have a species of sheep which they call *Hāndu*, delicate and sweet in flavour and wholesome. Apparel is generally of wool, a coat of which will last for some years. The horses are small, strong, and traverse difficult ground. There are neither elephants nor camels. The cows are black and ill-shaped, but give excellent milk and butter. There are artificers of various kinds who might be deservedly employed in the greatest cities. The *barār* system is little in use, as a brisk traffic is carried on at their own places of business. Snakes, scorpions and other venomous reptiles are not found in the

According to Cunningham (*Ladak*, p. 210) the Ladakī sheep are of two kinds, the tall black-colored *Huntha* used chiefly for carrying burdens and the pretty diminutive sheep of *Parth* used only for food. The common sheep is the *Huntha* which with the exception of the *Parth* breed is almost the only kind of sheep to be found throughout Tibet. It is much larger than any of the Indian breeds, the height averaging from 27 to 30 inches. Nearly the whole of the traffic is transported on these sheep which are food, clothing and carriage and are the principal wealth of the country. Drew (*Quinn's and Kishin's*, p. 248) gives the average weight carried by them at from 24 to 32 lbs. The *Parth* sheep when full grown is not larger than a southdown lamb of 5 or 6 months, and is said by Moucrot to equal in the fineness and weight of its fleece and flavour of its mutton any race hitherto discovered. The oxen are the yāk or chauri-tailed bull and the yāk cow, Brimo or Dima, and they reproduce with the common cattle. The yāk is kept chiefly for loads, being generally too intractable for the plough. The cow is kept only for milk. The most valuable hybrids are the *Dia* bull and *Droma* cow, the produce of the male yāk and common cow.

cities. There is a mountain called *Mahādeva* and in any spot whence its summit can be seen, no snake exists, but fleas, lice, gnats and flies are very common. From the general use of pellet-bows which are fitted with bow-strings, sparrows are very scarce. The people take their pleasure in skiffs upon the lakes, and their hawks strike the wild-fowl in mid-air and bring them to the boats, and sometimes they hold them down in the water in their talons, and stand on them, presenting an exciting spectacle.

Stags and partridges likewise afford sport and the leopard too is tracked. The carriage of goods is effected by boat, but men also carry great loads over the most difficult country. Boatmen and carpenters drive a thriving trade. The Brāhman class is very numerous.

Although *Kashmir* has a dialect¹ of its own, their learned books are in the Sanskrit language. They have a separate character which they use for manuscript work, and they write chiefly on *Tuz*² which is the bark of a tree, worked into sheets with some rude art and which keeps for years. All their ancient documents are written on this. Their ink is so prepared as to be indelible by washing. Although, in ancient times, the learning of the Hindus was in vogue, at the present day, various sciences are studied and their knowledge is of a more general character. Their astrological art and astronomy are after the manner of the Hindus. The majority of the narrow-minded conservatives of blind tradition are *Sunnis*, and there are some *Imāmis* and *Nur Bakhshis*,³ all perpetually at strife with each

¹ The languages of Kashmir are divided into 13 separate dialects. Of these Dogri and Chibali which do not differ much from Hindustāni and Panjābi, are spoken on the hills and the Punch and Jammu country. Kashmiri is mostly used in Kashmir proper and is curiously and closely related to Sanskrit. Five dialects are included in the term *Pahāri*: two are Tibetan spoken in *Baltistān*, *Ladakh* and *Chāmpas*, and three and four varieties of the Dard dialects of Aryan origin in the North-West. The thirteen dialects are enumerated and discussed by Drew (*Jummoo and Kashmir*).

² *Tuz* in the *Burhān i Qāfi* is said to be the bark of a tree used to wrap round saddles and bows. Dr. King identifies it with the well-known birch, Betula Bhojpattra, Wall. *Bhojpattra* he states is the current vernacular name.

³ As the account of this sect in Ferishta has been almost entirely passed over by Briggs in his translation, the omission may be here made good and will serve the double purpose of supplementing his version and elucidating the present text. With the following note may be compared a monograph on the Roshaniyah sect by Dr. Leyden in the XIth Vol. Asiatic Researches.

Mirzā Haidar (Doghlāt) in his work the *Kitāb i Rashidi* says that formerly all the inhabitants of Kashmir were of the Hanifi sect. In the time of Fath Shāh, a man named Shamsu'ddin came from Irāq and declared himself to be a follower of Mir Muhammad Nur Bakhsh. He introduced a new form of religion which he called *Nurbakhshi*, which accords neither with the Sunni or Shia belief. And the followers of this sect, like heretics, consider it their duty to revile and abuse the three Caliphs and Ayesha, but unlike the Shias,

The *Tolah* in this country is 16 *māshās*, each *māshā* being equal to 6 *surkhās*.¹ The gold mohur weighs 16 *dānis*, each *dāni* equalling 6 *surkhās*, being 4 *surkhās* more than the ordinary mohurs of Delhi. *Rop Sāsmu* is a silver coin of 9 *māshās*. The *panchhu* is of copper, equal to the fourth of a *dām* and is called *kaserah*. One-fourth of this is the

With reference to the monetary system of Kashmir, Stein indicates the connection between the terms used by Abul Fazl for the various denominations of coins and their modern equivalents in Kashmir. Thus *Panchuhu* is the same as *Punisa*, (Skr. *Panchabimsati*), *hāth* unchanged (Skr. *sata*), *Sansu* same as *Sasun* (Skr. thousand). According to Abul Fazl *Bahagani*, (*bārakanī*) is equal to $\frac{1}{4}$ *Panchuhu*. Stein corrects it and says that the above denomination represented one-half of the *Panchuhu*. The term *bah* in Kashmir means twelve and *bahabani* as a twelver. All the terms used above with only one exception are stated to have survived in Kashmir to this day in the popular system of reckoning, notwithstanding the repeated changes which the currency of the State has undergone since Akbar's time. Stein, *Chronicle*, Vol. II, 312. [J. S.]

bahgani, [*barakani*], of which again one-fourth is called *shakri*.

4 *kaserahs* = 1 *rāhat*.

40 *kaserahs* = 1 *sāsmu*.

1½ *sāsmu* = 1 *sikkah*.

100 *sikkahs* = 1 *lakh* which, according to the imperial estimate, is equal to one thousand *dāms*.

The whole country is regarded as holy ground by the Hindu sages. Forty-five shrines are dedicated to *Mahadeva*, sixty-four to *Vishnu*, three to *Brahmā*, and twenty-two to *Durga*. In seven hundred places there are graven images of snakes which they worship and regarding which wonderful legends are told.¹

Srinagar is the capital and is 4 *farsakhs* in length. The rivers *Bihat*, *Mār*, and *Lachmahkul*² flow through it. The last-mentioned runs occasionally dry: the second, at times, becomes so shallow that boats cannot pass. This has been a flourishing city from ancient times³ and the home of artificers of various kinds. Beautiful shawls are woven, and they manufacture woollen stuffs (*Saqarlāt*) extremely soft. *Durmah*, *pattu* and other woollen materials are prepared but the best are brought from Tibet. *Mir Sayyid Ali Hamadāni*⁴ resided for some time in this city, and a monastery founded by him still preserves his memory. To the east is a high hill known as the *Koh i Sulaimān*, and adjoining the city are two large lakes always full of water, and it is remarkable that their water will not deteriorate in good savour and wholesomeness for any length of time provided that their free exit is undisturbed.

¹ Serpent-worship, according to Genl. Cunningham, has been the prevailing religion in Kashmir from time immemorial. A full account of Hindu serpent-worship in Hastings' *Encyclo.*, xi. 411-419 (Kashmir on p. 412). J. S.

² The Jhelum, which nearly intersects the valley is formed, says the *I. G.*, by the junction of three streams, the *Arpat*, *Bring* and *Sandaram*, and receives in its course numerous tributaries. It mentions the *Tsont i Kul*, or apple-tree canal connecting the *Dal* or city lake, with the Jhelum which it enters opposite the palace and the *Nalli Mār* which flows into the Sind near *Shādipur* connecting the *Auchar* with the *Dal*. The *Dudganga*, a stream of good volume joins the river on the left bank at the city of *Srinagar*.

³ *Srinagari*, the old capital, prior to the erection of *Pravarasenapura* is stated in the *Raja Tarangini* to have been founded by *Asoka*, who reigned between B.C. 273-232. It stood on the site of the present *Pāndrethān*, and is said to have extended along the bank of the river from the foot of the *Takht i Sulaimān* to *Pāntasok*, a distance of more than three miles.

⁴ This monastery is built entirely of wood. It is still extant and known as the *Khānqāh i Mu'alla*, on the right bank of the *Bihat* above *Zenu Kadal*, the fourth bridge of the town of *Srinagar*.

Near the town of *Brang* [Bring] is a long defile in which is a pool seven yards square and as deep as a man's stature. It is regarded as a place of great sanctity. Strange to say it is dry during eleven months, but in the Divine month of *Urdi-bihisht* (April), water bubbles forth from two springs. First in one corner of it is a cavity like a mortar called *Sendh brāri*: when this becomes full, the spring rises in another corner called *Sapt rishi*. From these two sources the pool runs over. Sometimes it boils up for three hours, and at times for only a second. Then it begins to decrease till not a drop remains. At three periods of the day, *viz.*, morning, noon and evening, this rise occurs. Various flowers are thrown in as offerings to either spring, and after the reflux of the water, the flowers of each votary are found in their respective springs.¹

But this, like the divining cup is a contrivance of the ancients to secure the devotion of the simple.

In this vicinity also is a spring, which during six months is dry. On a stated day, the peasants flock to worship and make propitiatory offerings of a sheep or a goat. Water then flows forth and irrigates the cultivation of five villages. If the flush is in excess, they resort to the same supplications, and the stream subsides of its own accord. There is also another spring called *Kokar Nāg*, the water of which is limpid, cold and wholesome. Should a hungry person drink of it, his hunger will be appeased,² and its satisfaction in turn renews appetite. At a little distance, in the midst of a beautiful temple, seven fountains excite the wonderment of the beholder. In the summer time self-immolating ascetics here heap up a large fire around themselves, and with the utmost fortitude suffer themselves to be burnt to ashes. This they consider a means of union with the Deity. There is also a spring which produces touchstone, and to the north of it a lofty hill which contains an iron mine.

The village of *Vij Brāra*, one of the dependencies of *Aneych* is a place of great sanctity. It was formerly a large

¹ Tieffenthaler ascribes the cause of the phenomenon to the melting of the mountain snows under the influence of the sun which descending along hollows or by subterranean passages reach this cavern and boil up within it. The later ebullitions he conceives, are due either to the shade of the trees or the declining force of the sun on the snows. Bernier's opinion is somewhat the same. *Voyages*, II, 293.

² Vigne (I, 339) on the contrary bears testimony to its being provocative of appetite. The spring, situated about 2½ miles from the iron works at Sof Alan, forms a stream equal in volume to that of Vernag and far superior in the quality of its water.

city¹ and contained wonderful temples. In the vicinity is an upland meadow called *Nandimarg*, of which I know not whether most to praise its level sweep of mead, the loveliness of its verdure and flowers, or the bountiful virtues of its streams and its air. In the village of *Pampur*, one of the dependencies of Vihi, there are fields of saffron² to the extent of ten or twelve thousand *bighas*, a sight that would enchant the most fastidious. At the close of the month of March and during all April, which is the season of cultivation, the land is ploughed up and rendered soft, and each portion is prepared with the spade for planting, and the saffron bulbs are placed in the ground. In a month's time they sprout and at the close of September, it is at its full growth, shooting up somewhat over a span. The stalk is white, and when it has sprouted to the height of a finger, it begins to flower one bud after another in succession till there are eight flowers in bloom. It has six lilac-tinted petals. Usually among six ³filaments, three are yellow and three ruddy. The last three yield the saffron. When the flowers are over, leaves appear upon the stalk. Once planted it will flower for six years in succession. The first year, the yield is small: in the second as 30 to 10. In the third year it

¹ The principal ancient cities of Kashmir are the old capital of Srinagari and the new, Pravarasenapura which was lost in the former name: Khagendrapura and Khanamusha, identified with Kākapur on the left bank of the Bīhat, ten miles to the south of the Takht-i Sulaimān, and Khunamoh, four miles north-east of Pampur: Vijipara and Pantasok. The former twenty-five miles south-east of the capital: the latter three miles from the Takht-i Sulaimān; Surapura the modern Sopur, mentioned in the Kashmir chronicles as Kamluca: Kanishkapura, corrupted to Kāmpur: Hushikapura probably Baramula: Jushikapura now Zukru or Zukur four miles north of the capital: Parihasapura built by Lalitaditya (A.D. 723—760): Padmapura, now Pampur: and Avantipura, now only a small village, Wantipur, seventeen miles south-east of the present capital. Cunningham, pp. 95, 103.

² See Vol. I, p. 84 where the method of cultivation of this plant is explained somewhat differently.

³ I am indebted to Dr. King for the following note:

"There are three stamens and three stigmas in each flower. The latter yield the saffron. The style divides at the level of the anthers into three yellow drooping branches which hang out of the flower and become gradually thickened and tubular upward, stigmas dilated, notched and often split down one side, dark orange coloured. The mode of collection and preparation of saffron varies in different countries, but it consists essentially in removing the stigmas with the upper part of the style from the other parts of the flower and afterwards drying the parts detached. A not uncommon adulteration of saffron is made by intermixing the dyed stamens of the saffron crocus. It takes from 7,000 to 8,000 flowers to yield 17½ ounces of fresh saffron which by drying is reduced to 3¼." *Medicinal Plants* by Bentley and Trimen, IV, 274. In the *Waqiāt-i Jehāngiri*, it is asserted that in an ordinary year, 400 maunds or 3,200 Khurasāni maunds are produced. Half belongs to Government, half to the cultivators and a ser sells for about 10 Rs. A note states that one good grain of saffron contains the stigmata and styles of 9 flowers; hence 4,329 flowers yield one oz.

reaches its highest point and the bulbs are dug up. If left in the same soil, they gradually deteriorate, but if taken up they may be profitably transplanted.

In the village of *Zewan* are a spring and a reservoir which are considered sacred, and it is thought that the saffron seed came from this spring. When the cultivation begins, they worship at this fount and pour cow's milk into it. If as it falls it sinks into the water, it is accounted a good omen and the saffron crop will be plentiful, but if it floats on the surface, it will be otherwise.

In the village of *Khrin* 360 springs refresh the eye and each of these is accounted a means of divine worship. Near this is an iron mine.

*Maru Adwin*¹ adjoins *Great Tibet* where the *Handu* is found of the best breed and large in size, and carries heavy burdens. Near this is a hill called *Chatar Kot* on the summit of which snakes are so numerous that no one can approach it. There is also a high hill difficult of ascent, on which is a large lake. It is not every one that can find his way to it, for it often disappears from sight. At the foot of the mountain in different places images of *Mahādeva* fashioned of a stone like crystal are found and are a source of wonder.

In the neighbourhood of *Achh Bal*, one of the dependencies of *Khattār* is a fountain which shoots up to the height of a cubit, and is scarce equalled for its coldness, limpidity and refreshing qualities. The sick that drink of it and persevere in a course of its waters, recover their health.

In the village of *Kotihār* is a deep spring, surrounded by stone temples. When its water decreases, an image of *Mahādeva* in sandal-wood appears. The quality of this spring does not alter.

In the vicinity of *Wular* is a lofty mountain, containing a salt spring. The Kashmir stag² is here found in numbers.

Matan [Martand] stands upon a hill and once possessed a large temple. There is a small pool on the summit, the water of which never decreases.* Some suppose this to be

¹ Mare Wurdwun according to Vigne.

² The Bārā Singha or Kashmir stag, (*Cervus Cashmerianus*).

* Martand, situated on the highest part of the *Karewah* or raised plain between *Islāmābād* and the higher mountains. The temple is described by Hügel as "Korau Pandan," the beautiful ruins of which are the finest in Kashmir. Vigne inverts the order as Pandu Koru. At 150 yards distance as the *Chāh i Bābil* or well of *Hārut* and *Mārut* whose story does not need repetition. The spring referred to in the following paragraph is that of

the *Well of Babylon*, but at the present day there is no trace of anything but an ordinary pit.

On the slope of the hill is a spring, at the head of which a reservoir has been constructed, full of fish. The sanctity of the place preserves them from being touched. By the side of it is a cave, the depth of which cannot be ascertained.

In *Khāwarpārah* is a source, whose waters tumble headlong with a mighty roar.

In the village of *Aish*¹ is the cell of *Bābā Zainu'ddin Rishi*. It is in the side of a hill. It is said that in ancient times the hill held no water, but when he took up his abode there, a spring began to flow. For twelve years he occupied this cell and at length closed its mouth with a large stone and never went forth again, and none has ever found trace of him.

The town of *Dachchhinpārah* is on the side of a mountain bordering *Great Tibet* and is fed by the waters of the above-mentioned spring. Between *Great Tibet* and the above-mentioned *parganah* is a cave in which is an image in ice called *Amar Nāt*.² It is considered a shrine of great sanctity. When the new moon rises from her throne of rays, a bubble as it were of ice is formed in the cave which daily increases little by little for fifteen days till it is somewhat higher than two yards, of the measure of the yard determined by His Majesty; with the waning moon, the image likewise begins to decrease, till no trace of it remains when the moon disappears. They believe it to be the image of *Mahādeva* and regard it as a means (through supplication) of the fulfilment of their desires. Near the cave is a rill called *Amrāoti*, the clay of which is extremely white. They account it auspicious and smear themselves with it. The snows of this mountainous tract nowhere melt, and from the

Bawan, one of the holiest in Kashmir, swarming, says Vigne, (I, 359) with Himalayan trout. Hügel gives the legend of the caves one of which he was assured extended 10 kos, and that no one who ever entered, had been known to return. He penetrated to the end of it in a few minutes. Matan is the name of the *Karawah* at the end of which, according to Moorcroft, the Martand temple stands (II, 255) ascribed like most of the architectural remains to the Pāndus.

¹ The village of *Aish Maqām* or the abode of pleasure, holds in a long building situated conspicuously on the left bank of the *Lidar*, the shrine of the saint. He directed that a tomb should be erected where his staff should be found, as his body would disappear. It is still missing. See Vigne, II, 6.

² The *Amarnāth* cave is marked in Drew's map, south-east of *Baltal* and *Sonamarg*, near the sources of the *Sind* river. Its history and ceremonies are told by Vigne, II, 8. The ice bubble was doubtless a stalactite. See Moorcroft, II, 252.

extreme cold, the straitness of the defiles and the rough inequalities of the road, they are surmounted with great toil.

In the village of *Dākhāmun* is a spring, and whenever its water boils up and becomes turbid its surface is covered with particles of straw and rubbish, the dust of dissension arises in the country. A quarry of Solomon's stone¹ is in the vicinity of which utensils are fashioned.

About the *parganah* of *Phāk* grow a variety of herbs and plants. Adjoining is a large lake called *Dal*. One side of it is contiguous to the city and on its surface a number of floating islands² are constructed which are cultivated, and fraudulent people will at times cut off a piece and carry it away to a different position. *Sultān Zainul Abidin* constructed in this lake a causeway (*sad*) of clay and stone one *kos* in length from the city to this *parganah*. In the vicinity also is a spring of which the sick drink and are restored to health.

In the village of *Thid*, is a delightful spot where seven springs unite: around them are stone buildings, memorials of bygone times. There is also a source which in winter is warm and in summer cold.

In the village of *Bāzwāl* is a waterfall from the crest of *Shāhkot*. It is called *Shālahmār*. Here fish are caught in numbers. A streamlet is caged at two ends and when the water is carried off, the fish between are taken.

In *Ishibāri* is a spring held sacred by the people of Hindustān, called *Suryasar*, surrounded by stone temples. *Shakarnāg* is a spring which is dry all the year, but should the 9th day of any month happen to fall on a Friday, it bubbles up and flows from morn till eve, and people flock to partake of its blessings.

In the village of *Rambal* are a spring and a pool. Those who have special needs throw in a nut, if it floats, it is an augury of success; if it sinks, it is considered adverse.

In *Bānihal* is a temple dedicated to *Durgā*. If any one desires to learn the issue of a strife between himself

¹ Applied indiscriminately to both agate and onyx. Tieffenthaler describes a stone of their country, as green with white streaks which is worked with diamond powder and made into phials, saucers, hafts of daggers and the like. It is probably a kind of jade.

² Cucumbers and melons are commonly grown on them. Their construction is described by Moorcroft (II, 138) with the thoroughness which characterizes his observations. The causeway is called by Vigne, (II, 99) *Sad i Chodri* and is carried entirely through the lake to the village of *Isha Bryri*, four miles on the opposite side.

and his enemy, he fills two vessels with boiled rice, the one representing his own fortunes, the other those of his foe, and places them in the temple and closes the doors. On the following day the devotees present themselves to learn the result. In whose vessel roses and saffron are found, his undertaking will prosper, and that which is full of straws and dirt, portends the ruin of the person it represents. Stranger still, in a dispute where it is difficult to discover the truth, each party is given a fowl or a goat and sent to the temple. They then poison each of these animals and severally rub them with their hands. His animal whose cause is just recovers, and the other dies.

In the *Ter* tract of country is the source of the *Bihat*. It is a pool measuring a *jarib* which tosses in foam with an astonishing roar, and its depth is unfathomable. It goes by the name of *Ter-nāg*¹ and is surrounded by a stone embankment and to its east are temples of stone. In the village of *Kambar* is a spring called *Bawan Sindh* which during two months of the spring time is in agitation. It is always full and its water never decreases.

on the following Thursday and during the succeeding seven days is again dry and once more fills on the Thursday next following, and so continues for a year.

In the village of *Matalhāmah* is a wood in which is a heronry,¹ the feathers are taken for plumes, and the birds are here regularly fed.

Near *Shukroh* is a low hill on the summit of which is a fountain which flows throughout the year and is a place of pilgrimage for the devout. The snow does not fall on this spur.

In *Nāgām* is a spring called *Nilah Nāg*, the basin of which measures 40 *bigahs*. Its waters are exquisitely clear and it is considered a sacred spot, and many voluntarily perish by fire about its border. Strange to relate omens are taken by its means. A nut is divided into four parts and thrown in, and if an odd number floats, the augury is favourable, if otherwise, the reverse. In the same way if milk (thrown in) sinks, it is a good omen, and if not, it is unpropitious. In ancient times a volume, which they call *Nilmat*, arose from its depths, which contained a detailed description of *Kashmir* and the history and particulars of its temples. They say that a flourishing city with lofty buildings is underneath its waters, and that in the time of *Badu Shāh*,² a Brāhman descended into it and returned after three days, bringing back some of its rarities and narrated his experiences.

In the village of *Biruwā* is a spring and in its water lepers bathe early on the first day of the week and are restored to health. In the vicinity is a plateau, a pasture ground for cattle, the grass of which has peculiar fattening properties.

In the village of *Halthal* of the *parganah* of *Yech* is found a quivering tree.³ If the smallest branch of it be shaken, the whole tree becomes tremulous.

Lār borders on the mountains of *Great Tibet*. To its north is a lofty mountain which dominates all the surrounding country, and the ascent of which is arduous. At its foot are two springs, two yards distant from each other, the waters of one being extremely cold and those of the other

¹ The word is pronounced *Oukar* or *Okar* and signifies a heron. See Vigne, I, 306. The heronries are strictly guarded.

² *Badu Shāh* is Zainul Abidin (Vigne, II, 73).

³ Dr. King informs me that the Aspen (*Populus tremula*) occurs wild in the N. W. Himalaya. The *P. Euphratica* of which the leaves are as tremulous as the aspen, is also common in many parts.

exceedingly hot. They are considered sacred and the bones of bodies are here reduced to ashes: the bones and ashes of the dead are cast into a large lake on the mountain and this ceremony is regarded as a means of union with the Divinity. If the flesh of an animal fall into it, a heavy fall of snow and rain ensues. The river called *Sind* which rises in *Tibet*, is wholesome to drink, and is so clear that the fish in it are visible. They strike them with iron spears and catch them also in other ways. *Shahāb-u'ddinpur* is on the banks of the *Bihat*, and about it are large plane trees which is a favourite resort. The *Sind* joins the *Bihat* at this point.

In *Tulmulā* is an area of about 100 *bighas* in extent which is flooded during the rains, and remains somewhat moist even after the waters have dried up. The people plunge in sticks of a yard in length, more or less, and work them about, and thrusting their hands into the holes pull out fish of four pounds weight and more, but commonly of small size.

In *Satpur* is a pool, the depth of which cannot be fathomed. It is held in great veneration and is a place of worship. *Bhutesar* is a temple dedicated to *Mahādeva*. Whoever approaches to pay his devotions, hears the sounds of ceremonial worship and no one can tell whence they proceed.

In *Khoihāma* which adjoins *Little Tibet* is a large lake called the *Wular* twenty-eight *kos* in circumference. The *Bihat* flows into it and its course is somewhat lost to the eye. Here *Sultān Zainul Abidin* built a large palace called *Zain Lanka*.¹ Boats full of stones and branches of trees are sunk in the lake and pulled up by ropes after the lapse of three or four months, and many fish are taken that have homed there. The capture of water-fowl here affords considerable sport, and in the village of *Ajas*, stags are chased down to the lake and taken. Near *Māchhāmu* is an island covered with trees which when shaken by the wind, cause the island also to quake.

Saffron is also cultivated in *Paraspur*. It formerly held a lofty temple which when destroyed by *Sikandar* father of *Sultān Zainul Abidin*, a copper tablet was discovered on which was inscribed in *Sanskrit*, that after the

¹ See Vigne, II, 153. The legend of the Lanka islet is given in Muhammad Aūzam's *Hist. of Kashmir* translated by me in the *A. S. Journal*, XLIX, Part I, 1880.

lapse of eleven hundred years, one Sikandar would destroy it and gather for himself exceeding great chastisement.¹

In the *Pargana* of *Kamrāj*² at the village of *Trahgām* the residence of the *Chaks* is a fountain of sweet water called *Chatarnāg* and in the middle is a stone building of great age. The fish grow to great size but whosoever touches them, is afflicted by some calamity.

Near *Kargon* is a defile called *Soyam*³ where an area of ten *jaribs* of land becomes so hot at the time of the conjunction of Jupiter and Leo that trees are burnt up and a vessel of water if left on the ground will boil. A flourishing little town stands here. From *Kamrāj* is a defile, one end of which touches *Kāshghar* and on the west lies *Pakli*, where gold is obtained in the following manner. The skins of long-haired goats are spread in the fords of this river, with stones placed round them that the current may not bear them away. They are taken up after three days and left in the sun. When dry, they are shaken, yielding their three *tolahs* weight of gold dust. *Gilgit* is the name of another pass which leads to *Kāshghar*. Gold is there obtained by soil washings.

At two days' distance from *Hāehāmūn* is the river named *Padmati* which flows from the *Dārdu*⁴ country. Gold is also found in this river. On its banks is a stone temple called *Sārādā* dedicated to *Durgā* and regarded with great veneration. On every eighth *tithi* of *Shuklapaksha*, it begins to shake and produces the most extraordinary effect.

¹ Cunningham alludes to this at p. 102 and adds, 'The same story is told by Ferishta with the addition of the name of the Rāja whom the translator calls *Bahnūt* (a mistake for *Lāldit*, the contracted form of *Lalitaditya* among the Kashmiris).

² *Kamrāj* and *Merāj* were two large districts into which Kashmir was divided from the earliest times, the former being the north half of the valley below the junction of the *Sind* with the *Jhelum*, and the latter the south half, above that junction. Cunningham, p. 94. Vigne calls the village *Tāragāon* (II, 139) the village of the stars. The remains of ancient masonry round a fine spring were still to be seen, some of the blocks little inferior in size to those of Martand.

³ *Suhoyum* in Vigne, (II, 281) who states that it lies near the village of *Nichi Hama* in the *Pargana* of *Machinpora* at the north-west end of the valley, and that 36 years before his visit an intense heat was found to issue from the spot. The phenomenon has several times occurred, a white smoke being occasionally seen to issue from the ground, but without sulphurous smell or fissures in the soil.

⁴ Few people can be traced through so long a period in the same place as these whom H. H. Wilson (Moorcroft, II, 266, n.) identifies as the *Dāradas* of Sanskrit geography, and *Daradræ* or *Daradæ* of Strabo. He supposes them to be the *Kāfirs* of the *Muhammadans*, though now nominally converted to Islam. The auriferous region of the *Dāradas* is mentioned by Humboldt (*Cosmos* II, p. 513. E. C. Otté) who places it either in the *Thibetian* highlands east of the *Bolor* chain, west of *Iskardo*, or towards the desert of *Gobi* described also as auriferous by *Hewen Thsang*.

The system of revenue collection is by appraisement and division of crops, assessments for crops paying special rates and cash transactions not being the custom of the country. Some part of the *Sair Jihāt* cesses, however, are taken in cash. Payments in coin and kind were estimated in *kharwārs* of (*Shālī*) rice. Although one-third¹ had been for a long time past the nominal share of the State, more than two shares was actually taken, but through His Majesty's justice, it has been reduced to one half. According to the assessment of Qāzi (Alī)* the revenue was fixed at 30 lakhs, 63,050 *kharwārs*, 11 *taraks*, each *kharwār* being 3 *man*, 8 *sers* *Akbarshāhi*. A weight of two *dāms* is called a *pal*, and $\frac{1}{2}$ and $\frac{1}{4}$ of this weight are also in use.

Seven and a half *pals* are considered equivalent to one *ser*, two *sers* are equal to half a *man*, and four *sers* to a *tarak*, and sixteen *taraks* to one *kharwār*. A *tarak*, according to the royal weights (of Akbar) is eight *sers*. Taking the prices current for several years, the Qāzi struck an average of the aggregate, and the *kharwār* (in kind) was ascertained to be 29 *dāms*, and the *kharwār* in money was fixed according to the former rate of $13\frac{8}{25}$ *dāms*. The revenue, therefore, amounted to 7 *krors*, 46 lakhs, 70,411 *dāms*. (Rs. 1,866,760-4-5), out of which 9 lakhs, 1,663 *kharwārs* and 8 *taraks* were paid in money, equivalent to 1 *kror*, 20 lakhs, 22,183 *dāms*. (Rs. 300,554-9-2). The revenue fixed by Āsaf Khan, was 30 lakhs, 79,443 *kharwārs*, of which 11 lakhs, 11,330 $\frac{1}{2}$ *kharwārs* were in money.

¹ The immemorial tradition in Kashmir considered the whole of the land as the property of the ruler. Of some portions of the *khālsa* lands the sovereigns divested themselves by grants in *jagir* for various periods. The Sikhs made a general resumption, ousted the possessors of grants and reduced thousands to destitution. In Moorcroft's time (II, 125) the *khālsa* lands were let out for cultivation. Those near the city as Sar Kishti, head or upper cultivation, those more remote Pai-Kishti, or foot and lower. When the grain was trodden out, an equal division took place formerly between the farmer and the government, but the latter advanced its demands till it appropriated $\frac{1}{4}$ of the Sar-Kishti and $\frac{1}{4}$ of the P. K. crop. The straw fell generously to the share of the cultivator who was also permitted to steal a portion of his own produce by the overseer,—for a consideration. In the time of Zainu'l Aābidin, the rice crop (the staple) is said to have been 77 lakhs of *kharwārs*. In Moorcroft's day it was 20, at from $2\frac{1}{2}$ to $6\frac{1}{2}$ Rs. a *kharwār*. His weight-measures differ from those of Abul Fazl, a *kharwār* being 16 *taraks*, a *tarak* 6 *sers*, a *ser* 20 *pals*, a *pal* $3\frac{1}{2}$ Mahomed Shāhi rupees, which (the rupee being 173.3 grains) should make the *ser* nearly 2 pounds. The actual *ser* was, however, not above one pound avoirdupois, and a *kharwār* or ass-load was therefore 96 pounds. A horse-load equalled 22 *taraks*.

* See pp. 347 and 411 of Vol. I, where further information is given regarding the revenue system, its exactions and the disturbances which led to the Qāzi's murder.

The cesses *bāj* and *Tamghā*,¹ were altogether remitted by His Majesty, which produced a reduction of 67,824½ *kharwārs*, equivalent to 898,400 *dāms*. (Rs. 22,460). For the additional relief of the husbandman, five *dāms* on the price of a *kharwār*, were thrown in. Although the revenue, in *kharwārs*, of *Āsaf Khān* was in excess of that of *Qāzi Ali* by 16,392 *kharwārs*, yet calculated by money the receipts are less, after deducting the remissions, by 860,034½ *dāms* (Rs. 21,500-13-7), because he estimated the *kharwār* in money which is of lower relative worth, above its value.

In the revenue returns forwarded by *Qāzi Ali* to the Imperial Exchequer, forty-one *parganahs* are taken while the return submitted by *Āsaf Khān* contains but thirty-eight, there being thirty-eight in point of fact. For *Qāzi Ali* on a review of the question separated the two villages *Karnā* and *Dārdu*, of the *parganah* of *Kamrāj*, and dividing the *parganah* of *Sāir i Mawāzi* into two, constituted these into two *parganahs*. In former times certain selected towns of each *parganah* were denominated *Sāiru'l Mawāzi* (village-group) and were held as *Khālisa*.² *Qāzi Ali* united forty villages of the *Marāj* side under the name of *Parganahi Hāveli* and retained eighty-eight villages of *Kamrāj* according to the former distribution, as *parganah* of *Sāiru'l Mawāzi*.

The whole kingdom was divided under its ancient rulers into two divisions, *Marāj* on the east, and *Kamrāj* on the west.

At the present day that a great part of the army in Kashmir has been withdrawn, the local militia consists of 4,892 cavalry and 92,400 infantry.

Sarkār of Kashmir.

Containing 38 *Mahals*. Revenue 3,011,618 *kharwārs*, 12 *taraks*, being equivalent to 62,113,040½ *dāms*. (Rs. 1,552,826); out of which 9,435,006 *kharwārs*, 14 *taraks* is

¹ *Tamghā* has been already defined at p. 63 of this Volume, as being a demand in excess of the land revenue and *bāj* is simply a toll or tax and must here have a somewhat similar application, but there were various other taxes in excess of land revenue, such as *Jihāt*, *Sāir Jihāt*, *Farua'āt* and others whose nature is defined at p. 63. Elliot discusses the value of the terms at p. 6, Vol. II, of his *Races of the North-West Provinces*.

² *Tamghā* occurs later under Kabul, signifying inland tolls.

³ Lands of which the revenue was the property of the government, not being made over in grants or gifts, *jāgir* or *Inām* to any other parties. Also lands and villages held immediately of government and of which the State is the manager or holder. Wilson, Gloss.

paid in money, equivalent to 12,501,880 *dāms*. (Rs. 312,547). Castes, various. Cavalry, 3,202. Infantry, 27,725.

The Marāj Tract.

Containing 22 *Mahals*. Revenue 1,792,819 *kharwārs*, equivalent to 35,796,122½ *dāms*, (Rs. 894,903), of which 670,551 *kharwārs*, 12 *taraks* are paid in money, equivalent to 8,885,248 *dāms*, (Rs. 222,131-3-2). Cavalry, 1,620. Infantry, 4,600.

City of *Srinagar*. Revenue 342,694 *kharwārs*, 12 *taraks*, in money, 342,996 *kharwārs*, 8 *taraks*; in kind, 1,698 *kharwārs*, 4 *taraks*.

Parganahs east of Srinagar, 3 Mahals.

	In kind	In money	Cavalry	Infantry	Castes
	<i>Khar-wārs Taraks</i>	<i>Khar-wārs Taraks</i>			
Yech	144,102 0	62,034 4	5	50	Khamash ? and Zinal. Bahtā, Brāhman.
Brang	78,834 4	8,769 8	68	1000	
Vihi	209,632 8	161,968 8	12	400	

Parganahs, north-east, 7 Mahals.

	In kind	In money	Cavalry	Infantry	Castes
	<i>Khar-wārs Taraks</i>	<i>Khar-wārs Taraks</i>			
Wular	128,656 4	12,605 8	20	200	Dardah and Shāl.
Phāk	71,111 12	17,402 8	
Dachhinpār	75,153 0	6,902 12	20	100	Khān. Khāwar. Dard.
Khāwarpār	45,226 8	3,575 8	100	500	
Khattār	37,479 4	3,221 12	15	300	
Maru Adwin (Maru Wardwun, Vigne)	5,041 0	200 half bow- men	200	
Matan	190,43½	18,62½	20	100	Bhāt.

Parganahs, south-east, 11 Mahals.

		In kind	In money	Cavalry	Infantry	Castes
		<i>Khar-wārs Taraks</i>	<i>Khar-wārs Taraks</i>			
Ādwin	101,432 4	14,815 16*	1	100	Dard.
Yech	98,369 0	14,377 4	6	30	Brāhman.
Banihāl	6,435	...	400	4000	Si-har.
		40 horseloads				
Bātu	3,515 0	4,235 8	50	300	Nāik.
		besides transit duties remitted				
Devsar	85,644 8	822 8	300	000	Zinah.
Zinahpur	15,875 4	1,799 1	20	...	
Soparsaman	6,133	2,003 4	70	200	Kamboh.
		besides dues on firewood				
Shūdarah	39,167 0	8,550 12	Thakur.
Shukroh	45,224 0	12,757 8	20	...	Ashwār.
Nāgām	189,770 12	22,576 4	15	100	Bhāt.
Ver	12,270 8	838	500	5000	Sahsah. ¹

* This must be a mistake for 12, as 16 *taraks* make a *kharwār*: in the Arabic numerals the 2 and 6 are easily confounded. A horse load is 22 *taraks*.

¹ Var. Sahah, Sansah, Nakhah.

Kamrāj Tract.

Containing 16 *Mahals*. Revenue 1,218,799 *kharwārs*, 12 *taraks*, equivalent to 26,316,918 *dāms*. (Rs. 657,922-15-2). In money, 272,954½ *kharwārs*, equivalent to 3,616,632 *dāms*. (Rs. 90,415-12-9). Cavalry, 1,590. Infantry, 16,965.

Parganahs, north-west.

	In kind	In money	Cavalry	Infantry	Castes
	<i>Khar-wārs Taraks</i>	<i>Khar-wārs Taraks</i>			
Zinahkar	13,253 0	32,55½ 0	50	100	Bhāt,
Khoihāma	83,670 12	15,522 0	50	1000	Musalman.
					Zinah. ²

² Var. Ahir.

Parganahs, south-west.

		In kind	In money	Cavalry	Infantry	Castes	
		<i>Khar- wārs Taraks</i>	<i>Khar- wārs Taraks</i>				
Indarkol	9,553	4	7,238	0	Bhāt.
Paraspur	18,830	12	3,352	8	Siyāhi.
Patan	4,799	4	523	0	30	110	Bhāt, Musalmān.
Bānkāl	115,233	12	20,280	4	200	500	Bākri.
Barwī	57,098	12	13,383	0	35	30	Kahār.
Telkām	15,415	12	4,435	4	...	30	Pandit.
Dinsu	53,219½		17,038½		150	400	Doni.
Dachhin Khāwarah ..	36,222	4	20,653	0	25	300	Khasi, Kanku, Zinah.
Sāir n'l Mawāzi ..	192,641	4	18,553	12	
Khoi	12,945	0	370		...	15	Rawer.
Kamrāj	342,844	4	103,725	4	1000	10,000	Chak.
Karohan	115,474	0	29,779	12	...	110	

SOVEREIGNS OF KASHMIR.

Fifty-three princes reigned during 1266 years.

I.

Ugnand.

Damodar,	} his sons.
Bāl,	

Thirty-five princes succeeded whose names are unknown.

II.

Lavah, (var. Lava.)

Kishen, his son (var. Kish.)

Kahgandra, his son.

Surandra, his son.

Godhara, of another tribe.

Suran, his son.

Janaka, his son.

Shachinar, (var. Hashka, Bishka).

Asoka, son of Janaka's paternal uncle.

Jaloka, his son.

Damodar, descendant of Asoka.

Hashka,	} three brothers. Buddhists.
Zashka,	
Kaniska,	
Abhiman.	

III.

		Y.	M.	D.
Rājā Ganand (Gonerda III) reigned	...	35	0	0
„ Bhikan (Vibhishana), his son	...	53	0	0
„ Indrajita, his son	...	35	6	0
„ Rāwana, his son	...	30	0	0
„ Bhikan II, his son	...	35	6	0
„ Nara, (also called Khar), his son	...	39	9	0
„ Sidha, his son	...	60	0	0
„ Utpalāchah, his son	...	30	6	0
„ Hiranya, his son	...	37	7	0
„ Hirankal, his son	...	60	0	0
„ Abaskaha, his son	...	60	0	0
„ Mihirkal, his son	...	70	0	0
„ Baka (Vaka), his son	...	63	0	13
„ Khatnanda, his son	...	30	0	0
„ Vasunanda, his son	...	52	2	0
„ Nara, his son	...	60	0	0
„ Aja (Aksha), his son	...	60	0	0
„ Gopāditya, his son (MSS. Kopārat)	...	60	0	6
„ Karan, his son	...	57	0	11
„ Narendraditya, his son	...	36	3	10
„ Yudishthira, his son	...	48	0	10

IV.

Six princes reigned 192 years.

Pratapāditya, said to be a descendant of				
Vikramāditya	32	0 0
Jaloka, his son	32	0 0
Tanjir, (Tunjina) his son	36	0 0
Bijai, relation to above	8	0 0
Jayandra, (var. Chandra), his son	37	0 0
Ārya Rāj	47	0 0

V.

Ten princes reigned 592 years, 2 months, 1 day.

	Y.	M.	D.
Meghavāhana, a descendant of Judishthira	34	0	0
Srishtasena, his son ...	30	0	0
Hiran, his son ...	30	2	0
Mātrigupta, Brāhman ...	4	9	1
Pravarasena, a descendant of Meghavāhana	63	0	0
Judishthira, his son ...	39	3	0
Lakshman, called also Nandradit ...	13	0	0
Ranāditya, his younger brother ...	30	0	0
Vikramāditya, his son ...	42	0	0
Bālāditya, his younger brother, no issue ...	36	0	0

Seventeen princes reigned 257 years, 5 months, 20 days.

Durlabhavardhan, son-in-law of Bālādīt ...	36	0	0
Pratapāditya, grandson of his daughter ...	50	0	0
Chandrapira, his eldest son ...	8	0	8
Tārāpira, his brother ...	4	0	24
Lalitāditya, another brother ...	36	7	11
Kuvalayāpirā, his son ...	1	0	15
Vajrāditya, his brother ...	7	0	0
Prithivyāpirā, his son ...	4	1	0
Sangrāpirā, grandson of Lalitāditya by a son	7	0	0
Jayāpira, ditto ...	31	0	0
Jajja, his brother-in-law ...	some months		
Lalitāpira, his son ...	12	0	0
Sangrāmapira, his brother ...	37	0	0
Brihaspati, son of Lalitāpira ...	12	0	0
Ajitāpira, or Ajayāpira, son of Prabhubāpira	36	0	0
Anangāpira, son of Sangrāmapira ...	3	0	0
Utpalāpira, son of Ajayāpira.			

VI.

Fifteen princes reigned 89 years, 1 month, 15 days.

Avanti Varmā, of the Chamār caste ...	28	3	3
Sankar Varmā, his son ...	18	7	19
Gopāl Varmā ...	2	0	0
Sankat, said to be his brother ...	0	0	10

Y. M. D.

Sugandhā Rāni, mother of above-mentioned			
Gopāl ...	2	0	0
Pārtha, son of Sukh Varmā ...	15	0	10
Mārjit Varmā, son of Sukh Varmā, his			
brother ...	1	1	0
Chakra Varmā ...	10	0	15
Sura Varmā, his brother ...	1	0	0
Pārtha, son of Mārjit ...	1	4	0
Chakra Varmā, second time ...	0	6	0
Sankar Vardhana, son of Mir Vardhana ...	3	0	0
Chakra Varmā, third time ...	3	0	0
Unmatt Avanti Varmā, son of Rājā Pārtha	2	2	0
Surma (Sura) Varmā, second time, last of			
the Chamār princes ...	0	6	0

VII.

Ten princes reigned 64 years, 3 months, 14 days.

Jasasra (Jasaskar) Dev, a peasant ...	9	0	0
Buranit, an uncle's descendant ...	0	0	1
Sangrāma Deva, son of Jasaskar ...	0	6	7
Parva Gupta, one of his subjects ...	1	4	0
Khema (Kshema) Gupta ...	8	6	0
Abhiman, his son ...	14	0	0
Nanda Gupta, his son ...	1	1	9
Tribhuvana ...	2	0	7
Bhimā Gupta, son of Abhiman ...	4	3	20
Diddā Rāni, mother of Abhiman ...	23	6	0

Twenty-seven princes reigned 351 years, 6 months, 17 days.

Sangrāma, son of Adirāj, nephew of the Rāni	24	2	0
Harirājā, his son ...	0	0	22
Ānanta, his son ...	5	5	0
Kalasa Deva, his son ...	26	0	0
Utkarsā, his son ...	0	0	22
Harsha, son of Kalasa ...	12	0	0
Uchal, grandfather of Harsha ...	10	4	2
Riddha, son of Siddha, one of the murderers	[one night and 3 hours]		
of Uchal ...			
Salhan, brother of Uchal ...	0	3	27

			Y. M. D.
Susalha, brother of Salhan	7 10 0
Bhekhyājar, son of Haras	0 6 12
Rājā Susalha, second time	2 3 0
Jaya Singh, son of Susalha	27 0 0
Parmānak, son of above	9 6 10
Dati (var. and G. Danji Deva), his son	9 4 17
Jas Deva, his younger brother	18 0 13
Chag (Jag) Deva, son of above	14 2 0
Rājā Deva, his son	23 3 7
Sangrāma Deva, his son	16 0 10
Rāma Deva, his son	21 1 13
Lachhman (Lakshman) Deva, son of a			
Brāhman	13 3 12
Sinha Deva, chief of Labdar of Daskhinpārah	14 5 27
Sinha Deva, brother of above	19 3 26
Rinjan of Tibet, a native of that country	10 some months
Adin Deva, relation of Sinha Deva	15 2 10
Rāni Kotā Devi, wife of Adin Deva	0 6 15

Thirty-two princes reigned 282 years, 5 months, 1 day.

A.H.	A.D.		Y. M. D.
715	1315	Sultān Shamsu'ddin, minister of	
		Sinha Deva	...
750	1349	„ Jamshid, his son	2 11 25
752	1351	„ Alāu'ddin, son of Shams-	1 10 0
		uddin	...
765	1363	„ Shahābu'ddin	12 8 13
785	1386	„ Qutbu'ddin, son of Hasan-	20 0 0
		uddin	...
799	1396	„ Sikandar, his son whose	15 5 2
		name was Sankār	...
819	1416	„ Ali Shāh, his son	22 9 6
826	1422	„ Zainul Abidin, younger	6 9 0
		brother of Ali Shāh	...
877	1472	„ Hāji Haīdar Shāh, his son	52 0 0
878	1473	„ Hasan Khān, his son	1 2 0
891	1486	„ Muhammad Shāh, his son	12 0 5
902	1496	„ Fath Shāh, son of Ādam	2 7 0
		Khān, son of Sultān	
		Zainul Abidin	...
			9 1 0

Y. M. D.

911	1505	Sultān Muhammad Shāh, a second time ...	0	9	9
		„ Fath Shāh, a second time	1	1	0
		„ Muhammad Shāh, a third time ...	11	11	11
		„ Ibrahim, his son ...	0	8	25
942	1535	„ Nāzuk Shāh, son of Fath Shāh, (<i>Ferishta</i> , “son of Ibrahim, son of Muhammad Shāh”) ...	1	0	0
		„ Muhammad Shāh, a fourth time ...	34	8	10
		„ Shamsi, son of Muhammad Shāh ...	0	2	0
		„ Ismāil Shāh, his brother ...	2	9	0
		„ Nāzuk Shāh, a second time	13	9	0
		„ Ismāil Shāh, a second time	1	5	0
948	1541	Mirzā Haidar Gurgān ...	10	0	0
		Sultān Nāzuk Shāh, a third time	1	0	0
		Ghāzi Khān, son of Kāji Chak ...	10	6	0
971	1563	Husain Chak, his brother ...	6	10	0
		Ali Chak, brother of Husain Chak	8	9	0
986	1578	Yusuf Shāh, his son ...	1	0	20
		Sayyid Mubārak Shāh, one of his nobles ...	0	1	25
		Lohar Chak, son of Sikandar, son of Kāji Chak ...	1	2	0
		Yusuf Shāh, a second time ...	5	3	0
		Yāqub Khān, his son ...	1	0	0

Thus this series of 191 princes, reigning throughout a period of 4,109 years, 11 months and 9 days, passed away.

When the Imperial standards were for the first time borne aloft in this garden of perpetual spring, a book called *Rāj Tarangini* written in the Sanskrit tongue containing an account of the princes of Kashmir during a period of some four thousand years, was presented to His Majesty. It had been the custom in that country for its rulers to employ certain learned men in writing its annals. His Majesty who was desirous of extending the bounds of knowledge appointed capable interpreters in its translation which in a

short time was happily accomplished. In this work it is stated that the whole of this mountainous region was submerged under water and called *Sati Sar*. *Sati* is the name of the wife of *Mahādeva*, and *Sar* signifies a lake. One day of *Brahmā* comprises 14 *manvantaras*. Up to the 40th year of the Divine Era, of the seventh *manvantara*, at which time Kashmir began to be inhabited, 27 (*kalpas*) each of four cycles (*yug*) as before mentioned, have elapsed and of the twenty-eighth three cycles, and of the fourth cycle, 4,701 solar years. And when, according to the legend which they relate, the waters had somewhat subsided, *Kasyapa*¹ who is regarded as one of the most sublime amongst ascetics, brought in the Brāhmans to inhabit the new region. When men began to multiply they sought to have a just ruler over them, and experienced elders, solicitous of the public weal met together in council and elected to the supreme authority one who was distinguished for his wisdom, his large understanding, his comprehensive benevolence and his personal courage. From this period dates the origin of their monarchical government which proceeded thus to the time of *Ugnand* 4,044 years prior to this the 40th year of the Divine Era.² *Ugnand* fell by the hand of *Balbhadra*, the elder brother of *Kishan* in the battle fought at *Mathurā* between *Kishan* and *Jarāsandha* rājā of Behār. *Dāmōdara* (his son), to avenge his death marched against some of the relations of *Kishan* who were hastening to a marriage festival in *Qandahār*, and was killed fighting on the banks of the *Sind*. His wife being then pregnant and the astrologers foretelling that it would prove a son, *Kishan* bestowed on him the government of the province. Thirty-five princes succeeded, but through their tyranny their names are no more remembered. When *Lavah* ascended the throne, justice was universally administered and deeds met their just recognition. He founded in *Kamrāj* the great city of *Lavapur* the

¹ According to Tieffenthaler, he was called *Cashapmir*, from *Cashapa* grandson of *Brahmā* and *mer*, a mountain or habitation. Bāber mentions in his Memoirs that the hill country along the upper course of the Indus was formerly inhabited by a race called *Kās* from whom he conjectures that Kashmir received its name. The *Kasia regio* of Ptolemy applies to the race and seems to confirm his conjecture. *Kasyapa* was the son of *Marichi* the son of *Brahmā*, and was father of *Vivasvat* the father of *Manu*. His name signifies a tortoise which form he assumed as *Prajapāti*, the father of all, and had a large share in the work of creation. He was one of the seven great Rishis.—Dowson.

² As the 40th year of Akbar's reign is A.H. 1003, commencing 5th Dec. 1594 and ending 25th Nov. 1595 A.D. the date of *Ugnand* would be B.C. 2449.

ruins of which are still to be traced. It is said to have held 800,000,000 houses. As the sage of *Ganjah*¹ well says :

House linked to house from Ispahan to Rai
Like jointed canes, I've heard, stretch countless,
So that a cat might trace the distant span
From roof to roof twist Rai and Ispahan ;
But if the tale my credit doth belie,
The teller is its surety, faith not I.

Danavadar (II) is said by some to have been one of the descendants of *Asoka*. He was a pious devout prince but was transformed into a snake through the curse of an ascetic. In the reign of *Rājā Nara* the Brāhmans prevailed over the Buddhists and levelled their temples to the ground. *Rājā Mihirakal* was a shameless tyrant, but by the strange freaks of fortune he made extensive conquests. As he was once returning homewards by the pass of *Hastibhanj*, an elephant lost its footing, and its screams and manner of falling caused him such amusement that he ordered a hundred ele-

¹ Shalāh Nizāmi, who was born in that town. The lines occur in the *Haft Payar*, one of the *Khamyah* or Five poems of Nizāmi.

* See Thomas's *Jainism or the Early Faith of Asoka* for this theory, which modern scholars have rejected.

phants to be precipitated in a similar manner. From this circumstance the pass received its name, *hasti* signifying *elephant*, and *bhanj*, *injury*. During his reign, a large rock blocked up the ferry of a river, and, however much it was cut away, it yet increased again during the night to its ordinary dimensions. Remedies were proposed in vain. At length a voice came forth intimating that if touched by the hand of a chaste woman, the rock would displace itself. Time after time it was touched by women in succession, and when no effect was produced, he ordered the women to be put to death for incontinence, the children for bastardy, and the husbands for consenting to the evil, until three *krors* of human beings were massacred. The miracle was at length effected by the hand of a chaste woman, a potter by trade and caused great wonder. The Rājā being afflicted by various diseases, burnt himself to death.

Rājā Gopadit possessed considerable learning and his justice increased the extent of his sway. The slaughtering of animals was forbidden throughout his dominions and high and low abstained from eating flesh. The temple which now stands on *Solomon's Hill* was built by his minister.

Rājā Judishthira in the beginning of his rule administered the state with an impartial hand, but in a short space through his licentious conduct and intimacy with base associates, his subjects became estranged from him, and the kings of Hindustān and Tibet were arrayed against him. The chiefs of Kashmir threw him into prison.

During the reign of *Rājā Tanjin* (Tunjin) snow fell when the sun was in Leo (July, August). The crops were destroyed and a terrible famine threw the country into disorder.

Rājā Jayandra possessed a minister wise, loyal and virtuous, and void of levity and dissimulation. His equals bore him envy, and the wicked at heart but specious in appearance, sought his ruin and undermined his influence by underhand misrepresentations. As princes are on these occasions apt to err and do not investigate closely, forgetful of former experiences of what envy can effect, the minister was overthrown, and banished in disgrace. His strange destiny, however, did not deprive him of his composure. He allowed not grief to encompass him, but gladdened his days with cheerfulness of heart. His wicked enemies represented him as aiming at the throne, and the Rājā,

ignorant of the real facts, ordered him to be impaled. After some time had elapsed, his spiritual preceptor happened to pass that way and read on the frontal bone of his skull that he was destined to disgrace and imprisonment and to be impaled, but that he should again come to life and obtain the sovereignty. Amazed at learning this, he took down the body and secretly kept it and continued in supplication to the Almighty. One night the spirits gathered round and by their incantations restored the corpse to life. In a short time he succeeded to the throne, but his experience of life soon induced him to withdraw into retirement.

Meḡhavāhan was renowned for his virtues and gave peace and security to Hindustān as far as the borders of the ocean. After the death of *Rājā Hiran* without issue, the chiefs of Kashmir paid allegiance to *Rājā Bikramājī* the ruler of Hindustān. *Rājā Mātrigupta* was a learned Kashmiri Brāhman. *Bikramājī* profited by his wisdom but did not advance his temporal interests. He, however, gave him a sealed letter to convey to Kashmir and furnishing him with a small sum of money for his expenses as he started, despatched him on his mission. The Brāhman set out with a heavy heart. On his arrival in Kashmir, the letter was opened. It ran thus. 'The bearer has rendered important services at my Court and has experienced many reverses of fortune. On the receipt of this letter, let the government of the country be entrusted to him, and be this mandate obeyed under fear of the royal displeasure.' The chiefs met in council and yielded their submission.

Rājā Pravarasena had withdrawn from the country and lived in retirement in Hindustān. A devout and enlightened servant of God predicted to him the good tidings of his future elevation to a throne. On the faith of this, he went to Nagarkot and possessed himself of that place. On hearing of the death of *Bikramājī*, *Mātrigupta* abdicated and setting out for Benares lived in seclusion. *Pravarasena* was universally distinguished for his justice and liberality. He founded *Srinagar*¹ the capital of the country and

¹ The old capital previous to the erection of *Pravarasenapura* is stated to have been founded by *Asoka* (*Rāj Tarangīni*, i, 104), (B.C. 263—226). It stood on the site of the present *Pāndrethān* and is said to have extended along the bank of the river from the foot of the *Takht-i Sulaimān* to *Pāntasok*, a distance of more than three miles. It was still the capital in the reign of *Pravarasena I*, towards the end of the 5th century when the king erected a famous symbol of the god *Siva*, named after himself *Pravareswara*. The new capital was built by *Pravarasena, II*, in the beginning of the 6th century. *Anct. Geog. India*, 97.

rendered it populous during his reign with 600,000 houses. With surpassing munificence he sent to *Mātrigupta* the aggregate of eleven years' revenue of Kashmir which that personage bestowed upon the indigent. *Rājā Ranāditya* was a just prince and made many conquests. In the neighbourhood of Kishtawār near the river Chenāb, he entered a cave with all his family and many of his courtiers, and was seen no more; many strange legends are related regarding him. *Rājā Bālāditya* invaded Hindustān and extended his dominions to the borders of the sea.

In the reign of *Rājā Chandrapira* the wife of a Brāhman appeared to him claiming justice, saying, that her husband had been killed and the murderer was undiscovered. He asked her if she suspected any one, to which she replied that her husband was of an amiable disposition and had no enemy, but that he often had disputations on points of philosophy with a certain person. This man was brought up but strenuously denied the accusation, and the complainant would not accept an ordeal by fire or water lest the man should employ some supernatural means of escaping it. The Rājā in his perplexity could neither eat nor sleep. An enlightened sage appearing to him in a vision taught him an incantation to be uttered over rice-meal scattered about, upon which the suspected person was to walk. If the foot-steps of *two* people were observed as he passed over it, he was not to be suffered to escape. Through this suggestion the truth was discovered and punishment duly meted out. But as a Brāhman could not be put to death, an iron image of a man without a head was made and his forehead branded therewith.

Rājā Lalitāditya devoted himself to the prosperity of his kingdom and in the strength of the divine aid overran Irān, Turān, Fārs, Hindustān, Khata, and the whole habitable globe, and administered his dominions with justice. He died in the mountains of the north, and it is said that he was turned into stone by the curse of an ascetic, but others relate the story differently.

Rājā Jayāpira reached a lofty pitch of glory and his conquests were extensive. Ninety-nine thousand nine hundred and ninety-nine horses were bestowed by him in charity at Benares, and his gifts to the poor were on the same munificent scale. He asked of the elders whether the army of his grandfather Lalitāditya or his own were the

larger. They answered that his contained but 80,000 litters, whereas 125,000 of such conveyances were arrayed under his grandfather's standard, by which proportion he might judge of the numerical strength of his other retinue. When he had proceeded some distance on his march of conquest, his brother-in-law, *Jajja*, who was in Kashmir disputed the throne. The nobles of the king, in anxious fear for their wives and children, betrayed him and preferred their outward reputation before their true honour. The *Rājā* hastened alone to Bengal, and with the aid of troops from that country, repossessed himself of his kingdom, *Jajja* being slain in battle.

Rājā Lalitāpira took low companions into favour and associated with buffoons, and his wise councillors withdrew from the court. His minister finding remonstrance of no avail, retired from office.

Rājā Sankar Varmā conquered Gujarāt and Sind, and overran the Deccan, but left it in the possession of its ruler. Although in the beginning of his reign he followed a virtuous course, he lacked perseverance. The intoxication of worldly prosperity plunged him into every vice.

During the reign of *Rājā Jasaskardeva*, a Brāhman lost a purse of a hundred gold *mohurs*. Under the impulse of violent grief he resolved to make away with himself. The thief hearing of this, asked him how much he would be satisfied to take, if he discovered the purse. The Brāhman answered, "Whatever you please." The thief offered him ten *mohurs*. The Brāhman, sore at heart, appealed to the *Rājā* who inquired into the case, and sending for the thief ordered him to restore ninety *mohurs*, intending by this, that the amount the thief desired to keep for himself, should be the portion of the Brāhman.

In the reign of *Sinhadeva*, a Muhammadan named Shāh Amir who traced his descent to Arjun the *Pandava* was in the royal service. About this time Dalju the chief commander under the king of Qandahār, attacked and plundered the kingdom. The *Rājā* took refuge in the mountain passes and levied forcible contributions on the people, and sent them to him and entreated him as a suppliant. The invader withdrew, dreading the severity of the weather, and many of his troops perished in the snow. About the same time also, *Rinjan*, the son of the ruler of Tibet invaded the country which was reduced to great

distress. On the death of the Rājā, the sovereignty devolved on *Rinjan* who was distinguished for his munificence. He appointed *Shāh Mir* his minister whose religion, through intimacy and association with him, he eventually adopted.

When *Rājā Adindeva* died, the aforesaid *Shāh Mir* by specious flattery and intriguing, married his widow. In the year 742, A.H. (1341-2, A.D) he caused the *khutbah* to be read, and the coin to be minted in his own name and assumed the title of *Shamsu'ddin* and levied a tax of one-sixth on all imports into Kashmir. It had been revealed to him in a dream that he would obtain the sovereignty of the kingdom.¹

Sultān Alāu'ddin issued an ordinance that an unchaste woman should not inherit of her husband.

Sultān Shahābu'ddin encouraged learning and proclaimed an equal administration of the laws. Nagarkot, Tibet and other places were overrun by him.

During the reign of *Sultān Qutbu'ddin* Mir Sayyid Ali Hamadāni arrived in Kashmir and was received with great favour.

Sultān Sikandar was a rigid follower of religious tradition and a bigot. He overthrew idolatrous shrines and persecuted people not of his faith. During his reign, Timur invaded Hindustān and sent him two elephants. *Sikandar* desired to pay his homage to that conqueror, but on his road to the interview he learnt that it was reported in Timur's camp that the sovereign of Kashmir was bringing with him a present of a thousand horses. Concerned at the untruthfulness of this rumour he returned and sent his excuses. Ali Shāh appointed (his brother) Zainul Abidin regent in his stead and set out for Hijāz. By the persuasion of foolish and evil advisers² and through inconstancy of purpose, he returned with the view of recovering his authority in Kashmir and aided by the Rājā of Jammu he took possession

¹ Such is the literal translation according to the punctuation of the text which I suspect is in error. Ferishta states that Shamsu'ddin abolished the exactions of his predecessors and having repaired the ruin, caused by the invasion and exactions of *Dalāu*, by written orders fixed the revenue at 1/6th of the produce. The text as corrected runs as follows: "Assumed the title of Shamsu'ddin and fixed the revenue at one-sixth of the produce. Before his arrival in Kashmir, it had been revealed to him in a dream that he would obtain &c."

² These, states Ferishta, were his father-in-law the *Jammu Rājā*, and the chief of *Rajauri*.

of the kingdom. Zainul Abidin set out for the Panjāb and joined Jasrat of the Khokhar¹ tribe. Ali Shāh collecting a large army advanced into the Panjāb and a great battle took place in which Ali Shāh was defeated and fell into obscurity while *Zainul Abidin* recovered the sovereignty of Kashmir. Jasrat leaving Kashmir advanced against Delhi but defeated by Sultān Bahlol Lodi retreated to Kashmir and with the assistance of an army from its monarch, conquered the Panjāb.

Zainul Abidin overran Tibet and Sind. He was a wise prince, devoted to philosophical studies and it was his fortune to enjoy universal peace. He was regarded by high and low as a special servant of God and venerated as a saint. He was credited with the power of divesting himself of his corporeal form, and he foretold that under the dynasty of the *Chaks*, the sovereignty of Kashmir would be transferred from that family to the monarchs of Hindustān, which prediction after a period of years was accomplished. His benevolence and love of his people induced him to abolish the capitation tax (*levied on other than Muslims*) and to prohibit the slaughtering of cows, as well as penalties and presents of all kinds. He added somewhat to the measure of the *Jarib*. His private revenues were drawn from copper mines. He often personally administered medicinal remedies² and resolved all difficult undertakings with ease. Robbers were employed in chained gangs on public works. His gentleness of disposition dissuaded men from the pursuit of game, and he himself ate no flesh or meat. He caused many works to be translated from the Arabic, Persian, Kashmiri and Sanskrit languages. During his reign musicians from Persia and Turkestan flocked to his court; among them Mulla Undi the immediate pupil of the famous Khwājah Abdu'l Qādir arrived from Khurāsān, and Mulla Jamil who in singing and painting was pre-eminent among his contemporaries. Sultān Abu Saïd Mirzā sent him presents of Arab horses and dromedaries from Khurāsān

and Bahlol Lodi king of Delhi and Sultā Mahmud of Gujarāt were in friendly alliance with him.

Sultān Hasan, collecting an army invaded the Panjāb and encountering Tārtār¹ Khān (Lodī) in several actions devastated the country.

In the reign of *Fath Shāh*, Mir Shamsu'ddin one of the disciples of Shāh Qāsim Anwār,² came from Irāq and promulgated the *Nur Bakhshi* doctrines, from which period date the dissensions between *Sunnis*, and *Shias* in this country.

During the third reign of *Muhammad Shāh* when he recovered the kingdom by the help of Sultān Sikandar (Lodi of Delhi), Bābar invaded Hindustān.

During *Sultān Ibrāhīm's* domination, Abdul Mākri³ represented to Sultān Bābar that Kashmir might be conquered with little difficulty. Shaikh Ali Beg, Muhammad Khān and Mahmud Khān were therefore despatched to that country and obtained some success, but the intrigues of the people prevented a settlement and they returned with gifts and presents and *Nāzuk Shāh* succeeded to the government. Under the reign of *Muhammad Shāh* for the fourth time, the emperor Humāyun ascended the throne of Delhi, and when Mirzā Kāmran⁴ was at Lahor, the officers formerly despatched to Kashmir (Ali Beg and Muhammad Khān) persuaded him that Kashmir could be taken with little trouble. The Mirzā therefore, despatched Mahram (Beg) *Kokah* with a body of troops to that country which they occupied. Massacres were frequent and their intolerable tyranny drove the people to rise till the Mughal chiefs sued for terms and withdrew. In the year A.H. 930, (1523-4) by command of Sultān Said Khān of Kāshghar, his son

¹ The Delhi governor of the Panjāb and the country at the foot of the hills.

² Ferishta places the accession of Fath Shāh in A.H. 894 (A.D. 1488-9), about which time occurred the arrival of Shāh Qāsim son of Sayyid Muhammad *Nur Bakhsh*, and the establishment of his doctrines as the prevailing creed. All religious grants and places of worship were made over to this sect, among the most illustrious converts to which were the Chak tribe.

³ He was the son of Ibrāhīm Mākri who was minister in chief to Muhammad Shāh during his second reign. Abdāl Mākri his son played a considerable part in the stirring events of this time and was eventually driven from court by the intrigues of the minister Malik Kāji. He went to India and incited Bābar to the conquest of Kashmir. Fearing that the inhabitants would be opposed to the foreign rule of the Mughals, the enthronement of Nāzuk the son of Ibrāhīm was adopted as a pretext to conciliate the Kashmiris, who, on his instalment in authority, dismissed the troops of Bābar with conciliatory gifts.

⁴ Brother of the Emperor, governor of Kabul and Qandahār, to whom Humāyun had ceded the government of the Panjāb and the Indus frontier.

Sikandar Khān and Mirzā Haidar advanced into Kashmir at the head of 10,000 troops by way of Tibet and Lār, and taking an enormous booty retired after a short time under terms of peace. In the year A.H. 948 (1541-2) Mirzā Haidar, by command of Humāyun a second time entered Kashmir, guided by some of the natives of that country, as has been related in former accounts, and took possession of a part of Great Tibet. Kāji Chak came to Hindustān and bringing with him the aid of an army from Sher Khān, engaged Mirzā Haidar but was defeated. The Mirzā won over the Kashmiris by peaceful and conciliatory measures, so that he succeeded in having the *Khutbah* read and the coin minted in the name of Humāyun, the Kashmiris having previously read the *Khutbah* in the name of Nāzuk Shāh.

At the present time under the sway of His Imperial Majesty it is the secure and happy abode of many nationalities, including natives of Persia and Turkestān as well as of Kashmir.

CORRECT LIST OF RULERS OF KASHMIR.*

Historical Kings of Kashmir.

Asoka	C. 260 B.C.
Jalauka,			
Kanishka,			
Gananda III.			
Mihir Kula,			
<i>Karkota dynasty.</i>			
Durlabha Vardhana	...	627-649 A.D.	
Pratāpāditya II or Durlabha,			
Chandrapida	713, 720.
Tārāpida,			
Lalitāditya Muktapida	...	736, 747.	
Kuvalayapida			
Vajrāditya			
Bāppiyaka			
Prithivīyapida			
Samgrāmāpida			
Jayapida	end of the 8th Century.
Cippata Jayapida	...	826-838.	

* *Camb. Hist. of India*, iii. 277-293.

Ajitapida	850/1.
Anangapida	
Utpalapida	
<i>Line of Utpala</i>	855/856—939 A.D.
Utpala	died 853.
Sukhavarman	r. 855-56.
Avantivarman	856-883.
Sankaravarman	883-902.
Gopālvarman	902-904.
Sankata	rule for 10 days in 904.
Sugandhā, Gopālvarman's	
widow	defacto ruler 904-'6.
Pārtha	906-921.
Pangu	921-923.
Chakravarman	923-933, 935-937.
Suravarman I	933-934.
Unmattāvanti	937-939.
Suravarman II	939.
<i>Line of Viradeva</i>	939-949.
Yasaskaradeva	939-948.
Sangrāmadeva	948-49.
<i>Line of Abhinava</i>	949-1003.
Parvagupta	949-950.
Kshemagupta(Diddā-Kshemā)	950-958.
Abhimanyu	958-972.
Nandigupta	973.
Tribhuvana	973-975.
Bhimagupta	975-980.
Diddā	980-81—1003.
<i>Lohara dynasty</i>	1003-1171.
Sangrāmārāja	1003-1028 A.D.
Harirāja	Rule for 22 days.
Ananta	1028-1063 A.D.
Kalasa	1063-1089.
Utkarsa	1089.
Harsa	1089-1101.
<i>Period of civil war and inter-</i>			
<i>necine strife</i>	1101-1339.
Uccala	1101-11.
Salhana	1111-12.
Sussala	1112-28.
Jayasinha	1128-1155.
Paramānuka	1155-1165.
Vantideva	1165-1171.

<i>Line of Buppādeva</i>	...	1171-1286.
Buppādeva	...	1171-1180.
Jassaka	...	1180-98.
Jagadeva	...	1198-1212-13.
Rājadeva	...	1212-13-1235.
Saṅgrāmadeva	...	1235-52.
Rāmadeva	...	1252-73.
Lakṣmandeva	...	1273-86.
.....
Sinhadeva	...	1286-1301.
<i>Tibetan dynasty</i>		
Rinchana	...	1320-23.
Udyādeva	...	1323-38.
Kotadevi	...	1338.
<i>Muslim Sultans of Kashmir.</i>		
Shamsuddin Shah	...	1346-1349.
Jamshed	...	1349-1350.
Alauddin	...	1350-59.
Shihābuddin	...	1359-1378.
Qutbuddin	...	1378-1394.
Śikandar	...	1394-1416.
Ali Shah	...	1416-1420.
Zain-ul-Ābidin	...	1420-1470.
Haider Shah	...	1470 Dec. 1471 or Janv. 1472.
Hasan Shah	...	1472-1489.
Muhammad Shah	...	1489, 1497, 1499-1526, 1529-1534.
Fath Shah	...	1489-1497, 1498-99.
Ibrāhim Shah, I	...	1526-27.
Nāzuk Shah	...	1527-29, 1540, 1551-52.
Shamsuddin Shah	...	1534-1540.
<i>A new line.</i>		
Mirza Haider Shah	...	Nov. 1540-1551.
Ibrāhim Shah	...	1552-55.
Ismail Shah	...	1555-57.
Habib Shah	...	1557-61.
Ghāzi Shah	...	1561-1563, 64.
Nāsiruddin Husain Shah	...	1564-1569-70.
Ali Shah	...	1570-1579.
Lohar Chakk	...	1579-80.
Yusuf Shah	...	1579, 1580-86.
Yaqub Shah	...	1586-89.

Peoples of Kashmir.

Bakhri—a clan claiming Rajput origin, found in several districts of the Panjab, converted to Islam by Bahauddin Zakariya, Rose, *Glossary of Panjab tribes and castes*, II, 39.

Khasa—Khasaka tribe, mod. Khakhas, Stein, *Chron.* II, 519.

Khawar—Var. *Kahu*,—*Either* Kahoi, a Jat clan found in Amritsar and Multan, *or* Kahut, another Jat clan found in Gujrat and Rawalpindi districts, Rose, 245.

Khamash—Rose mentions a Jat clan *Khamah*, resident in Multan, *ibid*, 491.

Bat, Bhat, or Bhatta,—Jarrett's classification of them as Muhammadans is not tenable, for there are Hindu Bhats as well, Rose, *ibid*, 94-101.

Kambah—Kamboh, "one of the finest cultivating tribes" found also in the Panjab, claiming descent from Raja Karan and saying that their ancestor fled to Kashmir. They belong to different religious persuasions. Rose, II, 442-446.

Doni—*Either* Dhunia, a weaver caste *or* Dun, so called from Duhna to milk, hence milkman, Rose, II, p. 251.

Chak—*Either* a Kamboh clan *or* a sept of Jats, Rose, II, p. 146.

Shal—conjectured *Chahal*, Rose, III.

Siyahi—Sahi?, sometimes pronounced Chhahi in Ludhiana, a Jat tribe claiming descent from Solar Rajputs, Rose, III, p. 342. *Shahiya?*

Rawar—is it Rayar, a Jat clan of Amritsar? Rose, III, 332.

Sahasu—Sahasni?, a Jat clan of Amritsar, Rose, III, 342.

Thakur—representing the high-caste population of Kashmir. Rose. III. p. 326-329.

NOTES ON PLACES IN KASHMIR.

(Compiled by Prof. N. B. Roy)

P. 351. Qambar Ver—possibly the hill of Kamelania Kotta (anc. *Kramavarta*), a watch-station on the Pir Pantsal range. Stein, *Chron.* II, 292.

P. 352. Hasti Bhanj—Stein (*Chron.* Book I, n. 302) derives the name from Sanskrit *hasti*, elephant and W. Panjabi *vanj* to go. He describes this route in *J.A.S.B.*, 1895, pp. 376 sq., *Chron.* II, 394.

Tangtalah—5 miles n. of Pir Pantsal pass. For details Stein (*Chron.* II, 398).

P. 356. Behat—Vyath or Vitasta, embodiment of Parvati. Stein, Bk. I, 29, its legendary origin and course above Srinagar. *Chron.* II, 411, 415. *Cam. Hist. Ind.*, III, 286.

Mar—ancient name *Mahasarit*. (Stein, *Chron.* ii. 416). This stream drains the Dal lake to the east of the city of Srinagar, and carries off the surplus waters of the lake towards the Vitasta (Jhelum).

Lacham-Kul—canal of Srinagar (Stein, *Chron.* II, 457).

Sayyid Ali Hamadoni,—For anecdotes about him, Vigne, I, 82-83; shrine, Moorcroft, II, 120, Percy Brown, II, 83.

P. 357. Brang—modern Bring.

Sendhbrar—mod. Sundbrar. Stein identifies it with the spring of the goddess *Samdhya*. The spring flows during uncertain periods in the early summer, three times in the day and three times in the night. (*Chron.* I, note 33. *Chron.* II). Sendhbrar—Vigne writes about this tirtha saying,—on the 15th of Har (corresponding to 13th June), several thousand people are assembled, nearly naked—and wait for the rising of the water; those who are nearest to it, shaking peacock's feather over it as an act of enticement and veneration. When the basin perceptibly begins to fill, the immense multitude exclaim Sondi, Sondi, (it appears), and then they fill their brazen water-vessels, drink and perform their ablutions and return towards their home. Read Bernier's description, *Travels*, Brock's ed., II, p. 153.

P. 357. Kokar Nag—a tirtha in the Bring valley, situated a mile above the village of Bidar. The seven fountains inside the temple, mentioned by Abul Fazl, are the

spring now known as *Sweda Nag*. (Stein, 1899, *J.A.S.B.*, 181, *Chron.* II, 469.)

Iron mine—Located by Vigne, I, 337, he describes the route from Shahabad to Sof-ahun where the principal or in fact the only iron works of the valley are to be seen.

Vej Brar—modern Vija-brar, one of the most famous *tirthas* of Kashmir, so called from the ancient shrine of Siva Vijayeshwar. The place being situated on the way to Martand and Amarnath, is much frequented even at the present day. (Stein, *J.A.S.B.*, pp. 173-175. *Chron.* II, 463).

P. 358. *Nandi-marg*—a beautiful mountain down situated on the eastern slopes of the Pir Pantsal range, about 12 miles s.e. of Supyan, 33. 34 N. 75 E. Bates, *Kashmir Gazetteer*, 287. Vigne, I, 299.

Pampur—mod. Pampar, ancient Padma-pur, the chief place of the Vihi pargana. Stein, *Chron.* II, 450; Stein, *J.A.S.B.*, 167.

P. 359. Zewan—mod. Zevan, ancient *Jaya-van*, in the Vihi pargana. Here is a pool sacred to Takshiaka, the lord of snakes, which is visited annually by pilgrims. (Stein, *J.A.S.B.*, 166, *Chron.* Bk. I, 220 note, 166).

Khriu—mod. *Khruv*, ancient *Khaduvi*. Stein noted an abundance of fine springs in and about Khruv, and a mystical diagram called Sayambhu chakra, above the village which is held sacred to Jvalamukhi Durga, *Chron.* II, 459.

Maru Adwin—*Madivād-van* valley situated along the range that forms the eastern frontier of Kashmir, running from the Zoji-la almost due south towards Kastawar. (Stein, *Chron.* II, 435). Vigne (*Travels*, i: 354) noticed here a tank, 100 yards square.

Achh Dal—misreading for *Achabal*, a short distance from Sundabrar. Here was formerly a country-house of the kings of Kashmir, and then of the Mughal Emperors. See Bernier's *Travels*.

Khattar—mod. *Kutahar*, in the valley of Arapath or Harsapath which opens to the east of Islamabad. Stein derives the word from *Kapateshwar*, a *tirtha* on the southern side of the valley close to the village of *Kother*. (Stein, *J.A.S.B.*, 179, *Chron.* II, 467).

Kotihar—mod. *Kother*, near Achabal. Here is the deep spring of *Pāpa-sudan* (or Remover of sin), mentioned by Kalhan. Siva is believed to have shown himself here in the disguise of pieces of wood floating on the water.

(Stein, *J.A.S.B.*, 179). The route to this *tirtha* is described fully by Vigne (i. 351).

Wular—*Ṭular*, ancient Holada. It is situated in the pargana of the same name, comprising the valley opening to the n.e. of the Vitasta, between Dachunpor and Vihi. (Stein, *Chron.* I, Bk. I, note 306, II, 460, *J.A.S.B.* p. 168).

Matan—Martand *tirtha*, situated in the eastern portion of the Lidar valley, at a distance of about 2 miles from Islamabad. For a description of its most famous temple, Vigne (i. 385-391), Moorcroft (ii. 255-256), Percy Brown (*Ind. Arch.* i. 181), Stein (*J.A.S.B.*, 176-178).

P. 360. Well of Babylon—The reference is to the imprisonment of two angels, Harut and Marut, in a well in Demavand for their submission to sin and temptation. (*Encyclo. Islam.* ii. 272). Vigne says that at a distance of 150 yards from the temple there was the residence of a faqir whose duty was to superintend the existence of a well called the *Chah-i-Babul*. (*Travels*, I, 361).

Kharwar-para—mod. Khovur-pur. The source mentioned here is a small river that feeds the northern branch of the principal tributary of the Behat. (Stein, *Chron.* II, 465).

Dachchhin-para—mōd. Dachunpor, a district situated east of the confluence of the Vitasta and the Gambhira, and comprising the whole western side of the Lidar valley, and also the low-lying tract between the Vitasta and the lower course of the Visoka. (Stein, *J.A.S.B.*, 170, Stein, *Chron.* II, 461).

Amarnath—Situated north of the Lidar valley but south of the high peak, (about 10 miles east-south of Zoji-La) that marks the eastern boundary of Kashmir. For a description of this *tirtha* which is the most popular of Kashmirian *pilgrimage places*, read, Stein, *J.A.S.B.*, p. 94, 163-4, *Chron.* Vigne, II, 7-8, Moorcroft, II, pp. 252-53.

P. 361. Dāl lake—Situated east of Srinagar, and forming one of the most favoured spots of the Srinagar valley. The floating gardens which covered its surface in Abul Fazl's time are described by Stein, *J.A.S.B.*, 105, *Chron.* II, 417, Moorcroft, II, 115, 137-140, Vigne, II. 90-91. Drew, *Jammu and Kashmir*, 186.

Thid—ancient Thed which was adorned by king Aryaraja with *mathas*, divine images and lingas. Stein, *Chron.* II, 135. The seven springs mentioned by Abul Fazl

still exist, but other remains do not, Stein, *J.A.S.B.*, 1879, *Chron.* II, 454.

Shalamar—Shalimar, this *bagh* along with *Nishat* and *Nasim*, form the three most delightful places on the Dal lake, Drew, *History of Jammu and Kashmir*, 187, described by Vigne, *Travels*, Vol. II, 100-101, Stein, *Chron.* II, 456 fn.

Ishibari—mod. Isabar, lying a short distance from the *Nishat* garden and *Suresvari Ksetra*, still sacred to *Durga-Suresvari* who is worshipped on a high crag to the east of the village. Of the several springs in and about Isabar, two are mentioned by Abul Fazl,—*Suryasar* and *Shakarnag*, one of them might be what is stated by Stein to be *Gupta-ganga*, forming the chief attraction of the place and filling an ancient stone-lined tank in the centre of the village, Stein, *J.A.S.B.*, p. 161, Stein, *Chron.* II, 455.

Rambal—mod. *Ranyal*, anc. *Hiranyapur*, north of *Srinagar*, situated at the foot of the ridge running down to the opening of the *Sindh Valley*. Stein mentions the existence of a spring to the south of the village. Stein, *J.A.S.B.*, 163, *Chron.* II, 456.

P. 362. Banihal—anc. *Bansala*. Stein says nothing about the temple of *Durga* mentioned by Abul Fazl, but he refers to a group of peaks sacred to *Brahma*, *Vishnu* and *Siva*. (Stein, *J.A.S.B.*, 71, *Chron.* II, 393). The pass of the same name has always been a convenient route of communication towards the Upper *Chenab* valley and the eastern *Panjab* hill states, *Chron.* II, 392.

Ver—Old name of *Shahabad* pargana, comprising the valley of the *Sandran* river (Stein, *Chron.* II, 469):

Vernag—Situated in the *Sandran* valley. The stone temples of Abul Fazl's time have disappeared; their materials having been partly used for the construction of a fine stone enclosure which *Jahangir* built around the spring. (Stein, *J.A.S.B.*, 182, *Chron.* II, 411, 469. Vigne, *Travels*, i. 332. Moorcroft, ii. 249).

Kambar—Bates mentions a village *Kammar* in the *Shahabad* valley, near the left bank of the *Sandran* river. Below this village lies at present the *ziarat* of *Qadam Rasul*. *Kas. Gaz.*, 223, nothing is said about the spring.

Devsar—mod. *Devasar*, anc. *Deva-saras*, drained by the *Visoka*. (Stein, *J.A.S.B.*, 183, *Chron.* II, 470).

Balau—probably anc. Bilava, about 4 miles north-east of Drabgam, Stein, *Chron.* II, 473.

Veshau—mod. *Visoka*. Stein refers to a place named Gudar where a small stream called the Godavari falls down the hill, as a *tirtha* of some repute (*J.A.S.B.*, 184).

Kuthar—Jarrett suggests Kausar-nag, a lake two miles long described by Stein (*J.A.S.B.*, 71). Stein, *Chron.* II, 393.

P. 363. Shukroh—Jarrett's identification with Zuyru (4 m. n. of the capital) is far-fetched. Stein identifies it with the modern *Sukru*, where the ancient *tirtha* of Kalyanpur (mod. *Kalampur*) still stands, on the high road from Pir Pantsal to Srinagar. The fountain of the *Ain* is that at the mod. *Buda-brar* (anc. Bheda-giri). (Stein, *J.A.S.B.*, 186).

Nila-nag—situated in a valley between two spurs descending from the Pir Pantsal range. Stein points out that Abul Fazl has here made the mistake of transferring to this spring the legends of the famous Nila-nag at Vernag. (Stein, *J.A.S.B.*, 190, *Chron.* II, 475).

Birūwa—mod. *Biru* (anc. *Bahurupa*), situated west of Dunts and towards the Pir Pantsal range. (Stein, *J.A.S.B.*, 192).

Halthal—Halathal in Yech. Stein took it for *Salasthal* (*Chron.* II, 475).

Lar—anc. *Lahara*, comprises the whole of the valleys drained by the Sind and its tributaries. (Stein, *Chron.* II, 488).

P. 364. Shahab-ud-dinpur—*Shadipur*, at the confluence of the Vitasta and the Sindhu, (Stein, *Chron.* II, 379).

Tulmula—mod. *Tulamul* (anc. *Tulamalya*) situated in the midst of the Sind delta. According to Stein, the spring here is still held sacred. (Stein, *J.A.S.B.*, 210, *Chron.* II, 488).

Satpur—

Bhutesar—in the narrow gorge of the Kankanai river, which flows past the south foot of the spur. Two miles above Vāngath are found the ruins of some 17 temples of various size and dimension. These ruins were identified by Stein with the temple of Bhutesar. (Stein, *J.A.S.B.*, 211).

Khoihama—mod. *Khuyahom* (anc. *Khuyasrama*) stretching in a semi-circle round the north shore of the Volur lake. (Stein, *Chron.* II, 488; *J.A.S.B.*, 209).

Volur lake—anc. Mahāpadmasaras, 12 kos n.w. of Srinagar, a most striking physical feature in the western portion of Kashmir. For details, Stein, *Chron.* II, 423, Moorcroft, II, 111.

Zain Lanka—built by Sultan Zain-ul-abidin, in the midst of the Volur lake. (Stein, *Chron.* II, 423). Described by Moorcroft, II, 224.

Machhamu—Stein suggests that the village of *Ratasum* represents it, though there is a pargana of the name *Manchahom*. (*Chron.* II, 477).

Paraspor—anc. *Parihaspur*, the capital of Lalitaditya. The plateau on which it stood, is "about two miles from north to south and its greatest breadth is not much over a mile." The Badrihel canal bounds it on the north. In the S.W. part are the ruins of two large temples, much decayed but still showing dimensions which considerably exceed those of the great temple of Martand. On that part of the Udar which lies to the n.e. and towards the Badrihel *nala*, there is a whole series of ruined structures. The four great temples of Vishnu Parihasa-Keshava, Mukta-Keshava, Mahavaraha, and Govardhan-dhara, as well as the Rajvihar with its colossal image of Buddha, must all be looked for among the ruins. Extremely decayed condition." (Stein, *Chron.* II, 477, sec. iv, 194-204).

P. 365. Kamraj—anc. *Krama-rajya*, as distinguished from *Maraj* (*Madhya-rajya*). In modern times it designates only the parganas to the west and north-west of the Volur lake (Stein, *Chron.* II, 436).

Trahgam—anc. *Tri-gaini*, mod. *Trigam*, 1½ miles n.e. of the Paraspor ruins. (Stein, *Chron.* II, 329, 479).

Kargon—Kherigam, a short way from Sardi (Stein, *Chron.* II, 282).

Soyam—(derived from *Swayambhu*) half a mile south-west of the village of Nichahom, in the Machipur pargana, where volcanic phenomena are observed in a shallow hollow formed between banks of clay and sand. Hot vapours issue from fissures in the ground. (Stein, *Chron.* I, Bk. I, note 34).

Haehamun—mod. *Hayahom*, on the pilgrim route to Sarala (Stein, *Chron.* II, 280, 486).

Padmate—miswritten for *Madmati* (=Madhumati). Stein suggests that Abul Fazl here confuses the Madhumati

with the Kishanganga, which (latter) alone flows from the Dard country. The notice of gold being found in the river, clearly refers to the Kishanganga, which drains a mountain region still known as auriferous. (Stein, *Chron.* II, 247).

Dardu—mod. Dard.

Sarada tirtha—situated on a small hill above the junction of the Kishanganga and the Madhumati. (Stein, *Chron.* I, Bk. I, note 37, for temple ii. 284-287).

P. 368. Phak—comprising the tract lying between the east shore of the Anchiar, the range towards the Sind valley and the hills which enclose the Dal on the east and the south.

Khattar—Kutahar pargana, comprising the valley Arupath or Harsapatha opening to the east of Islamabad. Stein, *Chron.* Vol. II, p. 467.

Matan—comprising the plateau on which the temple of Martand stands. Stein, *Chron.* Vol. II, 466.

P. 369. Adwin—Adavin, lies north of Divasar, reaching from the western end of Khur-Naravao to the lower course of the Visoka. Stein, *Chron.* Vol. II, 471.

Itch=Yech—anc. Iksika, comprises the tract to the immediate vicinity of Srinagar. Stein, *Chron.* II, 475.

Batu—Bot, adjoining Adavin on the north-east, Stein, *Chron.* II, 472.

Devsar—Divasar, adjoins the pargana of Shahabad Ver on the west and comprises the tract of alluvial plain drained by the Vesau, Stein, *Chron.* II, 470.

Zinahpur—Zainapur, comprising the northernmost portion of Adawin, Stein, *Chron.* II, 471.

Soparsaman—Suparsamun, comprising the villages lying at the foot of the spurs descending into the plain west and north-west of Supiyan. Stein, *Chron.* II, 472.

Nagam—(anc. Nagram), situated north of Chrath Pargana, Stein, *Chron.* II, 474.

Zinahkar—Zaingir, comprises the fertile Karewa tract between the Volur and the left bank of the Pohur River, Stein, *Chron.* II, 487.

Khoihama—Khuyahom, stretches in a semi-circle round the north shore of the Volur lake. Stein, *Chron.* II, 488, Bates, 233.

P. 370. Indarkol—Mod. Andarkoth, (anc. Jayapura) comprises the marshy tract south of the Volur. Stein, *Chron.* II, 480).

Paraspor—comprising the well-defined little tract lying between the marshes on the left bank of the Vitasta immediately to the south-west of Shadipur. Stein, *Chron.* II, 300. According to Stein, the Paraspor Udar, until some sixteen years ago, continued to form a separate pargana, *ibid*, p. 333.

Patan—Anc. Samkarapur, situated on the direct road between Srinagar and Baramula. Stein, *Chron.* Vol. II, 481.

Bankal—Bangil, anc. Bhangila, situated between Firozpur and Patan, sloping down from the mountains to the morass on the left bank of the Jhelum.

Telkam—Tilgama, a very small pargana, adjoins Patan.

Dinsu—Dunts, west of Yech and close to Srinagar. Stein, *Chron.* II, 470.

Sair-ul-Mawazi—lying on the left bank of the Vitasta with Chrath. Stein, *Chron.* II, 474.

Khoi—Khuhy, north of Patan and Tilagam.

Karohan—Karnav, anc. Karnaha, north-west of Kashmir lying between the Kishanganga and the Kajanāg range. Stein, *Chron.* II, 405.

P. 378. Solomon's Hill—mod. Takht-Sulaiman, anc. Gopadri. The temple referred to is the shrine of Siva Jyesthesvara, built on the summit by Gopāditya; for the description of this tirtha, Stein, *Chron.* II, 159.

Sarkār of Pakli.

Its length is 35 and its breadth 25 *kos*. It is bounded on the east by *Kashmir*, on the north by *Kator*,¹ on the south by the territory of the *Gakhars*, and on the west by *Atak Benāres*. Timur left a few troops to hold this tract, and their descendants remain there to this day. Snow lies perpetually on these mountains and at times falls on the plains. The period of winter is longer than the summer. The rainfall is somewhat similar to Hindustān. It is watered by three rivers, the *Kishan Ganga*, the *Bihat* and the *Sindh*. The language of the country differs from that of Kashmir, Hindustān or Zābulistān. Vetches and barley are the principal crops. Apricots, peaches and walnuts grow wild, it not being the custom to plant fruit trees. Game and horses, camels and buffaloes are of middling account: goats and poultry, plentiful. The rulers of this district generally paid tribute to Kashmir.

Sarkār of Sawād (Swāt).

It comprises three districts, those of *Bimbar*, *Swāt* and *Bajaur*. The first is 16 *kos* long by 12 broad and is bounded by *Pakli* on the east, *Kator* and *Kāshghar*² on the north, *Atak Benāres* on the south and *Swāt* on the west. Two roads approach it from Hindustān, viz., the *Sherkhāni* pass and the *Balandari Kotal*; although both routes are difficult to traverse, the first is the more rugged.

The second district (*Swāt*) is 40 *kos* in length by 5 to 15 in breadth. On the east lies *Bimbar*; to the north *Kator* (*Kunar*) and *Kāshghar*; to the south *Bigrām*³ and on the west *Bajaur*. It possesses many defiles. Near the *Damghār* pass which leads to *Kāshghar* is the town of *Manglor*⁴ the

¹ Ferishta says (p. 144) that Kattor or Katār is a place of note in the Kafirstān country, but in the maps Kunar occupies a corresponding position.

² By *Kāshghar* cannot be meant the well-known town of E. Turkestan which is too far removed, but Chitral or Kāshkar, which, according to Erskine, (*Bābar's Memoirs*) is a corruption of Kāshghar with the territory of which it was long included. The *Kāsia* or *Akhassa regio* of Ptolemy beyond Mount Imāus has perhaps given its name to both Kāshghar and Kashmir.

³ *Bigrām* is said by Cunningham (p. 29) to signify "the city" *par excellence* and is applied to 3 other ancient sites near Kābul, Jalālābād and Peshāwar. Masson derives the name from the Turki *bi* or *be* "chief" and the Hindi *grām*.

⁴ *Manglaur* was the capital of Udyāna, the Sanskrit name for the modern districts of Panjkora, Bajaur, Swāt and Buner. It is mentioned by Hwen Thang as Mung-kie-li or Mangalu.

residence of the governor. It is entered by two routes from Hindustān, viz., the passes of *Malkand Baj* [Malakand] and *Sherkhānah*. It has no extremes of heat or cold, and though snow falls, it does not lie in the plains for more than three or four days; in the mountains it is perpetual. It is springtime here during the periodical rains of Hindustān. Rainfall occurs and the spring and autumn are very delightful. Its *flora* are those of Turkestan and India, wild violets and narcissus covering the meadows, and various kinds of fruit trees grow wild. Peaches and pears are excellent, and fine hawks and falcons are obtained. It also possesses an iron mine.

The third district (Bajaur) is 25 *kos* in length by 5 to 10 in breadth. On the east lies *Swāt*, on the north *Kator* and *Kāshghar*, on the south *Bigrām*, and on the west *Kuner* (and) *Nurkil*.¹ Numerous passes lead from Kābul.

An ancient mausoleum² exists here, and there is a strong fortress which is said to be the residence of the governor. Amir Sayyid Ali Hamadāni died here and his body was conveyed to *Khutlān* by his last testament. Its climate is similar to that of *Swāt*, but the extremes of cold and heat are greater. It has only three roads, one from Hindustān called *Dānishkol*, and two from Kābul, one called *Samaj* and the other *Kuner* and *Nurkil*, the easiest of these being *Dānishkol*. Adjoining this and between the mountains and the Indus and Kabul rivers, is a plain, 30 *kos* in length by 20 to 25 *kos* in breadth.

The whole of this tract of hill and plain is the domain of the *Yusufzai* clan. In the time of *Mirzā Ulugh Beg* of Kābul, they migrated from Kābul to this territory and wrested it from the Sultāns who affected to be descended from a daughter of Alexander Bicornutus. It is said that this monarch left some of his treasures in these parts with a few of his kindred and to this day the descendants of this band dwell in these mountains and affect to show their genealogical descent from Alexander.³

¹ Erskine states that *Kuner* and *Nurgil* form another Tumān situated in the midst of Kafiristān which forms its boundary. . *Nurgil*, says Bāber, lies on the west and *Kuner* on the east of the Cheghān sarāi or Kāmeh river, p. 143.

² The text is here confused, and the translation has been made after correction from Babar's *Memoirs*.

³ See Elphinstone's *Cabul*. App. C, p. 617.

Under the present ever-during Imperial sway, of the lawless inhabitants of this country, some have been put to death, others imprisoned, while some happily dwell under their tribal rule.

Sarkār of Daur, Banu and Isakhel.

This territory is to the south-east of *Kābul*, and is inhabited entirely by Afghāns. It is the principal settlement of the *Shirāni*, *Kararāni* and *Waziri* tribes.

Sarkār of Qandahār.

It is situated in the third climate. Its length from *Qalāt Banjārah* to *Ghor* and *Gharjistān*¹ is 300 *kos*: its breadth from *Sind* to *Farah* is 260 *kos*. On its east lies *Sind*; to the north *Ghor* and *Gharjistān*; on the south *Siwi*, and on the west *Farah*; *Kābul* and *Ghaznīn* on the north-east. Its mountains are covered with perpetual snow which seldom falls in the city.

Eighteen *dinārs* make a *tumān*, and each *tumān* is equivalent to 800 *dāms* [=Rs. 20]. The *tumān* of *Khurāsān* is equal in value to 30 rupees and the *tumān* of *Irāq* to 40.*

Grain is for the most part taken in *kharwārs*, the *kharwār* being equivalent to 40 *Qandahāri man*, or 10 of *Hindustān*.

The capital of the district is *Qandahār*. Its longitude is 107° 40', and the latitude 33° 40'. It has two forts. The summer heats are extreme and the cold in winter is considerable, but the ice-pits are filled in December and January. Once in three or four years a fall of snow occurs and is hailed with delight. Flowers and fruits are in abundance. Its wheat is extremely white, and is sent as a present of value to distant countries. At a distance of five *kos* is a hill called *Azhdarkoh* (the Dragon Hill) in which is a wonderful cave known as the *Cave of Jamshīd*. People

¹ Its limits are defined by Erskine, (p. 152), within Herat on the west, *Farah* on the south and *Ghor* on the east. *Encyclo. Islam*, ii. 141, gives "Ghardjistan, a tract on the upper valley of the Murghāb in Afghan Turkistan, . . . the country now occupied by the Firoz Kohis." [J. S.]

* *Tumān*. *Encyclo. Islam*, iv. 836. In the period of Mongol dominion, the *tumān* was 10,000 *dinārs*=60,000 *dirhems*. Value varied from country to country.

enter with lighted lamps, but the oppression of its atmosphere prevents exploration of its extent. Eight *kos* from *Qālāt* is a large mountain in the side of which is a huge cave called *Ghār i Shāh* (the King's Cave). Within it are two natural columns, one of which touches the roof of the cave and is 30 yards high. Water flows down it and enters a basin at its foot. The other is 11 yards in height. The waters of the *Hirmand* (Helmand) which rises between Balkh, and Kābul, flow in this direction along the skirts of the mountains. The meaning of *Hirmand* is 'abounding in blessings'. *Maulānā Muīnu'ddīn* in his history of Kurāsān records that it feeds a thousand streams. At a distance of 16 *kos* is a mountain, at the base of which is an area of land called *Natīl* [Tānil], formerly full of watercourses, where melons are grown in great quantity and perfection. The mountain has several clear springs. There is also an iron-mine, and at the foot of the mountain is an iron-foundry for the smelting of the ore, a work of ancient times.

West of Qandahār is a long torrid tract of country, (*Garmsir*) through which flows the *Hirmand*. One side of it touches the *Dāwar*¹ territory, and on the other *Sistān*. There are many forts and much cultivation on both sides of the river. In this neighbourhood once stood a large city, the residence of the Sultāns of Ghor, and many ruins still exist of the palaces of its ancient kings.

Between the *Hirmand* and Qandahār is the well-known city of *Maimand*, described in old astronomical tables.

Wheat and barley are called *Safedbari*.¹ The *jarib* of sixty (square) yards is used for measurements, but they reckon 30 yards of this according to the *Hijāzi jarib*, each yard of $24\frac{1}{2}$ digits, the *gaz* there in use; equal altogether to 54 *gaz* of Qandahār. In the exchequer, out of every ten *kharwārs*, two are taken for the minister of finance on account of revenue and *jihāt* cesses. Cultivation is reckoned under seven heads. In the registers, the best kind of land is marked with an '*Ain* [Arabic letter] and calculating the

¹ *Dāwar* or *Zamin Dāwar*, lies west of the Helmand, below the hills, in S.W. Afghanistan.

² Var. and G. *safedbari*. I am disposed to think the marginal reading correct and that it signifies *white crops* in contradistinction to the *sabzbari* or *green crops* that follow lower down, though it is not easy to see why rice should be relegated to the green, rather than the white class. There are, however, two kinds of *shālī* rice, the white requiring deep water and the red needing only a moist soil.

produce of each *jārib* at 3 *kharwārs*, 24 *man* are taken as revenue. Thus :

No.	Kind of land.	Distinguishing Marks. Arabic letter.	Produce in <i>Kharwārs</i> .	Revenue in <i>mans</i>
1	Best.	'ain	3	24
2	Best and Medium.	toi 'ain	2½	20
3	Medium.	toi	2	16
4	Medium and Poor.	dal toi	1½	12
5	Poor.	dal	1	8
6	Poor and Poorest.	dal-dal, dal	30 <i>man</i> .	6
7	Poorest.	dal-dal	8	4

But if the husbandman is incapable of sustaining this class of assessment, the produce is divided into three heaps, two of which are taken by the tenant, and the third is again subdivided into three shares, two of which go to the revenue department and the third is charged to incidental expenses.

The revenue from grapes also is taken by agreement and by paying a special rate. In the latter case experts appraise the average outturn of the vineyard and exact 4 *bābaris* for each *kharwār*. Under the reigns of Bābar and Humāyun the rate was fixed at 2 *bābaris* and 4 *tangahs*. The *babari* is one *miskāl* weight and 2½ are equivalent to the rupee. Besides these three (wheat, barley, grapes), upon nine other articles called *sabzbari*, 7½ *bābaris* are taken for every *jarib*, formerly rated at 5 *bābaris*, viz., rice (Shālī), musk-melons, water-melons, cucumbers, onions, turnips, carrots and lettuce. On other crops than these, two *bābaris* were formerly taken, the Turkomāns exacting three.

In the torrid tract (above-mentioned, between Dāwar and Sistan), the *safedbari* crops are divided into three heaps according to the Qandahār custom and all crops paying special rates are registered under the 'Ain and Toi class (No. 2), and for every *jarib*, 50 *man* of the torrid tract (*Garmsir*) equalling 20 *man* of Qandahār, are taken. The *kharwār* of this district is 100 *man*, equivalent to 10 *man* of Hindustān. Grapes are treated in the same manner as at Qandahār. All articles under *Sabzbari*, pay two *babaris* on each *jarib*.

In the Dāwar tract, produce under *safedbari* is apportioned in three heaps as described above and the exchequer receives for every 4 *jaribs*, one *kharwār* weight of Dāwar.

which is equivalent to one *kharwār* and ten *man* of Qandahār, and for other produce, one *kharwār* on three *jaribs*.¹

Sarkār of Qandahār.

Containing 24 *Mahals*. Revenue 8,114½ *tumāns*, 39,600 *dinārs*; 45,775 *sheep*; 45 *Balochi* horses; 3,752,977 *kharwārs* of grain; 420 *man* of rice; 2 *kharwārs* of flour; 20 *man* of clarified butter. It furnishes 13,875 Cavalry and 25,260 Infantry. Qandahār city—5,270 *tumāns* in cash; 35,120 *kharwārs* of corn; 550 horse; 1,000 foot.

Dependencies east of Qandahār.

Territory of Duki,¹ has a fort of unbaked brick. 6 *tumāns* in money; 1,800 *kharwārs* of grain; 12,000 *sheep*; 15 *Balochi* horses; *Afghāns* of the *Tarin* and and *Kākar* tribes; 500 horse, and 1,000 foot.

„ of *Pashang*; has an old fort of unbaked brick. 33 *tumāns* in money; 3,200 *sheep*; 500 *kharwārs* of grain; 1,500 horse and 1,500 foot.

„ of *Shāl*, has a mud fort; 4½ *tumāns* in money; 940 *sheep*; 780 *kharwārs* of grain; *Afghāns* of *Kāst* and *Baloch*; 1,000 horse, and 1,000 foot.

„ of *Mashtang*, (*Mastang*) has a mud fort; 10 *tumāns* and 8,000 *dinārs* in money; 470 *kharwārs* in grain. *Afghāns* of *Kasi*, and *Baloch* 100 horse and 500 foot.

„ of *Khelgari*, 12 *tumāns* in money; 415 *kharwārs* of grain; 200 horse, 300 foot.

Tribe of Pani, 60 *sheep*, an *Afghān* clan, 1,000 horse, 1,000 foot.

¹ Under the Caliphs, the land-tax was usually rated at $\frac{2}{3}$ of the produce of wheat and barley if the fields were watered by public canals; $\frac{1}{3}$ if irrigated by wheels or other artificial means; and $\frac{1}{4}$ if altogether unirrigated. If arable land were left uncultivated, it seems to have paid 1 *dirhem* per *jarib* and $\frac{1}{4}$ of probable produce. Of dates, grapes, garden produce, $\frac{1}{3}$ was taken either in kind or money; and $\frac{1}{4}$ of the yield of wines, fishing, pearls and generally of products not derived from cultivation, was to be delivered in kind or paid in value even before the expenses had been defrayed. The customs and transit dues, for which unbelievers paid a double rate, and the taxes on trades, manufactures and handicrafts were also sources of public revenue. Sir H. Elliot. (*Arabs in Sind*, p. 78). For Aurangzib's revenue regulations, based on Islamic orthodox doctrines, see J. Sarkar's *Mughal Administration*, Ch. XI.

Tribe of Abdāli, formerly paid revenue 1,000 sheep; fixed in the time of the *Qāzilbāshis*² at 100 *tumāns*, 400 horse, 600 foot.

„ of *Abdāli*, 2,800 sheep, 5 *kharwārs* of butter. Afghāns 2,000 horse, 3,000 foot.

„ of *Jamandi*, responsible for 11 *tumāns* and 4,000 *dinārs*. Afghāns, 30 horse, 20 foot.

Surkh Rābāt i Balochān, revenue included under city of Qandahār. 50 horse, 50 foot.

Dependencies south of Qandahār.

Qalāt Banjārah, has a strong mud fort. 30 Balochi horses, 30 camels,—Baloch—500 horse, 500 foot.

Shorābak, 1,200 sheep. Afghans. 200 horse, 100 foot.

Tribe of Bisakh, 225 sheep. Afghans. 200 horse, 300 foot.

„ of *Mirkhāni*, 9 *tumāns* in money, 3,250 sheep. Afghans. 200 horse, 400 foot.

„ of *Maswāni*, 200 sheep. 7 *man* of butter. Afghans. 50 horse, 100 foot.

Dependencies north of Qandahār.

Territory of Qalāt Tartuk [? Barluk] has a very strong mud fort. 520 *tumāns*, 9,600 *dinārs* in money. 4,346 sheep; 1,171 *kharwārs* (of grain?) 1 *man* of butter; 1 *kharwār* of rice. Ghilzai Afghāns. 2,200 horse, 3,820 foot.

Hazārah Dahlah, [*Dahna*] 1,454 sheep; 20 *kharwārs* of grain; 200 horse, 500 foot.

Hazār Banjah Banji, [?] 160 sheep; 15 horse, 50 foot.

Territory of Tarin, has a strong fort. 15,000 sheep; 1,000 *kharwārs* of grain. Hazārah tribe. 1,500 horse, 3,000 foot.

¹ *Duki* signifying a hill in the language of the country, and may be opposed to *Deshi*, or plain. Erskine's *Bāber*, p. 164.

² This name (*Qizil*, red, *bāsh*, head) was given to the seven Turkish tribes, descendants of the captives released by Timur at the request of Safi'uddin ancestor of Shaikh Ismail the first of the Saffavean monarchs. To the gratitude of these Carmanian captives the *Safi*, (*Anglice* Sophy) dynasty of Persia owed its elevation to the throne. See the XIVth Chapter of Malcolm's *History of Persia*. Round the red cap was twisted a turban in 12 plaits to the memory and in honour of the 12 Imāms. D'Herbelot. The term is applied generally to the Persians, and is so employed by Bāber, p. 181.

Dependencies west of Qandahār.

Territory of the torrid tract (Garmsir). 602 *tumāns*, and 8,000 *dinārs* in money; 12,000 *kharwārs* of grain. 200 horse, 2,000 foot.

„ of *Zamin Dāwar*, 1,200 horse, 1,000 foot.

Tribe of Siāhkhānah, 42 *tumāns*; 30 horse, 70 foot.

Fort of Kushk Nakhod, has a mud fort, revenue included under city of *Qandahār*.

Sarkār of Kābul.

It is situated in the third and fourth climates. - Its length from *Atak Benāres* on the Indus to the *Hindu koh* is 150 *kos*; its breadth from *Qarābāgh*¹ of *Qandahār* to *Cheghān Serā*, 100 *kos*. It is bounded on the east by *Hindustān*; on the north-west by the mountains and *Ghor*; between to the north lies *Anderāb* of *Badakshān*, the *Hindu koh* intervening; on the south by *Farmul* and *Naghr*. Adequate praise of its climate is beyond the power of pen to express, and although its winter is severe rather than moderate, it occasions no distress. The torrid and cold belts are so contiguous that the transition may be made from one to the other in a single day. Such approximation of summer and winter pasturage in an inhabited country is uncommon. Snow falls both in the plains and on the mountains; in the former from November and on the latter from September: *Bāber* states that the snowfall in the direction of *Hindustān* does not pass the crest of the *Bādām Chashmah*.² This doubtless was the case in those days, but at the present time it extends to the crest of the *Nimlah*, and indeed as far as the *Khaibar* pass. Even in summer

¹ According to *Tieffenthaler* 11 royal miles from *Ghazni* (about 19½ common miles) on the road to *Qandahār*, I, 21. The greater part of the account of this province is taken without acknowledgment by *Abul Fazl* from the *Memoirs of Bābar*, which should be in the hands of the reader for comparison and illustration of this brief sketch. *Chenghānsērāi* contains one village only, according to *Bābar*, and lies in the entrance of *Kāfiristān*. The large river known as the *Chenghānsērāi* river comes from the north-east behind *Rajaur*. Another smaller stream from the west after flowing through *Pich*, a district of *Kāfiristān*, falls into it. *Naghr* is sometimes written *Naghz*. It is now unknown but *Erskine* conjectures it to have been on the upper course of the *Kurram*, and *Farmul* probably *Urghun* where the Persian race of *Farmulis* still exist. *Niamatu'llah* (*Dorn's History of the Afghāns*, p. 57) says that *Farmul* was originally the name of a river running between the borders of *Kābul* and *Ghazni* and the dwellers on its banks were called *Farmulis*. See *Elphinstone's Cābul*, p. 315 for a fuller account of this division of the *Tājiks*.

² The pass of *Bādām Chashmah* lies south of the *Kābul* river between *Little Kābul* and *Bārikāb*. *Erskine*.

time covering is needed during the nights.~ There are various delightful fruits, but the melons are not so good.¹ Agriculture is not very prosperous. The country is surrounded on all sides by lofty mountains, so that the sudden invasion of an enemy is attended with extreme difficulty.

The *Hindu koh* separates Kābul from Badakshān and Balkh, and seven routes are employed by the people of Turān in their marches to and fro. Three are by the *Panjhir*² (valley), the highest of which is over the *Khawāk* pass; below this is *Tāl*, and the next lower in succession, *Bāzarak*. The best of these is *Tul* but it is somewhat long as its name implies. The most direct is over the heights of *Bāzarak*. Between the high range and *Parwān* are seven other heights called *Haft Bachah* (the *Seven Younglings*). From *Anderāb* two roads unite at the foot of the main pass and debouch (on *Parwān*) by the *Haft Bachah*. This is extremely arduous. Three other roads lead by *Parān* up the *Ghorband* valley. The nearest route is by the pass of *Yangi-yuli*,³ (the new road) which leads down to *Waliyān* and *Khinjān*; another is the *Qibchāk* pass, also somewhat easy to traverse, and a third is the *Shibertu*. In the summer when the rivers rise, it is by this pass that they descend by way of *Bāmiān* and *Tālikān*, but in the winter the *Ābdarah* route is chosen, for at this season, all other routes but this are closed.

¹ Bābar confirms or originates this fact, and adds that those raised from seed brought from Khurāsān are tolerable. He praises those of Bokhāra, but pronounces those of Akhsi, a district north of the Jaxartes, to be beyond comparison the best.

² The word is so written by Bābar, but, according to Cunningham, (p. 32), the true name is *Panchir*, the Arabs writing *j* for the Indian *ch*. The modern spelling is *Panjshir*.

³ I have corrected the inaccuracies of the text by the true readings in Bāber. Bāber himself passed through Bāmlān and by the *Shibertu* Kotal on his march from Khorasan to Kabul in February 1507. Three of these roads, the *πρωτοδ* of Strabo, leading to Bactria parted at Opiān near Charikār, the Hupīān of Bāber, identified with Alexandria Opiana by Cunningham who gives the routes as follows:

1. The north-east road, by the *Panjshir* valley, and over the *Khāwak* pass to *Anderāb*.

2. The west road by the *Kushān* valley, and over the *Hindu Kush* Pass to *Ghori*.

3. The south-west road up the *Ghorband* valley and over the *Hājiyak* (*Hājigak*) Pass to *Bāmiān*.

The first of these roads, he continues, was taken by Alexander on his march into Bactriana from the territory of the *Paropamisadae*, and by Timur on his invasion of India. The second road, he supposes Alexander to have followed on his return from Bactriana, as Strabo mentions the choice of another and shorter route over the same mountains. The third was taken by Chāngiz Khān after his capture of *Bāmiān*; by Moorcroft and Burnes on their journey to Bokhara.

There is also a road leading from *Khurāsān* to *Qandahār* which is direct and has no mountain pass.

From Hindustān five roads* are practicable. 1. *Karapah*, which after traversing two defiles, leads to *Jalālābād*. This route is not mentioned by Bāber and doubtless was not used in his time. 2. *Khaibar*, this was formerly somewhat difficult, but by the command of His Majesty it has been made easily practicable for wheeled conveyance, and at the present time travellers from *Turān* and *India* take this route. 3. *Bangash* which is reached by crossing the *Indus* at the *Dhankot* ferry. 4. *Naghr*. 5. *Farmul*, by which the *Indus* must be crossed at the *Chaupārah* ferry.

Eleven languages are spoken in this province, each nationality using its own, viz., Turkish, Mughal, Persian, Hindi, Afghāni, Pushtu, Parāchi, Geberi, Bereki, Lamghāni and Arabic.¹ The chief tribes are the *Hazārahs* and *Afghāns*, and the pasturage of the country is in the hands of these two clans. The *Hazārahs* are the descendants of the Changhatai army, sent by *Manku Qāān* to the assistance of *Hulāku Khān*. These troops were sent to these parts under the command of his son *Nikodār Oghlān*. Their settlements extend from *Ghazni* to *Qandahār* and from *Maidān* to the confines of *Balkh*. They number more than 100,000 families,² and the third part of which consists of cavalry. They possess horses, sheep and goats. They are divided into factions, each covetous of what they can obtain, deceptive in their common intercourse and their conventions of amity savour of the wolf.

The *Afghāns* consider themselves the descendants of the *Israelites*. They assert that their remote progenitor, named *Afghān*,³ had three sons, viz., *Saraban* to whom the *Sarabani* clan trace their lineage; the second, *Ghurghusht* from whom the *Ghurghustis* claim descent, and the third *Batan* to whom the pedigree of the *Batani* tribe is ascribed. From these three branches they developed into their several

* The best account of the passes between *India* and *Kābul* is C. R. Markham's paper on "The Mountain Passes on the Afghan Frontier of British India", in the *Journal* of the Royal Geographical Society, 1879. Also Holdich.

¹ Bāber adds *Pashāi*; *Gabri* is said in the *Khulāsatu'l Ansāb*, to be a place in *Bajaur*. Dorn, p. 131.

² Lit. houses; the Tartars reckon the numbers of their families by households, tents and sometimes by kettles. Erskine's *Bāber*.

³ In Dorn, *Abdur Rashid*, surnamed *Pathān*. Rose's *Glossary of Punjab Castes and Tribes*, for more accurate information.

clans, each distinguished by its eponymous tribarch. The following septs unite in SARABAN, viz., *Tarin*, *Baraich*, *Miyānah*, *Kharshin*, *Shirāni*, *Urmār*, *Kāsi*, *Jamand*, *Kheshgi*, *Katāni*,¹ *Khalil*, *Mohmandzai*, *Dāudzai*, *Yusufzai*, *Kaliyāni*,² and *Tarkalāni*. From GHURGHUSHT spring the *Surāli* (var. *Surāni*), *Jilam*, *Orakzai*, *Afridi*, *Jagtāni*, *Khattaki*, *Kararāni*, *Bāwar*, *Mansub*, *Kākar*, *Nāghar*, *Bāni*, *Maswāni*, *Pani*, and *Tāran*. To BATAN are ascribed the *Ghilzai*, *Lodi*, *Niyāzi*, *Lohāni*, *Sur*, *Bani*, *Sarwāni* and *Kakbor*.

It is said that *Mast Ali*³ *Ghori*-whom the Afghāns call *Matī* had illicit intercourse with one of the daughters of Batan. When the results of this clandestine intimacy were about to become manifest, he preserved her reputation by marriage, and three sons were born to him, viz., *Ghilzai*, *Lodi*, and *Sarwāni*.

Some assert the Afghāns to be *Copts*, and that when the Israelites came to Egypt from Jerusalem, this people passed into Hindustān. The tradition is too long to be condensed within narrow limits, but it is noticed in passing as a fanciful digression.

There are many wild tribes, such as the *Khwājah* *Khizri*, *Qāqshāl*, *Maidāni*, *Uzbek*, *Kalatki*, *Parānchi*, *Nilpurchi*, *Bakderi*, *Bahsudi*, *Sidibāi*, *Tufakandāz* (matchlockmen), *Arab*, *Gilahbān* (shepherds) and *Tuqbai* but not as numerous as the first mentioned, and most of them at the present time have become settled colonists.

The *City of Kābul* is situated in the fourth climate. Its longitude is 104° 40', and its latitude 34° 30'. It is one of

¹ According to the *Khulāsal-u'l Ansāb* (Dorn, p. 127) the Katānis possess no territory but are scattered in single families. From Nīāzi descend the Musakhail, Isakhail, Sambal Saharangh, conjointly called Nīāzis: they reside about the town of Makhad on the banks of the Indus as far as Dera Ismail Khān. The descendants of Pani reside about Shikārpur. Another account places them, after their expulsion from their country, about Jeypur and Jodhpur where they subsist by traffic and carry merchandise to the Deccan. Nāghar's descendants reside about Dera Ghāzikhān, and Kākaris near Qandahār. The word 'zai' or 'zacy' as Raverty writes the word, signifies 'son', and answers to Mac, Fitz, and O. Suffixed to the tribal name, it means 'a man' of the particular clan.

² Probably a miscript for Gagiyāni.

³ According to Dorn, Shāh Husain, Prince of Ghor, (pp. 46, 48, Part II). Matu was the name of Shaikh Patni's daughter and Shāh Husain not being of Afghān extraction, his descendants were called by the maternal name of Matī. The name of Ghilzai was given on account of the clandestine amour, 'ghil' signifying thief, and 'zai' born, a son.

the finest of ancient' cities, and is said to have been founded in the time of *Pashang*. It possesses a double earthwork fortress of considerable strength. To the south-west of the fortified town is a low hill which is a source of much beneficence, called *Shāh Kābul*,² doubtless with reference to an edifice erected upon it by one of its former kings. Upon its summit stands the citadel, and there was a separate ridge named *Aqābain*. As it somewhat overlooked the fort, it was included within its precincts by royal command. Skirting its base are fair embankments, pleasure-gardens and delightful groves, amongst which the *Shahr Ārā* (Pride of the City) are especially beautiful. The city is watered by two streams. One of these, called the *Jui Khatibān*, enters from *Lalandar* and flowing through the *Shahr Ārā* passes by the city; the other, the *Jui Pul Mastān*,³ more wholesome and limpid than the former, from the narrows of the *Deh i Yaqub* winds past the Delhi Gate and runs on to *Deh i Mamurah*. Near this a canal called *Mahum Anagah*⁴ has been brought, which is of extreme convenience, and adjacent is the *Gulkanah* quarter fair to the eye and dear to the heart. From the hill (of *Shāh Kābul*) flow three streams citywards; at the head of one is the shrine of *Khwājah Hamu* [Shams]; the second, according to popular belief, had been visited by the prophet *Khizr*; the third is over against (the tomb of) *Khwājah Abdu's Samad* known as *Khwājah Roshanāi*. The wise of ancient times considered

² It was the old capital of the country, says Cunningham, before the Macedonian conquest, and Ibn Haukal states that inauguration at Kābul was a necessary qualification for government in a king. Tieffenthaler names 4 gates, viz., *Lahor*, *Kābul*, *Nalbandi* and *Fatouhi*, adding that near this last was an ancient castle with mud walls. It was pulled down by Ahmed Abdālī, and the houses in front of the *Fatouhi* gate razed to the ground. A new fort was then erected of brick work 'sur un lieu élevé', and its garden laid out by the governor.

³ Erskine says that there is a hill south of Kābul on which Qābil (Cain) the founder, is said to have been interred, but the only hill south-west is that known as Bābar Badshāh where Bābar himself was interred, and is the great holiday resort of the people. Bābar's description is as follows: "There is a small ridge which runs out from the hill of Shāh Kābul and is called Aqābain, and there is besides another small hill on which stands the citadel. The fortified town lies on the north of the citadel." Erskine identifies Aqābain with that now called Ashikān Arifān, which connects with Bābar Badshāh. The Bālā Hissār is on the same ridge further east and south-east of the town. The beneficence of the Shāh Kābul mentioned in the text, is due to three streams that issue from it, two of which are in the vicinity of the shady and retired Gulkanah, the scene, as Bābar not regretfully notes, of many a debauch. The position of the citadel and of the conjoined hills, has been carefully described by Forster, *Travels*, p. 73.

⁴ It is a canal derived from the river Logar as it enters the plains of Shevaki and has a course of about five miles. I. G.

⁵ The name of Akbar's nurse (Anagah) who attended him from his cradle and exercised a backstair influence that affected many political fortunes.

Kābul and Qandahār as the twin gates of Hindustān, the one leading to Turkestan and the other to Persia. The custody of these highways secured India from foreign invaders, and they are likewise the appropriate portals to foreign travel.

In Kābul as well as in Samargand and Bokhāra, a *pargana* which comprises towns and villages is called a *Tumān*. The *Tumān of Bigrām* is called *Parashāwar*, the spring season of which is delightful. Here is a shrine greatly venerated called *Korkhatri*,¹ visited by people especially *yogis* from distant parts.

The *Tumān of Ncknihāl*² is one of the dependencies of *Lamghān*. The residence of the governor was formerly at *Adināhpur* but is now at *Jelālābād*. There is here no snow-fall and the cold is not so severe. Nine streams irrigate the cultivated lands; the pomegranates have no seed-stones. Near *Jelālābād* is the *Bāgh i Safā*³ (*The Garden of Purity*) a memorial of Bābar, and adjacent to *Adināhpur* is the *Bāgh i Wafā* (*The Garden of Fidelity*) another relic of the same monarch. To the south lies the stupendous range of the *Safed koh* (*The White Mountain*) with its perpetual snows from which it derives its name. In this neighbourhood is a low hill⁴ where when it snows in Kābul, a similar snowfall occurs.

¹ This shrine, is mentioned by Bābar as one of the holy places of the Hindu *yogis* who came from great distances to cut off their hair and shave their beards at this spot. He rode out to Bigrām to see the great tree but was not shown the shrine in 1505. Fourteen years later his curiosity was gratified. *Gor Khatri* was once a Buddhist monastery, (*I. G.*) then rebuilt into a Hindu temple, and now used as a *ṣaḍī*.

² In the *I. G.* *Nangihār* and by Bābar *Nangenhār* or *Nekerhār*, the district south of the Kābul river in the province of Jelālābād, that on the north, bounded on the west and east by the *Alingār* and *Kunar* rivers, being *Lamghān*. It lies along the Kābul river on the south, and the name is said to mean 'nine rivers'. The *I. G.* affirms it to be a distortion of the ancient name of *Nagarahāra*, identified by Lassen with the *Nagara* of Ptolemy regarded by Cunningham as identical with Jelālābād. *Adināhpur* is south of the Kābul river.

³ A garden of this name was planted by Bābar at *Keldah-Kehār* (*Kuller Kaher*) near *Pind Dādan Khān*, eleven years after that of the *Bāgh i Wafā* near *Adināhpur* south of the Kābul river. It was situated 10 *kos* from *Bahrah* in the middle of the hill of *Jud* on a level plot of ground in the centre of which was a lake which received the water of the surrounding hills and was about five miles in circumference. *Bahrah* or *Bhira* is marked in the maps 20 *kos* from *Kuller Kaher*, but the name is said to be common in the district.

⁴ Bābar is more explicit. 'On the south of the fort of *Adināhpur* is the *Surkh-rud* (runs into the Kābul river between *Jagdalik* and *Gandamak*). On the north is a detached mass of mountain dividing *Nangenhār* and the *Lamghānāt*. Whenever it snows at Kābul, the snow falls also on the top of this mountain by which means the people of the *Lamghānāt* can tell when it snows at Kābul.

The *Tumān of Mandrāur* : monkeys here abound. The *Alishang* river uniting with the *Alingār* joins the *Bārān*, while the *Cheghān Sarāi* river flowing through the north-east quarter enters *Kator*.¹

The *Tumān of Alishang* is surrounded by lofty mountains covered with snow in which is the source of the *Alishang* river. The inhabitants are called *Kāfirs*. In the vicinity is a tomb asserted by the people to be that of *Lām* the father of Noah, called also *Lamek* (*Lamech*). The people here pronounce the *kāf* like a *ghain*, and hence the currency of the name (*Lamghān*).

The mountainous *Tumān of Najrāo*² also is peopled by the *kāfirs*. Instead of lamp they burn the *chilghozah*.³ There is also an animal called the *Flying Fox*,⁴ which flies upward about the height of a yard. There is also a rat which exhales the smell of musk.

Charkh is a village of the *Tumān of Loghar* which gives its name to *Maulana Yaqub Charkhi*. *Sajāwand* is also one of the well-known villages of this *Tumān*.

The mountains of the *Tumān of Badrāo* (?) are the home of *kāfirs* and wild *Hāzarahs* and *Afghāns*.

The *Tumān of Alsā*⁵ is situated intermediately between the torrid and cold belts. Birds cross this tract about the beginning of spring and good sport is had.

¹ Bābar's words are : 'The river of *Cheghansarāi*, after passing through *Kaferistān* from the north-east, unites with the river *Bārān*, in the *Baluk* of *Kāmel* and then passes onwards to the east.'

² It lies north-east from *Kābul* in the hill country according to Bābar, who adds that their inhabitants are wine drinkers, never pray, fear neither God nor man, and are heathenish in their usages.

³ The seed of the *Pinus gerardiana*; the cone, which is as big as a man's two fists, and also the tree itself, said to be derived from *chihal* 'forty' and *ghoza* a 'nut'.

⁴ Copied from Bābar whose account is as follows : "It is an animal larger than a squirrel with a kind of leathern web stretching between its fore and hind feet like a bat's wing. It is said that they can fly a bowshot from a higher tree to a lower one. I myself have never seen them fly, but have let one go beside a tree which it quickly clung to and ascended, and when driven away, expanded its wings like a bird and came to the ground without injury." This must be the flying squirrel, which does not fly though wing-handed, but is supported by its membrane as it leaps.

⁵ Bābar, *Alah-sāi*, which Erskine says is now called *Tugow*. "It lies two or three farsangs east of *Najrāo* from which you advance straight towards *Alah-sāi*." Bābar places it between the cold and warm belts, and says that the birds take their flight across in the spring. Fowlers sit behind, scream and raise nets as the flights of fowl approach and intercept them. In the winter season the birds come down to the skirts of the hills and if in their flight they happen to pass over a vineyard they are no longer able to fly and are caught. A similar story is told of some fields near *Whitby*. (*Notes to Marmion*). The pomegranates of *Alah-sāi* are famous in the country, and are sent to *Hindustān*,

The *Tumān of Bangash*¹ furnishes 7,000 Cavalry and 87,800 Infantry, viz. :—

		Cavalry	Infantry
<i>Mohmand</i>	...	500	500
<i>Khālil</i>	...	500	6,500
<i>Dāudzai</i>	...	3,000	37,000
<i>Gagiyāni</i>	...	500	4,500
<i>Muhammadzai</i>	...	400	4,000
<i>Sini</i>	...	100	1,400
<i>Utmānkhail</i>	...	50	850
<i>Ghilzai</i>	...	100	2,900
<i>Khizrkhal</i>	...	30	950
<i>Sherzād</i>	...	20	1,400
<i>Kharguni</i> [Khar Kuli]	...	10	200
<i>Khattaki</i>	...	200	4,000
<i>Abdu'r Rahmāni</i>	...	100	2,500
<i>Afridi</i>	...	500	10,500
<i>Oruk, (Orakzai)</i>	...	500	5,500
		<hr/> 6,510	<hr/> 82,700

The *Tumān of Gardez*² has a strong fort. The houses are for the most part three and four stories high.

Ghaznin is situated in the third climate, and is also known as *Zābul*, and was the capital of Sultān Mahmud, Sultān Shahābu'ddin and several other monarchs.

This territory was formerly called *Zābulistān*, and some reckon *Qandahār* as included within it. Here is the last resting-place of *Hakim Sanāi*³ and many other saintly personages. The winter season is said to resemble that of *Samarqand* and *Tabriz*: A river runs from north to south which waters all the arable tracts. The cultivators are put

¹ Occupies the lower grounds from *Gardez* to *Kohāt*. *Bābar* says it is infested by Afghān robbers such as the *Khugiāni*, *Khirilchi*, *Buri* and the *Linder*.

² Upwards of sixty-five miles south-east from *Kābul*. *Bābar* says that the *Daroghā* of the *Tumān of Zurmat*, south of *Kābul* and south-east of *Ghazni*, resides at *Gardez* which is not named as a separate *Tumān*. Next follows the *Tumān of Farmul* omitted by *Abul Fazl*. It is notable only in the fact that the *Shaikhzādahs*, who were treated, as *Bābar* says, with such distinguished favour in *Hindustān* during the time of the Afghāns, were all of *Farmul* and descended from *Shaikh Muhammad Musalmān*.

³ This tomb is mentioned by *Elphinstone*, *Cābul*, 433. He was a mystic of high authority and repute whom the great *Sufi* *Maulanā Rum* looked up to as his master. He flourished under *Bahrām Shāh*, son of *Masaud Shāh* of *Ghazni* (A.D. 1118-52) to whom he dedicated his *Hadīqat ul Haqāiq*. He left also the usual *Diwān* which is necessary to every Persian poet's fame or ambition. He is said to have died in 1131 at the age of 62. *Encyclo. Islam*, iv. 146; *Browne, Lit. History of Persia*, ii. 317.

to great trouble as fresh soil has to be supplied each year to fertilize the land and it becomes then more productive than that of Kābul. The metal called *ruin*¹ is here abundant and is imported into Hindūstān. In the time of Bābar there was here a tomb which shook whenever the praises of Muḥammad were recited. The investigations of acute observers discovered that this was effected by fraud of relic-mongers.² There is also a spring into which if any filth be thrown, a thunderstorm ensues with a fall of snow and rain.

The *Tumān of Dāman i koh*³ has a profusion of flowers and its spring and autumn are matchless in beauty.

In the *Tumān of Ghorband* the variety of floral hues is beyond expression. Three and thirty species of tulips here bloom and one kind named the *rose-scented tulip* breathes the fragrance of the blush-rose.⁴

Mines of silver and lapis-lazuli are also found. Near the mountains is a sandy tract called *Kharājah Reg i Raxār*⁵ and from this quicksand, the sound as of drums is heard in the summer time.

In the *Tumān of Zohāk* and *Bāmiān*, the fortress of *Zohāk* is a monument of great antiquity, and in good preservation, but the fort of *Bāmiān* is in ruins. In the mountain-side caves have been excavated and ornamented with plaster

and paintings. Of these there are 12,000 which are called *Sumaj* and in former times were used by the people as winter retreats. Three colossal figures are here : one is the statue of a man, 80 yards in height; another that of a woman 50 yards high, and the third is that of a child measuring 15 yards. Strange to relate, in one of these caves is placed a coffin containing the body of one who reposes in his last sleep.¹ The oldest and most learned of antiquarians can give no account of its origin, but suppose it to be of great antiquity. In days of old the ancients prepared a medicament with which they anointed corpses and consigned them to earth in a hard soil. The simple deceived by this art, attribute their preservation to a miracle.

The territory of Kābul comprises twenty *Tumāns*. The Emperor Bābar in his Memoirs sets down the revenue at twenty lakhs of *Shāhrukhis*, inclusive of *Tamgha*² imposts, equivalent to three lakhs and twenty thousand *Akbar Shāhi* rupees, the rupee being reckoned at forty *dāms*.

At the present time notwithstanding the remission of various taxes, by the blessing of this ever-during rule, the revenue has reached the amount of six *krors*, seventy-three lakhs, six thousand, nine hundred and eighty-three *dāms*. (Rs. 1,682,674-9). The increase is to be attributed to the improved state of the cultivation, and also that *Parashāwar* and *Ashtaghar*³ were not included in the former account, and lastly, that the revenue officers of that time were not as capable as they are at present.

Sarkār of Kābul.

Containing 22 Mahals : Revenue 80,507,465 *Dāms* in money : *Suyurghāl* 137,178 *Dāms*. Cavalry, 28,187. Infantry, 212,700.

¹ The punctuation in the text is clearly misplaced.

² Inland tolls. See Vol. I, 189, but Bābar's words are : "The amount of the revenue of Kābul, whether arising from settled lands or raised from the inhabitants of the waste, is eight lakhs of *Shāhrukhis*." The word 'twenty' *bist* must be a copyist's error for *hasht* eight, as the Akbar Shāhi rupee being equal to 2½ *Shāhrukhis*, the whole would give exactly three lakhs and twenty thousand rupees. Erskine notes *tamgha* as the stamp tax. All animals, goods, clothes &c. brought into the country are stamped or marked and a tax collected.

³ A corruption of Hashtnagar, now a *tahsil* of the Peshāwar district. The "eight towns" of which it was composed were Tangi, Shirpao, Umrzai, Turangzai, Usmānzai, Rajur, Chārsada and Parāng. The last two are seated close together in a bend of the Kābul river and the sites of all are shown in Map IV. of Cunningham's *Anct. Geog.*, p. 46.

City of Kābul—Revenue, 1,275,841 *Dāms*. Cavalry, 7,000. Infantry, 15,000.

Dependencies east of Kābul.

	Revenue. D.	Sayurgahāi. D.	Cavalry.	Infantry.	Tribes.
Tamān of Bigrām ...	9,692,410
„ Neknihāl (Nangaiihār) ...	11,894,003	1,224	200	5,000	...
Buluk i Kāmāh (not recorded)

North.

	Revenue. D.	Sayurgahāi. D.	Cavalry.	Infantry.	Tribes.
Tamān of Mandrāur ...	2,684,880	...	50	500	...
„ Alishang ...	3,701,150	1948	25	5000	Alishang.
„ Alingār ...	1,544,670	...	500	1000	Lamghāni.
Buluk Nairāo ...	2,045,451	...	5000	3000	Kāfir.
Tamān of Loghar ...	3,193,214	22,950	50	500	...
„ Badrāo ...	413,888	...	25	500	...
„ Alsāi ...	600,000	5000	Dilazāk.
„ Panjhir (Panjshir) ...	451,940	35,000	Pani.

South.

	Revenue. D.	Sayurgahāi. D.	Cavalry.	Infantry.	Tribes.
Tamān of Bangash ...	3,332,347	...	7,057	87,800	Afghān.
„ Kohat (var. Kohast, Karbast) ...	701,620	...	300	5000	Orakzai &c.
„ Naghr (var. Naghar) ...	884,000	...	1000	7000	Afghān, Batakhan.*
„ Garder ...	2,030,032	...	200	1000	Afghān
„ Maidān ...	1,636,799	1,884	2000	...	Hamrah Maidāni
„ Gharnin ...	3,768,642	1,075	1000	5000	...

* Variant, *Shaku Khar*.

West.

	Revenue. D.	Suyurghāl. D.	Cavalry.	Infantry.	Tribes.
Tumān of Farmul ...	325,712	...	1000	5000	...
„ Dāman i koh ...	16,461,785	...	5000	30,000	...
„ Ghorband ...	1,574,760	...	3000	5000	Hazārāh and Tur- komān.
„ Zohāk Bāmiān ...	861,750	...	200	1000	...

In the year 77 of the Flight (A.D. 696-7) Abdu'l Malik b. Marwān removed Umayyah b. Abdu'l Malik from the government of Khurasān and conferred it upon Hajjāj b. Yusuf of the tribe of Thakif, and sent Abdu'llah b. Abu Bakr to Sistān, who levied an army, marched against Ranthel, king of Kābul. The latter unable to withstand him took refuge in the depths of the mountains. Abdu'llah not realising the difficulties of his undertaking eagerly pursued. The mountaineers barricading the passes with stone breastworks, blocked his road. The invading force was hard-pressed and reduced to extremity through want of provisions. Abdu'llah was therefore compelled to purchase a retreat with the sum of 700,000 *dirhams*, equivalent in present money value to 3,00,000 rupees. Shuraih b. Hāni in indignation at the compact advanced to an engagement notwithstanding his being stricken in years, and fell bravely fighting. Hajjāj on hearing of the event, reprimanded Abdu'llah and removed him from his command. In the year 80 (A.D. 699) he appointed Abdu'r Rahmān b. Muhammad Ashath to conduct the war against Ranthel and bestowed on him the government of Sistān and the adjacent territory. Abdu'r Rahmān on his arrival in Kābul adopted the former tactics, but prudently occupied each defile with his pickets and performing prodigies of valour, secured a large booty. The difficulties of the country, however, prevented its permanent occupation. Hajjāj disapproving his retreat sent him a severe reprimand in the following terms: "Although your exertions during the present year have been strenuous, the retribution demanded by your dishonourable retreat is that immediately on the receipt of this letter, you take possession of the country. Should you, through persistence in your own opinions or through fear of

the consequences to yourself, refuse to comply and defer operations till the coming year, you are removed from your command, are hereby required to look upon Ishāq b. Muhammad as your commander and to place yourself under his orders." Abdu'r Rahmān, confiding in the strength of possession, disloyally formed a compact with his officers and refusing submission, made peace with the king of Kābul and marched against Hajjāj. The conditions of peace were that Abdu'llah if victorious should altogether withdraw from Kābul and in no way molest it, but if defeated, the king should on his part afford him protection and assistance. Hajjāj was enraged at this rebellious conduct, and gave him battle outside the walls of Tustar.¹ Abdu'r Rahmān was victorious, and Hajjāj retreated to Basrah. A second engagement took place in which the rebel was defeated and took refuge in the fortress of Bast [in Luristan] which was held by one of his lieutenants. This accursed of God and man, with a view to ingratiate himself with Hajjāj, seized him with the intention of surrendering him to Hajjāj. The king of Kābul, on being informed of the circumstance, set out with the greatest expedition and releasing him, returned with him to Kābul. On several subsequent occasions; with the assistance of the king, he continued the war but without success. In the lunar year 84, (A.D. 703) Ranthel overcome by the persuasion and seductive promises of Hajjāj, sent Abdu'llah to him as a prisoner. The latter resenting the dishonour, whilst on the road, threw himself from a precipice and was killed.

In A.H. 107 (A.D. 725-6) under the caliphate of Hishām b. Abdu'l Malik, Amin b. Abdu'llah Qashari, governor of Khurasān conquered Ghor, Gharjistān, the territory of Nimroz² and Kābul and made (the latter) his capital. From that time continuously under the dynasties of Umayyah and Abbās, it was held by the governor of Khurasān, until under the Sāmānis, Alptegin a slave of that House, withdrew from their obedience, took possession of Ghaznin and Kābul and asserted his independence. On his death Sabuktegin father of the great Mahmud succeeded to the kingdom, and it continued under the House of Ghazni. From this it passed to that of Ghor and thence into the pos-

¹ Now, *Shuster* in *Khuzistān*. It was first conquered in A. H. 20 in the Caliphate of Omar.

² Usually applied to Sejestān. Elliot. *Arabs in Sind*, p. 172.

The Karoh or Kos.

Four thousand paces are one *mil*;
Know that the men of Hindustan call it a *kuroh*,
This pace is a cubit and a half;
Every cubit is six hand-breaths;
Each hand-breadth is six inches; and again each inch
Is the breadth of six barley-corns. Know all this,

53

dhapiyah,¹ which is the distance that a fast runner can traverse at one breath. Some assert that it is the distance within which a green leaf placed on the head of one who walks rapidly, will become dry.

In ancient tables of measurement by *farsakh* of distances and magnitudes, it is recorded that the circumference² of the globe according to the method of the old geographers, was 8,000 *farsakh*, but 6,800 of the modern school, while all agree in defining a *farsakh* as three *kos*. The former made the *kos* 3000 *gaz*, each *gaz* of 32 digits. The latter fixed it at 4000 *gaz*, each of 24 digitis. The digit with both was the breadth of six ordinary barley-corns placed front to back in succession, and the breadth of each barley corn was equal to the thickness of six hairs of the mane of a Turki horse. To short-sighted superficial observers, it would appear that these two systems differ in their estimate of the *kos*, but it is clear to the perspicacity of the far-seeing that their conclusion is the same, and the apparent difference is caused by the variance in the number of the digits as may be proved by the rule of proportion. This consists of four numbers, the first bearing the same ratio to the second, as the third does to the fourth, as for instance, two is to four as eight is to sixteen. Of the properties of this relation one is this that the product of the extremes is equal to the product of the means, as is evident from the example above mentioned. The proof is given in the 19th proposition of the 7th book of Euclid³ where the apparent contradiction is removed. The ratio of 3000 to 4000 is the ratio of 24 to 32. Although the four numbers are here

¹ The word is Hindi and means a short run according to Wilson's *Glossary*, about $\frac{1}{2}$ of a *kos* or half a mile.

² The circumference of the earth, according to our calculations is 24,897 miles and the *farsakh* is about $3\frac{3}{4}$ English miles; there are of course many local variations. Hamdu'llah Mustaufi, the author of the *Nuzhat'ul Qulub*, says that the *farsakh* under the Kaianian dynasty contained 3 miles of 12,000 feet; that of Khwarizm was 15,000 yards; in Azarbijān and Armenia, 12,000 yards, while in the two Irak's and the neighbouring provinces it was reckoned at 6000 yards, and in some other places at 8000.

³ The *Elements* of Euclid were restored to Europe by translations from the Arabic which were begun to be made under the Caliphs Harun and Mamun at a time when the very name of that geometrician had disappeared from the West. Nasiru'ddin Tusi (see p. 4, n. 4 of this Volume) in the preface to his Arabic Edition of the thirteen books of the *Elements*, describes their original composition by Euclid and the subsequent addition of two books by Hypsicles. From it I transcribe the enunciation of the proposition referred to in the text.

"When four numbers are proportionals, the product of the 1st and 4th = the product of the 2nd and 3rd, and if the product of the 1st and 4th = the product of the 2nd and 3rd, the ratio of the 1st is to the 2nd as the ratio of the 3rd to the 4th."

severally distinct, the product of 3000 and of 32 which are the extremes, is equal to the product of 4000 and of 24 which are the means, namely, 96,000. Thus the result in both is the same, and the discrepancy in the number of yards is through the difference in the number of digits. Each *farsakh* therefore consists of 12,000 *gaz* (of 24 digits) according to the measure of the moderns or of 9000 (of 32 digits) according to the *gaz* of the ancients. The properties and virtues of these proportional numbers are manifold. Among them are the following: If one of the extremes be unknown, multiply the means together and divide by the known extreme, and the quotient is the unknown extreme. For instance in the given example, if 2, the first extreme, be unknown, by multiplying the means together which are 4 and 8, we get 32. Dividing this by 16, the quotient (2) is the unknown extreme. In the same way, if the other extreme, which is 16, be unknown, by dividing the product of the means by 2, the known extreme, the quotient is 16. Again, if the unknown quantity be one of the means, we divide the product of the extremes by the known mean, and the quotient is the unknown mean. For example, if 4, the first mean, be unknown, by dividing the product of the extremes, which is 32, by the known mean which is 8, the quotient is 4. And if the second mean, 8, be unknown, by dividing the product of the extremes by 4, the quotient is 8.

By the same means the distance and altitude from the base of a given object can be ascertained. A staff of a given height is fixed upright. Its shadow and that of the elevate object are measured. The ratio of the shadow of the staff to the staff is proportional to the ratio of the shadow of the object-height to the height itself. Again, a staff is fixed in the ground in the same line with the height to be measured and regarded from such a point that the line of vision may pass over the top of the staff to the summit of the object-height; the ratio of the distance from the standpoint of vision to the base of the staff is to the height of the staff as the ratio of the distance from the same point to the base of the object is to the height of the object. And if the altitude of an object be measured in a mirror or water and the like, a position must be taken whence the incident line of vision may strike the summit of the (reflected) object-height. The ratio of the distance of the reflected summit from the foot of the spectator is to his height as the ratio of the distance

of the same point from the base of the object is to the height of the object. And if it be required to find the depth of a well, the observer must stand where his line of vision traversing the brink of the well touches the level bottom of the well on the side opposite to him. The ratio of the distance of the brink of the well from the foot of the observer is to his height as the breadth of the well is to its depth.*

Some take the *barid* as the standard measure of length and make.

1 <i>barid</i>	equal to	3 <i>farsakh</i> .
1 <i>farsakh</i>	„	3 <i>mil</i> .
1 <i>mil</i>	„	12,000 <i>bāa</i> (pole).
1 <i>bāa</i>	„	4 <i>gaz</i> .
1 <i>gaz</i>	„	24 digits.
1 digit	„	6 barleycorns.
1 barleycorn	„	6 hairs of a mule's tail.

According to the Hindu philosophers—

8 barleycorns stripped of husks and laid breadth-ways	make	1 digit (<i>angusht</i>).
24 digits	„	1 <i>dast</i> (cubit).
4 <i>dast</i>	„	1 <i>dand</i> (pole or perch) or <i>dhanuk</i> .
2000 <i>dand</i>	„	1 <i>karoh</i> or <i>kos</i> .
4 <i>karoh</i>	„	1 <i>yoojana</i> .

Some measure by the steps of a woman with a water-jar on her head and carrying a child in her arms, reckoning a thousand such steps to a *kos*.

Praise be unto God that the institutes of imperial administration have been completed and a general survey of the Empire, by the aid of divine grace, placed upon record. The numbers of the tribal contingents and the chronology of the ancient kings with some other particulars have cost considerable labour, and from the conflicting accounts received, I was well nigh relinquishing the task, but the decrees of fate cannot be resisted. I have set down what has best commended itself to my judgment, hoping that it may win lustre from the light of public acceptance and its errors escape the carping of illiberal criticism.

END OF VOLUME II.

* This method of calculating distance and altitudes is more scientifically given with illustrations in the *Siddhanta Stromani* of Pundit Bapu Deva.

BIBLIOTHECA INDICA

PUBLISHED BY

THE ROYAL ASIATIC SOCIETY OF BENGAL.

The Bibliotheca Indica is a collection of works belonging to, or treating of, oriental literatures and contains original text editions as well as translations into English, and also bibliographies, dictionaries, grammars and studies.

The publication was started in 1849, and consists of the Old and the New Series. The New Series was begun in 1860 and is still running.

Each issue bears a consecutive issue number. The Old Series consists of 205 issues; in the New Series 1558 issues have been published till December, 1st, 1947. These 1820 issues represent 100 different works; these works again represent the following literatures:—Sanskrit, Prakrit, Rājasthānī, Kashmirī, Hindi, Tibetan, Lushāi, Arabic, Persian.

Single issues may be bought separately, but three years after the completion of a work, no complete sets are broken for the sale of loose component parts.

The publications or information about them are obtainable from the Royal Asiatic Society of Bengal, 1, Park Street, Calcutta 16, or from the Society's Agents:

Messrs. Luzac & Co., 46, Great Russell Street,
London, W.C.

Messrs. Thacker, Spink & Co., Ltd., 3, Esplanade East,
Calcutta.

Messrs. The Moore Cottrell Subscription Agencies, New
York, U.S.A.

Residents of Europe may order from the above Agents.

All Cheques, Money Orders, etc., should be made payable to the Treasurer, Royal Asiatic Society of Bengal.

In India books are supplied by V.P.P.

BIBLIOTHECA INDICA SERIES

SOME OF THE PUBLICATIONS

1. Āin-i-Akbarī Eng. tr. Vol. I, (Blochmann) edited by D. C. Phillot. Vol. II. (Jarrett), Vol. III. (Jarrett).
2. Muntakhabu't-Tawārīkh (Badāūnī)—in 3 volumes—Translated by Ranking, Haig, Lowe.
3. Tabaqāt-i-Akbari—Text & Translation by B. De.
4. Manu Smṛiti—in 3 Vols.—Edited by Gangānāth Jhā.
5. Vaiḥānasa-Smārta-Sūtra—Text and Translation by W. Caland.
6. Vedānta-Pārijāta-Saurabha of Nimbarka and Vedānta-Kaustabha of Srinivāsa—in 3 Vols. Translated by Roma Bose.
7. Mārkaṇḍeya-Purāna—Translated by E. Pargiter.
8. Varna-Ratnākara of Jyotirīśvara-Kaviśekhara-cārya—Edited by S. K. Chatterji and Babua Misra.
9. Kuṭṭhaṇīmatam Kavyam . (Damodar Gupta)—Edited by Madhusudan Kaul.
10. Padmavati (Malik Muhammad Jaisi)—Translated by A. G. Shirreff.
11. The Legend of the Topes (THŪPAVAMŚA)—Translated by Dr. B. C. Law.
12. Maāsir-i-Alamgiri, Eng. tr. by Dr. Jadunath Sarkar.

